Sewage Works Journal

Published by

Federation of Sewage Works Associations

Lancaster, Pa.

Copyright, 1944, by Federation of Sewage Works Associations

Vol. XVI March, 1944 No. 2

Plant Operation:

The Chlorination of Sewage and Industrial Waste. By Harry A. Faber. Open Discussion 211

Postwar Planning in Syracuse and Onondaga County. By Glenn D. Holmes 218

Sewage Research:

A Critical Review of the Literature of 1943 on Sewage, Waste Treatment and Stream Pollution. By Willem Rudolfs, *Chairman*, H. E. Babbitt, G. P. Edwards, H. A. Faber, A. J. Fischer, H. W. Gehm, A. L. Genter, H. Heukelekian, H. J. Miles, F. W. Mohlman, C. C. Ruchhoft, L. R. Setter and L. W. Van Kleeck 233

Modified Sewage Aeration—Part II. By Lloyd R. Setter and Gail P. Edwards .. 278

Grease Removal by Vacuum Flotation. By Rolf Eliassen and H. B. Schulhoff .. 287

Grease Removal at Army Sewage Treatment Plants. By Rolf Eliassen and H. B. Schulhoff. Discussions by W. S. Mahlie and H. W. Gehm 296

Sewage Works Design:

Sewage Treatment Practice—Standards for Municipal Sewage Treatment Plants. By Arthur S. Bedell 318

Sewage Treatment for Homes and Institutions. By A. E. Berry 328

Operator's Corner:

The Value of Open Discussions on Operation Problems 333

The Operator's Forum:

I. Use of Sludge in the Victory Garden Campaign 333

II. Secondary Treatment—Present and Future 348

III. Wartime Operating Problems in Municipal and Army Sewage Treatment Plants 363

IV. The Broad Conservation Program of the War Production Board 372

Editorials:

Thanks to The Chemical Foundation 374

Paul Hansen—In Memoriam 376

Proceedings of Member Associations:

New York State Sewage Works Association 377

Member Association Meetings 381

Federation Affairs:

1943 Membership Prize 382
The Fifth Annual Meeting 382
Wanted—Sewage Works Accident Reports 383

Reviews and Abstracts:

T.N.T. Waste. By Stuart Schott, C. C. Ruchhoft, and Stephen Megregian 384
Glutamic Acid Content of Steffen's Waste. By David O'Day and Edward Bartow 385
Disposal of Citrus Wastes. By Howard W. Hall 386
Sludge Disposal at Horsham. By P. S. Browne 387
From Water Liquors to War Alcohol. By John R. Callaham 388
Predicting Flow-Friction Data for Sludges. By Joseph D. Parent 388

References to Sewage Literature 389

Member Association Officers 392

1943 Membership Directory 397

Honorary Members 397
Associate Members 397
Member Associations 398
Alphabetical Membership List 451

Plant Operation

THE CHLORINATION OF SEWAGE AND INDUSTRIAL WASTE*

By Harry A. Faber

Research Chemist, The Chlorine Institute, Inc., New York, N. Y.

The purpose of this paper is to present a critical summary of past and present applications of chlorination, in the treatment of sewage and industrial waste, and to attempt an evaluation of its future utility.

The general adoption of sewage chlorination had its inception when liquid chlorine became available as an article of commerce in the United States; that is, about thirty years ago. Research in that application started even earlier, when chloride of lime was recognized as a suitable disinfectant for water and sewage. In all the research since that time, only very limited attention has been devoted to the fundamental chemical changes accomplished by chlorination. Those investigators who have contributed to the basic knowledge of sewage chlorination can just about be counted on the fingers of two hands.

Chlorination is represented in sewage literature mainly by reports on operation and by operating results. There is a large field and a real need for more fundamental research, particularly in some of the newer applications of chlorine. Such studies, leading to refinements of present practice, would be amply justified by improvements in plant operation and by economy of chlorine.

For the purpose of analyzing the present state of knowledge, it will be useful to comment upon those chlorine applications which may be considered as well established uses. The list will include only: disinfection, B.O.D. reduction, and the control of odors and septicity.

Chlorination for disinfection is well established, if wide acceptance of this use may be taken as a criterion. But much remains to be learned of the efficiency and the basic factors affecting the efficiency of this use. Considerable study has been given to disinfection results at the Buffalo plant. Sedimentation and chlorination provide the degree of treatment required at Buffalo, and extensive research by Symons (1) showed that the maintenance of 0.1 p.p.m. residual chlorine after 15 minutes contact, when the total contact time is 30 to 45 minutes, accomplishes a 98.6 per cent kill on both coliform and total bacteria. Stream pollution studies show the coliform content of the Niagara River has been reduced by approximately 98 per cent since the inception of sewage treatment at Buffalo. As an example of the benefits accruing from research during 1941, the chlorine demand of the raw sewage increased 28 per cent over

* Presented at the Fourth Annual Meeting of the Federation of Sewage Works Associations, Chicago, Illinois, October 22, 1943.

what it had been for the previous two years. However, an average dosage increase of only 18.4 per cent was required because improved plant operation was brought about through laboratory study of dosage control.

Early studies regarding the effect of chlorine on B.O.D. reduction were made by Mohlman (2) and by Baity (3). Baity's comments warrant repetition. He wrote: "It now appears to have been demonstrated to the satisfaction of the most conservative and critical sanitarians that chlorine, when properly applied in proper amounts, may be depended upon to reduce the oxygen demand of the organic non-settleable constituents of sewage by an average of 25 to 30 per cent, as measured by the conventional B.O.D. determination on the unchlorinated and chlorinated waste. But what is the actual and practical effect of such treatment upon the receiving stream? After all, we treat such wastes to relieve conditions of pollution or contamination in the receiving body of water, and unless the use of chlorine effects an improvement commensurate with its cost and trouble, it is a vain and wasteful process." After detailed study of this treatment for an entire summer, the actual and practical effects were: An improvement in the physical appearance of the receiving stream, the control of odors, an increase of dissolved oxygen in the stream, reduction of stream B.O.D. and of bacterial counts.

The control of odors and the control of septicity by chlorination are closely related functions. Usually odors are considered undesirable because of their psychological effect upon people, and septic sewage is undesirable because of its profound effect upon biological treatment processes. These effects are usually difficult to measure. Perhaps no more convincing accomplishment can be cited than that described by Rawn (4): "It is difficult to conceive of a situation where the capacity of an activated sludge plant was increased fourfold by the simple expedient of up-sewer chlorination—nevertheless, such was the case at the Joint Disposal Plant of the Los Angeles Sanitation District some ten years ago. During the early years of operation of the District's system, sewage delivered through the warm, slow flowing sewers was black and septic with the solids finely comminuted. It was high in dissolved sulfides and low in good sedimentation qualities. Despite the fact that the quantity of sewage flowing into the plant did not exceed that for which the plant was designed, the activated sludge process was incapable of producing anything resembling a good effluent. By by-passing a portion of the load, and increasing the quantity by-passed until the plant was capable of handling the remainder, it became apparent that the condition of the incoming raw sewage was such as to reduce the plant capacity to one-fourth of that for which it was designed. Fortunately there was a means of correction at hand, in this instance, chlorination of the sewage at strategic points throughout the collection system and its maintenance in a fresh state while flowing to the plant. By this means the design capacity of the plant was restored at reasonable cost and without plant expansion."

Three well-established applications in thirty years does not appear

to be a high average. Other applications have been developed during this period. These include the use of chlorine for the control of activated sludge bulking, for the correction of trickling filter ponding, for the thickening of sludge, and for the removal of grease. Such applications of chlorination have proven to be thoroughly successful in some installations, of indifferent benefit in others, and useless or worse than useless in still others. Apparently that stage of chlorine utility has been reached in which further progress will depend upon the study of exactly how chlorine reacts in sewage and how to control its reactions. That is, certain principles not only must be recognized but must be applied in practice.

Biological processes of sewage treatment have been and are being given detailed study at individual treatment plants. As a result, many changes in practice have been adopted which improve the results accomplished by activated sludge, by trickling filters, and by still newer methods. In the same manner, the application of chlorine at individual plants warrants detailed study at those treatment plants because of its potential usefulness. Beyond its proven use as a means of killing pathogenic bacteria, its potential uses for the control of saprophytic bacteria, for reaction with organic matter, and for chemical oxidation, may make important contributions to plant operation. It must be kept clearly in mind that the process of sewage treatment is an integrated one, involving physical, chemical, and biological factors. Maximum efficiency is determined by no one of these factors alone but, rather, by each functioning in conjunction with the others.

A significant example is provided by the successful development of a process utilizing chlorine for the treatment of wool scouring waste, both to control a serious pollution load and to recover a valuable product. Chlorine was utilized for this purpose nearly twenty years ago, but never with entire success, despite the fact that it seemed the ideal chemical means for accomplishing such treatment. During the last two years, further study has been given to this application, at first with varying degrees of success. Only after detailed study was devoted to the physical, chemical, and biological characteristics of this waste, has it been possible to properly control the treatment. Once this was done, the process became a very simple one, requiring only that the wool scouring waste be treated fresh, and that calcium hypochlorite—chlorinated lime—be used instead of gaseous chlorine. Chlorine alone apparently reacts too vigorously with the protein matter but reacts in the desired manner when added as a chlorinated lime slurry. It may be of interest to mention that, after several months of pilot plant operation, this process is to be utilized at two woolen mills. One such treatment plant is in the design stage and one is under construction; the recovery of wool grease indicated at one mill is about one ton daily and, at the other, about two tons daily. The effluent produced will be fully acceptable from a pollution point of view, the process is odorless, and the recovered grease—at present prices—will return a profit on the plant installation and operation costs.

The special characteristics of chlorine have been applied to the treatment of other industrial wastes. For example, no suitable biological process was available for the handling of wastes containing cyanide compounds when such wastes created a new treatment problem. Chlorine is now used successfully as a chemical oxidizing agent to destroy cyanides in wastes from certain war industries. An experience has recently been cited in which the discharge of sulfur dye wastes increased the chlorine demand of a municipal sewage about five times over the normal demand. However, studies by the Connecticut State Water Commission have shown chlorine to be the cheapest and most satisfactory agent to treat this dye waste.

Perhaps the full possibilities of chlorination are not more widely and more successfully utilized because the process is regarded as such a simple one. It has been said that chlorination is not sufficiently dramatic. Usually no striking physical change is apparent when sewage is chlorinated, no impressive plant structures are required, nor do acres of aeration tanks or of trickling filters give visible evidence of the process.

But this may be misleading, for chlorination is not a simple process. Fortunately, to accomplish disinfection, some reduction of B.O.D. and the control of odors and septicity—it is necessary to determine only a sufficient dose and contact time. Yet there are other physical and chemical factors which must be taken into consideration if more specialized applications of chlorine are to be successfully and economically developed. Some of these factors, including the special reactions of certain organic and inorganic constituents of sewage and industrial waste have been pointed out in the sewage chlorination studies of Rudolfs (5).

There is another field, almost unexplored, which involves the application of chlorine in combination with other substances. Sufficient evidence has already appeared to indicate that the action of chlorine may be modified and controlled: (1) By applying it in conjunction with air, for more uniform distribution and more uniform reaction with organic matter; (2) by applying it as hypochlorous acid, after passage through limestone to remove the hydrochloric acid; (3) by applying it in mixture with lime, to provide an alkaline reaction instead of an acid one; (4) by applying it after reaction with iron or zinc, to limit its action upon organic matter. These are examples of chlorination control we already recognize and have used to a limited extent. There remain to be discovered many other combined uses suitable for special purposes.

Developments in chlorinating equipment have more than kept pace with chlorine applications. Chlorinators are now provided to feed gaseous chlorine, chlorine in solution, or hypochlorite solution. Such chlorinators operate by manual adjustment of dosage, by automatic adjustment of feed in proportion to volume of flow, by a program clock to maintain a different dosage rate at pre-selected intervals, and even by potential control which maintains a selected residual or sub-residual dosage corresponding to changes in both flow and chlorine demand of the sewage or waste.

At a time when physical and biological methods of sewage treatment are receiving more earnest and critical study than ever before, it appears that the potential uses of chlorine warrant the same study. Yet the two reports of the Federation Research Committee, published in the May and July issues of the *Journal* (6), include only six research projects involving chlorination out of a total list of 128 problems being investigated; and, actually, these involve study of only four different chlorination problems.

As newer and better methods of sewage treatment are developed and as the treatment of industrial wastes is more closely studied, chlorine still appears peculiarly suited for oxidizing, sterilizing, controlling odors, retarding the decomposition of protein matter, and coagulating, either alone or in combination with other chemicals. These characteristics should be utilized, among all other treatment means which engineers and operators have at their disposal. There is no better location to evaluate such applications on a given sewage or industrial waste than in the plant where that sewage or waste is treated.

REFERENCES

1. Symons, G. E., Velzy, C. R. and Johnson, J. W., "Third Year of Sewage Treatment Operation at Buffalo, N. Y." *Pub. Wks.*, 73, 1, 27 (1942).
2. Mohlman, F. W., Hurwitz, E. and Ruchhoft, C. C., "The Chlorination of Sewage and Effluents." *Proc. Eleventh Texas Water Works Short School*, January, 1929.
3. Baity, H. G., Merryfield, Fred and Uzzle, A. B., "Some Effects of Sewage Chlorination Upon the Receiving Stream." *This Journal*, 5, 429 (1933).
4. Rawn, A. M., "Sewage Flows and Composition Affecting Treatment." *This Journal*, 13, 66 (1941).
5. Rudolfs, Willem and Gehm, Harry W., "Sewage Chlorination Studies." *Bulletin 601*, New Jersey Agr. Expt. Station, March, 1936.
6. Committee Report, "Survey of Sewage Research Projects." *This Journal*, 15, 466 (1943), and 15, 702 (1943).

OPEN DISCUSSION OF PAPER BY HARRY A. FABER

Mr. H. A. Riedesel (Rockford, Ill.): Mr. Faber mentioned the treatment of wool scouring wastes. I would appreciate his discussing it more in detail.

Mr. Faber: There is not much more to be said. Treatment with chlorine gave erratic results and we found that the wastes had to be taken from the scouring train in a fresh state. If the waste was stale, bacterial changes took place which made treatment very difficult, but if the waste was received for treatment before septicity set in, a cracking resulted in the alkaline-chlorine solution much the same as when ferric chloride is applied to sewage sludge. There is a distinct separation of the solids from the liquid, the sludge collecting either at the bottom or on the top, leaving a clear yellow liquid having B.O.D. of about 50 p.p.m. This liquor imposes no appreciable load on the receiving stream or sewage treatment process.

The treatment is simple to control because of an immediate cracking

effect which results from the addition of calcium hypochlorite. Air is used mainly for mixing and the process simply consists of taking the fresh wool scouring waste, aerating it and adding calcium hypochlorite in such a dose that cracking takes place, with separation occurring in a few hours.

So far the method has been operated as a batch process. The clear liquid is drawn off and the sludge is treated with sulphuric acid to reduce the chlorine from the hypochlorite and to bring the pH to three or four. Then the sludge is filter-pressed and the grease removed.

Mr. C. D. McGuire (Columbus, Ohio): It seems to me that much can yet be done in the development of a sort of inhibitor to be used with chlorine, just as we use inhibitors with acids. We find so often that a much more selective action takes place. I would like to hear Mr. Faber's opinion about this.

Mr. Faber: I think that is exactly true and meant to stress the point that we have not studied the use of chlorine in an alkaline combination or with metals or, perhaps, many other substances that we have considered heretofore.

Mr. H. R. Shipman (Mankato, Minn.): Would the speaker enlarge upon the use of chlorine in the treatment of cyanide waste?

Mr. Faber: You will find several references in the literature regarding the practical breaking point of these wastes when treated by chlorination. The treatment consists merely of the addition of chlorine to the extent of the chlorine demand of the waste, and at that point the cyanide is completely decomposed. Nitrogen is released by the reaction.

Mr. H. L. Nelson (Washington, D. C.): A recent discussion in connection with chlorination as used in water treatment has brought out that there is a series of breaking points, rather than a single, clear breaking point. It seems that new and complex products are continuously produced as chlorine is added and that these products progressively break down. Does this also appear in the chlorination of sewage?

Mr. Faber: Yes, definitely. We know that many materials are easily oxidized with small doses of chlorine but that other substances may require not only higher dosages, but longer contact periods as well.

At the present stage of our knowledge, it does not appear that the employment of very high dosages of chlorine to reach such extreme breaking points in sewage will be economical. While the problem is purely a chemical one, the reaction does not take place nearly as quickly as we might wish.

Major Eliassen (U. S. Engineer Corps): In regard to the treatment of wool scouring wastes, have you had any comparative results on the effectiveness of aeration alone as against aeration plus chlorination? Did you not do some work along these lines with wool scouring wastes and domestic sewage at Rochelle, Illinois?

Mr. Faber: Yes, I made a study several years ago at Rochelle, Illinois, but it was an example, in my opinion, of poor research because we

were attempting to treat a waste which was highly variable in composition and rate of discharge. Satisfactory results by any treatment process depend, first of all, upon a uniform discharge of the waste, and in this particular installation we were confronted with very erratic conditions.

There are some limited data as to the removal by aeration alone and by aeration with chlorination, but the treatment was only moderately effective in this case because of the above condition. I believe that most industrial wastes should be treated in as concentrated form as possible rather than after dilution with domestic sewage. Such waste should preferably be treated at the source while fresh, and this was not done at Rochelle.

POSTWAR PLANNING IN SYRACUSE AND ONONDAGA COUNTY*

GLENN D. HOLMES

Consulting Engineer, Syracuse, N. Y.

Your reaction to Postwar Planning is perhaps like that of a great many others—"let's finish the war first." There are so many governmental agencies clamoring for lists of postwar projects we are becoming surfeited. The very name "postwar" causes a shudder and our hair to stand on end.

Our planning for Syracuse and Onondaga County is not a program to list or to make plans for all the conceivable projects which may be invented to make work or to give employment during the transition period which will follow the close of hostilities. If our program followed the stereotyped form with which you are all familiar, I would not be here to tell you about it. I am more certain I would not be contributing so much of my time and energy, with many others of our citizens, unless I believed it would be of benefit to our community and make our city a better and more enjoyable place in which to live.

Our city is a good place in which to live and make a home right now but like other wide-awake progressive cities, which have grown so rapidly, the development has not always been guided in the right direction.

Syracuse is advantageously located in the center of our State, near the center of Onondaga County and at the southern end of Onondaga Lake. Did you know that leading hotels of New York City acquired an enviable reputation by serving Onondaga Lake white fish? Their menus still carried Onondaga Lake white fish long after these fish had left for parts unknown.

Onondaga Lake and the lands for two miles "about it" was purchased by Sir William Johnson from the Indians in 1751. Industry started with the making of salt from nearby flowing springs. A grist mill, operated by water power, was built in 1805 and did a thriving business. When the old Erie Canal was completed in 1825 Syracuse salt was a most important cargo. The tolls collected for boating this salt went a long way toward paying the cost of the original canal.

At the time the New York Central Railroad was put through, about 1839, the merchants thought it too far from the center of the Village. The city was incorporated in 1847. It grew and prospered; the old canal has been filled and made a boulevard; the railroad has been moved from the center of the business district and elevated; no longer is Syracuse known as the town where the railroad runs through the streets but as the city of diversified manufacturing.

The story of Syracuse development is, of course, not greatly different from that of other American cities. Increases in population

* Paper presented at Spring Meeting of New York State Sewage Works Association, Rochester, N. Y., June 4–5, 1943.

continually brought new problems which required study and planning for the future. Pollution of the water courses necessitated intercepting sewers and sewage treatment; congestion of traffic required the widening of streets, the opening of new boulevards, and the elimination of grade crossings; gradual encroachment on the channels of the waterways by buildings was not appreciated until flood prevention became a real problem.

When the need for some unusual or large undertaking such as these, requiring special study and investigation, became urgent, a commission of perhaps 3 or 5 outstanding citizens has usually been appointed for the planning and execution of the work.

From its unpretentious beginning in the midst of a forest which was once considered a wilderness, Syracuse is now a city with more than 200,000 people. Its metropolitan area includes thriving villages and unincorporated communities with additional thousands of individuals who look to Syracuse for employment, the necessities of life, recreation and pleasure.

Buildings and homes like people grow old. There comes a time when property values depreciate. The owners who have accumulated sufficient means to acquire a modern residence move to a more desirable home in the suburbs or country. Income from rental of the old home declines until it is no longer sufficient to take care of upkeep and taxes. The old neighborhood becomes a liability rather than an asset and delinquent taxes are a serious problem. This is but one of many problems facing all of the older cities today.

We are living in an impatient age; the people complain and begrudge the time in getting to and from work, the movies, the airport or the golf links. The city is too congested, there is too much noise and confusion. Taxes are too high. What can be done about it?

Syracuse is the home of many large industries, working night and day in an "all out" effort to speed war production. Many factories are engaged exclusively in war work. Attractive wages have brought hundreds of men and women to the city. Some day the war will end. What can be done to prevent a repetition of the period that followed the first World War with its frantic scramble to find worthwhile public work?

The citizens of Onondaga County propose to find the answer to these questions right now, by inaugurating a Master Postwar Plan—the replanning of the metropolitan area.

The county and the city are so closely related in many ways that it is logical to include the whole community in this investigation. Both city and county have had their planning commissions for many years but in general their activities have been restricted in scope to particular problems for which funds have been allocated.

Our farsighted Mayor, Tom Kennedy, and the resourceful Director of the Syracuse Planning Commission, Sergei N. Grimm, must have burned gallons of midnight oil for they are responsible for putting an entirely new meaning into Postwar Planning. *Fortune* magazine

learned of these activities and sent an investigator to learn more particulars. As a result *Fortune* magazine and the *Architectural Forum*, both interested in the "Domestic Economy," are co-operating generously by furnishing several recognized expert planning consultants to give assistance and advice in developing the Master Plan. These magazines are more interested in postwar economic problems. Syracuse is more interested in the kind of a community we are to have in the future.

It is not the intention to make our city the largest or even the most prosperous in the country but the most livable. This means planning not only for the postwar period but for the far distant future as well.

The development of such a program requires the combined effort and the best talent available of planning experts, engineers, architects, statisticians, industrialists, business men, transportation executives, bankers, lawyers and all other public minded citizens.

To eventuate this objective, fifty men and women have been appointed to serve as the Syracuse-Onondaga Postwar Planning Council. Each member was chosen because of special knowledge or experience in some particular field which would be helpful in formulating the Master Plan.

The Council is resolved into three groups and with the assistance of public and private agencies, sub-committees and individuals is making an intensive investigation and study of all the ramifications of this undertaking.

The Research and Planning Group is concerned with the factfinding as related to the present situation of the community and its future needs.

The Ways and Means Group are delegated the task of solving financial and legal difficulties anticipated in consummation of the Master Plan.

The Public Participation Group is engaged in finding out what the community desires, what it needs and in stimulating interest by keeping the public informed on the progress being made.

Various agencies of the city and county are co-operating wholeheartedly in this work. The Chamber of Commerce is investigating the requirements of industry and commerce; the Council of Social Agencies is assembling information pertinent to community health, recreation and social delinquency; the City Planning Commission is making available a voluminous fund of data accumulated over years of study and research; the Syracuse Housing Authority will have a plan for rehabilitation and revitalization of the declining residential and mercantile areas; the County Park and Planning Board is engaged in the study of recreational facilities outside the city; the County Public Works Commission is developing tentative preliminary plans for flood control, drainage, water supply and sanitation throughout the county.

There is probably no one factor of greater influence on planning than population. How many people will reside in Onondaga County in the future and where will they live? Will present trends of growth or of

decline continue in different sections of the city, its suburbs and the villages, and for how long?

If these questions could be answered definitely and correctly, it would greatly simplify the problems of transportation, the widening of thoroughfares, the opening of new streets and highways. The most advantageous sites could be selected to best serve the future with new schools, fire stations, public buildings, parks and playgrounds. Plans for water supply, sewers, sewage treatment, garbage and rubbish collection and disposal as well as many others are dependent on the number of persons requiring service within a prescribed area.

Population statistics and related data are being assembled and made available to all groups by Prof. W. C. Lehman of Syracuse University who for many years has made this study a hobby. Duplication of effort by different groups is thus avoided, and more harmonious planning is assured.

The nature of the subsoil and the elevation of the ground water table is another subject of particular importance in planning structures where rock may be found not far from the surface on one side of a street and quicksand on the other. The abutments of the railroad bridge spanning Onondaga Creek, near the lake front, is supported on piles 220 feet long. Test piles driven to a depth of 120 feet for the Harbor Brook sewer floated the following day. Dr. E. T. Apfel, Geologist of Syracuse University, has completed a comprehensive survey of subsoil conditions, which will be of great value in all foundation problems.

You will observe that much of the work outlined is concerned with long range planning rather than for the immediate future.

One great difficulty at present is to obtain competent designers and draftsmen to prepare drawings. There are none to be found among the unemployed at present.

The program of the Council does not include the making of detail drawings and specifications for construction. This is the province of municipal departments, consulting engineers and architects. The Master Plan will initiate hundreds of construction jobs. These will be graded according to community needs and the ability to carry out. The Temporary State Commission, Postwar Public Works Planning, as an inducement to have plans and specifications completed and ready for awarding contracts, will pay half of the cost for such work. Application to the State Commission for such assistance has already been made for several of the projects included in the Master Plan.

In closing let me quote from a recent statement by our Mayor.

"Three important things must be kept in mind:

"First—That the initial concern of our country be to win the war.

"Second—That postwar planning be kept within the bounds of common sense.

"Third—That what is planned shall be within our means."

Sewage Research

A CRITICAL REVIEW OF THE LITERATURE OF 1943 ON SEWAGE AND WASTE TREATMENT AND STREAM POLLUTION

By Willem Rudolfs, *Chairman*, H. E. Babbitt, G. P. Edwards, H. A. Faber, A. J. Fischer, H. W. Gehm, A. L. Genter, H. Heukelekian, H. J. Miles, F. W. Mohlman, C. C. Ruchhoft, L. R. Setter, L. W. Van Kleeck

Committee on Research, Section A, Federation of Sewage Works Associations

The 1943 review of literature published on sewage and waste treatment reflects more accurately war conditions and war activities than any previous review. Last year the war activities were dominated by construction of new treatment plants, whereas now operation of plants is more in evidence.

In spite of the war activities the volume of printed matter pertaining to research, operators and developments is surprisingly large. Especially, since technical literature from foreign countries remained greatly curtailed. There is evidence that a considerable amount of research has been and is being performed in Russia, especially in connection with industrial waste treatment, such as sugar, dye, paper, pickling liquor, mine water, phenols, acids, and including disinfection and new methods. Unfortunately, few of the original publications and reports appear to be available in this country and the abstracts published contain insufficient detailed data to be of material value or allow judgment in regard to the importance of the work. It is hoped that some exchange arrangement may be made similar to that in force some years ago with the Moscow sewage experimental station.

The effect of war production plants discharging large quantities of more or less concentrated wastes has been a factor in stream pollution and operation of sewage treatment plants. Several surveys and studies published appear to indicate specific war-time wastes caused by explosives, alcohol and chemicals to be of greatest importance, while expansion of industry caused by war-time conditions are of importance to a lesser degree. Wastes produced by new products, including synthetic rubber and dehydrated foods are not a large problem for the country at large, but of some significance locally.

The revival of modified submerged contact aerators, with the construction of a considerable number of plants at military establishments, has brought to the fore the degree of purification accomplished, the difficulties in operation and cost. It appears that in this case again appli-

cation outstripped basic knowledge, resulting in some confusion and difficulties.

Considerable information relating to various types of trickling filters was published. Although much of the material is valuable, no new principles were disclosed. Some pertinent information pertaining to high-rate filters has added to the still scant basic knowledge available. Much more is needed to evaluate accurately this type of filter in relation to various other oxidation devices.

Knowledge pertaining to the activated sludge process is gradually accumulating. Increased knowledge appears to lead to re-examination of the basic principles involved. Partial activation, with the return of various quantities of sludge and reduced quantities of air to produce clarification and partial oxidation has been under study and has been applied for several years, particularly abroad. Earlier laboratory and pilot plant experiments at Philadelphia, Amsterdam, and several other places led to new designs and seemed to point the way to effective and comparatively inexpensive treatment. Newer experiments along these lines, conducted in New York, appear to be of particular interest for the future.

Little new basic information regarding sludge digestion, which is still the heart of the sewage treatment problem at many places, has been published. Although a dozen problems were under study, according to the survey of research problems published in the May and July, 1943, issues of the *Journal*, peculiarly, no fundamental work was suggested. Some of the problems under study undoubtedly will add materially to our present knowledge. However, the question arises whether it is perhaps time to compile, examine and restudy the available information as a basis for further study.

Utilization of sludge for agricultural purposes, particularly for victory gardens, was widely discussed. Opinions on the use of sludge for such purposes have been crystallized and do not vary greatly from previous ideas. Economic factors and psychological reasons will continue to dominate the use of this by-product.

Chlorination, which is used more in this country than anywhere else, still presents a number of problems. It appears that research on potential uses of chlorine has not kept pace with studies pertaining to physical and biological methods. This valuable adjunct of treatment warrants additional fundamental study.

Although circumstantial evidence seemed to point to a relation between poliomyelitis and pollution, the trend of the argument is now definite that naturally the virus should be found in sewage, but that it cannot be considered a water-borne disease. This deduction is mainly made from epidemiological knowledge. The whole question should not be over emphasized, but still bears watching. It is very doubtful that plant research can add materially to increased knowledge.

Abatement and control of stream pollution has been complicated and accentuated by the war and war industries. In some sections of the United States pollution control and abatement has decreased, whereas

in other sections a determined effort is being made to maintain prewar standards or increase abatement of pollution. In general, it appears that stream pollution has increased materially, primarily on account of increased industrial activities. In England the Central Advisory Water Committee considered the existing system of river pollution control generally inadequate and even sometimes wasteful. The creation of 29 new river boards to supersede existing authorities has resulted in considerable discussion. It seems that it is generally accepted that the drainage area is the best unit for river control. There is still a good deal of conflicting opinion in the United States regarding the best method of control. It seems that we are drifting into the possibility of some method of supervision, shared by Federal and State agencies, but no specific, uniform system, agreeable to all, has been developed or proposed.

Postwar planning has been succinctly expressed by "Blue Print Now." The blueprinting is thought of primarily in the sense of postwar construction. Construction is, however, only one phase of the entire problem. Both the legal phase and research form an integral part of postwar planning. It is only natural that these phases are lagging behind.

The annual review presented is not a complete enumeration of all papers published, but a more or less critical examination of the progress of the science and art. New processes rarely come to the surface spontaneously; a gradual development of new methods and a slow evaluation, based upon fundamental studies, is more logical. The review indicates a continued advancement in theory and practice, possibly leading to definite new developments.

GENERAL

(See also Stream Pollution section)

Disease.—Maxcy (165) and Maxcy and Howe (166) in reviews of the available evidence regarding the dissemination of poliomyelitis virus came to the conclusion that at present the evidence is insufficient to justify the belief that water or sewage is a medium of any practical importance. It is true that the virus has been isolated on several occasions from sewage but it does not seem to survive very long in this medium. The disease does not behave like a water-borne disease and the incidence is not correlated with the quality of water supplies.

The recovery of antibacterial substances obtained from soil organisms has been duplicated by Carlson and McKhann (42) by the isolation of an active principle from activated sludge antagonistic to *Staphylococcus aureus*, *E. coli* and especially to poliomyelitis virus. The substance could only be recovered from activated sludge which had been allowed to digest anaerobically for some time. It is to be expected that with further search, other active antibacterial substances and bacteria capable of producing bactericidal substances might be isolated from sewage treatment processes. The failure of intestinal and pathogenic

organisms to survive in polluted waters might be attributed to the presence of such substances.

Littman (154) described a rapid method for the isolation and identification of enteric pathogenic organisms from feces with the use of standard media. Monteverde and Ferramola (178) isolated bacteria belonging to the genus of Salmonella from Buenos Aires sewage.

Gordon (87) found viable cysts of intestinal protozoa such as Entamoeba in Moscow sewage as well as in effluents from the treatment plant. Standing for periods up to 6½ hours with and without $FeCl_3$ coagulation failed to eliminate all of the cysts. Exposure to concentrations of chlorine up to 12.7 p.p.m. for 30 minutes had no effect upon the cysts of *E. histolytica* (see also Cram references).

Bacteria.—Electron microscope examinations of bacterial cells have revealed according to Mudd (183), structural changes as a result of the action of germicidal agents dependent upon the penetration of the heavy metal ions or molecules into the cell and the interaction with the protoplasm resulting in the coagulation or escape of the protoplasm from the cell.

Zobell and Grant (275) have found that a medium containing only 0.1 p.p.m. glucose or peptone permits the growth of bacteria. This is a lower limiting concentration than reported before. The rate of multiplication and oxygen consumption in solutions containing less than 10 p.p.m. glucose and peptone is directly proportional to the concentration of the substrate. Sixty to seventy per cent of the organic substrate is oxidized and the balance is converted into bacterial protoplasm. Zobell (274) discussed the role of solid surfaces upon bacterial activity. He states that small quantities of organic matter are adsorbed from the water in dilute nutrient solutions containing less than 10 p.p.m. organic matter. The solid surfaces also provide a resting place for bacteria and may retard the diffusion of enzymes and hydrobyzates away from the cell thereby enhancing bacterial activity. The degree of roughness does not influence the attachment of bacteria but the solid surface must be distributed throughout the dilute solution to be most effective.

Grant and Zobell (90) have further demonstrated the ability of certain bacteria to oxidize hydrocarbons such as crude oil, petroleum ether, kerosene, gasoline and toluene. The concentration of the hydrocarbons used was 0.66 ml. per liter. The method of demonstration of the utilization of the hydrocarbons was by the measurement of oxygen utilization. The oxidation of other hydrocarbons such as paraffin wax, paraffin oil, vaseline, benzene, xylene, n-hexane, pyridine and naphthalene was also demonstrated. In general, aliphatic hydrocarbons are attacked more readily than cyclic or aromatic compounds and long-chains are more susceptible to bacterial oxidation than hydrocarbons of small molecular weight.

Wattie (254) states that zoogleal bacteria isolated from activated sludge and trickling filters might be considered in one group because of their similar cultural and biochemical characteristics. The floc-forming organisms isolated from trickling filters develop, under aeration, an acti-

vated sludge functionally similar to the floc-forming organisms isolated from activated sludge.

Corrosion of Pipes.—Soil corrosion of metallic iron through the activity of anaerobic sulfate-reducing bacteria was discussed by Starkey and Wight (235). Location of corrosive areas by the determination of oxidation-reduction potentials of the soil was attempted. The results indicate that highly reducing soil conditions can be detected from redox potential measurements. Since the development of sulfate-reducing bacteria and subsequent corrosion is associated with reducing conditions, such detection is of good diagnostic value. Good correlation between soil corrosiveness and degree of reduction of the soil was obtained.

Bunker (36) also subscribes and confirms to the theory advanced by Wolzogen Kühr on the role played by sulfate-reducing bacteria in the anaerobic corrosion of pipes in clay soils and discusses the effectiveness of a number of preventive measures such as pipe coatings, impregnated wrappings, cathodic protection, etc. He is doubtful of the value of the oxidation-reduction measurements as suggested by Starkey and Wight in locating corrosive areas.

Fertility Value.—Jenkins and Lockett (121) called attention to the loss of phosphorus in the effluent from sewage treatment plants. At Coleshill Sewage Works of the Birmingham Drainage Board, the total phosphorus in sewage is equal to 1.3 gm. of P per capita per day. The purified sewage contains 54 per cent of the P in the crude sewage. At Mogden (Middlesex Main Drainage Works) the crude sewage contains 1.56 gm. P per capita per day and the treated effluent 40 per cent of the amount present in the crude sewage.

Yushok and Bear (271), in discussing methods of preservation, deodorization and disinfection of poultry manure, state that whereas untreated manure lost a large percentage of its nitrogen as ammonia during storage, the addition of hydrated lime not only deodorized it but also reduced the losses of nitrogen. It also effectively killed most of the pathogenic bacteria in the manure.

Hazards.—The death of the three men from asphyxiation due to sludge gas from sludge flowing into a basement, reported by Brandt (32), brings forth once again the ever-present danger of sewer gas and the lack of adequate protection. As a method of reviving asphyxiation cases, Henderson (101) states emphatically that the pulmotor or "resuscitator" in which mechanical respiration by suck and blow method is used, is worse than useless and has been responsible for many deaths which might otherwise have been prevented. The fault with the device lies in the fact that the breathing induced by it is discordant and out of step with the patient's breathing and occasionally lung injury and hemorrhage is caused by mechanical damage done by the apparatus.

Sewer Ventilation.—Smith (226) discusses the experiences with forced sewer ventilation as a protection against sewer deterioration in Los Angeles. The section of North Outfall ventilated covered a length of six miles. The equipment consisted of a sawdust type blower which delivered 22,000 cubic feet of air per minute. The air was admitted

through the manhole covers covering a distance of three miles. Ventilation caused the disappearance of the wet, stringy substance composed of sulfides covering the sides of the sewer. The tile became dry and cement joints which formerly had been the consistency of soft putty dried and hardened. The exhausted air had a humidity of 100 per cent and hydrogen sulfide content of 16 p.p.m. A permanent station has been nearly completed on the basis of the earlier experimental work.

ANALYTICAL PROCEDURES

The approximate determination of dissolved oxygen by the amidol method has undergone a marked improvement by the spectrophotelometric measurements according to Ellis and Ellis (64). The red component of colors formed by amidol appeared proportional to the dissolved oxygen. The use of a spectrophotelometer set at 4,900 A.U. or a photelometer with a light filter which transmits primarily in the 4,900 to 6,000 A.U. zone was found desirable. The method was accurate to 0.1 p.p.m. in the range 0.2 to 2.5 p.p.m. and was effective up to 5.0 p.p.m. With provision to compensate for turbidities, the method should prove rapid and reliable.

The Massachusetts Department of Public Health (163), Elliassen and Schulhoff (63), Gehm (77) and others report control studies on the determination of grease in sewage or sludge. The status of grease determinations remains unchanged from that of the 1941 review of literature, except for the radical departure of extraction procedure reported by Gehm. In the latter case, the dewatered, dried, and weighed solids sample is extracted with hot mineral oil, filtered through a tared gooch, the residue washed with petrolic ether. After drying, the residue is weighed. The loss of weight yields a fair approximation of the amount of grease.

Mathis (164) satisfactorily substituted a clinical centrifuge for separating solids from the sample instead of vacuum filtration, in determining sewage influent and effluent suspended solids.

A new procedure was described by Klein (139) involving the use of ceric sulfate instead of $KMnO_4$ or dichromic acid for the oxygen consumed test of the strength of sewage. The ceric sulfate gave oxygen consumed values two-thirds that given by the dichromate test and two to three times that given by the permanganate test.

SEDIMENTATION

Giles (83) describes various types of inlet and outlet designs for rectangular tanks and concludes that the inlet devised by Hubbell (*this Journal*, July, 1934) is to be preferred. He also recommends the use of sloping walls at inlet and outlet ends of tanks instead of the usual vertical type. Rostenbach and Waterman (198) conducted tests on two circular clarifiers to determine the effect of curved distribution vanes attached to the curved baffle around the central feed pipe of one of the tanks. Otherwise the clarifiers were identical. They found that the baffles had no effect on the efficiency of suspended solids removal.

Escritt (65) reviews English practice in the design of sedimentation tanks and describes the design of a constant velocity detritus channel, parabolic in cross-section, controlled by a standing wave flume.

Dobbins (56) presents the results of studies to extend the theory of the effect of turbulent flow on the vertical distribution of suspended matter in streams or settling basins under conditions when the suspended matter is in equilibrium conditions. He derived further evidence of the validity of the logarithmic law for the vertical distribution of sediment at the equilibrium condition. Other things being equal, equilibrium concentrations depend upon the amount of material available at the bottom up to the point of saturation. When the bottom is saturated with a given material, the equilibrium concentrations depend upon the hydraulic conditions of the bed. The equilibrium concentration above the bed is independent of the depth of fluid provided that the bottom is saturated.

Camp (40) proposed a method for estimating the effect of turbulence in retarding settling in open channel flows based on Dobbin's work.

Camp (41) presented a basis of a method of design of settling tanks where the mean velocity gradient G the tank will have the optimum value for the settling of a particular suspension. With regard to flocculation, the speed of flocculation is proportional to the velocity gradient at a point. In mixing chambers equipped with mechanical stirring the speed of flocculation may be controlled by the speed of the paddles independently of the discharge rate, provided that the inlet velocity is very low.

Wallace and Habermehl (252), reporting on two years of operation of the Detroit plant, showed 47.5 per cent suspended solids removal and 38.9 per cent B.O.D. removal with an average detention time of 1.5 hours, from original and suspended solids content in the sewage of 232 p.p.m. and B.O.D. of 132 p.p.m. Part of the high B.O.D. removal is attributed to chlorine application. The operation of sludge scraping mechanism is continuous.

CHEMICAL AND MECHANICAL TREATMENT

Hyde and Rawn (118) in reviewing sewage treatment advances in America point out that despite few new installations of this type, interest in chemical treatment is still alive. This fact is evidenced both by the variety of papers and patents appearing in the recent literature and the number of research projects underway relating to it. An enumeration of the latter is found in a report by Rudolfs, et al. (202). Upon the fruition of such research depends the future of this method of treating sewage.

Extensive effort toward the improvement of processes employing lime continues. The approach has been toward providing a more thorough knowledge of this chemical and its function in sewage treatment. Although not concerned specifically with sewage treatment, a monograph by McAllister (167), dealing with the physical character of limes in respect to their applications, contains information of basic value.

The effect of production practice on settling characteristics, particle size, area and crystalline structure and electrostatic properties were studied. The conclusion derived was that the physical properties of lime can be controlled to an appreciable degree by the technique of manufacture. As a result of such research lime may in the future be "tailor made" to provide the characteristics best suited to a particular application such as sewage treatment.

Investigations by Rudolfs and Maggio (206) give a picture as to what physical qualities of a high calcium lime determine its effectiveness for sewage treatment. These authors state that with smaller particle sizes, clarification of sewage increases materially and lime having crystalline particle structure reacts more quickly in regard to pH adjustment as it is more soluble than amorphous types. They also conclude that the effectiveness of lime in reducing the coagulant demand of sewage is not merely a question of pH adjustment but that lime itself is an effective clarifying agent when properly applied.

Rudolfs and Nickol (208) studied the application of lime to sewage clarification and concluded that high calcium hydrate was the kind best suited. Lime in solution gave the best results in both pH control and clarification, a ten per cent slurry next best, and dry lime the poorest. Results approximately equal to those obtainable with lime solution were produced by adding dry lime to a portion of the sewage to be treated, stirring and adding this volume to the remaining sewage.

Burr (38), in discussing uses of ferric sulfate in sewage treatment, points out the odor controlling ability of this chemical and its apparent effect in increasing bacterial decomposition in sludge digestion and aerobic processes of sewage treatment when employed for treating the sewage.

Experiments of as yet purely academic interest are reported by Hansen and Gotaas (98) involving the clarification of sewage by flotation produced by surface active agents. A heterpolar laural amine hydrochloride of strong frothing and collecting properties was employed for most of the work. B.O.D. removals in the range of 85 per cent were obtained, when optimum dosages (60 p.p.m.) of the chemical were applied, on about 15 minutes aeration. The collected froth coalesced into clear liquid and sludge layers, and return of the former to untreated sewage reduced the dosage of chemical required from 20 to 25 per cent. The sludge obtained from this treatment digested readily despite the fact that the chemical was bactericidal to sewage. The reagent employed is, at present, too costly to consider practical application.

Operational reports brought out several new situations in which chemical treatment provided overload relief and added plant capacity in extraordinary circumstances. Leist (9) describes one such condition at Circleville, Ohio, where low sewage flows are treated by mechanical flocculation and sedimentation and chemical treatment is employed to keep plant performance at the same level during periods of high flow. The use of chemical treatment prior to the activated sludge process to

relieve the latter of overload due to cannery and creamery wastes at Celina, Ohio, is described by Uhlmann (245). Average results of two years operation, treating a sewage with a B.O.D. of 636 p.p.m., showed reductions of 49 per cent by lime-iron salt treatment and 96 per cent by combined chemical and activated sludge treatment. Difficulties resulting from fluctuations in the character and strength of sewage on account of batch waste discharges were numerous, and skilful supervision and control was required. It is interesting to note that chemicals were employed only when discharge of industrial waste was received or expected, thus holding the chemical cost down to an annual figure of $4.35 per m.g. passing through the plant.

McKeeman (169) reports that at Freeport, L. I., increased population overloaded the sewage treatment plant by more than fifty per cent. Application of chemical treatment, after only minor changes and additions to the units, produced a satisfactory effluent by the existing plant.

Chronic bulking in a mechanically aerated activated sludge plant in England led Edmondson and Goodrich (60) to perform considerable laboratory and plant experimentation with chemical treatment in an effort to find a means of alleviating the condition. Of particular interest was the inclusion in the plant trials of chemical feed to the aerators. Alum applied in this manner helped for a short time but did not produce lasting results. Chemical treatment applied in the pre-sedimentation unit to reduce the B.O.D. of the sewage reaching the aerators was best accomplished with alum or sulfuric acid and alum. Such treatment of the highly comminuted sewage averaging daily as high as 841 p.p.m. B.O.D. proved too costly and erratic so that other means were employed to relieve the bulking. Failure of chemical treatment to provide economical pretreatment was probably due either to the character of the sewage or the lack of proper chemical feeding, mixing and flocculating equipment.

New Brunswick, New Jersey (8) extended the capacity of a plant designed to handle 9 m.g.d. to 13.5 m.g.d. capacity by providing additional chemical feeding equipment and changing piping, gates and wiers. The increased capacity was necessary due to expansions in population and industry resulting from the war and had to be provided without construction of additional plant units.

Eight recent patents related to chemical treatment were found in the literature, most of these relating to details concerning the application of well-known coagulating agents. One really new coagulant is described by Slagle (224). This is a basic alum of the emperical formula $Al_2Cl_2 \cdot (OH)_2SO_4$ and is produced by treating an alum solution with calcium chloride and soda ash. Rapid floc formation in sewage at dosages lower than those required with alum is claimed for this chemical. Patents relating to the use of iron, manganese and cobalt bearing coagulants were issued to Jung (128), Jung and Schröder (129), Schneider (215) and Brintzinger (35). Nothing particularly novel was expounded in these patents nor in one issued to Henry (103) pertaining to the use of suspensions of lime containing coke dust, clay, soot or ash.

Coleman (48) patented a process utilizing ferric chloride together with an insoluble phosphate as a coagulant for which he claims acceleration of settling and production of a readily filterable sludge. Daily (51) obtained a patent covering the use of ozonated air for clarifying sewage.

Fischer (70) (71), experimenting in both laboratory and plant, demonstrated that removal of suspended solids by vacuator treatment could be raised to over 90 per cent by the use of ferric chloride.

The use of mechanical flocculation without the aid of chemicals to help solve San Diego's sewage problem is described by Phelps (189). Three 100-foot diameter clariflocculators were included in the plant design. Rudgal (200) points to high removals of suspended solids at Kenosha, Wisconsin, effected by flocculator treatment of sewage containing metallic trade wastes.

GREASE REMOVAL

Sufficient attention has been given grease removal in the past year to record here literature pertaining to it. Fales and Greeley (68) summarized the knowledge up to 1941 in creditable manner in a monograph on this subject.

Fischer (70) (71) presented two papers describing a process consisting of aerating sewage in a manner resulting in dispersion of fine bubbles of air in the sewage followed by reducing the atmospheric pressure above the sewage and resulting in rapid flotation of free grease and settleable solids. This process is known as "vacuation" and was shown to be capable of removing a considerable percentage of sewage solids and most of the free grease at extremely high overflow rates. Plant and laboratory experiments are presented dealing with the basic requirements and characteristics involved in the operation of the process and design of equipment employed is illustrated.

TRICKLING FILTERS

During 1943 considerable information was published relating to various types of trickling filters from the standpoints of general principles, evaluation, operation, design, and experimentation. Although much of this material is of value to the designing engineer, plant operator and research engineer, nothing involving new principles has been disclosed. As W. Watson states (155): "The present tendency seems to be the investigation of combinations of well-tried older methods." Due to war conditions, some of the interesting material published abroad prior to 1943 has not become available for an earlier review.

General.—In a clear and instructive manner, Lovett (155) shows what happens when microorganisms are provided with a suitable "anchorage" in purifying settled sewage by the various modern methods of contact treatment. The initial anchorage for the effective biological slime varies from that artificially provided in trickling filters, intermittent sand filtration, and contact aerators to that originating in the suspended solids of the sewage itself in the activated sludge process, where the active surfaces become more concentrated in the sludge floc.

The various processes are classified according to the size of the material providing the anchorage, and the broad types and particular developments of the processes are described by Lovett and discussed by various authorities. Considerable attention is devoted to all practical types of trickling filters. Such filters are regarded as better suited to partial high-rate treatment and are more shock-proof than the activated sludge process. At best, simple high-rate filtration is to be regarded as a useful partial treatment process. Even in this case, uniform dosing is of prime importance. Double filtration, alternating, and with recirculation of the effluent will deal with double the amount of sewage per cubic yard of medium daily of that which can be dealt with in any single filtration and the results will be better.

In the light of the foregoing, several critical comparisons of a general nature by Goldthorpe (85), Walton (253), and Greeley (93), deserve study. By taking for his subject a cubic yard of percolating bed material and examining it in the light of numerous experimental results in England and this country, Goldthorpe (85) states that the surface action between rivulets of trickling sewage, air, and percolating bed area with its countless members of a vast bacteriological community results in many physical, chemical and biological changes. The final result is a coagulation and oxidation of the suspended matters and oxidation and precipitation of matters in solution. In high-rate filtration the main effect is coagulation which corresponds to the action taking place in the upper layers of a normal filter where the instantaneous dosing rate is high.

Several tables are presented showing data on various experimental factors; *e.g.*, variety of filter media, percentage voids, distribution, time of contact, and oxygen demand of suspended solids in both trickling filters and activated sludge. From the close agreement between the last two items Goldthorpe concludes that the biological slime on filter media appears to be similar to the floes of activated sludge. In the former case, water trickles through a suspension of floes in air and in the activated sludge plant, air bubbles through a suspension of floes in water.

This paper was discussed by various English authorities. On the basis of experimental work done in England and this country, Lovett cited different answers to the question of optimum filter depth, that is, whether or not a cubic foot of filter media would do the same work in either a shallow (4 to 6 feet) or deep filter (10 feet). Those interested in this important question should read the comments made by Hamlin. Other points discussed relative to the Goldthorpe reference were effect of size of filter media on ponding and purification, slime growth, relation between time of contact and purification, area of air-liquid surface in a filter and activated sludge, frequency and amount of dosage.

Under the direction of the Board of State Health Commissioners Upper Mississippi River Basin Sanitation Agreement, a thoroughly instructive report on high-rate trickling filter performance has been arranged and edited by Walton (253). Warrick states that the objective

of the study has been to answer as many questions as possible concerning operation efficiencies to be expected under the various conditions met in actual practice and to set forth a reasonable basis for design of high-rate filters. This report contains an elaborate digest of test survey data and information on the performance of nine different plants in four different states. Some of these plants treat domestic sewage containing appreciable amounts of waste from dairy products, corn canneries, packing houses, and poultry produce. Some of the biological factors involved are presented by Wilson.

The report shows that recirculation definitely increases the reduction in total suspended solids and B.O.D. over that obtained by single stage treatment. The dependence of results obtained on uniform distribution of dose are measured and evaluated in a novel manner. Furthermore, recirculation through the primary clarifier is found advantageous to the clarification process only if the recirculated liquor contains sufficient solids to materially increase the concentration in the primary tank. All B.O.D. reductions are coordinated with dosage rates expressed in gallons per square foot of filter media daily. Some engineers may disagree with this method of expressing such rates. However, Lovett in the foregoing citation aptly states:

"The dose expressed as gallons per cubic yard per day gives no indication of the magnitude of the dose applied to the surface of the filter, which is coming to be regarded as a factor of great importance. For this reason, doses are sometimes given in terms of daily volume of sewage applied to a unit area. . . . An analogous rating to gallons per cubic yard per day widely used in America is million gallons per acre-foot per day."

By means of a broad analytical framework Greeley (93) presents a general critical comparison of the various methods of current biological treatment, including standard and high-rate trickling filters, activated sludge, and the Hays process of contact aeration. He defines current high-rate terms, briefly describes typical plants, and on the basis of reliable available operating data sets forth a logical illustrative procedure for comparing the different ratings of various types of high-rate treatment.

In computations for the performance of typical high-rate aeration plants the percentage removal of B.O.D. by aeration and final tanks is related to pounds of B.O.D. applied per 1,000 cubic feet of aeration tank. In such computations for trickling filters the percentage B.O.D. removal is related to the loading on filters in pounds B.O.D. per acre-foot per day. Possibilities for further studies and analytical factors are also indicated. As to the possible effect of temperature of applied sewage on trickling filter purification, he realizes the data submitted are at present not sufficient to include such a factor in a close appraisal. That the effect of seasonal temperature changes does have a definite influence on loading rates and filter bed depth is evident from the experimental work done at Baltimore by Keefer and Kratz (133) and at Johannesburg, S. A., by Wilson and Hamlin (260). Both of these studies were reviewed by this Committee in 1941. Furthermore, in a more recent report, Hamlin (97) emphasizes the possible influence of atmos-

pheric humidity and evaporation on the temperature and depth of open trickling filters and criticizes comparisons made between plants in different geographic regions without regard to this factor.

Dixon discusses Greeley's paper from the practical considerations of the Army's point of view. Compared to ordinary municipal treatment plants, Army post sewage is not only stronger but the sudden variations between minimum and peak loads offer a much greater shock to any high-rate treatment plant. Based on Army experiences, the quality of high-rate filter plant effluents is more variable in character than that produced by standard filters. Based on records at the Dallas municipal plant and a few Army camps Dixon, shows that experience does not always bear out the contention that unfavorable operating conditions, like ponding, are encountered in the range between high and standard rate loadings. Army experience with high-rate filters also indicates that satisfactory treatment, in terms of B.O.D., can be obtained if the loadings and/or recirculation ratios are correctly maintained. Operating filters in series as at Fargo, N. D., shows that it becomes progressively harder to remove the B.O.D. fractions left from previous stages. The import of these last two statements is brought out in the Lovett reference already cited.

Operation.—Vokes and Jenkins (251) show the effect of acid trade waste on bacterial beds of the Yardley sewage disposal works before and after enlargement of the works and employment of bioflocculation at high rates of flow. The Engineering and Contract Record (10) presents data relating to over 200 biofiltration plants in use at municipal and military installations in the United States and Canada. From the information presented it is possible to draw conclusions regarding the design of biofiltration plants for varying conditions. Nelson (184) also presents a general explanation and description of single and two-stage biofiltration systems with the number and sizes of plants in operation and the overall reduction in B.O.D.

There were several interesting reports on operational and processing problems. Eldridge (61) describes the operation of a 154 square feet recirculating filter constructed of silo tile with a holding and settling tank treating slaughter house wastes. The overall B.O.D. removal through the filter was 92 to 97.6 per cent and through the entire plant was 96.6 to 99.2 per cent. Barton (27) presents a comparison between the merits of activated sludge and bioflocculation at Findlay, Ohio. Activated sludge decreased the cost of removal on a B.O.D. basis but increased the cost of treatment and amount of sludge to be digested by increasing the percentage of water in the sludge.

The story of various changes necessary to increase the B.O.D. reduction from 78 to 90 per cent through the filters at Corpus Christi, Texas, is related by Allison (3). Howson (112) also presents an account of solving some operational troubles and plant difficulties in operating low-rate trickling filters at Westfield, N. Y., where industrial waste from fruit processing adds to the plant B.O.D. load and excessive infiltration increases the liquid load. For another locality, Cokato, Minn., King

(136) shows the solution of a problem of treating sewage from 1,400 population and a large volume of corn canning wastes. During the canning season the wastes are lagooned adjacent to the domestic sewage treatment plant and continuously recirculated back to the lagoon through a high-rate filter equipped with tile media. The partially purified waste in the lagoon then received further treatment in the village disposal plant.

The solution of the problem of reclaiming and rehabilitating trickling filter beds at Elgin, Illinois, is presented by Johnson (123). At this plant the dolomitic stone installed disintegrated rapidly in the top zone of the beds and caused pooling.

Military Installations.—Reid (194) describes the trickling filter design adopted for the R.C.A.F. which combines the merits of the biofilter and aerofilter and is capable of having the efficiency increased by forced ventilation or by regulation of recirculation. McLellan (172) shows that the engineers of the R.C.A.F. recommend high-rate and biofilters in designs for air-training camps of over 2,000 population in Western Canada. Hatch (99) presents some design factors for low and high-rate trickling filters for military installations in the United States.

There were some interesting reports on specific problems at three different army cantonments. Jessup (122) describes how two-stage biofiltration helps provide a high degree of treatment where the plant effluent discharges near wells from which the army camp water supply is drawn. By using symmetrically installed, identical units with manifolded pumps the installation provides material flexibility. Franks (74) briefly reports on the comparison of design and actual loadings of biofilters in an army post. Porter (192) relates how a biofiltration plant at an army camp for 30,000 was put into partial use several months before the plant was completed. Due to the flatness of the plant site, shallow, high-rate trickling filters with progressive recirculation were installed.

Research.—Tomlinson (243) describes and shows several figures of some of the fungi which occur in experimental filters treating sewage by single and alternating double filtration. The fungi belong to the genera *Fusarium, Oospora, Phoma,* and *Sepedonium.* An interesting experiment is described in which glass slides were placed on the surface of one of the alternating double filters in the presence and absence of light. *Fusarium* was the dominant fungus grown in the light, while *Oospora* predominated in the dark. In studying the decomposition of fungus mycelium a bacterium was isolated which decomposed the starved mycelium of *Sepedonium.*

Goldthorpe and Nixon (86) describe high-rate and double filtration experiments undertaken at Huddersfield, England, to improve plant results which deteriorated as a result of increased toxicity and the heavy chemical nature of the sewage since the commencement of the war. Two-stage dosing of settled sewage in a primary and secondary filter at high rates somewhat improved plant results. No evidence was obtained of the flushing action of sewage at the higher rates. The biologi-

cal observations made on these filters are presented by Reynoldson. He states that during the present wartime conditions the scouring activities of the *Psychoda* larvae were insufficient to maintain the primary filter in a condition suitable to effect reasonable purification. This condition was attained in the coarse half of the secondary filter and in the fine half during most of the year. The restriction of macrofauna to *Psychoda alternata* is undesirable both from purification and nuisance viewpoints.

Hamlin (97) again reports on the continuation of the forced draft and heating experiments on the two 100-foot diameter trickling filters at Johannesburg. Each of these filters is divided into twelve equal experimental sectors. The average flow of 138 gallons per cubic yard daily was increased to 357 gallons. The sectors provided with ventilation show the greatest purifying effect. In commenting on the results, Hamlin emphasizes another factor (meteorological) which effects the temperature and depth of open trickling filters and which other investigators seem to have overlooked. He points out that atmospheric conditions in South Africa differ from those in some other parts of the world, *i.e.*, the low climatic relative humidity and high evaporation result in rapid cooling of the top stone layer. He states: "Therefore, the value of the work done by a cubic yard of medium increases with the depth and yet one hears that some designers still believe it to be economical to construct shallow filters."

The report of the City of Manchester (160) relates some experiences with the filtration of settled sewage in a small, experimental, enclosed, aerated filter. During the four-months operation in 1941 when the dosing rate was slightly less than in 1940, the pressure required to force air through the filter gradually increased from 0.01 to 1.6 inches (water gauge). No improvement was brought about either by flow increase or by diluting with final effluent in varying proportions up to 50 per cent of the total volume. However, resting the filter on alternate days for three weeks brought about material improvement. The effluent at the dosing rates used did not meet the standard set by the Royal Commission of Sewage Disposal. One interesting observation is that the sludge collected in the humus tank averaged 8 per cent solids which was considerably denser than that normally produced by percolating filters. This sludge drained easily on open beds.

Schreiber (218) describes what is evidently a novel experimental trickling filter which was tried at the Stahnsdorf Sewage Works, Berlin. This filter contains a fine-grained medium (5 to 10 mm.), has a larger than normal contact area and smaller individual voids per unit volume of filter. It is aerated both from above and below and may be either backwashed with the medium in place or the medium is removed and washed by recirculation. It is claimed that this filter costs but one-half as much as the normal trickling filter and has an efficiency several times greater.

In discussing the role of filter-bed material in trickling filters, Demoll and Liebmann (54) claim that filter beds of lava have the best structure

for retaining water over longer periods and for rapid and complete colonization by organisms. Brick is unsuitable due to its capillary surface structure.

In studying the effect of the addition of sodium nitrate to sewage, Heukelekian (104) shows that among other things this compound acts to reduce the B.O.D. The mixing of sewage with trickling filter effluent results in a B.O.D. removal equivalent to the nitrate content of the effluent.

Edmondson and Goodrich (60) studied the recycling of highly-nitrified effluent to the trickling filter. The filter was operated at 275–500 gallon rates per cubic yard, not including the recirculated effluent which varied from 1:3 to 1:1. The filter through which the nitrified effluent was recycled did not pond and produced an effluent with 11–19 p.p.m. B.O.D. Previous experience indicated that the rate of application without recirculation of nitrified effluent could not be increased beyond 50–70 gallons per cubic yard without deleterious effects. On occasion when the filter ponded the application of nitrified effluent alone for two days cleared up the stones. The nitrates applied to the filter were completely reduced at the 2½ foot level.

Tomlinson (244) reported that when the film from different levels of the filter was aerated the nitrifying activity of the film from the top foot of the single filter was very low. The films collected from the lower levels had a higher nitrifying activity than the films from the corresponding levels in the alternating double filter. The nitrifying activity in the secondary filter was higher than that at the same level in the primary filter. It was also higher in the summer than in the winter period. Holtje (107) described some of the common microorganisms found in trickling filters.

Filter.—A trickling filter in which the fouled material in the bottom of the bed is washed and replaced on top of the filter, was tried out some years ago on a pilot plant scale with some success. The allowable rates of application were very high. A similar device, using filter media ⅛ to ½ inch in diameter and with the addition of aeration devices has been described by Schreiber (217). A considerable increase in efficiency and economy of construction is claimed for this type of filter.

Through experiments made on a laboratory trickling filter but 22 inches deep, Cram (50) concludes there was evidence that amoeba cysts and helminth ova may pass through trickling filters.

Patents.—Yeomans (269) patented a means of setting the hollow central distributor column of a trickling filter in true position. Marshall (161) patented a self-cleaning centrifugal spray nozzle. Levine (152) obtained a patent on a method of removing excess biological slime from trickling filter media by a combination of back-washing and air-blowing.

ACTIVATED SLUDGE

Based on comments and data furnished from 25 activated sludge plants, Wisely (265) has presented an excellent 27-page review of the practical methods of maintaining air diffusers, of disposing of waste

activated sludge and of controlling the principal operating variables of activated sludge. These variables are the concentration of aeration tank solids, the rate of sludge return, the rate of air application, the aeration period and the condition of the sludge.

Some new work has been done on the biology of activated sludge. Hoffman (106) in a study of the biology of conventional activated sludge and of sludge to which asbestos had been added (Z process), found fewer protozoa both in species and individuals in tanks of the Z process than in the activated sludge tanks. The same degree of purification was obtained by the two processes, but 5 to 7 times as long was required for treatment by activated sludge. He believes that the longer aeration period and the reaeration of sludge in the activated sludge process encourages the growth of the protozoa. The lack of protozoa in the Z process indicated to him that these organisms are not necessary for the purification of sewage. About 10 times as many free-swimming bacteria were found in the Z process as in the activated sludge, but the zoogloea developed to a much greater extent in the activated sludge. Hoffman thinks that the free bacteria of the Z process react more rapidly than the bacteria in the zoogleal floc.

On the other hand, the studies of Pillai (190) indicated that more sludge was formed and effluents of better quality were produced when protozoa were present with bacteria than when bacteria only were in the sewage. Protozoa aid especially in clarifying the sewage. Pillai and Subrahmanyan (191) found *Epistylis* was the most efficient of the protozoa in the purification of the sewage.

Ridenour, Carlson and McKhann (196) found that activated sludge in amounts as low as 1100 p.p.m. with a 6-hour aeration period, removed or inactivated the Poliomyelitis virus to the extent that it was noneffective to mice when injected intracerebrally.

Experiments conducted by Viehl (249) showed that an oxygen concentration of 1.5 p.p.m. in an aeration tank is sufficient for purification. The decomposition of organic matter was not accelerated at higher concentrations of oxygen although the rate of nitrification increased considerably. Rohlick (197) confirms this in his oxidation-reduction studies of activated sludge when he found that only if the dissolved oxygen content drops below 1.0 p.p.m. does the electrode potential begin to fall off. With a well-stabilized sludge, the drop in potential takes place quite slowly when aeration stops and intense reducing conditions will not occur for a long time following the cessation of aeration. Electrode potentials of aerated sludge depend upon the concentration of suspended solids and good correlation was found between the stage of oxidation of the sewage as measured by the rate of oxygen utilization and the oxidation-reduction potential.

Moore and Ruchhoft (179) also studied the oxidation-reduction potentials of fresh and stale sewage and activated sludge.

Gould (89) has reported on the operation of the Bowery Bay plant of New York City with its new type final settling tanks. The plant was designed for and has been operated with step-aeration. The first of

the 4 passes was used for reaeration of return sludge and sewage was added in equal increments at the end of passes 1, 2 and 3. The volume of return sludge was kept at about forty per cent of the sewage flow so that the suspended solids in the first pass would be low enough to maintain dissolved oxygen. In the final tanks, the direction of the sludge scrapers was reversed and the point of sludge withdrawal was placed at the end of the tank opposite to the incoming flow. The scrapers now operate in the same direction as the natural flow along the bottom of the tank. Velocity measurements have shown currents ranging from 5 to 10 feet per minute along the bottom of the tank toward the effluent end. As the scraper mechanism was designed for a velocity of 3 feet per minute, the function of the flights is limited to the removal of deposits which might lodge on the floor. The number of flights might well be reduced. The volume of tank provided per m.g. daily flow at Bowery Bay is only 57 per cent of that at Wards Island.

After experimentation at Two Rivers, Wisconsin, Sawyer, Rohlich and Tomek (211) concluded that the addition of waste activated sludge to the raw sewage prior to aeration seemed desirable as it resulted in about 25 per cent greater removal of B.O.D. than plain settling alone. In an attempt to evaluate the effect of stage addition of return sludge, Sawyer and Rohlich (212) arranged to add return sludge at any of 6 points in the aeration tanks ranging from the head end to the tail end of the tank. Even when all the sludge was added at the effluent end of the tank, the solids at the influent end were so high that it seemed to make little difference where the return sludge was added. Inability to control the back-flow of the sludge in the aeration tanks prevented them from obtaining conclusive results.

Plain sewage aeration, sewage aeration with the return of aeration tank effluent, and sewage aeration with the return of sludge to maintain less than 500 p.p.m. suspended solids in the aerator were studied by Setter (221) in an experimental plant supplied with a constant flow of 15 gallons per minute of settled sewage. With 1.5 hours aeration, suspended solids and B.O.D. reductions of 30 to 40, 60 to 65 and 65 to 75 per cent were obtained by plain aeration, the return of aeration tank effluent and the return of sludge respectively. With 3 hours aeration, the suspended solids and B.O.D. removals were 60 to 65, 65 to 75 and 75 to 85 per cent respectively. The sludge produced from aeration periods of less than 3 hours could be wasted at a concentration of 4.0 to 5.0 per cent solids. On storage, the sludge deteriorates quickly at summer temperatures, producing a vile odor.

Rudolfs (203) reported on the concentrating of activated sludge by compacting and flotation. Best results were obtained with flotation resulting from the addition of 8 to 16 pounds of calcium hypochlorite per 1,000 gallons of sludge. In 48 hours, he was able to obtain a concentration of 6 to 10 per cent. Compacting seemed more affected by the condition of the sludge than by the original density. Well-oxidized sludges required less chemical than poorly-conditioned ones.

Return sludge chlorination for the correction of bulking has been

practiced successfully at Lima, Ohio for 9 years. According to Smith (225) the dosage required is not less than 6 p.p.m. based on the sludge return flow or not less than 8 p.p.m. for each per cent of solids in the return sludge. Nearly complete recovery from bulking may be expected within 7 days after the beginning of the treatment. Smith emphasizes that chlorine should be used only for correction of bulking, not for prevention.

According to Wirts (263), the improved method of cleaning diffuser plates at Cleveland is to soak them for several hours in a cleaning solution consisting of a 2 per cent solution of sodium dichromate in sulfuric acid. Then the plates are drained and thoroughly cleaned in a special machine which forces air and water through the plates for about 1 minute. The cleaned plates have about 90 per cent of their original porosity. The cost of labor in handling the diffusers is about 80 per cent of the total cost of cleaning, which is about 45 cents per plate.

Some plant modification and enlargement has been reported from England. At the Yardley (250) plant in Birmingham, chemical precipitation with iron salts and lime has been used prior to aeration. Although the settled chemically-treated sewage contained 15–20 p.p.m. of iron, it responded well to treatment by activated sludge and showed no tendency to clog the diffuser plates.

Lamb (149) has described the new activated sludge unit at Worcester. It is twice as large as any of the existing units and was designed for a dry-weather flow of 1.5 m.g.d. If desirable, the new unit can be made to produce a high quality of sludge and the surplus transferred to any of the existing aeration tanks.

In order to overcome the bulking of activated sludge in the bio-aeration system (Sheffield type) at Coisley Hill Works at Sheffield, England, Edmondson and Goodrich (60) recycled a highly nitrified effluent from a high rate filter back to the aeration tanks. The effluent from the bio-aeration unit was applied to a special filter dosed at the rate of 500 gallons per cubic yard. With uniform rain-like distribution on the filter by spray jets, 20 p.p.m. of nitrate nitrogen was produced, which when returned to the settled sewage entering the aeration unit in the ratio of 1 : 1, contributed 70 p.p.m. of oxygen. During a period of one year when one of the bio-aeration units was operated on this basis the sludge did not bulk and produced a lower B.O.D. in the effluent than the other unit not receiving the recycled nitrified effluent.

Jackson (120) discusses the effect and control of large infestation of chironomid larvae in the activated sludge process. It destroys the clarification, purification and regeneration power of activated sludge. The sludge does not settle readily and decreases in volume. The larvae do not persist in the absence of D.O. in the tanks. They are found in the aeration and final settling tanks. They devour bacteria, protozoa and organic matter in the sludge. Pyrethrum compounds are the most effective means of control. The floc is not affected by doses used to control the insect. The effective dosage is 1 pound per 5,000–20,000 gallons of sludge.

SUBMERGED CONTACT AERATORS

There are at present 74 plants being built or are in operation using the Hays contact aeration process. Most of them have been built recently and many of them are located in military establishments. Griffith (94) reviews the development of the process since 1930 and particularly since 1938 when experiments had reached a point to permit the application. In 1939 the first municipal plant employing this process was built in Elgin, Texas (pop. 1,230), which has given a B.O.D. reduction of 90–95 per cent. The typical layout provides for screening, primary settling and two-stage contact aeration, each stage followed by settling. The total detention time in the three settling tanks is 3.37 hours at average design flow. The contact plates best suited for this purpose are asbestos cement $^3/_{16}$ in. thick, set vertically and at right angles to the tank axis about $1^1/_2$ in. apart. Air is supplied from the bottom of the tank six inches below the plates. Slime forms and discharges from the plates. Complete treatment is accomplished in $1^1/_2$–$2^1/_2$ hours aeration period under average daily flow conditions. Design requirement calls for 82 square feet of plate area per pound of B.O.D. loading. Adequate aeration is supplied with about 0.33 cubic feet of air per minute per square foot of aerated water surface and a total air of 0.9 cubic feet per gallon of sewage. Certain mechanical and operational difficulties have been encountered.

Greeley (93) enumerates a number of operating and mechanical difficulties encountered in this type of plant. Although some of these operating troubles are not inherent to the process, the operation of the plants has been difficult. The difficulties have been less and performance better in smaller plants with weaker sewages. The operating results given for a small plant of this type indicate a B.O.D. reduction of 82 per cent in aeration and final tanks. The B.O.D. applied per 1,000 cubic feet of air was 0.47 pounds and was twice as high as in activated sludge plants.

Franks and Obma (75) state that there are six army plants utilizing the Hays process in the Seventh Service command territory, which have all given trouble both from the operating and reduction standpoints. Two of the plants turning out a clear effluent are loaded only about 60 per cent of design and a peculiar odor is in evidence even in these plants.

Lackey and Dixon (145) reported on the biological life in plants using the Hays process. The survey included eleven plants, both army and municipal. Out of seven of these plants for which B.O.D. values in the influent and effluent are given, two had B.O.D. values in the effluent of 11 p.p.m. or less, four with values of 45 to 62 p.p.m. and one with 93 p.p.m. The influent B.O.D. in the latter case was 391 p.p.m. The flora and fauna were sharply limited. In the plants producing a good effluent the protozoa, rotifers and worms were characteristic of good activated sludge or a standard trickling filter. In the plants containing no dissolved oxygen the dominant protozoa consisted of five genera of protozoa and four genera of flagellates characteristic of Imhoff tanks or foul waters. It is stated that the biological composition of the film indi-

cated insufficient utilization of or access to air. Filamentous organisms such as *Beggiotoa* and *Sphaerotilus natans* were found in abundance. Great quantities of sulfur bacteria were characteristic of all plants.

CHLORINATION

Chlorination under Wartime Conditions.—Describing the design and operation of sewage treatment plants at military installations, Hatch (99) notes that, where required, chlorination is provided for disinfection of effluents or control of odors. Specifications call for a contact period of 15 minutes based on the 4-hour average maximum flow and equipment is designed to supply a dosage of 80 pounds per m.g. based on the 24-hour average flow. As an emergency measure, prior to completion of secondary treatment units, Porter (193) constructed and operated successfully an automatic hypochlorite solution feeder at one plant. Sodium hypochlorite was employed because of the low freezing point of this solution (minus 10° F.) and was found to function satisfactorily at temperatures even below its freezing point. The use of a lagoon and the maintenance of 4 to 5 p.p.m. residual chlorine provided a satisfactory degree of treatment.

At the Buffalo plant, according to Johnson (124), injector tips (used in the chlorinator injector throats and normally fabricated of "Isolantite") were needed but not available. Serviceable duplicates were made of babbitt metal, but proved too heavy; of hard rubber, but this stock then became exhausted; and finally of phenolic base plastic, which is now giving satisfactory service.

Chlorination for Disinfection.—With its chlorine feeding capacity of 27 tons per day, Detroit ranks as the largest municipal installation in the world. Wallace and Habermehl (252) report that post-chlorination has been found to be more economical than prechlorination in this plant, because of the extreme and rapid fluctuations in the hourly chlorine demand values. Chlorine dosage rates are anticipated by determining the chlorine demand of the influent, thus providing a 90-minute period for testing and for manual setting of chlorinators. In 1942 the chlorine demand tests showed an average dosage of 6.0 p.p.m. (238 tons per month). The demand satisfaction of 103 per cent accomplished an average monthly reduction of 97 per cent in coliform bacteria except during two months when breaks in water mains interrupted the operation of feeding equipment. During these months, the average monthly reduction was above 90 per cent.

Since operation of the Cleveland Easterly plant, the waters of six adjacent Lake Erie bathing beaches have shown (7) reductions in total bacterial contamination of about 90 per cent and in coliform organisms of about 85 per cent. This modern activated sludge treatment plant employs effluent chlorination during the summer months, as described by Wirts (261). The chlorine dose averages between 4 and 5 p.p.m., and this provides a residual of 0.5 to 1.5 p.p.m. in the effluent.

The first contract for construction of the Toronto sewage treatment plant was reported (22) as awarded in September of 1942. This con-

struction will include primary sedimentation, sludge digestion, and chlorination units.

Chlorination for Control of Odors.—At the Cokato, Mo., municipal sewage treatment plant, separate pretreatment of corn canning wastes is accomplished on a recirculating filter. According to King (136), this filter was a source of objectionable odors until it was enclosed. An exhaust fan is utilized to give increased circulation of air, the air is discharged through a duct above the roof, and chlorination of the exhaust air is provided for odor control. The plant effluent is also chlorinated for disinfection and oxygen demand reduction.

When a wartime increase in connected population doubled the sewage flows for which the Lawton, Oklahoma, activated sludge treatment plant was designed, the effluent quality was little better than the raw sewage. Hendrick (102) described how chemical coagulation and high-rate filter units were added to provide an adequate degree of treatment. The Scott-Darcey process is used to produce ferrous chloride for odor control and ferric chloride for coagulation.

Chlorination for Control of Activated Sludge Bulking.—In a review of activated sludge plant control practice by Wisely (265), five plants are reported to have found the chlorination of return sludge efficacious in controlling filamentous organisms and in reducing the high initial oxygen requirements of bulking sludge. It appears that, for best results, such treatment should be instituted as soon as bulking becomes imminent and the chlorine should be applied at carefully-controlled rates.

The chlorination of return sludge has been used as a control method by Smith (225) at Lima, Ohio, for more than nine years. His experience indicates that it should be used for correction rather than for prevention of bulking. The use of at least six p.p.m. chlorine based on return sludge flow, or of at least eight p.p.m. for each one per cent solids in the return sludge has been found a suitable dose at the Lima plant. This treatment effects nearly complete correction of bulking within seven days after the start of chlorination. Data show the use of chlorine for this purpose has risen gradually from about 1,100 pounds per year to 9,200 pounds, but this consumption is considered economical since the power requirements for air compression have been reduced to a reasonable figure despite the fact that the plant operates in excess of its rated capacity.

Chlorination for Control of Filter Ponding.—The construction of one standard-rate filter unit at the Westfield, N. Y., plant created an especially difficult ponding problem. Howson (112) studied the application of chlorine solution directly from the chlorinator discharge hose to the surface of the filter; this treatment removed the ponds but also inactivated the filter for about five weeks. Flooding the filter with chlorinated water (having a residual of about 10 p.p.m. after 20 minutes contact) also eliminated ponding for two weeks, but inactivated the filter for about three weeks. After a series of experiments, it was found that flooding the filter at monthly intervals, and by chlorinating the top 3 to 4 feet of water (5 to 8 p.p.m. residual) the ponding was kept under con-

trol with no apparent harm to the filter activity. At another trickling filter plant, employing aero-distributors and handling industrial wastes, Nussbaumer (112) employed prechlorination (a 70-lb. per mg. dose) and post-chlorination (a 30-lb. per mg. dose). This treatment controlled odors and gave a satisfactory residual for disinfection.

An operation report by Kunsch (143) notes that, since wastes received at the Danbury, Connecticut, plant are in a fresh condition, it has been possible to eliminate the original practice of chlorinating the settled sewage prior to its application to the trickling filters. Chlorine is now added only when filters are flooded and this routine has reduced the former 15 ton per year chlorine requirement by 20 per cent.

Chlorine for Special Applications.—Textile wastes containing sulfur dyes have long been recognized as causing a high chlorine demand. Van Kleeck (246) reports that, at one large municipal plant in Connecticut, the demand of such wastes was far in excess of the original chlorinator capacity. The normal domestic sewage demand of 10 to 12 p.p.m. was increased to 60 p.p.m. and higher (500 pounds of chlorine per m.g. of sewage treated). The construction of holding basins and even discharge of the waste has corrected the wide fluctuations in chlorine demand which previously caused dosage difficulties. Studies showed chlorine to be the cheapest and most satisfactory oxidizing agent to treat the sulfur dyes.

The excessive load imposed by returning digester supernatant liquor to chemical flocculation units is described by Bell (29) as reducing alum floc to a colloidal form impossible to settle. By applying a heavy dose of chlorine in the primary tank for a 2-hour period, during the discharge of supernatant liquor, this condition was corrected.

According to Barnes (26) exceptionally high water rates at the Bowling Green, Ohio plant led to the use of sewage effluent from final tanks to supply the chlorinator injector feed. Cost of the pumping installation was about $300 and this has been fully justified; the charge for water previously averaging $223 per year was reduced by this installation to $28 in 1942, and this in spite of an increased use of 1,000 pounds of chlorine in that year over the amount applied in previous years.

Chlorination Research.—In studying the concentration of an activated sludge, using various physical methods and adding chemicals, Rudolfs (203) found that flotation resulting from the addition of calcium hypochlorite produces a dense sludge, varying from 6 to 10 per cent solids in 48 hours compacting. The quantity of hypochlorite required varied from 8 to 16 pounds per 1,000 gallons of waste sludge. Compacting with this chemical is affected by the character of the sludge rather than by its original density. Well-oxidized sludge requiring less chemical than poorly-settling sludges. Turbidity and B.O.D. of the liquor increases, but the addition of 50 p.p.m. ferric chloride prior to the addition of calcium hypochlorite produces a clear transparent liquor with a lower B.O.D. than the original sewage. While this enhances drainability of the sludge, vacuum filter experiments indicate that a sludge compacting to 8 to 9 per cent solids dewaters slowly. The liquor

contains some residual chlorine and upon return to the influent would have no detrimental effect or would conceivably aid in control of odors.

A report on an investigation of the effect of break-point superchlorination on the B.O.D. of oxidized and settled sewage effluents has been published by Groff and Ridenour (95). Their results indicate that the amount of chlorine required to obtain the "break" was dependent upon the amount of nitrogenous material present, and that it was measured by the total second-stage B.O.D. of the sewage. The laboratory experiments appeared to show no increased reduction in the 5-day B.O.D. over that obtained with the low dosages of chlorine commonly employed, but the reduction was permanent. Beyond the first few p.p.m. added, the B.O.D. of a chlorinated sewage varied directly with the residual chlorine.

In reviewing the reported studies of chlorination as a means of inactivating the virus of infantile paralysis, Maxey and Howe (166) conclude there is no justification for the statement that present-day methods of chlorination are of little value for this purpose. They point out the technical difficulties of duplicating actual conditions in experimental studies.

At a time when physical and biological methods of sewage treatment are being more critically appraised than ever before, it appears that the potential uses of chlorine warrant the same study. Yet the two reports of the Federation Research Committee (202) include only six research projects involving chlorination out of a total list of 128 problems being investigated; and, actually, these involve study of only four different chlorination problems.

SLUDGE DIGESTION

General.—McLean (170) (171) discusses the basic principles and important factors involved in sludge digestion.

Research.—Nitrogen changes during digestion were studied by Snell (230). Results showed that unless nitrogen were present in the form of nitrates or nitrites (a very unlikely condition), nitrogen gas would not be formed during digestion. This would indicate that further studies on the composition of digester gases would be worthwhile, as most digester gas analyses show an undetermined fraction assumed to be nitrogen.

Difficulties in digesting undiluted human excreta due to the formation of large amounts of ammonium carbonate are pointed out by Snell (231). Corrective measures by carbonating the digesting sludge or the addition of carbon dioxide producing substances are outlined. A design of digester in which there is a horizontal screen at an intermediate depth is suggested. It is highly questionable whether this design would be practical due to blinding of the screen.

Straub (236) described detailed experiments involving the digestion of carrots, cabbage and potatoes, and concludes that all three vegetables digest satisfactorily when properly seeded. Less gas was obtained than from ordinary raw sewage sludge. Strong odors, controllable by acti-

vated carbon or ortho-dichlor benzene were obtained in the cabbage digestion experiment.

The digestibility of paper pulp mixed with raw sewage sludge was studied by Straub (237). No harmful effects were noted in a C : N ratio range of 20 to 111. The addition of lime was necessary to correct acidity.

Rudolfs and Faulk (207) give results of experiments on the treatment of digester overflow liquor with lime and with ferric chloride. The use of both chemicals gave best clarification, but the oxygen consumed reduction did not exceed about 60 per cent.

Design.—A comprehensive outline on the method of computing heat losses from digesters is given by Wittwer (267). Similar design information is presented by Kozma (142) who stresses the importance of proper tank insulation for effecting heat economies.

Two methods of treating digester overflow liquor are described in *this Journal* (4) (186). In the first, the liquor is treated on a recirculating back-washed filter. In the second, an atomizing aerator is used.

Operation.—Bell (29) indicates the advantages of chlorination in the primary settling tank of a chemical precipitation plant where the digester overflow is returned to the raw sewage. Rowntree (199) describes a fish ladder aerator which improved the settling characteristics of the overflow liquor.

Berg (31) outlines methods of improving digester operation based on experiences at San Antonio. Gunson (96) describes methods used at Denver in stage digestion whereby the digestion was improved by controlled heating and mixing. In *Public Works* (13), improvements in digestion by reducing the amount of raw sludge pumped to the digester are described. *Sewage Works Engineering* (17) presents a round table discussion on the scum problem in digesters.

Schick (214) describes the damage to digester heating coils at Van Wert, Ohio, caused by electrolysis or corrosion. At Aurora, Illinois (18), studies were undertaken on the corrosiveness of sulfur in digester gas. Anderson (5) describes the overhauling and repairs to a gasometer at Rockville Center, New York, where severe pitting was caused by the corrosive action of the gas.

Operation of gas engines at Aurora, Illinois, is described by Sperry (233), and at Cedar Rapids, Iowa, by Gottlieb (88). In the first case 75 H.P. gas engines are connected directly to sewage pumps, and in the second a 210 H.P. unit drives a generator.

Data.—Operating data at Findlay, Ohio, are given by Barton (27); at the Cleveland Southerly and Westerly Plants by Flower (72) and Gerdel (80); at Aurora, Illinois, by Sperry (232); and at the Birmingham, England, Yardley Plant by Vokes and Jenkins (251). Many other annual plant reports have been prepared and presented during the past year. Unfortunately, their distribution has been necessarily limited and they are, therefore, not generally available. A more general abstracting of these reports and the publishing of these abstracts would be highly desirable.

Patents.—Bach (23) covers a digestion process wherein mesophilic digestion of sludge is followed by thermophilic digestion. Moerk and Eisenberg (175) describe a process wherein sludge is digested aerobically. Kurtz (144) shows a fixed-covered tank for stage digestion of sludge in which the tank is separated into compartments by vertical partitions, and in which there is a gas dome disposed within the cover communicating with each of the compartments. Downes (57) shows a stage digestion tank in which the unit is divided into two compartments by means of a horizontal partition. Means are provided to operate the compartments in series or parallel, and to prevent undue upward or downward pressure on the partition.

SLUDGE DISPOSAL

In 1943 interest was centered on the following topics: Use of sludge as fertilizer; vacuum filter practice; sludge incineration; elutriation of sludge; and advantages of digestion of sewage sludge prior to final disposal.

Use of Sludge as Fertilizer.—Wisely (264) in a sound editorial suggested the use of digested, air-dried sludge in Victory gardens *only* when it is spread over the ground surface in the fall and spaded in before the garden is planted, with an admonition not to use any sludge where raw-edible vegetables are to be grown. The additional safeguard of using year-old sludge by domestic users is also suggested.

At least one municipal sewage treatment plant (141) (Rutherford, N. J.) planted a victory garden to demonstrate the beneficial effect of sewage sludge on vegetables, and Van Kleeck (247) suggested how it might be used in the war emergency.

Van Kleeck (247) in discussing digested or heat-dried activated sludge pleas for its more general use, not only for its fertilizer value, but particularly as a soil conditioner. He states that failure to make use of it is a waste of a natural resource. It is admitted that there are problems to be overcome at many treatment plants before all or (in some cases) even a part of the sludge cake can be disposed of as a soil conditioner, but in view of the dearth of farm manure, the outlook for such disposal is deemed encouraging with sound development.

Backmeyer (24) at Marion, Indiana, has discontinued vacuum filtration of digested sludge and delivers liquid sludge for use as fertilizer in Victory gardens and to farmers. This change has reduced the cost per ton of dry solids from $8.75 for vacuum filtration to $2.90 for liquid disposal. Such disposal is attended, however, by more public health hazards and there is likelihood of objectionable odor. It is surprising that the practice is acceptable for Victory gardens.

Cram (50), working with the co-operation of the personnel of the United States Public Health Service Station at Cincinnati, Ohio, reports interesting laboratory experiments with the effect of various treatment processes on the survival of protozoan and worm parasites in sewage. The sewage used in the experiments was artificially inoculated. Her findings regarding sludge bear comment. The protozoan parasites

causing amoebic dysentery in man apparently are killed by ordinary digestion processes. However, the large round-worm and hookworm ova do survive both digestion and subsequent drying of sludge. The temperature of digestion appeared to have little effect on their survival and drying for as long as 118 days of indoor drying or 170 days of outdoor drying was required to impair their viability. Heating of dried sludge to 103° C. for three minutes destroyed all round-worm eggs. It is probable that flash-dried sludge (which is subject to 1,000° F. for 5 to 10 seconds) would be free of all parasitic eggs. The author's thoughts are timely since they focus attention on a possible health hazard in the use of sewage sludge as fertilizer as the war progresses. While examination of sludges from 16 municipal sewage treatment plants in California showed, with one exception, no eggs of parasitic helminths, 27, or slightly over one-third of the samples from 17 army camps in 8 southern states revealed such eggs. The return of parasitic infected military and other personnel from the tropics and Orient may conceivably cause these organisms to appear in numbers in municipal sewage. It is, therefore, a public health problem that will bear watching now and immediately after the war.

Vacuum Filter Practice.—Lynch and Mann (156) in a joint paper discuss vacuum filter operation at Auburn, New York, and Cortland, New York. At Cortland, when five different brands of high calcium lime (95 to 97 per cent CaO) were tried, filter yields from 6.4 to 10.5 pounds of dry solids per square foot per hour were obtained. The results, at least with Cortland's particular digested sludge, showed that the CaO content of the lime was not the only factor affecting its ability to coagulate solids for dewatering. Rudolfs (205) has previously shown that the CaO content of hydrated lime is not its only factor affecting coagulation of sewage. Apparently filter operators would do well to check commercially-available limes in their respective communities for their relative coagulating properties.

Backmeyer (24) increased his filter yields with higher lime additions and less ferric chloride, but reports more lime carbonate scale blinding the filter cloths and drum openings, and dismantling of the filtrate pump every few days for a cleaning with acid. In summer the stronger ammonia fumes in the filter room were also unpleasant.

The writers concur with previous writers that the best chemical mixing results are obtained with the shortest possible mixing time.

Again at Cortland, pH studies showed the filtering qualities of the conditioned sludge improved with each rise in pH up to about 10.0. Any pH above 10 and up to 13 failed to affect the filtrability of the sludge to any great extent. The Committee might comment that beyond a certain point, additions of lime do not increase the pH of the sludge mixture. Thus, an economy results in the use of lime through pH checks of the sludge filtrate.

The cleaning of filter cloths at both Auburn and Cortland has proved unsuccessful. Cloth failure seems to be more a matter of age than of hours of service, and unless cloths are in practically continuous opera-

tion, they do not seem to have the life to stand acid baths. Dundas (248) at Chicago also finds the life of filter cloths to be largely a function of time rather than tonnage output. Cloths are subject to rotting, and their life is frequently determined by a crust of iron oxide formed on the back of the cloth. The Committee has observed many filter installations at small plants where hours of actual cloth use are far below averages at larger plants, primarily because of the actual age of the cloths.

The time required to replace filter cloths at Auburn was greatly reduced by the substitution of half-round soft wood strips of moulding held in place by six finishing nails instead of the bars of brass with numerous brass screws used to insure a tight fit of the cloth between each compartment of the vacuum filter. The change netted a saving of $3.00 in cost of brass screws and 20 man-hours of labor for each change of filter cloth. Palmer (187) states that at Detroit, use of ½-inch sash cord for the metal bars has cut the time of reclothing in half and the required number of workmen by one-third. The sash cord has a useful life of about three reclothings. Velzy (248) at Buffalo also finds sash cord a satisfactory substitute for the metal strips. Apparently metal division bars will not be used by manufacturers of vacuum filters in the future. Because of cloth blinding conditions at the point of panel divisions on the filter, Palmer found that with all panel sash cords in place the loss in cake production may easily amount to more than 20 per cent. This is because the air blow is not as effective in cleaning the cloth at the divisional strips. With only every third panel sash cord in place the loss in cake production was reduced to less than 7 per cent.

Gerdel (80) has experienced trouble at the Westerly plant in Cleveland with scale deposits in the filter wire-supporting screens. A rubberized cloth used as an apron between the filter drum and agitator, containing hydrochloric acid, has dissolved the clogging scale. The acid bath is repeated every six months.

The same plant installed in 1940 a new filter cake chute to divert filter cake from the incinerators to a point outside the incineration building. Other plants have found this convenience a real help in sludge disposal during incinerator breakdowns and repairs, which do occur. Such a by-pass is a practical necessity at all sewage plants using incinerators.

Velzy (248) at Buffalo leans toward the use of manual rather than automatic devices for applying chemicals in sludge conditioning. Manual control is proving superior there and elsewhere in permitting operators to readily check the rates of chemical additions. Buffalo is also using muriatic acid for cleaning lime scale from filter screens and pipe lines. The strength of acid, amount and method of treatment are not detailed in the discussion.

At the District of Columbia plant, Fuhrman (248) has been troubled with sagging of hard-rubber pipes used for handling ferric chloride solution or conditioned sludge. Replacement of this pipe by steel pipe with a hard-rubber lining was the remedy. Here no lime is used for

sludge conditioning and analyses of discarded filter cloths reveal 52 per cent iron salts. A 24-hour exposure to a 1 per cent solution of oxalic acid increases cloth life about 30 per cent. The acid is made up in the filter pan and the filter drum with the clogged cloth in place turned in the solution.

During week-end shutdowns the filter cloths at Washington, D. C. would develop fungus growths. Saturating the cloths every idle day in a 100 p.p.m. solution of copper sulfate placed in the filter pan has prevented cloth disintegration from this source. It is not stated whether the copper solution is salvaged or discarded each day.

Schroepfer (248) in the same symposium gives improvements in filter practice at Minneapolis-St. Paul since the start of operations. The costs of operation and maintenance of the sludge disposal processes (including incineration) have been decreased from $6.97 per dry ton in 1938 to $3.41 in 1941. This amounts to a total annual reduction of $50,000. This saving is attributed largely to the advantage of having a relatively large number of professional engineers and chemists in supervisory positions.

Every effort is made at Minneapolis-St. Paul to obtain a concentrated raw sludge for conditioning. Within limits, this is always desirable for high efficiency. An average of 9.35 per cent dry solids sludge is handled after concentration. Considerable attention has been given the process of mixing in the conditioning tanks. Compressed air for mixing has been decreased in pressure with more points of admission, baffling changed, riffle boards used for dispersion of chemicals, and the detention period reduced from 13 minutes to 7 minutes. An 8-ounce Canton flannel cloth has been adopted at this plant. Proper washing and an acid bath for cloths have prolonged their life from 150 to 250 more hours. One to two carboys of hydrochloric acid (in 600 gallons of water), together with an inhibitor, is used after 350 hours of service. Cloths are washed with a spray set to impinge along the filter drums almost at right angles to the drums. A washing every 4 to 8 hours has marked effects on the quantity of conditioning chemicals required. A method has been developed for washing cloths without filter shut-downs. The wash-water pipe and nozzles would be installed under the cake discharge apron so that the filter section next to submerge in the filter vat would be washed. A trough suspended immediately above the sludge level would return the spent wash water to the overflow box on the filter. To date (1942), because of its recent conception and the priorities required, this scheme has not been incorporated in the plant. If adopted, it will not only provide a clean filter medium, but, in effect, will result in providing additional filter area.

Schroepfer in this symposium has considerable to say about the economical filter rate. Filter rates of 8 to 10 lbs. per square foot per hour have been reduced to 3.55 pounds per square foot per hour, and indications are that 2 pounds per square foot per hour would be the most desirable at Minneapolis-St. Paul based on total annual charges. Based on the tonnages produced at this plant, a reduction in the filter rate from

7 pounds to 2 pounds per square foot per hour would result in a saving in operation and maintenance costs of approximately $125 a day, or about $45,000 annually.

Schroepfer suggests a more accurate index of filter rates than the commonly-used unit of pounds per square foot of installed filter capacity per hour. This, he points out, does not furnish an accurate measure of the number of square feet of filtering surface utilized in a given period, since it does not take into account varying filter speeds. The index, "pounds per square foot" based on actual filter surface used, is suggested. To compute this a revolution counter for the filter drum is the only addition required.

Elutriation of Digested Sludge.—Fuhrman, in a discussion previously mentioned (248), states that at Washington, D. C., without elutriation, the sludge produced would require about three times the ferric chloride now used for conditioning. Elutriation shows a saving of $11,000 per year, or enough to pay for its installation every 4 or 5 years. This brings to mind the Committee's report for 1942 in which the favorable results from elutriation at Hartford, Connecticut, were given.

Backmeyer (24) reports an interesting modification of elutriation in describing the washing of digested sludge from a primary digester with cold quarry water. The sludge is pumped at a rate of 50 g.p.m. and the quarry water at 110 g.p.m. to the secondary sludge digester. This unique method of digester operation tends to stop sludge gasification, gives a more concentrated sludge (about 3 per cent more total solids) and a clear supernatant for return to the sewage. Results over a limited period have been very promising.

Sludge Drying and Incineration.—Velzy (248) at Buffalo reports abrasion troubles with flash drying, especially in the dryer proper, the induced draft fan, and at bends in pipe lines and ducts handling gases, powdered sludge, and fly ash.

In the pipe lines and ducts an economical solution has been the use of concrete wear backs at the bends. The concrete stands wear for a considerable time and is easily replaced.

A lower speed in the cage mill of the flash dryer has increased its life from two to about five months. Adjustment in the type of assembly has resulted in easy replacement of worn parts and the re-use of portions of these parts.

Severe wear on the induced draft fan (with a blade life of only about two months) was corrected by moving the fan to the clean air side of the cyclone. One unit in this location has operated for more than a year to date (1943) without showing appreciable wear.

Velzy comments that this abrasion problem is one that may vary widely in severity in different plants. It would seem that the Buffalo sludge may have an unusually high percentage of inorganic fines.

Dundas and McLaughlin (248) list eight factors necessary for economical sludge drying, free from nuisances, to prepare sludge for efficient combustion or for use as a fertilizer:

(1) Maximum surface exposure.
(2) Thorough agitation of the wet material.
(3) Temperature potential of gas.
(4) Velocity of drying gas.
(5) Responsive and flexible temperature control.
(6) Deodorization of gases vented from the drying operation.
(7) Instantaneous water removal; and
(8) Preservation of fertilizer qualities.

They state all eight of them are efficiently performed in the flash drying equipment in use at Chicago.

In their discussion is an excellent presentation of the theory of sludge combustion. Most of the definitions of smoke, they state, are unsatisfactory and vague. The amount of visible solids discharged from a stack is not a complete indication of its nuisance value. For drying and incinerating sludge, they list as supplementary fuels in the order of their desirability: digester gas, natural gas, and fuel oil. In large installations, powdered coal is satisfactory.

Johnson (125) also discussed the problem of sludge disposal developments at the Southwest works in Chicago. The activated sludge from this plant as well as the North Side plant is mixed, concentrated and conditioned with $FeCl_3$ (6–9 per cent) and filtered on vacuum filters. The cake containing 80–85 per cent moisture is dried to 5 per cent moisture in flash driers having a capacity to evaporate 160,000 pounds of water per hour.

The cost of disposal of sludge at the Minneapolis-St. Paul sewage treatment plant was reported (16) to be $3.27 per ton. Ferric chloride dosage for conditioning was 1.2 per cent and lime 3.44 per cent as CaO of the dry weight of sludge. The average life of the filter cloth was 493 hours as compared to 326 hours in 1940. The average filter rate was reduced from 5.5 in 1940 to 3.4 pounds per square foot per hour in 1941 to save chemicals. The average moisture in the filter cake was 66.3 per cent.

The elutriation tanks in Detroit have been used for the treatment of digester supernatant which contains 4 per cent solids according to Wallace and Habermehl (252). After 6–8 hours sedimentation in these tanks the sludge compacts to 11–12 per cent solids. Filter production was 7.0 pounds dry solids per square foot per hour for raw sludge and 6.0 pounds for digested sludge. Slightly more chemicals were required for digested sludge than for raw. In 1942 mixed raw and digested sludge was filtered successfully, giving a filter production of 6.8 pounds of solids per square foot per hour with an average dosage of 8.3 per cent CaO and 2.7 per cent $FeCl_3$. The cake produced averaged 31.2 per cent solids. Canton flannel filter cloths have lasted 400 hours. In the incineration of the filter cake, 0.35 gallon of oil per ton of material was used, mostly during the warming up period.

At Cranston, R. I. plant the disposal of digested sludge by elutriation is reported to have saved 50 per cent of the cost of ferric chloride

according to Horne (110). Elutriation is in two stages, the elutriate produced from the second tank being used in the first while in the former only clean water is used. The ratio of clean water to sludge is 3:1. The elutriated sludge is vacuum filtered and incinerated in a Nichols-Hereshoff multiple hearth incinerator.

The sludge disposal at the San Diego plant will be by elutriation, vacuum filtration, drying in Raymond flash drier, and the dried sludge will be sold as fertilizer, according to Phelps (189).

Wishart, Jepson and Klein (266) state that vacuum filtration of excess activated sludge is effected by the freshness and condition of the sludge. On storage of activated and raw sludge, reducing substances are produced which increase the ferric chloride demand. Aeration of such stale sludges for 1–2 hours reduces the ferric chloride demand. Aeration is beneficial even with fresh activated sludge.

The Value of the Digestion of Sludge as an Intermediate Step in its Disposal.—Velzy (248) and Genter (79) present again the advantages of digestion. Velzy points out that digestion tanks absorb the irregularities in quantity of raw sludge obtained, permit a shorter operating week for dewatering and incineration, provide gas as fuel for boilers and auxiliary heat for incinerators, and deliver a sludge of reasonably uniform characteristics for filtration and burning.

Genter (79) in discussing sludge disposal at Minneapolis-St. Paul, views sludge digestion as essentially a wet combustion process in which the solids are mineralized before further dewatering. In view, he says, of the fact that the bacteria in this process do this work for nothing and with much less wear and tear on the relatively long-lived equipment involved, produce much less solids to be dewatered, and plenty of gaseous fuel for plant heating, the economics of raw sludge incineration can be seriously questioned when compared with sludge digestion, elutriation, and vacuum filtration, especially on the sludges listed in his discussion. In fact, by using the latter procedure at Minneapolis-St. Paul, he doubts if final sludge incineration would be needed, because the digested sludge cake would have a soil value that is out of the question with raw sludge. Genter further states that the argument that initial costs and fixed charges for digestion and elutriation space and equipment may offset the gains due to sludge mineralization has lost its validity in the numerous installations practicing this procedure.

MECHANICAL EQUIPMENT

Equipment in the field of sewage treatment was not an important subject for authors during 1943. Most articles on the subject deal with maintenance, a few with municipal installations, and fewer with military installations. Among the few makeshift innovations resulting from war conditions are timber and concrete manhole covers (11). Howson (112) indicates, in his discussion of his method of overcoming troubles with the trickling filter distributors at Westfield, N. Y., a typical example of the problems involved and how they are being overcome in

wartime. Cohn (47) features the importance of maintenance of equipment in time of war, covering the more common types of equipment found in sewage treatment works. Gerdel (81) discusses maintenance problems in connection with the Westerly Plant at Cleveland, Ohio. Sperry (233) emphasizes the importance of proper care in the maintenance and operation of gas engines. Gottleib (88) uses his experience at Cedar Rapids for the same purpose, and Taylor (239) adds to knowledge gained from experience with gas engines.

Equipment in use at plants is listed in an excellent series of articles by various authors, including MacDowell (157), Kozma (140), Moseley (180), Horne (109), Squire (234), Frazier (76), King (137), and in an anonymous article (20) on the plant at Hartford, Connecticut. A series of excellent articles (21) is presented by a large number of authors in *Water Works and Sewerage*. These articles are set forth from the viewpoints of the manufacturer and of the user. Setter (221) describes a variable speed, variable stroke return sludge pump in use at Ward's Island; Allison (3) discusses the motor-driven and reaction-driven distributor arms at Corpus Christi; and Lynch and Mann (156) describe a unique vacuum filter at Auburn, New York.

The very few new installations include pumps at Freeport, Long Island, as described by McKeeman (169), driven by slip ring motors with variable speed control. Eldridge (61) states that a high-rate recirculating filter was installed to serve the Tetfer Packing Co. at Owassa, Michigan. Whether or not high-rate filters should be classed as equipment or process of treatment may be open to question but Greeley (93) points out that much effort has been given to their development during the past decade, and Dixon (55), in discussing Greeley's article brings out the importance of mechanical equipment in connection with such filters. Among the few sewage treatment plants involving new types of equipment is the Bowery Bay plant described by Gould (89) which includes an unconventional type of scraper mechanism in the settling tank, and the plant at Cranston, R. I., described by Horne (108) which is well provided with conventional mechanical equipment.

In view of the relatively large amount of work that has been done for military installations, the number of papers on such work is small. Hatch (99), in his article on military installations, fails even to mention mechanical equipment. Such cavalier treatment of the subject is not universal, however, for Reinke and Pratt (195) discuss the use of sewage treatment equipment in military establishments in California; Cleary (45) discusses developments in late 1942 and early 1943 with particular reference to army practice and the use of equipment; Franks and Obma (75) give recognition to the important part played by the equipment manufactured by every company in the United States when they state that in every case where the equipment is being applied to the job for which it was intended, an excellent performance is being obtained. White (259) tells of the installation of a mechanical grit collector and other mechanical equipment at Spartanburg, S. C., to aid in handling the sewage from Camp Croft.

Prospects for the future extensive use of sewage treatment equipment in South America are not good, according to Cleary (46), whereas he believes that the general prospects for postwar development in the United States and abroad are good. For the postwar period, Marshall (162) sounds an optimistic note when he "points with enthusiasm" to the very excellent and comprehensive lines of modern, time-tested materials, equipment and supplies available now for engineers, officials, and operators on postwar projects.

STREAM POLLUTION

Abatement and Control.—The problems of stream pollution abatement and control have been complicated and accentuated by the war and war industries during the year. Weston (258) stated that in Massachusetts pollution due to wastes from war industries had increased in streams. Such cases were impracticable of correction at present and only in extremely bad situations had court action made possible construction of remedial works. Adams (1) discussed the gain in importance of the pollution control problems in the State of Michigan. The Stream Control Commission (173) reports that municipal control improvements are virtually at a standstill in Michigan unless a war-connected need can be met in no other way. In Ohio (14) a court held that a municipal corporation had no right to discharge sewage into a stream to pollute the same; and the Michigan Supreme Court (12) reversed a lower court and held that evidence supported the contention that the present raw sewage disposal method (at Huron, Mich.) constituted a menace to health and welfare, thus justifying the Stream Control Commission's order to construct a remedial plant. In Maine the Sanitary Water Board (19) studied the pollution of the Androscoggin River and recommended the construction of sewage treatment plants for all municipalities over 1,000 population. De Baun (53) discussed the stream pollution problem from the standpoint of organic fertilizer loss and suggests that with techniques now known most of these valuable substances could be recovered.

The bill (H.R. 98) introduced in the House of Representatives on January 7, 1943, to create a division of water pollution control in the United States Public Health Service was discussed by Beals (28). Mohlman (177) has pointed out that industrial pollution of streams is increasing from expansion of basic industries and the establishment of many new industries and has presented a program for curbing industrial pollution. Wolman (268) discussed the huge deferred demand for abatement that is accumulating during the war and estimated, on the basis of a $200,000,000 program for the Ohio River basin, a one billion dollar postwar pollution abatement program for the entire United States.

Weldert (256), Haupt (100) and Husmann (115) have discussed stream pollution problems in Germany. The Central Advisory Water Committee of England published its third report (43) and recommended the establishment of twenty-nine new river boards to supersede existing

authorities and be responsible for all questions of drainage, water conservation, pollution, land irrigation, navigation and fishing. This board considered the existing system of river-control as generally inadequate and sometimes wasteful. Hurley (114) in reviewing the above report pointed out that it disappointed some groups because it did not recommend transfer of responsibility for sewage disposal to regional bodies. However, it was universally accepted that the present state of river-control in England was unsatisfactory and that the drainage area was the best unit for river control. Hurley discussed the workability of what might be called quality and quantity boards for river-control and presented good reasons for regionalization of sewage disposal.

Bacteriology and Biology.—Petrilli (188) considered bacteriophage important in self-purification but Flu (73), on the other hand, found no increase in the phage titer and no participation of the bacteriophage during the process of self-purification. Hutchison, et al. (116) isolated a number of microorganisms antagonistic to *Esch. coli* from surface waters and studied the reduction in *Esch. coli* in the presence of these antagonists. Paracolon organisms are aberrant coliforms that are isolated especially during gastro-enteritis outbreaks and comprise a distinct biological group according to Stuart, et al. (238). These authors reported on the physiological properties and complex serological structure of paracolon but found no proof of pathogenicity. Gilliland and Vaughn (84) in a study of pigmented coliforms reported 12 strains in genus *Escherichia* and 3 in genus *Aerobacter* and found that most strains require relatively low temperatures (19° C.) for pigment formation. Sage and Spaulding (210) reported two biochemically atypical strains of *Eberthella typhosa* which caused classical form typhoid fever. Minkevich, et al. (174) studied the direct detection of typhoid and dysentery bacteria in water and the connection between the occurrence of typhoid and the presence of para agglutinating strains of *Bact. coli*. They obtained direct isolation of *B. para typhosus* in 38.3 per cent of samples and concluded that the bismuth sulphite method of Wilson and Blair should be used in direct detection studies. The available quantitative data on the relative prevalence of coliform organisms and *Eberthella typhosa* was summarized by Kehr and Butterfield (134) and presented as rates of *B. typhosa* per million coliforms at varying levels of typhoid fever morbidity in communities contributing such pollution. Evidence indicated that these ratios remained constant though bacterial reductions by natural purification processes. The data presented emphasize the basic value of the coliform test as an indicator of the possible presence of pathogens, for on the basis of the principles developed the authors showed that the calculated expectancy of typhoid fever in Detroit closely approached that actually developed.

A study of the plankton relationship to chemical factors and environment in the White River canal was made by Hupp (113) who reported that the heaviest plankton population was downstream from the point of sewage pollution, the location of the peak being governed by the rate of river flow. Brinley (33) also found pronounced variations in chemi-

cal properties and plankton populations along the course of the White River, apparently caused principally by the entrance of sewage. From additional studies, Brinley (34) concludes that secondary treatment effluents do not give the usual toxic degradation zones obtained with raw sewage and consequently the entire stream is benefitted biologically by the available plant foods introduced. Lackey (146) (147) reported on the effects of distillery wastes on the microscopic flora and fauna of a small creek and also studied the plankton, algae and protozoa of two Tennessee rivers. Lackey, et al. (148) showed that a small stream contained a large flora and fauna within 10 miles of head waters despite the lack of any pollution or fertilization other than rural agricultural drainage and that enrichment by phosphorus and nitrogen from a small town (6,700 pop.) sewage treatment plant failed to greatly increase either the species or numbers of algae and protozoa in a five-mile stretch below. Thomson (241) studied the effect of organic pollution and silt in rivers on the behavior of *Anopheles minimus* and reported that albuminoid ammonia and oxygen consumed were found to be the best analyses for indicating the suitability of breeding places. Both of these criteria were lowest in the type of water selected by *A. minimus*.

Chemical Analyses and B.O.D.—Grassy (91) studied the use of turbidity determinations in estimating suspended load in streams and concluded that turbidity measurements supplemented by a few gravimetric determinations may cut laboratory costs considerably in such studies, with little reduction in accuracy. Moshel (181) described a test for pollution based on foam formation of samples on shaking. Schwarz, et al. (220) have developed a method for determining the colloid content of a water polarographically. Eberling (59) determined the concentration of phenol wastes in water required to kill fish and reported that it was the higher boiling point fractions of the carbolic oil which were the most toxic in water. Ettinger et al. (66) pointed out that the standard methods procedure for preserving phenols in polluted river samples was ineffective and recommended copper sulfate treatment for preservation. Scott (219) described the procedure for phenols in water and also found copper sulfate effective for sample preservation.

The nitrate results on polluted streams over a period of years were analyzed by Rudolfs and Heukelekian (209). They found that the quantity of nitrates was materially higher in the spring and fall than in the summer and winter and that the amounts could be correlated with the volume of flow.

Tödt (242) developed an electrochemical method for the determination of dissolved oxygen by means of which the decrease of oxygen can be followed in sulfite solutions. Skopintsev (223) found that the dissolved oxygen reaches a maximum deficiency under ice coverage on the Volga. Zhdanov (272) also studied the low oxygen content which caused fish mortality on the Volga under ice coverage and reported that oxidation of wastes from paper and cellulose mills caused this condition. Other chemical studies of rivers in the U. S. S. R. were those of Inlev (119) on the Piasina and those of Drachev and Skopintsev on the

Volga (58), on the Dubra and other rivers (222). Pollution studies involving determinations of free CO_2, dissolved oxygen, alkalinity and H-ion concentrations were made on the principal streams, reservoirs, lakes and ponds in the Lake Ontario watershed by Faigenbaum (67).

Jordan (127) used "quality profiles" based on B.O.D. to indicate the condition for an entire watercourse. Lauster (150) reported on low temperature B.O.D. studies on the Red River of the North and concluded that the 30-day demand at 0° C. approximated the 5-day 20° C. B.O.D. and that adequate inoculation with low temperature organisms is important in low temperature studies. Gifft (82) reviewed the mathematics of the B.O.D. determination and proposed the following equation to simplify calculations without appreciable errors:

$$\text{B.O.D.} = \frac{W_2 - D_2}{P} + S_1 - W_2$$

where W_2 = D.O. in incubated diluting water (blank), D_2 = D.O. in incubated dilution (sample), P = decimal proportion of sample in the dilution, S_1 = D.O. in the undiluted sample. A calculator of the alignment chart form was also presented.

Standards.—Burn (37) discussed classification of natural waters with regard to use and standards of quality for various uses, emphasizing that present and proposed future uses of water must be considered when a limiting standard for pollution is formulated. Cherkinskii and Ginsburg (44) studied the effect of arsenic and copper from the manufacture of Paris green in a river and concluded that limits of 2 to 4 p.p.m. of arsenic and 0.4 p.p.m. of copper did not interfere with self-purification in streams. From the hygienic standpoint, however, 0.15 p.p.m. of arsenic was considered the upper limit.

Reaeration and Oxygen Sag.—Howland (111) presented graphical methods which make it possible to apply the oxygen sag formula used by Streeter, with slight modification and under certain limitations to a stream in which occurs not only biochemical oxidation and reaeration, but sedimentation and absorption, and in which various constant proportional rates of oxygen utilization are being exerted by the sludge blanket. These methods constitute a direct computation of the constants of the equation from the experimental data and Howland suggests that they might also be used to advantage in the formulation of processes of sewage treatment.

Surveys.—McGauhey et al. (168) reported on a one-year study of a 22.5 mile stretch of the Roanoke River. This area received the sewage from a population of 100,000 besides tannery and viscose rayon plant wastes. The authors conclude that the stream is unfit for recreational purposes, detrimental to fish life and injurious to hydraulic machinery; and that the industrial wastes produce the greatest chemical and physical pollutional effects. The shore pollution studies conducted by Hyde (117) at San Francisco over a period of years showed a definite improvement in the physical and bacteriological condition of the water.

A very interesting report based on extensive investigation is made of the problem of sewage disposal and bay and shore pollution at Santa Monica Bay which has led to the quarantining of a 10-mile section of the beach (30). The Hyperion fine-screening plant and outfall built in 1925 has deteriorated and become overloaded by the increase of contributing population from 500,000 in 1920 to 1,757,000 in 1942. The 5,000-foot outfall leaks so badly that 20 to 80 per cent of the sewage fails to reach the end of the outfall. The currents in the bay are sufficient to prevent sludge bank formation but onshore surface currents carry in sewage, debris, grease and pollutional organisms. Studies of surf water, sand and sewage grease indicated the frequent presence of members of the typhoid organisms.

A study of the Meramec River which drains an area of 3,980 square miles, which is rugged in character and not well suited to agricultural purposes and which has been extensively developed for recreational purposes, was reported by Kehr and Johnson (135). Although the population of the Meramec watershed was about 131,700 in 1940, most cities have adequate sewage treatment works and the basin is relatively free of pollution. The dissolved oxygen was never under 50 per cent saturation at any point studied. With the exception of a few short stretches below sources of pollution, the median of all coliform determinations at all stations was less than 500 per 100 ml. The chemical determinations indicated that the stream was free from appreciable quantities of industrial or mine waste although some of the largest lead mines in the southwest are located in the basin. A tentative standard of purity of 500 coliforms per 100 ml. is suggested for streams used for swimming and other recreational uses and it was believed that this standard could be maintained by the construction of additional sewage treatment facilities, including chlorination.

The Maine Sanitary Water Board's study (159) of the Androscoggin River indicated that this river with a drainage area of 3,470 square miles was seriously polluted for a distance of 135 miles from Berlin, N. H., to Brunswick. Nuisance conditions exist on the river during summer and it is unfit for fishing or recreational purposes. About 96 per cent of the present pollution reaching the main river is due to industrial wastes and 92 per cent is due to pulp and paper wastes. An abatement program to make the river satisfactory for fishing or recreational purposes was considered impractical but it is proposed to prevent nuisance conditions by the maintenance of a standard of 2 p.p.m. of D.O. at all points, and remedial measures to attain this end were studied.

The final Ohio River Survey report (185) presents results of a survey directed by Section 5 of the River and Harbor Act, approved August 26, 1936. Information is presented pertaining to sources and amounts of polluting material from 3,708 municipalities and 1,800 industrial plants discharged into the watercourses of the 204,000 square miles of the Ohio River Basin. Effects of these discharges are indicated by the results of 131,000 tests made on 71,000 samples collected at 2,000 points on streams in the basin.

"Besides furnishing water for more than 7,000,000 persons and for industrial processes, the streams of the Ohio River Basin are used for the disposal of sewage by some 8,500,000 people and almost two-thirds of this sewage receives no treatment. Industrial wastes with an oxygen demand equivalent to sewage from almost 10,000,000 additional persons enter the streams. Pollution problems are further complicated by the effect of waters containing 1,800,000 tons of acid per year which flow or are pumped from active and abandoned coal mines in the extensive coal fields of the basin.

"Many water supplies, both domestic and industrial, suffer from the effects of these polluting substances and outbreaks of intestinal diseases, apparently water-borne, have occurred following periods of low stream flow. Recreation facilities have been damaged. Fish and other aquatic life have been detrimentally affected. Streamboats, barges, other river craft and structures, pumps, pipe lines and condensers exposed to acid stream waters have been attacked."

Cost estimates are presented covering a comprehensive pollution control program. The estimated total of approximately $180,000,000 includes interceptors and municipal treatment plants, industrial waste treatment or other industrial waste corrective measures and a mine-sealing program. Annual charges for operation, interest and amortization approximate $18,500,000. Cost estimates are based on average experience from 1928 to 1940.

The six supplements are as follows:

"A. Collection of Data on Sources of Pollution." This includes memoranda to field engineers, sample reports and a complete set of field inspection and summary forms.

"B. Organization and Methods of Laboratory Studies." This includes a brief discussion of the laboratory work, copies of laboratory memoranda on analytical procedures, the specifications for the mobile (trailer) laboratory units and a complete set of laboratory forms.

"C. Acid Mine Drainage Studies." This is a detailed report of the studies and is summarized in Volume I of the report proper.

"D. Industrial Waste Guides." This volume of industrial waste information is reviewed in SEWAGE WORKS JOURNAL, Volume XV, No. 2, March, 1943, p. 226.

"E. Epidemiological Studies." This supplement presents the results of field studies of water-borne disease in the Ohio River Basin made during 1939–40.

"F. Biological Studies." This is a special report on a study of stream biological communities and fish life in Ohio River Basin streams.

INDUSTRIAL WASTES

General.—The 1943 literature on the disposal of industrial wastes was concerned primarily with those industries which manufacture munitions or supplies for war. Explosives, ordnance, petroleum, alcohol, synthetic rubber, metal trades, chemicals, dehydrated foods and meat products industries were expanded to an unprecedented degree and the resulting increased volumes of wastes imposed heavy loads on sewage treatment works, streams, lakes and harbors.

At Marion, Indiana (24), cannery and dairy wastes resulted in an increase of flow from 2.45 m.g.d. in 1941 to 3.65 m.g.d. in 1942; of solids

removed, from 2.46 tons per day in 1942 to 4.45 tons per day in 1942; and of population equivalent, based on B.O.D., from 29,880 in 1941 to 37,220 in 1942. At Akron, Ohio, Schaetzle (213) reports that wastes from rubber reclaiming works were largely responsible for increasing the flow from 36 m.g.d. in 1938 to 55 m.g.d. in 1942–43 and sludge from 43 tons per day to 86 tons per day. Greatly increased volumes of colored wastes and heavy oil were received in 1942–43, one shot of oil amounting to 34 cu. yds. in two days. During a strike of five days, the suspended solids dropped from 339 to 181 p.p.m. and B.O.D. from 185 to 96 p.p.m.

Industrial wastes at Muskegon Heights, Michigan (6), interfered seriously with operation of the activated sludge plant. Wastes from metal-working industries contained oil, soda ash, cyanides and chromium and excessive concentrations of organic matter were discharged in strong wastes from a slaughter house. The latter wastes have been distributed more uniformly over the 24 hours, while the metal, oil and soda wastes have been discharged to a storm sewer and thence to the river, without any ill effects except occasional patches of floating oil.

An excessive loss of fuel oil was reported at the Easterly Sewage Treatment Works in Cleveland (262), traced to a drop forge company. It was estimated that 37,500 gallons of oil, worth $1,400, was lost during the month of May. The flow was stopped abruptly when the company was informed of the loss on June fourth.

TNT Wastes.—The most important explosive manufactured for war uses is TNT. A negligible tonnage was produced prior to the war, but in 1941 a number of large plants were constructed and production reached its peak in 1943. The raw materials for TNT are toluol, sulfuric acid, nitric acid and sodium sulfite. Nitric acid is made at the TNT plant by catalytic oxidation of liquid ammonia, and sodium sulfite from sodium carbonate plus sulfur dioxide produced by burning sulfur.

The wastes from TNT plants are of two types (176), yellow, highly acid wash waters, and the so-called "red water" from the purification of crude TNT by a solution of sodium sulfite called "sellite." The composite wastes, before dilution with cooling water, are deep red with a color of 125 on the platinum-cobalt scale even after 1 to 500 dilution. They have a pH of 1.4 or less, contain about 4,500 p.p.m. acidity and about 3.5 per cent total solids. The wastes are very resistant to decomposition (216) and all available methods for removal of organic matter and color were found ineffective, except by the use of large amounts of chlorine (176, 216). However, restriction of use of chlorine led to the study of the disposal by dilution alone (227). It was found that a dilution of 1 to 10,000 would remove all objectionable color and permit the river water to be used for drinking purposes, after filtration, with only a slight increase in color of 15 or 20. If the water is not used for drinking purposes, a dilution of 1 to 3,000 is permissible. For lower dilutions, storage is provided, or where the dilution is quite low or the wastes are discharged into lakes or bays, complete evaporation of the concentrated wastes is practiced.

Smokeless Powder.—Wastes from smokeless powder contain a large amount of free sulfuric acid, some nitric acid, and a small amount of alcohol (227). The acid averages 2,000 p.p.m., equivalent to one pound per pound of product. The B.O.D. averages 50 p.p.m., giving a population equivalent of 2,500 per 100,000 lb. product per day.

Other Explosives.—Tetryl, a "booster" used for exploding the relatively inert TNT, is manufactured on a small scale as compared with TNT. The wastes are similar in composition and volume per unit of product (228). Nitroglycerine wastes (229) are relatively unimportant as sources of pollution. The glycerine recovered from waste fats is used very little for munitions in this country, but nitroglycerine is used in admixtures with guncotton to produce "cordite" used by the British as a propellant (52).

Acid Wastes.—Rudolfs (201) has reported that acid industrial wastes in the Rahway Valley trunk sewer reduced the pH to 2.5, with occasional alkaline wastes giving a pH of 9.6, and frequent fluctuations in this range. It was found that there was little mixing in the sewer, but the slugs of acid and alkali followed each other as discharged to the treatment works. The digesting sludge became acid, had an objectionable odor, and would not dry. Hydrated lime was then added in a pretreatment plant for the industrial wastes, with equalizing and mixing capacity of 1.0 hour for 1.0 m.g.d., and an average lime usage of 1,440 lb. per million gallons, added as a slurry after the wastes had equalized in the first set of tanks, which equalized the fluctuations to a range of pH from 4.9 to 9.0. After liming, mixing and settling, the pH varied from 7.1 to 8.5, and after admixture with the sewage, the pH levelled off at from 7.0 to 7.4.

Thatcher (240) describes a similar plant in England, where milk of lime is added to acid chemical wastes. At present 4 tons of hydrated lime are used per day. The wastes are mixed in a preliminary tank, then milk of lime is added at a fixed amount prior to mixing with submerged paddles, then additional milk of lime is added by a motorized valve controlled by an antimony electrode pH apparatus, to give an alkaline effluent after settling in final Mieder tanks.

A study of various alkalies was made by Rudolfs (204) to determine whether other alkalies improve the action of lime. It was found that a combination of dolomitic hydrated lime with soda ash was preferable over lime, soda ash or caustic soda alone. The smallest volume and lowest dry weight of sludge was obtained when using 80 per cent dolomitic lime and 20 per cent soda ash, but the sludge did not settle so well as when dolomitic lime was used alone.

Metal Pickling.—Recovery of sulfuric acid from spent iron pickling liquor was studied in the laboratory by Gehm (78). Acetone was used to separate crystals of ferrous sulfate. Addition of 250 cc. of acetone to 250 cc. of pickling liquor containing 15.75 per cent $FeSO_4$, reduced the $FeSO_4$ content to 2.75 per cent. It was estimated that 3 per cent of the acetone was lost. This procedure is similar to the de Lattre process, in which methanol is used to precipitate the ferrous sulfate.

Hodge (105) has patented apparatus and procedure, using acetone, for precipitating ferrous sulfate from waste pickling liquor. Mohlman (177) reported that in the Calumet area of Chicago, pickling wastes from nine steel plants discharge 3,500 tons of iron and 3,340 tons of sulfuric acid per year into the Calumet River. In spite of all the work that has been done on disposal of pickling liquor, the problem appears far from being solved. Hodge states that the big problem is still the utilization of the large amount of recoverable copperas, and hopes for increased use of iron salts in water and sewage treatment.

Pickling of brass and copper has greatly increased during the war. The toxic effect of copper salts on biological processes of sewage treatment has been known for many years, yet sewage treatment works still get into difficulties because of copper-bearing wastes. Rudgal (200) reports finding 3,000 p.p.m. copper in the bottom layers of sludge in heated digesters at Kenosha, Wisconsin. The sewer carrying the rinse waters from the brass plant, along with part of the city's sewage flow, was by-passed directly to Lake Michigan. The gas production then increased from 2,100 to 44,000 cu. ft. per day. Bottle experiments showed that 200 p.p.m. copper would inhibit digestion. Rudgal computed that if the sewage contained only 1.0 p.p.m. copper and half was removed by sedimentation, the average copper content of the sludge would be 215 p.p.m., enough to stop all sludge digestion in one week.

Removal of copper from brass mill wastes has been studied for years by the State Water Commission of Connecticut. In their Ninth Report (49) data are presented showing that about 90 per cent of the copper losses are in the wash waters, estimated to contain 355 p.p.m. sulfuric acid and 76 p.p.m. copper. Operation of a pilot plant is recommended to determine the results and costs of treating such liquors with lime.

Brass mill wastes also contain large amounts of oil, which is used along with a stream of water on the hot rolls to facilitate operation. Mohlman (176) reported loss of oil varying from 243 to 5,188 lb. per day and of copper from 277 to 1,744 lb. per day from a brass mill in Chicago, although a number of proprietary oil separators were installed in the plant. Van Kleeck (246) found cutting oils from machine shops to be very detrimental to operation of Connecticut sewage treatment works.

Chromium wastes have been studied in England with reference to their effect on sewage treatment. In Texas, Wells (257) reported such wastes interfered with operation of an activated sludge plant at Grand Prairie.

Pulp and Paper.—An extensive investigation of industrial wastes polluting the Androscoggin River in Maine was made by Metcalf and Eddy for the Maine Sanitary Water Board (159). Several large paper mills contribute 92 per cent of the total pollution, and concentrated sulfite wastes account for 71 per cent of the total. Storage lagoons costing one-half million dollars are recommended, in which these liquors will be held at times of low water flow and discharged in high water.

An extensive review of recent information on sulfite wastes is included in the report.

In Michigan, progress is being made by the Stream Control Commission (173) in study of the problem of disposal of paper mill wastes at Kalamazoo. An inventory of waste discharges of all mills in the valley has been made and pilot plant studies have been undertaken at 7 of the 14 mills to determine the relative efficiencies of plain settling and chemical precipitation of book and board mill wastes. A flotation type save-all has been installed at one mill for treatment of white water.

In Wisconsin (255) investigations are under way on methods of treatment of sulfite wastes, recently including operation of a 15-foot trickling filter, and study of methane fermentation, contact aeration and ponding with stream-flow control.

Alcohol.—The production of alcohol from sulfite waste has been undertaken on a plant scale recently, at the Thorold, Ontario, plant of the Ontario Paper Company (39). The process of fermentation used is stated to produce 18 gallons of alcohol per ton of pulp and it is expected this can be increased to 25 gallons. (One ton of pulp produces 2,000 gallons sulfite waste liquor.) The liquor contains 10 to 13 per cent solids, of which about 15 per cent is fermentable sugars. It is claimed that this process removes 60 per cent of the B.O.D. of the sulfite liquor, but this appears high and must be checked by further studies.

Klassen (138) calls attention to the increase of alcohol production in Illinois, and expresses concern over the effect of the wastes on the Illinois River. Mohlman (176) estimated that the wartime alcohol program, increasing from 272 million gallons in 1943 to 550 million gallons in 1944, would produce wastes equivalent, on the B.O.D. basis, to a population of 27 million, if no steps were taken to recover wastes by utilization of still slops.

Glue and Gelatin.—Jones (126) reports from Coventry, England, that a lime effluent from a gelatin works had caused stoppage of a 9-inch sewer, thus leading to studies on the treatment of the wastes. The plant discharged only 200 gallons per day of the strong lime waste and 100,000 g.p.d. of wash waters. Alumino-ferric was found to be the best coagulant. The lime wastes were diluted with four volumes of wash waters, treated with 20 lb. alumino-ferric, and allowed to settle. A clear, bright, odorless effluent was obtained which it was thought could be used again for process purposes. Duplicate tanks were proposed, and an ash bed for draining sludge.

The U. S. Glue Division of Peter Cooper Corporation (15) has installed a plant for treatment of wastes, consisting of a bar screen, two 6-ft. diameter revolving drum screens of a combined capacity of 3,500 g.p.m., and two 25 ft. by 125 ft. settling tanks, with scum skimmers. The screenings are reused for glue stock and grease is rendered from the scum.

Laundry Wastes.—Eliassen and Schulhoff (63a) report experimental work on treatment of laundry wastes by flotation. Ferric chloride, alum, sulfuric acid and lime were used as coagulants, alum proving

to be the most economical for the results obtained. Use of 300 p.p.m. alum, with a few minutes aeration and vacuum treatment for 15 minutes, produced a scum which removed 78 per cent of the B.O.D. and 72 per cent of the grease. Nothing is reported on disposal of the scum.

Milk Products.—A treatment plant for milk products wastes in Indiana is described by Linderman (153). The plant consists of a holding tank and a high-rate recirculating filter 30 ft. in diameter and 6 ft. deep, with crushed boulders 3½ in. to 4 in. diameter as filter media. Wastes are pumped intermittently from a sump to the holding tank, and continuously from the holding tank to the filter, with recirculation back through the filter when no wastes are being pumped to the holding tank. The filter was designed to treat 16,000 g.p.d. with a B.O.D. of 1,050 and to effect 90 per cent removal of B.O.D. In two tests made by the State Board of Health on October 8 and November 24, 1942, the rates of flow were 12,700 and 11,000 g.p.d., respectively, but the B.O.D.'s were 2,390 and 2,900 p.p.m. Final effluents had B.O.D.'s of 346 and 262 p.p.m., the removals being 85.6 and 91.0 per cent. Suspended solids were reduced from 442 to 128 p.p.m. on October 8, and from 812 to 211 p.p.m. on November 24.

Textile.—Eldridge (62) has described experimental investigations of the treatment of textile wastes at the Yale Woolen Mills, Yale, Michigan. It was necessary to equalize the wastes in a holding tank in order to get consistent results. The optimum dosage of chemicals was 1 pound lime and 3 pounds ferric chloride per 1,000 gallons. Removals of B.O.D. varied from 66 to 78 per cent, and of suspended solids from 69 to 94 per cent. The sludge was very watery, containing only 2 per cent solids. Filter leaf tests indicated the moisture content could be reduced to 76 per cent by a vacuum filter.

Food Products.—Dehydration of foods became very important in 1943 because of the war shipping requirements and lend-lease quotas. Wastes from dehydration of vegetables and fruits are similar to set-pack cannery wastes in general characteristics. The heaviest tonnage of dehydrated vegetables is potatoes, for which the quota in 1943 was 136 million pounds out of a total of 356 million (176). Results of studies of potato dehydration wastes in California have been published by Gray and Ludwig (92). The potatoes are peeled by abrasive carborundum units, which rub off from 15 to 30 per cent of the potato solids. An average of 600 gal. of water is used per ton of potatoes and the B.O.D. averages about 1.0 lb. per ton, per percentage loss, or about 20 lb. per day. For a plant of ordinary size (one ton per hour) this amounts to 480 lb. per day. Further losses occur in the water in which the cut, peeled potatoes are washed. The volume is 2,500 gal. per ton of potatoes (four times the wash water volume) but the losses of B.O.D. are about equal to the loss of B.O.D. in the wash water, 480 lb. per day. Total losses, therefore, with 20 per cent lost in the peeler water, are 960 lb. B.O.D. per day for a plant with a capacity of one ton per hour.

Wastes are screened through a 60-mesh shaker screen, and the effluent is spread out on sand beds, of which there are seven, each 20 by 170

ft. in area. A new bed is used daily. It is doubtful whether this type of treatment would be successful elsewhere than in California or on sandy soils in southern states.

On the whole, however, dehydration wastes are not a large problem, estimated as amounting to a population equivalent of only 670,000 for the entire United States (176).

The problem of disposal of cannery wastes has been discussed by Fenlon (69). He gives results of analyses of wastes from various canning operations, reviews several methods of treatment including screens, chemical treatment, and disposal of ensilage juice. He states that industrial wastes can be treated more cheaply in conjunction with regular municipal wastes than alone.

Experimental studies have been reported by Young (270) on the treatment of cherry waste waters at North East, Pennsylvania. The wastes range in volume from 600 to 1,800 gallons per ton of cherries handled and in B.O.D. from 700 to 2,100 p.p.m. Pitter juices are highly concentrated, but amount to only 5 gallons per ton of cherries handled, and it is recommended that this waste be hauled away and disposed of on land. Experimental treatment of all wastes comprised screening through 40-mesh screens, coagulation with 22 gr. per gal. lime and 8 gr. per gal. ferrous sulfate, and settling for 2 hours. B.O.D. was reduced from 967 to 382 p.p.m., or 60 per cent, and suspended solids from 605 to 74 p.p.m., or 88 per cent.

Meat Packing.—The urgent need for improving the recovery of grease in meat packing plants led Mortenson (182) to make extensive investigations in the plants of Swift and Company of the efficiency, or lack of efficiency, of grease traps and grease basins in packinghouses. He reports the technique of the method he has developed for testing grease basins, which in brief consists of settling the effluent of such basins in a calibrated barrel, at such rates that the grease has time to rise to the surface. The grease is then skimmed, analyzed and computed to pounds per 1,000 lb. of live weight of animals slaughtered. For efficient basins, the loss should not exceed 0.1 lb. per 1,000 lb. animals slaughtered. Maximum capacities are 1 to 2 hours detention period and minimum velocities 0.25 to 0.50 ft. per minute. The WPB has widely circulated Mortenson's results and recommendations among the packinghouses of the U. S., and instigated the formation of a Committee of the Chicago Section of the American Chemical Society (9) for assistance to packers or other manufacturers who desire to improve their salvage of grease. The WPB consultant estimates that this program of salvage has resulted in an increased annual recovery by meat packing and processing companies throughout the nation of about 100 million pounds of grease.

Eldridge (62) reports results obtained with a high-rate recirculating filter treating waste from the small slaughterhouse of the Telfer Packing Company, Owosso, Michigan. Wastes were formerly emptied untreated into a ditch and created intense odors. The plant installed consisted of a storage tank holding one day's flow, from which wastes were

pumped to a filter 14 feet in diameter and 6 feet deep with a granite rock media 3 to 4 inches in diameter. The rate of application was 20 m.g.a.d., with about 4.5 recirculations. Two tests showed B.O.D. in the final effluent of 18 and 57 p.p.m. and suspended solids 28 and 23 p.p.m., from raw wastes with 2,200 and 1,750 p.p.m. B.O.D. and 1,160 and 420 p.p.m. suspended solids (although 1,364 and 1,344 p.p.m. in settled effluent). The kill on the days of tests was 15 cattle on September 22 and 5 cattle, 4 lambs and 27 hogs on September 23 (not many, but still a lot of red points).

Mahlie (158) describes the various sources of wastes from packinghouses, consisting of wasted blood, wash waters from the killing floors, wastes from the wet rendering process, and paunch wastes. The wastes from rendering are almost eliminated if dry rendering is used. Most packers remove paunches and contents, which are about 1.0 cubic feet in volume and weigh 40 pounds. The contents are fibrous and have no value. A survey of wastes from four packinghouses in Ft. Worth indicated a loss of 5-day B.O.D. of from 2.3 to 4.5 pounds per "hog equivalent" which means about 250 pounds live weight (equal to 18.4 to 36.0 pounds per ton live weight). Packinghouse wastes receive more or less pretreatment in Ft. Worth, including fine screens, grease traps and settling basins. Effluents range from 740 to 2,580 p.p.m. B.O.D., 256 to 13,323 p.p.m. suspended solids, and 221 to 553 p.p.m. grease. The effect of these wastes on the Ft. Worth sewage treatment works is not discussed, but Mahlie states that the industry should not be allowed to introduce wastes which adversely affect the operation of a plant or sewage system and place an unwarranted burden on the city taxpayers, either by increased operation costs or increased plant construction.

Phenol and Gas Plant Wastes.—The simultaneous biological purification of phenolic wastes from coke ovens and gas plants with sewage is readily feasible if the amounts of phenol are relatively small (130). Experiments made under summer and winter conditions on trickling filters and by soil filtration showed that in spite of the presence of phenols, alcohols, pyridine and cyanides, purification and stabilization could be accomplished. The experiments showed that preliminary detarring is essential. Kazachkov (132) found that additions of aluminum hydroxide (waste waters from aluminum plants) causes a rapid precipitation and removal of finely-divided particles of coal and coke. Waste from gas generating stations can be purified according to Zhukov (273) by mixing with sewage and subjecting to biological filtration. The wastes can be treated by detarring by filtration or coagulation, followed by lime water addition to form non-volatile calcium salts and to separate the ammonia in the free state; the liquor can be distilled to obtain ammonia in the form of a 20–25 per cent aqueous solution. The water from the lime precipitate may be evaporated to concentrate the calcium salts of the fatty acids produced, followed by drying to obtain commercial salts. The vapors are washed with caustic materials whereby most of the phenols are separated in the form of sodium phenolate. The vapor condensate can be treated by biological filters or the

purification can be accomplished by repeated adsorption before discharge into ponds or reservoirs. Agafoshin (2) gives a description of the extraction of phenols from waste waters and discusses the advantages and disadvantages of the extraction methods using benzene and tritolyl phosphate. These methods of extracting do not require preliminary detarring. Multistage extraction is preferable. Kazachkov (131) discusses the amounts of waste waters produced by the various departments of a coke-producing plant. The suspended solids vary greatly and the B.O.D. of the wastes depends upon the source of waste. Settling prior to biological treatment in ponds is feasible. Optimum purification results were obtained by the extraction and adsorption methods and from blowing out the phenols with steam (Koppers method). Dephenolization by chlorination requires large amounts of chlorine and caustic materials.

References

1. Adams, M. P., "Pollution Control Problems Gain in Importance and Variety under War's Impact." *Mich. Public Health*, **30**, 187 and 193 (Oct., 1943).
2. Agafoshin, N. P., "Dephenolization of Waste Waters of Gas-Generating Stations, Utilizing Brown Coal, by Tritolyl Phosphate." *Inst. Vodosnabzheniya, Kanalizatsii Gidrotekh. Sooruzhenii i Inzhenernoi Gidrogeol.*, 1940 (Part 1), 57-73; *Khim. Referat. Zhur.*, 1940, No. 9, 81-2.
3. Allison, S. L., "Trickling Filter Operation as Practiced at Corpus Christi." *This Journal*, **15**, 729 (1943).
4. American Well Works, "Digester Supernatant Treatment. Advertisers' Contribution." *This Journal*, **15**, 989 (1943).
5. Anderson, C. G., "Overhauling and Repairs to Methane Gasholder." *This Journal*, **15**, 535 (1943).
6. Anderson, R. A., "Industrial Wastes Create Problems at Muskegon Heights, Michigan." *This Journal*, **15**, 742 (1943).
7. Anon., "Bathing Beaches Show Sewage Treatment Value." *Amer. City*, **58**, 2, 15 (1943).
8. Anon., "When War Industry Wastes Hit a Sewage Treatment Plant." *Amer. City*, **58**, 5, 11 (1943).
9. Anon., Chicago Section, Am. Chem. Soc., *Chemical Bulletin*, **30**, 184 (1943).
10. Anon., *The Eng. and Contract Record* (Toronto), **56**, 14, Aug. 25 (1943).
11. Anon., "Metal Manhole Covers Replaced with Timber or Concrete." *Eng. News Rec.*, **131**, 157 (1943).
12. Anon., "Order of Stream Control Commission to Construct Sewage Treatment Plant Upheld." *Pub. Health Rept.*, **58**, 1198 (1943).
13. Anon., "Pumping Sludge to and from Digestion Tanks." *Pub. Wks.*, **74**, 336 (1943).
14. Anon., "City's Liability for Stream Pollution." *Pub. Wks.*, **74**, 4, 48 (1943).
15. Anon., "Glue Works Waste Recovery System." *Pub. Wks.*, **74**, 5, 55 (1943).
16. Anon., "Operating Results of the Minneapolis-St. Paul Sewage Treatment Plant." *Pub. Wks.*, **74**, 12, 13 (1943).
17. Anon., "The Round Table." *Sew. Wks. Eng.*, **14**, 30 (1943).
18. Anon., "Aurora Studies Corrosiveness of Sulfur in Digester Gas." *Sew. Wks. Eng.*, **14**, 24 (1943).
19. Anon., "Maine Sanitary Water Board Considers River Pollution." *Sew. Wks. Eng.*, **14**, 208 (1943).
20. Anon., "Metropolitan Sewage District Treatment Plant, Hartford, Conn." *Sew. Wks. Eng.*, **14**, 384 (1943).
21. Anon., Reference and Data Section, *Water Wks. and Sew.*, **90**, 231 (1943).
22. Anon., "Toronto Contracts for Sewage Treatment Plant." *Water and Sew.* (Canadian), **46**, 20 (1943).

23. Bach, H., "Treatment of Sludge." *U. S. Pat. 2,315,577* (April 6, 1943).
24. Backmeyer, D., "Sludge Concentration and Disposal at Marion, Indiana." *This Journal*, **15**, 1201 (1943).
25. Backmeyer, D., "War Industries Increase Flow and B.O.D. at Activated Sludge Plant." *Sew. Wks. Eng.*, **14**, 22 (1943).
26. Barnes, L. B., "Effluent Used for Chlorinator." *Sew. Wks. Eng.*, **14**, 578 (1943).
27. Barton, B. H., "Interesting Extracts from Operating Reports." *This Journal*, **15**, 739 (1943).
28. Beals, C. E., "Water Pollution Control." *Nebraska Municipal Review*, 223, 8 (Feb., 1943).
29. Bell, E. A., "How's Your Supernatant?" *Water Wks. and Sew.*, 90, 281 (1943).
30. Belt, E., "A Sanitary Survey of Sewage Pollution of the Surf and Beaches of Santa Monica Bay." *Calif. Sew. Wks. Jour.*, **15**, 1, 27 (1943); also, *Rept. Bur. San. Eng., Calif. St. Bd. Pub. Health* (June, 1943).
31. Berg, E. J., "Management of Sludge Digesters." *This Journal*, **15**, 724 (1943).
32. Brandt, A. D., "Notes on an Accident at a Small Sewage Treatment Plant Resulting in the Deaths of Three Workers." *This Journal*, **15**, 1096 (1943).
33. Brinley, F. J., "The Effect of Pollution Upon the Plankton Population of the White River, Indiana." *Investigations of Indiana Lakes and Streams*, 2, 137–143 (1942). Indiana Dept. of Conservation, Indianapolis.
34. Brinley, F. J., "Sewage Algae and Fish." *This Journal*, 15, 1, 78–83 (1943).
35. Brintzinger, H., *German Pat. 736,171*.
36. Bunker, H. J., "The Corrosion of Mains in Clay." *The Surveyor*, 102, 443; also, 459 (1943).
37. Burn, G. A. H., "Studies in Stream Pollution." *Eng. Contract Rec.*, **56**, 14, 50 (1943).
38. Burr, F. K., "The Application of Ferric Salts in Water and Sewage Treatment." *Water Wks. and Sew.*, **90**, 347 (1943).
39. Callaham, J. R., "From Waste Liquors to War Alcohol." *Chem. and Met. Eng.*, **50**, 104 (Dec., 1943).
40. Camp, T. R., "The Effect of Turbulence in Retarding Settling." *Proc. Second Hydraulics Conf., Bulletin 27, Univ. Iowa Studies in Eng.* (1943).
41. Camp, T. R. and Stein, P. C., "Velocity Gradients and Internal Work in Fluid Motion." *Boston Soc. of Civil Eng.*, **30** (Oct., 1943).
42. Carlson, H. J. and McKhann, C. F., "Removal of Poliomyelitis Virus from Sewage by the Activated Sludge Process and the Separation from Sludge of an Antibacterial and Antiviral Substance." *Am. Jour. Pub. Health*, **33**, 1347 (1943).
43. Central Advisory Water Committee Report (England), "River Control." *H. M. Stationery Office* (1943); also *The Surveyor*, **102**, 2691, 345 (1943).
44. Cherkinskii, S. N. and Ginsburg, F. I., "Waste Water Containing Arsenic from the Manufacture of Paris Green." *Vodos. Sanit. Tekh.*, **14**, 2, 99 (1939); *Ges. Ing.*, **64**, 663 (1941).
45. Cleary, E. J., "Municipal Affairs and Sanitation Activities." *Eng. News-Rec.*, **130**, 191 (1943).
46. Cleary, E. J., "Sewage Disposal in South America." *Eng. News Rec.*, **131**, 551 (1943).
47. Cohn, M., "Equipment Maintenance in Time of War." *Sew. Wks. Eng.*, **14**, 469, 534 (1943).
48. Coleman, J. H., *U. S. Pat. 2,264,290*.
49. Connecticut State Water Commission, Hartford. Ninth Biennial Report for Years 1941–1942. *Public Document No. 78*.
50. Cram, E. B., "The Effect of Various Treatment Processes on the Survival of Helminth Ova and Protozoan Cysts in Sewage." *This Journal*, **15**, 1119 (1943).
51. Daily, J. M., *U. S. Pat. 2,320,512*.
52. Davis, T. L., "The Chemistry of Powder and Explosives." John Wiley and Sons (1943).
53. De Baun, R., "The Wealth that Flows to the Sea." *New Jersey Agr.*, **25**, 2, 7 (1943).
54. Demoll, R. and Liebmann, H., "Role of Filter Bed Material in Sewage Purification with Trickling Filters." *Ges. Ing.*, **65**, 55 (1942).
55. Dixon, R. M., *This Journal*, **15**, 1078 (1943).

56. Dobbins, W. E., "Effect of Turbulence on Sedimentation." *Proc. Amer. Soc. Civil Eng.*, **69**, 235 (1943).
57. Downes, F. A., "Sludge Digester." *U. S. Pat. 2,335,562* (Nov., 1943).
58. Drachev, S. M. and Skopintsev, B. A., "Chemical Characteristics of the River Volga in the Region Between Kalinin and the Mouth of the River Dubna According to Data of 1931–4." *Hydrochem. Material* (U.S.S.R.), **12**, 151 (1941).
59. Eberling, G., "The Action of Phenol-Containing Wastes as Related to an Investigation of the Section of the Rhine Between Mayence and Emmerich during the Years 1935–37." *Vom Wasser*, **14**, 81 (1939–40).
60. Edmondson, J. H. and Goodrich, S. R., "The Cyclo-Nitrifying Filter." *The Surveyor*, **102**, 5332 (1943).
61. Eldridge, E. F., "Recirculating Filter for Treatment of Slaughter Wastes." *Mich. Eng. Exp. Sta. Bull. No.* **96**, 18 (1942). Also *Water Wks. and Sewc.*, **90**, 449 (1943).
62. Eldridge, E. F., "Textile Waste Treatment, Yale Woolen Mills." *Mich. Eng. Exp. Sta. Bull.* **96**, 3 (1942).
63. Eliassen, R. and Schulhoff, H. B., "Grease Extraction from Sewage and Sludge." *This Journal*, **15**, 491 (1943).
63A. Eliassen, R. and Schulhoff, H. B., "Laundry Waste Treatment by Flotation." *Water Wks. and Sew.*, **90**, 418 (1943).
64. Ellis, M. M. and Ellis, M. D., "Photoelectric Determination of Dissolved Oxygen with Amidol." *This Journal*, **15**, 1115 (1943).
65. Escritt, L. B., "Continuous Flow Sedimentation in the Treatment of Sewage." *Surveyor*, **101**, 433 (1942).
66. Ettinger, M. B., Schott, S. and Ruehhoft, C. C., "Preservation of Phenol Content in Polluted River Water Samples Previous to Analysis." *Jour. Am. Water Wks. Assoc.*, **35**, 3, 299 (1943).
67. Faigenbaum, H. M., "Chemical Investigation of the Lake Ontario Watershed." *N. Y. State Conservation Dept. Biol. Survey No. 16, Suppl. to 29th Ann. Rept.* (1940).
68. Fales, A. L. and Greeley, S. A., "The Grease Problem in Sewage Treatment." *Proc. Amer. Soc. Civil Eng. Transactions, No. to*, 2, 507 (1943).
69. Fenlon, E. A., "How to Meet the Demand for Better Waste Disposal." *Food Industries*, 84 (July, 1943).
70. Fischer, A. J., "Vacuum Flotation." *Eng. News Rec.*, **130**, 297 (1943).
71. Fischer, A. J., "Vacuum Flotation of Sewage and Industrial Wastes." *Mich. Eng. Exp. Sta. Bull.* **98**, 13 (1943).
72. Flower, G. E., "Southerly Sewage Treatment Plant." *This Journal*, **15**, 110 (1943).
73. Flu, P. C., "Are Bacteriophage Indicative of Self-Purification of Surface Water?" Leeuwenhoek. *Jour. Microbiol. Serol.*, **7**, 93 (1941).
74. Franks, J. T., "Interesting Extracts from Operation Reports—Army Post XVII." *This Journal*, **15**, 554 (1943).
75. Franks, J. T. and Ohma, C. A., "Operating Experiences at Army Sewage Treatment Plants." *This Journal*, **15**, 1088 (1943).
76. Frazier, R. W., "Oshkosh, Wisconsin, Sewage Treatment Plant." *Sew. Wks. Eng.*, **14**, 424 (1943).
77. Gehm, H. W., "A Rapid Method for Determining Grease in Sewage and Sludges." *Water Wks. and Sew.*, **90**, 305 (1943).
78. Gehm, H. W., "Recovery of Free Acid From Pickling Liquors." *Ind. Eng. Chem.*, **35**, 1003 (1943).
79. Genter, A. L., "Dewatering, Incineration, and Use of Sewage Sludge—A Symposium—Discussion." *Proc. Amer. Soc. of Civil Eng.*, **69**, 323 (1943).
80. Gerdel, W. E., "Westerly Sewage Treatment Plant." *This Journal*, **15**, 104 (1943).
81. Gerdel, W. E., "Problems of Plant Operation and Coordination." *This Journal*, **15**, 1183 (1943).
82. Gifft, H. M., "The Mathematics of B.O.D. Determinations." *Water Wks. and Sew.*, **90**, 8, 313 (1943).
83. Giles, J. H. L., "Inlet and Outlet Design for Sedimentation Tanks." *This Journal*, **15**, 609 (1943).

84. Gilliland, J. R. and Vaughn, R. H., "Biochemical Characteristics of Pigmented Coliform Bacteria." *Jour. Bact.*, **45**, 499 (1943).
85. Goldthorpe, H. H., "A Cubic Yard of Percolating Bed Material and a Few Assumptions Based on Experimental Evidence." *The Surveyor*, **102**, 177, 243 (1943).
86. Goldthorpe, H. H. and Nixon, J., "Treatment of Sewage on Percolating Filters at Huddersfield." *The Surveyor*, **101**, 425 (1942).
87. Gordon, E., "Purification of Sewage from Cysts of Intestinal Protozoa." *Med. Parasitol. Parasitic Diseases* (U.S.S.R.), **10**, 236 (1941).
88. Gottlieb, W. H., "Fifty Thousand Hours of Gas Engine Service." *Sew. Wks. Eng.*, **14**, 412 (1943).
89. Gould, R. H., "Improved Final Settling Tanks at Bowery Bay." *Civil Eng.*, **13**, 279 (1943).
90. Grant, C. W. and Zobell, C. E., "Oxidation of Hydrocarbons by Marine Bacteria." *Proc. Soc. Exp. Biol. and Med.*, **51**, 266 (1942).
91. Grassey, R. G., "The Use of Turbidity Determinations in Estimating the Suspended Load of Natural Streams." *Jour. Amer. Water Wks. Assoc.*, **35**, 4, 439 (1943).
92. Gray, H. F. and Ludwig, H. F., "Characteristics and Treatment of Potato Dehydration Wastes." *This Journal*, **15**, 71 (1943). Also *Calif. Sew. Wks. Jour.*, **15**, 1, 64 (1943).
93. Greeley, S. A., "High-Rate Biological Treatment." *This Journal*, **15**, 1062 (1943).
94. Griffith, L. B., "Contact Aeration for Sewage Treatment." *Eng. News-Rec.*, **130**, 138 (1943).
95. Groff, G. and Ridenour, G. M., "Effect of Break-Point Chlorination on the B.O.D. of Sewage." *This Journal*, **15**, 847 (1943).
96. Gunson, C. P., "Controlled Heat and Mixing Improve Stage Digestion." *Sew. Wks. Eng.*, **14**, 20 (1943).
97. Hamlin, E. J., "The Maintenance, Operation and Control of Sewage Treatment Plants." *Trans. of the Minutes of Proc. of the South African Society of Civil Engineers*, 17–26 (1942).
98. Hansen, C. A. and Gotaas, H. B., "Sewage Treatment by Flotation." *This Journal*, **15**, 242 (1943).
99. Hatch, B. F., "Sewage Treatment at Military Installations." *This Journal*, **15**, 839 (1943).
100. Haupt, H., "Stream Pollution and Questions of the Locations of Industries Producing Waste Waters." *Gas. Ing.*, **64**, 567 (1941).
101. Henderson, Y., "The Return of the Pulmotor as a 'Resuscitator': A Back-Step Toward Death of Thousands." *Sci.*, **98**, 547 (1943).
102. Hendrick, W. B., "Outgrowing an Activated Sludge Plant." *Munic. City*, **58**, 7, 44 (1943).
103. Henry, R. A., *U. S. Pat. 2,306,523.*
104. Heukelekian, H., "Effect of the Addition of Sodium Nitrate to Sewage on Hydrogen Sulfide Production and B.O.D. Reduction." *This Journal*, **15**, 259 (1943).
105. Hodge, W. W. (to Mellon Institute of Industrial Research), *U. S. Patent 2,322,134* (1943).
106. Hoffman, S., "Contributions to the Biology of Activated Sludge." *Arch. Hyg., Berl.*, **126**, 175 (1941); *Summary of Current Literature*, **15**, 91 (1942); *Public Health Eng. Abst.*, **23**, 49 (1943).
107. Holtje, R. H., "The Biology of Sewage Sprinkling Filters." *This Journal*, **15**, 14 (1943).
108. Horne, R. W., "Compact Sewage Treatment Works Units at Cranston, Rhode Island." *Civ. Eng.*, **13**, 417 (1943).
109. Horne, R. W., "A Complete Sewage Treatment Works at Cranston, Rhode Island." *Sew. Wks. Eng.*, **14**, 290 (1943).
110. Horne, R. W., "Up-to-the Minute Cranston, Rhode Island, Sewage Disposal Plant and Sewerage System." *Pub. Wks.*, **74**, 5, 20 (1943).
111. Howland, W. E., "Mathematical Formulation of the Oxygen Sag." *This Journal*, **15**, 3, 512 (1943).
112. Howson, J. T., "Standard Rate Filter Operation Experiences at Westfield, New York." *This Journal*, **15**, 817 (1943).

113. Hupp, E. R., "Plankton and Its Relationship to Chemical Factors and Environment in the White River Canal, Indianapolis, Ind." *Butler University Botan. Studies*, **6**, 30 (1943).

114. Hurley, J., "River Control with Special Reference to Pollution Prevention." *The Surveyor*, **102**, 455 (1943).

115. Husmann, W., "Chemical Aspects of Sewage Discharge into Streams." *Ges. Ing.*, **64**, 571 (1941).

116. Hutchison, D., Weaver, R. H. and Scherago, M., "The Incidence and Significance of Microorganisms Antagonistic to *Escherichia* in Water." *Jour. Bact.*, **45**, 29 (1943).

117. Hyde, C. G., "Shore Pollution Reduction at San Francisco." *This Journal*, **15**, 1 (1943).

118. Hyde, C. G. and Rawn, A. M., "Developments in Sewerage and Sewage Treatment." *Water Wks. and Sew.*, **90**, 41 (1943).

119. Inlev, V. S., "Chemical Sketch of River Piasina." *Hydrochem. Material* (U.S.S.R.), **12**, 169 (1941).

120. Jackson, R. B., "The Chyronomid Fly and Its Effect on the Activated Sludge Process." *Mich. Eng. Exp. Sta. Bull.*, **98**, 42 (1943).

121. Jenkens, S. H. and Lockett, W. T., "Loss of Phosphorus During Sewage Purification." *Nature*, **151**, 306 (1943).

122. Jessup, A. H., "Two Stage Biofiltration Sewage Treatment Plant for an Army Camp." *Civil Eng.*, **13**, 168 (1943).

123. Johnson, F. E., "Rehabilitation of Trickling Filter Beds." *This Journal*, **15**, 91 (1943).

124. Johnson, J. W., "Sewage Plant Maintenance in Wartime: Mechanical Units." *This Journal*, **15**, 262 (1943).

125. Johnson, L. M., "Sludge Drying Developments at Chicago, Ill." *Proc. Amer. Soc. Civil Eng.*, **69**, 1015 (1943).

126. Jones, C. B. O., "Pretreatment of Waste Effluents." *Surveyor*, **102**, 437 (1943).

127. Jordan, G., "Representation of the Quality of Water in Running Streams." *Paper Fabr.*, **40**, 58 and 66 (1942).

128. Jung, H., *German Pat. 725,879.*

129. Jung, H. and Schröder, W., *German Pat. 724,206.*

130. Kabakova, L. F. and Vil'gel'mov, V. N., "Biological Purification of Phenolic Waste Waters." *Inst. Vodosnabzheniya Kanalizatsii Hidrotekh. Sooruzhenii i Inzhenernoi Hidrogeol.*, 1940 (part 1), 5. *Khim. Referat. Zhur.*, 1940, 8, 81.

131. Kazachkov, L. I., "Waste Waters of Coke Chemical Plants." *Sanit. Kharakteristika Prom. Stochnykh Vod* 1940, 37; *Khim. Referat. Zhur.*, 1940, 9, 80.

132. Kazachkov, L. I., "Waste Waters of Aluminum Plants." *Sanit. Kharakteristika Prom. Stocknykh Vod* 1940, 69; *Khim. Referat. Zhur.*, 1940, 9, 80.

133. Keefer, C. E. and Kratz, H., Jr., "Experiments With High Rate Trickling Filters at Baltimore." *This Journal*, **12**, 477 (1940).

134. Kehr, R. W. and Butterfield, C. T., "Notes on the Relation Between Coliform Organisms and Enteric Pathogens." *Pub. Health Repts.*, **58**, 589 (1943).

135. Kehr, W. Q. and Johnson, W. S., "A Study of the Pollution of the Meramec River." *Rept. Eng. Div. of the Missouri State Bd. of Health*, **42** (1943).

136. King, W. E., "The Cokato Sewage Disposal Plant." *Water Wks. and Sew.*, **90**, 359 (1943).

137. King, W. E., "Lakefield, Minnesota, Sewage Disposal Plant." *Sew. Wks. Eng.*, **14**, 493 (1943).

138. Klassen, C. W., "Illinois War Industries Utilize and Treat Wastes." *Sew. Wks. Eng.*, **14**, 372 (1943).

139. Klein, L., "The Strength of Sewage; Some Comparative Results." *Jour. Proc. Inst. Sew. Purif.*, **174** (1941).

140. Kozma, A. B., "Joint Meeting Rutherford, East Rutherford, Carlstadt, Bergen County, New Jersey Treatment Plant." *Sew. Wks. Eng.*, **14**, 32 (1943).

141. Kozma, A. B., "Victory Garden Demonstrates Sludge." *Sew. Wks. Eng.*, **14**, 133 (1943).

142. Kozma, A. B., "The Design of Digestion Tanks for Efficient Gas Production." *Water Wks. and Sew.*, **90**, 25 (1943).

143. Kunsch, W. M., "Danbury, Connecticut." *This Journal*, **15**, 1211 (1943).
144. Kurtz, A. L., "Digestion of Sewage Solids and Like Matter." *U. S. Pat. 2,331,031* (1943).
145. Lackey, J. B. and Dixon, R. M., "Some Biological Aspects of the Hays Process of Sewage Treatment." *This Journal*, **15**, 1129 (1943).
146. Lackey, J. B., "The Effects of Distillery Wastes and Waters on the Microscopic Flora and Fauna of a Small Creek." *Pub. Health Repts.*, **57**, 253 (1942).
147. Lackey, J. B., "The Plankton, Algae and Protozoa of Two Tennessee Rivers." *Am. Midland Naturalist*, **27**, 191 (1942).
148. Lackey, J. B., Wattie, E., Kachmar, J. F. and Placak, O. R., "Some Plankton Relationships in a Small Stream." *Am. Midland Naturalist*, **30**, 2, 403 (1943).
149. Lamb, P., "Worcester Sewage Works Extensions." *The Surveyor*, **102**, 411 (1943).
150. Lauster, K. C., "Some Low Temperature Biochemical Oxygen Demand Observations." *Official Bull. North Dakota Water and Sew. Conf.*, **10**, 17 (1942).
151. Leist, E. F., "Fitting Chemical Precipitation to a Sewage Treatment Plant." *Amer. City*, **58**, 1, 47 (1943).
152. Levine, M., *U. S. Pat. 2,317,782* (1943).
153. Linderman, I. E., "Treatment of Milk Waste, United Milk Products Company, Berne, Indiana." Ind. St. Bd. of Health, *Sewage Gas*, **5**, 19 (1942).
154. Littman, M. L., "Rapid Identification of Enteric Pathogenic Bacteria." *War Medicine*, **4**, 31 (1943).
155. Lovett, M., "Some Recent Developments in the Biological Treatment of Settled Sewage." *The Surveyor*, **101**, 371, 381, and 401 (1942).
156. Lynch, J. T. and Mann, U. T., "Rotary Vacuum Filtration of Sludge and the Effect of War on Operation." *This Journal*, **15**, 807 (1943).
157. MacDowell, R. F., "Kingsford Heights, Housing Project Sewage Treatment Plant." *Sew. Wks. Eng.*, **14**, 548 (1943).
158. Mahlie, W. S., "Industrial Waste Pretreatment at Fort Worth, Texas." *This Journal*, **15**, 521 (1943).
159. Maine Sanitary Water Board, Augusta. *Bull. 1* (1942).
160. Manchester, City of; Rivers Department Report for the Two Years Ended, 31, March, 1942.
161. Marshall, A. M., *U. S. Pat. 2,314,123* (1943).
162. Marshall, W. B., "Post War Projects of Sewage Works Equipment Manufacturers." *This Journal*, **15**, 1054 (1943).
163. Mass. Dept. of Public Health Division of San., *Eng. Ann. Rept.* (1941).
164. Mathis, A. L., "An Easier Method for Determining Suspended Solids." *Water Wks. and Sew.*, **90**, 386 (1943).
165. Maxcy, K. F., "Hypothetical Relationship of Water Supplies to Poliomyelitis." *Amer. Jour. Pub. Health*, **33**, 41 (1943).
166. Maxcy, K. F. and Howe, H. A., "The Significance of the Finding of the Virus of Infantile Paralysis in Sewage." *This Journal*, **15**, 1101 (1943).
167. McAllister, R. W., "Physical Test Methods for Lime and Their Significance in Industrial Application." *National Lime Assoc. Monograph* (1942).
168. McGaughey, P. H., Eich, H. F., Jackson, H. W. and Henderson, C., "A Study of the Stream Pollution Problem in the Roanoke, Virginia, Metropolitan District." *Bull. Virginia Polytechnic Insti.*, **35**, 120 (1942).
169. McKeeman, E. C., "Operation of Freeport, Long Island Sewage Treatment Plant Before and After Improvements." *This Journal*, **15**, 828 (1943).
170. McLean, D. L., "A Review of Developments in Sludge Digestion Processes." *Eng. and Contr. Rec.*, **56**, 34, 17 (1943).
171. McLean, D. L., "Sewage Sludge Digestion." *Water and Sew.*, **81**, 8, 13 (1943).
172. McLellan, R. A., "Sewage Treatment at Air Training Schools in Western Canada." *Water and Sew.* (Toronto), **81**, 15 (1943).
173. Michigan Stream Control Commission, Lansing. *Sixth Biennial Rept. for Years 1941–1942.*

174. Minkevich, I., Joffe, F. and Shafir, A., "Direct Detection of Typhoid-Paratyphoid Bacteria and of Para-Agglutinable Strains of Bact. Coli as Criteria in the Epidemiological Evaluation of Water Pollution." *Jour. Microbiol., Moscow*, **5**, 114 (1940); *Sum, Current Lit.*, **15**, 45 (1942).

175. Moerk, F. N. and Eisenberg, G. M., "Sewage Treatment." *U. S. Pat. 2,326,303* (1943).

176. Mohlman, F. W., "Industrial Wastes in Wartime." *This Journal*, **15**, 1164 (1943).

177. Mohlman, F. W., "Industrial Waste Disposal." *Chem. and Met. Eng.*, **50**, 127 (1943).

178. Monteverde, J. J. and Ferramola, R., "Investigation of Bacteria of the Genus Salmonella in the Liquid Sewage of the City of Buenos Aires." *Anales. Soc. Cient. Argentina*, **133**, 417 (1942).

179. Moore, W. A. and Ruehhoft, C. C., "Oxidation Reduction Studies. II. Oxidation Reduction Potentials Developed in Sewage and Sewage Activated Sludge Mixtures." *This Journal*, **15**, 880 (1943).

180. Moseley, H. H., "Papillon Creek Sewage Treatment Plant, Omaha, Neb." *Sew. Wks. Eng.*, **14**, 251 (1943).

181. Moshel, A. I., "A Test for the Detection of Organic Substances in Water." *Lab. Prakt* (U.S.S.R.), **14**, 12, 24 (1939).

182. Mortenson, E. N., "Are You Losing War Materials and Dollars Down Your Sewer?" *National Provisioner*, Apr. 24, May 1, 1943.

183. Mudd, S., "Changes in the Bacterial Cell Brought About by the Action of Germicides and Antibacterial Substances as Demonstrated by Electron Microscope." *Amer. Jour. Pub. Health*, **33**, 167 (1943).

184. Nelson, F. G., "Treatment of Sewage by the Biofiltration System." *Official Bull. North Dakota Water and Sew. Wks. Conf.*, May, 1943.

185. Ohio River Pollution Survey—Final Rept. to the Ohio River Comm., U. S. Pub. Health Serv., Office of Stream San., Cincinnati, Ohio. Three volumes, 793 pages, plus six supplements 823 pages (1943).

186. Pacific Flush-Tank Co., "The P.F.T. Supernatant Liquor Treater, Advertisers' Contributions." *This Journal*, **15**, 1018 (1943).

187. Palmer, C. L., "Filter Room Practice—Vacuum Filter Economy." *This Journal*, **15**, 547 (1943).

188. Petrilli, F. L., "Importance of the Presence of Bacteriophage for Self-Purification of Lake Water Containing Different Amounts of Pollution." *Igiene Mod.*, **6**, 207 (1940).

189. Phelps, B. D., "Solving Boomtown, San Diego, Sewage Problem." *Pub. Wks.*, **74**, 7, 14 (1943).

190. Pillai, S. C., "The Function of Protozoa in the Activated Sludge Process." *Curr. Sci.*, **10**, 84 (1941); *Summary of Curr. Lit.*, **14**, 151 (1941); *Pub. Health Eng. Abst.*, **23**, 45 (1943).

191. Pillai, S. C. and Subrahmanyan, V., "Role of Protozoa in the Activated Sludge Process." *Nature*, **150**, 525 (1942); *Chem. Abst.*, **37**, 1216 (1943).

192. Porter, H. F., "High-Degree Treatment for Camp Sewage." *Eng. News Rec.*, **130**, 106 (1943).

193. Porter, H. F., "Improvised Sewage Treatment at an Army Camp." *Pub. Wks.*, **74**, 6, 14 (1943).

194. Reid, G. G., "Sewage Treatment for the R.C.A.F. by Trickling Filters." *Water and Sew.* (Toronto), **80**, 29 (1942).

195. Reinke, E. A. and Pratt, J. W., "Sewage Disposal Practice at Military Establishments in California." *Calif. Sew. Wks. Jour.*, **14**, 38 (1942).

196. Ridenour, G. M., Carlson, H. J. and McKhann, C. F., "Effect of Activated Sludge Process on Poliomyelitis Virus." *This Journal*, **15**, 673 (1943); *Amer. Jour. of Pub. Health*, **33**, 1083 (1943).

197. Rohlich, G. A., "Oxidation Reduction Potential Measurements in Activated Sludge and Activated Sludge Sewage Mixtures." *Sew. Wks. Eng.*, **14**, 348 (1943).

198. Rostenbach, R. E. and Waterman, E. L., "Sedimentation of Sewage." *This Journal*, **15**, 453 (1943).

199. Rowntree, B., "Fish Ladder Aerator Improves Supernatant Liquor." *Sew. Wks. Eng.*, **14**, 415 (1943).

200. Rudgal, H. T., "War Time Problems in Sewage Treatment." *Sew. Wks. Eng.*, **14**, 94 (1943).
201. Rudolfs, W., "Pre-Treatment of Acid Chemical Wastes." *This Journal*, **15**, 48 (1943).
202. Rudolfs, W., Committee Report, "Survey of Sewage Research Projects." *This Journal*, **15**, 466 (1943), and **15**, 702 (1943).
203. Rudolfs, W., "Concentration of Activated Sludge by Compacting and Flotation." *This Journal*, **15**, 642 (1943).
204. Rudolfs, W., "Acid Waste Treatment with Lime." *Ind. Eng. Chem.*, 35, 227 (1943).
205. Rudolfs, W., "Effect of Lime in Coagulation of Sewage." *Pub. Wks.*, 73, 15 (1942).
206. Rudolfs, W. and Maggio, W. A., "Hydrated Lime in Sewage Treatment." *Pub. Wks.*, **74**, 1, 11 (1943).
207. Rudolfs, W. and Faulk, L. L., "Treatment of Supernatant Digester Liquor." *Pub. Wks.*, **74**, 8, 13 (1943).
208. Rudolfs, W. and Nickol, G. B., "Two Step Lime Addition for Sewage Coagulation and pH Control." *Pub. Wks.*, **74**, 9, 30 (1943).
209. Rudolfs, W. and Heukelekian, H., "Relation Between Stream Flow and Quantities of Nitrates." *Sew. Wks. Eng.*, **14**, 349 (1943).
210. Sage, D. N. and Spaulding, E. H., "A Study of Two Atypical Strains of Eberthella Typhosa." *Jour. Bact.*, **44**, 647 (1942).
211. Sawyer, C. N., Rohlich, G. A. and Tomek, A. O., "Studies on Activated Sludge at Two Rivers, Wisc." "Part I. Effect of Preaeration of Sewage and Wasting of Activated Sludge." *Sew. Wks. Eng.*, **14**, 65 (1943).
212. Sawyer, C. N. and Rohlich, G. A., "Studies on Activated Sludge at Two Rivers, Wisc." "Part II. Stage Addition of Activated Sludge." *Sew. Wks. Eng.*, **14**, 234 (1943).
213. Schaetzle, T. C., "Wartime Effects on Treatment Plants." *This Journal*, **15**, 1193 (1943).
214. Schick, V. R., "Electrolysis and Corrosion Damage Digester Heating Coils." *Sew. Wks. Eng.*, **14**, 540 (1943).
215. Schneider, P. C., *U. S. Pat. 2,310,655.*
216. Schott, S., Ruchhoft, C. C. and Megregian, S., "Laboratory Study of TNT Wastes." *Ind. Eng. Chem.*, **35**, 1122 (1943).
217. Schreiber, A., "The Circulating Trickling Filter." *Gesundh. Ind.*, **6**, 247 (1942).
218. Schreiber, A., "Entwickelung neuer Wege zur Biologischen Abwasserreingigung." *Zeits. Verein deutscher Ingenieure*, **85**, 391 (1941).
219. Scott, R. D., "Determination of Phenol Content of Surface Waters." *Jour. Amer. Water Wks. Assoc.*, **35**, 592 (1943).
220. Schwarz, K. E., Schroder, H. J. and Stackelberg, M. V., "The Polarographic Determination of Surface Active Substances in Water." *Z. Electrochem.*, **48**, 6 (1942).
221. Setter, L. R., "Modified Sewage Aeration. Part I." *This Journal*, **15**, 629 (1943).
222. Skopintsev, B. A. and Drachev, S. M., "Chemical Characteristics of Rivers Dubna, Sestra, Yakhroma, Iksha and Volgusha According to Data of 1932–33." *Hydrochem. Material* (U.S.S.R.), **12**, 155 (1941).
223. Skopintsev, B. A., "Composition of the Volga and Several Rivers of the Volga Basin During the Period in Which They Are Frozen Over." *Hydrochem. Material* (U.S.S.R.), **12**, 159 (1941).
224. Slagle, E. A., *U. S. Pat. 2,312,198.*
225. Smith, E. E., "Control of Activated Sludge Bulking by Chlorination." *Water Wks. and Sew.*, **90**, 209 (1943).
226. Smith, H. G., "Ventilation of Large Sewers in Los Angeles." *Calif. Sew. Wks. Jour.*, **15**, 1, 71 (1943).
227. Smith, R. S. and Walker, W. W., "Smokeless Powder Wastes." *Pub. Health Repts.*, **58**, 1373 (1943).
228. Smith, R. S., "Tetryl Wastes." *Pub. Health Repts.*, **58**, 1404 (1943).
229. Smith, R. S., "Nitroglycerine Wastes." *Pub. Health Repts.*, **58**, 1409 (1943).
230. Snell, J. R., Anaerobic Digestion. II.—Nitrogen Changes and Losses During Anaerobic Digestion." *This Journal*, **15**, 56 (1943).
231. Snell, J. R., "Anaerobic Digestion. III.—Anaerobic Digestion of Undiluted Human Excreta." *This Journal*, **15**, 679 (1943).

232. Sperry, W. A. "Interesting Extracts from Operation Reports—Aurora (Ill.) Sanitary District—1942." *This Journal*, **15**, 949 (1943).

233. Sperry, W. A., "Gas Engine Operation at Aurora, Illinois." *Sew. Wks. Eng.*, **14**, 479 (1943).

234. Squire, A. B., "Manchester, N. Y. Sewage Treatment Plant." *Sew. Wks. Eng.*, **14**, 338 (1943).

235. Starkey, R. L. and Wight, K. M., "Soil Areas Corrosive to Metallic Iron Through Activity of Anaerobic Sulfate-Reducing Bacteria." *Amer. Gas. Assoc. Monthly*, May, 1943.

236. Straub, C. P., "Digestion Studies on Pure Vegetables." *This Journal*, **15**, 658 (1943).

237. Straub, C. P., "Digestion Studies on Paper Pulp." *This Journal*, **15**, 857 (1943).

238. Stuart, C. A., Wheeler, K. M., Rustigan, R. and Zimmerman, A., "Biochemical and Antigenic Relationships of the Paracolon Bacteria." *Jour. Bact.*, **45**, 101 (1943).

239. Taylor, H. W., "Sludge Gas Engines." *Amer. City*, **58**, Mar. p. 62, Apr. p. 62, May p. 73 (1943).

240. Thatcher, H. D., "Acid Neutralization Plant with Mechanical pH Control." *The Surveyor*, **102**, 463 (1943).

241. Thomson, R. C., "Studies on the Behavior of Anopheles Minimus. Part IV. The Composition of the Water and the Influence of Organic Pollution and Silt." *Jour. Malaria Inst. of India*, **4**, 63 (1941).

242. Tödt, F., *Ges. Ing.*, **65**, 76 (1942).

243. Tomlinson, T. G., "Some Aspects of Microbiology in the Treatment of Sewage." *Jour. Soc. Chem. Ind. Trans. and Comm.*, **61**, 53 (1942).

244. Tomlinson, T. G., "The Nitrifying Activity of the Biological Film from Different Depths in Percolating Filters Treating Sewage by the Processes of Alternating Double Filtration and Single Filtration." *Proc. Soc. Agr. Bact.*, **13**, 5 (1942).

245. Uhlman, P. A., "Three Years' Treatment of Sewage at Celina, Ohio." *Pub. Wks.*, 73, 3, 13 (1943).

246. Van Kleeck, L. W., "Discussion of Industrial Wastes in Wartime." *This Journal*, **15**, 1177 (1943).

247. Van Kleeck, L. W., "Sludge as Fertilizer in the War Emergency—Its Place and Use in Victory Gardening." *Water Wks. and Sew.*, **90**, 177 (1943).

248. Velzy, C. R., Fuhrman, R. E., Schroepfer, G. V., Van Kleeck, L. W., Dundas, W. A. and McLaughlin, C. P., "Dewatering, Incineration and Use of Sewage Sludge—A Symposium." *Proc. Amer. Soc. of Civil Eng.*, **69**, 42 (1943).

249. Viehl, K., "The Effect of the Content of Oxygen on the Biochemical Oxygen Demand and on the Natural Self-Purification of Water as well as on the Activated Sludge Process." *Zeits. f. Hygiene und Infections Krankheiten*, **122**, 533 (1940).

250. Vokes, F. C. and Jenkins, S. H., "Sewage Works Modification, Yardley (Birmingham) Plant Alterations and Additions." *The Surveyor*, **102**, 121 (1943).

251. Vokes, F. C. and Jenkins, S. H., "The Yardley Sewage Disposal Works of the Birmingham, Tame and Rea District Drainage Board." *Jour. Inst. Civ. Eng.*, **2**, 65 (1942)

252. Wallace, W. M. and Habermehl, C. A., "Two Years Operation of Detroit Sewage Treatment Plant." *Mich. Eng. Bull.*, **98**, 29 (1943).

253. Walton, G., "High Daily Rate Trickling Filter Performance." March, 1943 Report Made under the Direction of the Bd. of State Health Commissioners, Upper Miss. River Basin San. Agreement.

254. Wattie, E., "Cultural Characteristics of Zooglea Forming Bacteria Isolated from Activated Sludge and Trickling Filters." *This Journal*, **15**, 476 (1943).

255. Weidner, J. P., "Cooperative Research Program on Sulfite Waste Liquor." *Paper Mill News*, **66**, 14 (1943).

256. Weldert, R., "The Maintenance of the Purity of Our Streams." *Chemikerztg.*, **65**, 384 (1941).

257. Wells, W. N., "Chrome Wastes in an Activated Sludge Plant." *24th Texas Short School*, Austin (1943).

258. Weston, A. D., "Community Sanitation in Wartime." *Water Wks. and Sew.*, **90**, 337 (1943).

259. White, G. W., "Enlargement of Disposal Plant of Spartanburg, S. C." *Water Wks. and Sew.*, **90**, 241 (1943).
260. Wilson, H. and Hamlin, E. J., "Eighth Annual Report on Sewage Disposal, Johannesburg" (1939–40).
261. Wirts, J. J., "Operating the Easterly." *Amer. City*, **58**, 3, 37 (1943).
262. Wirts, J. J., "Report on Operation of the Easterly Sewage Treatment Plant, Cleveland, Ohio." *This Journal*, **15**, 99 (1943).
263. Wirts, J. J., "Economies of Cleaning Air Diffusion Media." *Water Wks. and Sew.*, **90**, 205 (1943).
264. Wisely, W. H., "Sewage Sludge for Victory Gardens?—Editorial." *This Journal*, **15**, 710 (1943).
265. Wisely, W. H., "Summary of Experience in Diffused Air Activated Sludge Plant Operation." *This Journal*, **15**, 909 (1943).
266. Wishart, J. M., Jepson, C. and Klein, L., "Vacuum Filtration of Sewage Sludge." *Nature*, **152**, 249 (1943).
267. Wittwer, N. C., "Theory and Practice of Sewage Sludge Digestion Tank Heating." *Water Wks. and Sew.*, **90**, 229 (1943).
268. Wolman, A., "Stream Pollution Abatement to Cost a Billion Dollars." *Sew. Wks. Engr.*, **14**, 135 (1943).
269. Yeomans, C., *U. S. Pat. 2,314,182* (1943).
270. Young, C. H., "Treatment of Cherry Waste Waters." *Pub. Wks.*, **74**, 24 (1943).
271. Yushok, W. and Bear, F. E., "Poultry Manure." *N. J. Agr. Exp. Sta. Bull. 707* (1943).
272. Zhdanov, S. P., "Peculiarities of the Winter Hydrochemical Regime of the Volga River in 1939–40 and Their Causes." *Compt. Read. Acad. Sci.* (U.S.S.R), **33**, 84 (1941).
273. Zhukov, A. I., "Filtration Fields for Purifying Waste Waters from Gas Generating Stations." *Inst. Vodosnabzheniya Kanalizatsii Hidrotekh. Sooruzhenii i Inzhenernoi Hidrogeol.*, 1940 (Part I), 36–57; *Khim. Referat. Zhur.*, 1940, 9, 82.
274. Zobell, C. E., "Effect of Solid Surfaces upon Bacterial Activity." *Jour. Bact.*, **46**, 39 (1943).
275. Zobell, C. E. and Grant, C. W., "Bacterial Utilization of Low Concentrations of Organic Matter." *Jour. Bact.*, **45**, 555 (1943).

MODIFIED SEWAGE AERATION—PART II

By Lloyd R. Setter and Gail P. Edwards

Principal Sanitary Chemist and Chief of Laboratories, New York City Department of Public Works, Bureau of Sewage Disposal Operation

The modified sewage aeration studies previously reported (2) showed that an average of 75 to 85 per cent of the presettled sewage influent suspended solids and B.O.D. was removed after three hours aeration followed by one to two hours settling when the aeration tank suspended solids were maintained at 150 to 500 p.p.m. A lesser degree of treatment was achieved when only aeration tank effluent was returned. In the study 58 tests of seven or more days duration were grouped into three types of aeration and each type was further subdivided into 5 or 6 ranges of similar aeration period. Within a given range of similar aeration period the tests varied considerably with respect to the amount and concentration of returned sludge, the temperature or season of the year, the concentration of influent B.O.D. load, the aeration tank suspended solids, the dissolved oxygen condition in the aeration and final tanks, the adoption of step aeration, etc. Often several tests of apparently similar operating conditions produced significantly different effluent qualities.

It is the purpose of this paper to indicate a method of combining variables so that each test falls into a coherent pattern permitting rational interpretation and to indicate the limitations and possibilities of modified sewage aeration.

Expression of Effluent Quality

The quality of the final effluent as measured in parts per million of suspended solids and B.O.D. is a function of the influent quality. Also, similar to many physical, chemical and biological reactions, the unimolecular reaction may be assumed to apply to modified sewage aeration. The unimolecular reaction mathematically says that a constant percentage of remaining substance reacts in unit time. Thus if 50 per cent or 50 of 100 p.p.m. are removed in 1 hour then 50 per cent of the remaining or 25 p.p.m. will be removed in the second hour and 50 per cent of the remaining or 12.5 p.p.m. will be removed in the third hour. Many will recognize this as the law of diminishing returns. Seemingly discrepant results of sewage aeration fit into a logical treatment pattern when the effluent on tests of relatively similar detention, temperature, and operating conditions is expressed as a percentage of the influent quality.

The Aeration Period

Since the above reaction rate bears a logarithmic relation to the time of contact it is important to have an accurate estimation of the aeration

period. The calculation of the aeration period as the capacity of the aerator divided by the sewage flow plus the return flow may be entirely satisfactory for activated sludge when a return flow of 25 per cent or less is relatively constant. However, such a simple aeration period leads to gross errors when 20 to 100 per cent of aeration liquor or sludge is returned or when a process of step aeration is studied. In the pilot plant studies the sewage detention period obtained by dividing the capacity of the aerator in gallons by the sewage flow in gallons per hour and the aerator contact period obtained by dividing the capacity of the aerator in gallons by the sewage plus return flow in gallons per hour were averaged to give the aeration period in hours. In step aeration tests the contact period was determined separately for each pass and then totalized.

Temperature

Tests performed during different seasons of the year under fairly similar operating conditions produced particularly discordant results. From a knowledge of the effect of temperature on the speed of chemical and biological reactions it was obvious that the most important factor contributing to the apparent discrepancies was that of temperature. In order to correct or account for the temperature variance resource was taken in Phelps' (1) comprehensive studies on the effect of temperature on the deoxygenation of dilute sewage. According to his investigations the deoxygenation coefficient at any temperature, t, is equal to 0.1 times $1.047^{(t-20)}$; where t is the temperature in degrees Centigrade. The 0.1 factor in the formula refers to the deoxygenation at 20° C. for dilute sewage as in streams and applies to specific conditions of aerobic activity. The $1.047^{(t-20)}$ is the temperature factor which probably has general application to aerobic activity. Thus, the relative rather than the absolute deoxygenation value at different temperatures has special merit in sewage treatment. A convenient arrangement of the relative deoxygenation (or activity of aerobic microorganisms) at different temperatures in degrees Fahrenheit is as follows:

Temp. F.	Relative Activity
50	0.63
55	0.72
60	0.815
68	1.00
70	1.05
75	1.195
80	1.35

The table shows that over the normal sewage temperature range at Wards Island (50 to 80° F.) the microbial activity more than doubles. The higher the temperature the greater the activity or the more work (aerobic decomposition) done in unit time. Thus, the effect of temperature is one of lengthening or shortening the time factor or aeration period. In order to compensate for the effect of temperature so that summer and winter tests are directly comparable, it is necessary to multiply

the observed aeration period by the relative activity factor to obtain an "equivalent aeration period" at 68° F. By the adoption of this method of combining variables otherwise discordant seasonal results fit into a logical pattern of treatment.

Dissolved Oxygen

Tests performed under conditions of no dissolved oxygen in part of the system during part of each day usually produced poorer results than when oxygen was present throughout the system most of the time. Since the mixed liquor demand for oxygen varies from 1.5 to 3 p.p.m. in 30 minutes depending primarily on the momentary B.O.D. loading and the concentration of "returned" solids amounting to 100 to 400 p.p.m. of suspended solids in the aerator, a dissolved oxygen of about 3 p.p.m. in the aerator effluent was found necessary to maintain aerobic conditions throughout the system. At least traces of dissolved oxygen in the first pass of the aerator or in the final tank effluent seemed desirable for maximum efficiency. The classification of solids in the final tank apparently reduced the oxygen demand in the bulk of the final tank liquor so that septicity did not occur in 1 to 2 hours settling. The immediate return of a dilute sludge in modified sewage aeration apparently prevented gross septicity of the sludge.

If only the volume of aeration tank in which fair oxygen conditions is considered in calculating the detention period, the purification obtained corresponds to the "effective aeration period." This indicates that a degree of aeration insufficient to produce traces of dissolved oxygen in the liquor is not necessarily deleterious to the process and that the control of the dissolved oxygen in the aerator may afford a means of varying the "effective aeration period."

Weekly Average Results of Modified Sewage Aeration

The individual effluent results of 25 tests of sewage aeration with the return of aeration tank effluent equal to from 20 to 100 per cent of the sewage flow is presented in the top curve of Fig. 1. Each circle, triangle, and square represents the average percentage of influent B.O.D. and suspended solids remaining in the effluent after 1.5 to 2.5 hours settling in the final tank. The logarithm of the percentage impurities remaining in the effluent are plotted against the equivalent detention or aeration period at 68° F. in hours. The mean curve for the open circles is representative of aeration with return liquor under "good" oxygen and operating conditions. The aeration tank suspended solids (A.T.S.S.) were roughly 80 p.p.m. or 20 to 30 per cent less than the influent suspended solids. The open squares represent tests in which the dissolved oxygen in the first pass was often found to be zero or the average dissolved oxygen of the aerator effluent was frequently less than 3 p.p.m.

The triangles are average results of tests in which the aerator solids became classified either due to a low air supply or usually a poor dis-

tribution of the air. Poor air distribution resulted when a grid of one inch pipe was placed in each pass of an aerator to double the wall or contact surface. Instead of getting increased treatment by doubling the contact surface, the pipe grid impeded the circulation of the liquid, caused poor air distribution in the bottom third of each pass, created septic sludge blankets, and substantially decreased the efficiency of treatment.

Modified sewage aeration in which final tank sludge was quickly returned in volumes of roughly 10 per cent of the sewage flow is shown in the bottom four curves of Fig. 1. The lowest curve is a single test run



FIG. 1.—A correlation of secondary treatment efficiencies by modified sewage aeration at equivalent (68° F.) aeration periods.

consisting of one final tank effluent at 3 hours aeration and two artificial effluents at 0.75 and 1.63 hours aeration, respectively, and an aeration tank suspended solids average of 440 p.p.m. The curve is drawn connecting points. Similarly the next higher curve is a single test run of two artificial effluents (the supernatant of samples of aerator liquor settled for ten minutes) and one final effluent in which the aerator effluent averaged 410 p.p.m. The third or middle curve is a mean curve of 19 tests with an average aerator suspended solids of 326 p.p.m. For individual tests, the average temperature varied from 54 to 77° F., the aerator suspended solids varied from 105 to 370 p.p.m., and the influent B.O.D. varied from 99 to 178 p.p.m. In spite of the very great variations of conditions, it may be observed that the individual points group

themselves closely about the mean curve when the per cent impurities in the effluent are plotted against the equivalent aeration period at 68° F.

The fourth curve from the bottom, similar to the two bottom curves, is a single test run at 77° F. with an average aerator suspended solids of 180 p.p.m.

The characteristic of the unimolecular reaction is that when the percentages of remaining reactants are plotted against time on semilogarithmic paper, the resulting curve is a straight line. However, it is frequently observed that if the time of reaction is prolonged, the rate of reaction decreases more than the theoretical and the curve gradually becomes asymptotic to the time axis. It is to be observed that this same tendency appears in all of the curves in Fig. 1 and particularly for those of higher aeration tank solids.



FIG. 2.—The effect of aeration tank suspended solids on the average percentage of influent B.O.D. and suspended solids remaining in the final effluent for a two hour and three hour modified sewage aeration period at 68° F.

A rough picture of the effect of aeration tank solids may be obtained by plotting the percentage of remaining impurities (suspended solids or B.O.D.) at a constant aeration period for each of the curves in Fig. 1 against the aeration tank suspended solids. The data for a two and three hour equivalent aeration period at 68° F. is presented in Fig. 2 showing the effect of aeration tank suspended solids exclusive of the wall film solids on the efficiency of secondary treatment. Up to a limiting value of 500 to 600 p.p.m. of aerator suspended solids, an increase in the suspended solids yields substantially improved effluents for relatively short aeration periods. However, a somewhat greater air supply will be needed to maintain satisfactory oxygen conditions and the very dense excess sludge at low aeration tank solids will become less dense at higher aerator solids for a given aeration period. Beyond 600 to

800 p.p.m. the effluent will become charged with impurities occasionally exceeding that of the influent, the excess sludge will become very thin, and aerobic condition will be maintained with difficulty. The high degree of treatment achieved by activated sludge requires a longer aeration period, somewhat higher aerator solids and a greater air supply. The solids concentration of excess activated sludge is usually relatively low.

The Diurnal Effect

Just as the activated sludge process, the mechanism of purification by modified sewage aeration may be viewed as the result of physical and chemical reactions such as oxidation, reduction, and accretion which are initiated by or are the direct result of biological activity. A reliable practical method of measuring the quantity of potential activity should prove invaluable in the interpretation of treatment results. At present, the common index is the aeration tank suspended solids although it is probable that a variable fraction are actually the "active solids." Assuming a good index of activity then within limits the ratio of active solids to influent (B.O.D.) load should bear an inverse relation to the parts per million of suspended solids and B.O.D. in the final effluent. In the pilot plant studies, a relatively large amount of wall film solids further complicated interpretations. Undoubtedly, a larger fraction of these solids than the suspended solids was "active" particularly when the wall film was thin. In studying the diurnal fluctuation in modified sewage aeration, the "active solids" were assumed to be the aeration tank suspended solids plus the wall film solids minus the influent suspended solids, all expressed in p.p.m.

The hourly results of experiment 5L (2) adjusted for the lag due to the aeration period were recapitulated and are presented in Fig. 3. The curves show that the final effluent quality in p.p.m. B.O.D. or percentage of the influent suspended solids and B.O.D. remaining in the effluent varies inversely as the ratio of "active solids" to influent B.O.D.

Somewhat contrary to practical plant operation, the pilot plant, which operated under constant sewage flow and constant wasting of excess sludge, was subject to high fluctuations of aerator solids. During the three days of hourly testing, the returned solids based on the mixed liquor flow (influent sewage plus return sludge flow) varied from 130 to 300 p.p.m. while the wall film solids amounted to 270 p.p.m. on the same basis. When the returned solids were at a minimum, the influent B.O.D. was rapidly approaching a late morning high value. Shortly before midnight, the "active solids" had reached a maximum while the influent B.O.D. was rapidly approaching a minimum. The ratio of "active solids" to influent B.O.D. (Fig. 3) varied from a minimum value of 2 between 2 and 4 P.M. to a maximum value of 3 to 4 at 10 A.M. It may be observed that when the ratio increased above 2.25 to 2.5 there was a definite improvement in the effluent B.O.D. and an effluent B.O.D. of less than 30 p.p.m. was achieved when the ratio exceeded about 3.5.

If the wall surface area to aerator capacity is reduced to that of a

practical plant then the return of more final tank solids or a higher aeration tank suspended solids presumbly must be maintained to secure a high ratio of "active solids" to influent B.O.D. However, since 600 to 800 p.p.m. suspended solids in the final tank influent are critical values above which the efficiency of the final tank is drastically decreased, it is obvious that the ratio of "active solids" to influent B.O.D. will be quite low during a substantial part of the diurnal cycle when the influent B.O.D. exceeds 200 p.p.m. and as a consequence the effluent will deteriorate.



FIG. 3.—The diurnal fluctuation of effluent quality and the ratio of "active solids" to influent B.O.D. in modified sewage aeration expt. No. 51, Nov. 17–20, 1942.

A Comparison of Treatment at Different Temperatures

A summary of plain sewage aeration and modified sewage aeration at different temperatures is presented in Fig. 4. The five upper curves represent pilot plant aeration results computed to a temperature of 68° F. The bottom eight curves are two sets of four computed curves showing the quality of the effluent at different aerator suspended solids con-



FIG. 4.—The effluent quality of plain sewage aeration and modified sewage aeration with varying amounts of aeration tank suspended solids for different aeration periods at 50° F., 80° F., and 68° F. (equivalent aeration period).

tent at the minimum yearly sewage temperature of 50° F. and at the maximum yearly temperature of 80° F. These three sets of curves indicate a high seasonal or temperature fluctuation of effluent quality. Fortunately, the degree of treatment achieved is inversely proportional to the B.O.D. load that the receiving water will sustain. From the standpoint of an equitable distribution of treatment between sewage plants and the receiving water, a variable effluent quality depending on the temperature and the size and use of the receiving water seems justifiable. However, stipulated constant standards of effluent quality may require the incorporation of a variable modified aeration period, a variable aeration tank solids, and necessarily, a variable air supply.

Summary

Modified sewage aeration, a process of activated sludge sewage treatment consisting of a short aeration period and a relatively small amount of return solids, was studied in a pilot plant having a maximum flow of 25 gallons per minute. A method of treatment accounting was found whereby each test of different aeration period and aerator solids content agreed to a logical pattern of treatment efficiency. When the more important variables were combined into the "effective aeration period" corrected to a standard temperature and the ratio of influent solids load to the "active solids" or biological culture returned or present in the aerator, the percentage removed of influent suspended solids or B.O.D. could be predicted. Since the detention of solids in the final tank was reduced to less than 30 minutes, it did not represent an important variable.

Conclusion

Modified sewage aeration is a process of partial sewage treatment intermediate between primary sedimentation and high rate single stage filters or activated sludge. Any degree of treatment between sedimentation and activated sludge appears possible by controlling the air supply, the aeration period, and the amount of returned solids. For partial treatment, low air supply and small tank capacity are needed and dense excess sludge will be produced. For more complete treatment, a greater air supply and tank capacity are needed and a less dense excess sludge will be produced. The treatment apparently reaches a critical value when the aeration tank suspended solids exceed 600 to 800 p.p.m.

References

1. Phelps, E. B., "The Oxygen Demand of Polluted Waters." U.S.P.H.S. Bull. No. 173, p. 81 (1927).
2. Setter, L. R., "Sewage Aeration. I." *This Journal*, 15, 629 (1943).

GREASE REMOVAL BY VACUUM FLOTATION*

By Rolf Eliassen and H. B. Schulhoff

Major and Asst. Chemist, North Atlantic Division, U. S. Army Engineers

The prevalence of appreciable amounts of grease and related substances in the sewage emanating from Army camps is a well established fact. Recent programs for the conservation of fats, together with the installation of grease traps in all mess halls, has led to a marked reduction in the grease content of sewage and the consequent recovery of untold pounds of vital war materials. However, grease in the raw sewage still presents a problem of considerable magnitude at Army sewage treatment plants.

In an attempt to solve a particularly pressing grease problem, an effort was made to evaluate the relative efficiencies of various methods of grease removal on the sewage under consideration. Among the methods of assisting in the removal of grease was that utilizing the principle of vacuum flotation.[1] No data was available on the effectiveness of this principle in the removal of grease from sewage. It was necessary to conduct pilot plant studies to determine the conditions under which this method was applicable to Army camp sewage. Consideration was also given to the need for the addition of chemicals in order to achieve greater removals of grease.

Vacuum flotation is merely another means of accomplishing separation of solids from liquids by floating the solids to the surface of the liquid. Most substances fitting into the categories which make up the ambiguous term of grease are lighter than water, but they are usually held in suspension by various means so that the separation is not easily accomplished by mere difference of specific gravities. In the case of sewage, the grease may be tied in with other solids so that the apparent specific gravity may be greater than that of water and the grease settles with the other sludges. It has been found that the addition of air to sewage will increase the release of grease. By the simple expedient of small air bubbles attaching themselves to particles of grease the apparent specific gravity of the combined matter is lowered and the grease will float to the surface more readily. By observation it has been noted that the smaller air bubbles are far more effective inasmuch as they will attach themselves to smaller particles of grease and will remain attached until they have reached the surface of the liquid. The principle of vacuum flotation does not alter this fundamental concept in any manner.

The use of vacuum is only for the purpose of inducing small air bubbles to form in the liquid. In order to make sure that enough air is present in the sewage to be released, a short period of aeration is em-

* Presented at the Fifteenth Annual Meeting of the New York State Sewage Works Association, New York City, January 22, 1943.

ployed prior to the application of vacuum. The purpose of this aeration is to saturate the sewage with air at atmospheric pressure. Aeration may be accomplished through mechanical devices or by diffusing air through the sewage. The large air bubbles resulting from this aeration must be released before vacuum is applied. A separate tank or vessel is utilized for this purpose. The application of vacuum causes the release of great numbers of very fine bubbles of air inasmuch as the amount of air which can be held in a saturated solution decreases with a decrease of pressure. These fine air bubbles will attach themselves to the well dispersed grease particles and bring about a very effective flotation of grease. It should be noted that the only purpose of the vacuum is to generate the fine air bubbles.

The apparatus employed in these pilot plant studies is shown in Fig. 1. The vessel in which vacuum flotation was achieved was a Lucite



FIG. 1.—Experimental vacuum flotation apparatus.

tube, 6 ft. long and with a diameter of 6 inches. In order to simulate plant conditions, it was found that the depth was an important factor and, consequently, a 6 ft. tube was used. In like manner, it was found that the diameter of the tube had to be large enough to eliminate any effects of surface tension or other side wall influences which would occur if a smaller tube were used.

Twenty liters of sample were placed in the tube to the depth noted in Fig. 1. The sewage was aerated for five minutes by means of compressed air admitted at the bottom of the tube through a porous diffuser bulb. After aeration, several minutes were allotted for the larger bubbles of air to escape through the vent at the top of the tube. After

closing the necessary valves, a vacuum equivalent to 15 inches of mercury was applied over the surface of the liquid in the tube. Experiments indicated that between eight and eighteen inches of mercury the degree of vacuum did not make much difference in removals accomplished. The selection of fifteen inches as the basis for the tests was made because it was found that the equipment could be handled most readily at this point.

In order to control the amount of vacuum within narrow limits, it was found necessary to employ a vacuum reservoir. This ironed out any irregularities in the operation of the vacuum pump. The degree of vacuum was closely regulated by means of the mercury column which acted as a vacuum control. In all the runs the vacuum was maintained for ten minutes. This allowed sufficient time for all of the air bubbles to form and rise to the surface. The rate of rise of these bubbles was quite rapid and varied with the size of solid matter being buoyed to the surface.

After flotation, a sample of the remaining sewage was withdrawn from the center of the tube as shown in Fig. 1, making sure that the vacuum was still maintained over the surface of the liquid. This was accomplished by manipulation of the valves noted over the sample bottle in Fig. 1. By placing the bottle on the tube under the same degree of vacuum, the sewage in the tube above the bottle would flow into the latter and the solid particles on the surface of the tube would not be disturbed to any appreciable extent. Analyses of the sewage sample were made for petroleum ether soluble matter and any other determinations of interest.

The basis of grease determination in the analyses was petroleum ether soluble matter in accordance with accepted practices in the sewage works field. In order to achieve consistent results within a reasonable time, it was necessary to refine the technique involved in the usual method of determining greases. This method has been reported in a previous paper by the authors.[2] It is significant to note that consistent results were obtainable and that many analyses could be made concurrently in the course of a day's work.

Tests were first conducted on raw sewage without the addition of other agents. The average results of these tests are presented in Table I and are shown graphically in Fig. 2. It will be noted that the per cent removal of petroleum ether soluble matter (hereafter called P.E.S.M.) increased with the strength of the sewage based on the value of the P.E.S.M. in the raw sewage. The removals of P.E.S.M. in the flotation process varied from 45 to 67 per cent.

Experiments were conducted to determine the effect of the addition of coagulants to the raw sewage. It was reasoned that the presence of a gelatinous floc would present a greater surface area to which the air bubbles could attach themselves. This would facilitate the coagulation and subsequent removal of greater quantities of grease. The results of experiments using ferric chloride are shown in Table II and are

TABLE I.—*Removal of P.E.S.M. by Vacuum Flotation*

Number of Runs Averaged	P.E.S.M.—P.P.M.		Per Cent Removal
	Raw Sewage	Treated Sewage	
3	23	13	43
2	86	45	48
4	118	56	52
4	165	67	59
3	233	77	67



FIG. 2.—Removal of P.E.S.M. by vacuum flotation vs. strength of sewage.

presented graphically in Fig. 3. The dosages of ferric chloride are based upon 100 per cent $FeCl_3$. It will be noted that with sufficient dosages of iron salts it is possible to remove almost all of the grease. However, the cost involved would be too great for normal operating conditions. The addition of 50 p.p.m. $FeCl_3$ brought about the removal of 64 per cent of the P.E.S.M. or an increase of 47 per cent in the amount of grease floated. This dosage is within the range which may be employed in the coagulation of sewage in a chemical precipitation plant.

TABLE II. *Removal of P.E.S.M. by Vacuum Flotation and Coagulation with Ferric Chloride*

	Raw Sewage	Ferric Chloride Dosage—P.P.M.						
		0	10	20	30	50	100	150
Average P.E.S.M.—P.P.M.	97	53	45	43	41	35	25	11
Per Cent Removal		45	53	56	58	64	74	89

Experiments were also conducted on the use of alum as the coagulant. The results of these tests are shown in Table III. Dosages of alum are indicated as p.p.m. of commercial alum. The increase of re-



FIG. 3.—Effect of ferric chloride on P.E.S.M. removal.

moval obtainable through the use of this chemical is appreciable but the large quantities necessary for markedly different results would preclude its use under normal circumstances.

Vacuum flotation has been employed in the paper industry for some years as a means of recovery of fibers before discharging white water to streams or other methods of disposal.[3] The machinery in which this is accomplished is known as the Adka Save-All. Since paper pulp is

TABLE III.—*Removal of P.E.S.M. by Vacuum Flotation and Coagulation with Alum*

	Raw Sewage	Alum Dosage—P.P.M.		
		0	50	100
Average P.E.S.M.—P.P.M.	137	79	62	48
Per Cent Removal		42	55	65

floated readily by the fine bubbles produced in the vacuum flotation unit, it was decided to observe the effect of paper pulp on the removal of grease from sewage. The results of these experiments are indicated in Fig. 4. It may be seen that high removals of grease may be accomplished but large quantities of paper pulp would be required. While the cost of this would be quite low, the problem of sludge disposal would be aggravated. The use of this material would not be practicable unless high removals could be achieved with low dosages of paper pulp.

Of late years, considerable interest has been evidenced among sanitary engineers in the application of chlorine gas together with air to raw sewage to facilitate the removal of grease.[4, 5] Experiments were conducted on the effect of aero-chlorination on the removals of grease by the vacuum flotation unit. Chlorine gas was added to the air used for aeration of the sewage for ten minutes prior to flotation. Removals of petroleum ether soluble matter achieved in the course of these tests

are presented in Table IV and are shown in Fig. 5. Removals of suspended solids obtained in the same tests are shown in Table V. Similar



FIG. 4.—Effect of paper pulp on P.E.S.M. removal.

TABLE IV.—*P.E.S.M. Removal by Aero-Chlorination and Vacuum Flotation*

Run No.	P.E.S.M. in Raw Sewage P.P.M.	P.E.S.M. in Treated Sewage—P.P.M.: Chlorine Dosage—P.P.M.					
		0	5	10	15	20	25
1	139	45	45	51	56	38	65
2	152	77	95	90	99	63	88
3	153	55	61	83	82	83	85
4	187	75	81	88	78	79	89
Ave.	158	63	70	78	79	66	82
Per Cent Removal		60	55	51	50	58	48



FIG. 5.—Effect of aero chlorination on P.E.S.M. removal.

TABLE V.—*Suspended Solids Removal by Aero-Chlorination and Vacuum Flotation*

Run No.	Susp. Sol. in Raw Sewage P.P.M.	Susp. Sol. in Treated Sewage—P.P.M. Chlorine Dosage—P.P.M.					
		0	5	10	15	20	25
1	502	193	221	157	158	169	200
2	576	324	360	342	358	292	306
3	466	322	300	290	270	268	310
4	584	287	350	326	329	333	309
Ave.	532	282	308	279	279	266	281
Per Cent Removal		47	42	47	47	50	47

results on B.O.D. removals are shown in Table VI. It will be noted that the addition of chlorine gas to the air had no appreciable effect one way or the other on the removal of grease, suspended solids, or B.O.D., from the sewage in the vacuum flotation unit.

Experiments were also conducted to determine the effect of the addition of sulphuric acid to the sewage. Additions of acid up to 250 p.p.m. had no effect on removal of grease from the sewage.

TABLE VI.—*B.O.D. Removal by Aero-Chlorination and Vacuum Flotation*

Run No.	B.O.D. in Raw Sewage P.P.M.	B.O.D. in Treated Sewage—P.P.M. Chlorine Dosage—P.P.M.					
		0	5	10	15	20	25
1	660	500	500	520	460	550	490
3	420	350	360	200	240	320	250
4	633	486	509	497	475	520	497
Ave.	571	444	456	436	392	463	412
Per Cent Removal		22	20	24	31	19	28

DISCUSSION

These experiments were conducted on Army camp sewage having a grease content of from 25 to 250 p.p.m. This is a much higher grease content than normally found in domestic sewage. Hence the results should be applied with limitations to sewage from municipal plants except in cases where industrial wastes such as those from packing houses or similar establishments discharge high quantities of grease-containing substances.

As far as Army camps are concerned, it may be noted that the vacuum flotation process is very effective in separating grease-containing solids from the liquid phase. The floated materials form a scum on the surface of the liquid in the flotation unit. By suitable mechanical skim-

mers this scum could readily be removed on a plant scale. Further removals of grease would undoubtedly follow in the settling tank and other treatment units which exist in the normal sewage treatment plant. The higher the grease content of the sewage the better the removals which would be obtained.

The addition of chemicals further increases the removal of grease. However, the use of chemicals in the normal plant would depend upon an economic balance between the need for additional removals as compared with the cost of chemicals. This in turn would depend upon the treatment given the sewage following the vacuum flotation unit. The commonly used coagulants, such as ferric chloride and alum, gave good results at fairly high dosages of chemicals. Paper pulp was successful in increasing the removal of grease from the sewage. The large quantities necessary for appreciable increase in grease removal precluded its effectiveness from a practical standpoint in view of the large quantity of increased sludges which would have to be handled.

Aero-chlorination was not effective in bringing about an increase in the removal of grease from the sewage in the vacuum flotation unit. No attempt was made to measure any increase or decrease in the amount of scum formed by the addition of chlorine gas to the air during the aeration period, or during the period of applying vacuum. The only criterion of grease removal was the P.E.S.M. content of the effluent from the vacuum flotation unit as compared with the P.E.S.M. content of the raw sewage. The reason for this criterion is that the problem at hand was the reduction of the grease content of the sewage entering an Army treatment plant in order to improve the operation of the secondary treatment process. This same reasoning would apply to most sewage treatment problems of this nature.

Summary

Experiments conducted on Army camp sewage indicate that the vacuum flotation process may be used to advantage in the removal of grease from sewage. The process depends for its action upon the sewage first being saturated with air. This is accomplished by rapid aeration by mechanical or by diffused air. The sewage is then placed under a vacuum in which condition a super-saturation of air exists in the sewage. Air is released in a myriad of fine bubbles which adhere to particles of grease and other organic matter. Flotation of the combined air and solid matter ensues. The air is released at the surface of the liquid at which point the scum must be collected by mechanical means. Pilot plant tests utilizing this method indicate that removals of from 45 to 67 per cent of the petroleum ether soluble matter may be obtained from raw sewage depending upon its strength. Coagulants would further increase the removals of the solids. These coagulants include alum, ferric chloride and paper pulp. Aero-chlorination was found to have no effect on the removal of grease by this method. Based on these

experiments, the removals obtained without the addition of any chemicals should be satisfactory as long as primary sedimentation follows the vacuum flotation unit.

References

1. Fischer, A. J., *Engineering News-Record*, **130**, 297 (1943).
2. Eliassen, R. and Schulhoff, H. B., Sewage Works Journal, **15**, 491 (1942).
3. Anspach, Sven, *Paper Trade Journal*, **104**, 40 (1937).
4. Faber, H. A., *Water Works and Sewerage*, **84**, 171 (1937).
5. Wiest, G. J., *Water Works and Sewerage*, **85**, 1103 (1938).

GREASE REMOVAL AT ARMY SEWAGE TREATMENT PLANTS

By Rolf Eliassen and H. B. Schulhoff

Major and Assistant Chemist, Repairs & Utilities Branch, North Atlantic Division, U. S. Army Engineers

The prevalence of grease in sewage emanating from Army camps is well known to the sewage works profession. Analyses of Army sewage for grease content have indicated daily averages of from 25 to 250 p.p.m. of petroleum ether soluble matter, with peak values running up to 1,000 p.p.m. over short periods of time. These values are far in excess of those ordinarily met with in sewage from a normal residential community.

High grease content in Army camp sewage as compared with municipal sewage may be attributed to a number of factors. In the first place, the rigorous physical life of the soldier requires the consumption of more meat by troops than the equivalent normal civilian population. This, together with the use of many fried foods, leads to greater quantities of fats present in spent dishwater. At each mess hall grease traps are installed following the sinks or dish washing machines. Experiments have shown that these grease traps will accomplish an average removal of approximately fifty per cent of the grease present in sink waste waters. The remaining grease passes to the sewer in relatively high concentrations.

Secondly, large quantities of soap are utilized in Army camps. The nature of the soldiers' activities and the stress on cleanliness lead to a greater number of daily shower baths per unit of population than would take place in an ordinary community. Shower water will contain a considerable amount of derivatives of fatty acids in the form of spent soaps. This is evident from observation of any of the sewage treatment plants at Army camps shortly after the morning or evening showers have been taken by the troops. Surfaces of settling tanks will be covered in many instances with a lather of suds and grease.

Many Army camps have large laundries installed. These would have a similar effect to those in a normal city. The effect of laundry waste on increasing the grease content of sewage is obvious. Analyses of these wastes have indicated grease contents of 500 to 1,000 p.p.m.

All of the above factors are subject to wide variations depending upon regulations or facilities prevailing at each Army post. One of the most important causes for variation in grease content has been the frequency and reliability of grease trap cleaning. Attempts have been made to enforce regulations that require the mess sergeants to clean the traps two or three times a week in order to prevent accumulated grease from passing into the sewerage system. Grease skimmed from

the traps has been salvaged at many posts and sold to rendering establishments.

Of primary interest to the sanitary engineer is the effect of grease on the operation and maintenance of sewerage systems and sewage treatment plants. The grease contained in the hot liquids from the dish washing machines or sinks is usually in a molten state. When the dish water mixes with the contents of the sewers, the grease is cooled and may solidify if the temperature of the sewage is low enough. The affinity of grease for other surfaces may lead to deposition on the sides and invert of the sewer to such an extent that free flow is retarded or obstructed.

In one instance it was found that a ten inch steel pump discharge pipe carrying raw sewage was clogged to such an extent that an opening with an effective diameter of only 2½ in. remained. Consider the effect of this reduction in pipe size on the power requirements for the pumps. For a given quantity of sewage, the velocity will vary inversely as the area of the pipe or the square of the diameter. Since head loss and power vary as the square of the velocity, they must vary inversely as the fourth power of the diameter. In the case cited above, the diameter was cut to one-fourth of its original value. This means that the velocity was 16 times greater and the power requirements 256 times greater than would have been necessary to force the sewage through the same length of clean pump discharge pipe.

Grease problems in the various units of the sewage treatment plants are common. The skimming of primary settling tanks may be accomplished mechanically with varying degrees of effectiveness, depending upon the type of mechanism furnished in the plants. In a number of instances skimming mechanisms have not been provided, particularly at the smaller camps where Imhoff tanks or plain settling tanks were constructed. Skimming may be quite a problem to the plant operator if the grease content in the raw sewage is relatively high.

Experience has shown that grease containing substances will digest, giving a high yield of gas (1). If the grease is well interspersed among the other solids, no difficulty need be experienced in the digesters. However, in many instances the grease will separate from the other sludge particles and form a hard mat many feet thick riding as a scum at the top of the digester. This is particularly true where scum from the primary settling tanks is pumped directly to the digesters. Many Army sewage plants have been plagued with heavy blankets of scum which had to be broken up by some means, either hydraulic or mechanical. Several camps have resorted to separate disposal of scum by burial, burning or drying beds. None of these methods is acceptable for general practice. Most satisfactory results on the digestion of grease without attending difficulties have been obtained at those plants in which the primary digesters were provided either with high-speed mechanical stirring devices or sludge recirculation into the scum zone and at the point of entrance of raw sludge into the digester. Only by assurance of thorough dispersion of grease particles with raw and seed

sludge can the operator be reasonably free from grease problems in sludge digesters.

Secondary treatment processes utilizing biological organisms to remove dissolved, colloidal, and suspended organic matter from sewage are frequently adversely affected by grease. Heukelekian (2) has demonstrated this in connection with activated sludge. As with anaerobic digestion, grease may be broken down, but at a slower rate. Hence, a longer period of aeration and a larger percentage of solids in the mixed liquor would be required to oxidize the grease without interference with the oxidation of the remaining putrescible organic matter removed from the sewage.

Similar situations have arisen with trickling filters. The presence of large amounts of grease in the effluents from primary settling tanks has resulted in coating some of the zoogleal jelly with grease. The slower oxidation of these substances has led to the lowering of oxidation capacity of trickling filters and the consequent need for larger rock volumes to affect the same degree of treatment were the grease not present in the sewage.

Auxiliary Methods

The removal of grease from sewage ahead of secondary treatment is of primary interest to the operators of Army sewage treatment plants. All plants are equipped with primary settling tanks of some type. Consideration should, therefore, be given to the effect of the settling tank on the grease bearing particles in the sewage. Only three possibilities present themselves. The grease can either go up to form scum, go down to form sludge, or remain suspended in the sewage to contribute grease content to the effluent. Auxiliary methods of grease removal to augment the removals obtained by the rising or settling of grease in settling tanks have been sought by sanitary engineers for many decades. These have included the following:

a. Plain skimming tanks
b. Chemical precipitation
c. Diffused air aeration
d. Mechanical aeration
e. Aero-chlorination
f. Vacuum flotation

Each method must be followed by the primary settling tanks in order to accomplish removal of solids, as well as additional grease removal. These methods have been in use at Army sewage treatment plants operated under the jurisdiction of the authors.

Much has been written about the virtues of each process of grease removal, but few comparative studies have been made to indicate to designing engineers the conditions under which each process would be applicable. Such a study was undertaken by the authors to determine the increase in the efficiency of grease removal obtained by the application of the methods noted above to Army camp sewages.

A criterion of efficiency of grease removal had to be established in order to permit evaluation of the effect of each of these methods of grease removal. At the same time, consideration had to be given to the changing characteristics of the sewage at each plant and at different posts.

Since the most detrimental effect of grease on sewage is on the biological processes of secondary treatment, the condition of the primary clarifier effluent is of greatest importance. It is known that the primary tank will remove an appreciable percentage of grease as sludge or scum (3). What interests the operator is any further removal which can be obtained over and above primary settling. Thus, the quantity of grease removed by the settling tank can be accepted as the standard of comparison for each sewage. Any further increase in grease removal beyond the standard would indicate the effectiveness of the auxiliary method applied ahead of the settling tank.

Experiments were conducted in a number of different ways in an attempt to secure a true evaluation of the effectiveness of each method of grease removal. It was necessary to use laboratory and plant studies, alone and in combination, in order to secure a complete analysis. The details of each experiment will be outlined in conjunction with the presentation and discussion of the data.

Results of experimental work are only of value to the extent that analyses are made on representative samples of the material being studied. This is particularly true when low concentrations of grease are found in liquids such as sewage. The use of composite samples taken with the greatest care in accordance with accepted sampling procedure is highly essential. Wherever possible, statistical averages should be taken of a number of composite samples. This will lead to the greatest consistency of results and consequently the most accurate analysis of the processes under consideration. This procedure was followed where feasible in the work described in this paper.

Analytical work was carried out in the trailer laboratory specially equipped for sewage analysis. A previous paper (4) was devoted to a description of this laboratory. Standard methods of analysis (5) were used in most instances. It was necessary to develop a refinement of technique for the determination of petroleum ether soluble matter in sewage. This method has been reported in another paper (6) by the authors.

Diffused Air Aeration

The practice of aerating sewage for a short period prior to settling has received wide acceptance. One of the most common methods of aeration is the diffusion of compressed air over a certain portion of the bottom area of the aeration tank by means of porous plates (7). A unit of this type had been installed at one of the Army sewage treatment plants (Plant A) operated under the supervision of the authors. Primary settling and secondary treatment by slow sand filtration followed the aeration process. It was desirable to make a study of the efficiency

of this method of grease separation in order to determine whether similar units should be installed at other posts where grease difficulties were being experienced in secondary treatment processes.

It was unfortunate that the design of the raw sewage pumping station at this treatment plant permitted the accumulation of large quantities of grease in the wet well. Frequent discharges of grease in slugs made representative sampling difficult and results inconsistent. Pilot plant studies were resorted to as the best means of securing comparative results on removals of grease by aeration plus settling as compared with plain settling.

Samples of raw sewage were composited for a half hour by taking 5 gallon samples every few minutes until 50 gallons had been composited. Solids were kept in suspension by the agitation of dumping fresh samples into the tank. Two 20 gallon tanks were then filled with this sewage. To make certain that both tanks received similar sewages, the filling was switched from one tank to the other every few gallons. Subsequent analyses for grease and suspended solids showed that the sewages in each 20 gallon tank were virtually the same. The depth of liquid in each tank was two feet.

In one tank quiescent settling was begun immediately after filling. This settling took place for 30 minutes to approximate a settling rate of 4 feet per hour, or an overflow rate of 720 gallons per square foot per day, the normal value for primary settling tanks. After 30 minutes a sample was taken a few inches below the scum layer to represent the effluent from a plain settling tank.

In the other tank the sewage was subjected to aeration by diffused air for 10 minutes at a rate of 0.3 cubic foot per minute. This was equivalent to a rate of 0.15 cubic foot per gallon of sewage. After aeration quiescent settling was permitted to take place for 30 minutes at the same rate as noted above for the unaerated sample. A sample taken under the scum layer represented the effluent from a settling tank preceded by diffused air aeration.

Aero-chlorination was also studied as part of these experiments. Chlorine gas was added directly to the air in accordance with standard practice (8). Dosages of 5 and 10 p.p.m. were added over the entire aeration period. The settling period following aero-chlorination was the same as with the previous experiments.

The results of these experiments have been averaged and are presented in Table I. These can best be interpreted by means of graphical representation. If individual analyses were plotted, the scatter diagrams which resulted would give a good indication of trends. As pointed out previously, when dealing with grease analyses of sewage, it is far better to average the results of many composite samples. This has been done wherever possible by averaging the results into various groups depending upon the value of the grease contained in the raw sewage.

Fig. 1 shows the average results obtained during the course of the many runs utilizing the apparatus and procedure noted above. It was

TABLE I.—*Removal of Grease by Aeration and Settling—Plant A*

Raw Sewage Grease P.P.M.	Settling			Aeration Plus Settling				Difference Per Cent Removed
	Effl. P.P.M.	Removed P.P.M.	Removed %	Cl₂ P.P.M.	Effl. P.P.M.	Removed P.P.M.	Removed %	
37	20	17	46	0	21	16	43	−3
40	28	12	30	10	30	10	25	−5
49	32	17	35	5	31	18	37	+2
64	32	32	50	0	33	31	48	−2
64	42	22	34	10	42	22	34	0
66	35	31	47	5	36	30	46	−1
97	43	54	56	0	44	53	55	−1
115	54	61	53	10	52	63	55	+2
130	43	87	67	5	49	81	62	−5
132	38	94	71	0	41	91	69	−2



FIG. 1.—Removal of grease by aeration and settling—Plant A.

found expedient to express results in terms of grease removed in the process. This was obtained from the difference between the grease contents of the raw and treated sewages. In Fig. 1 the grease removed in p.p.m. has been plotted against the grease content of the raw sewage. All methods have been plotted on the same graph, namely, plain settling, aeration followed by settling and aero-chlorination with 5 and 10 p.p.m. of chlorine preceding settling. It will be noted that all of the results lie on virtually the same curve, indicating that no further increase in removal can be expected over plain settling by any of the methods used in this series of experiments.

This conclusion is more clearly brought out by the method of presentation indicated in Fig. 2. In this curve, the percentage of grease removed has been plotted against the grease in the raw sewage. It will be seen that no difference is noted in the results obtained by any of these methods as compared with plain settling.



FIG. 2.—Comparison of per cent removals of grease by aeration and settling.

The graph above the main curve of Fig. 2 has been drawn to show the difference between the per cent removal of grease by each of the methods and the per cent removal by plain settling. It will be noted that in most cases the removals by aeration or aero-chlorination were no greater than those by plain settling. On the basis of these results, it can readily be seen that no advantage was gained by the auxiliary methods of grease removal as compared with plain settling.

Since grease is present in sewage mostly in suspended and colloidal form, removals of grease should parallel those of suspended solids. Analyses of the raw sewage and effluents were made for suspended

TABLE II. *Removal of Suspended Solids by Aeration and Settling—Plant A*

Raw Sewage Susp. Solids P.P.M.	Settling			Aeration Plus Settling				Difference Per Cent Removed
	Effl. P.P.M.	Removed		Cl_2 P.P.M.	Effl. P.P.M.	Removed		
		P.P.M.	%			P.P.M.	%	
109	77	32	29	0	76	33	30	+ 1
143	80	63	44	5	94	49	34	− 10
170	98	72	42	0	96	74	43	+ 1
174	100	74	43	10	109	65	37	− 6
225	102	123	55	5	112	113	50	− 5
231	110	121	52	10	107	124	54	+ 2
244	124	120	49	0	127	117	48	− 1
320	134	186	58	5	146	174	54	− 4
433	142	291	67	10	125	308	71	+ 4

solids in order to serve as a check on results obtained by means of grease analyses. The average results are shown in Table II. These have been plotted in Fig. 3, with removal of suspended solids plotted against the suspended solids content of the raw sewage. The results are similar to those obtained with grease analyses; removals of sus-



FIG. 3.—Removal of suspended solids by aeration and settling—Plant A.

pended solids are the same for aeration, aero-chlorination and plain settling. This is further emphasized by the method of presentation in Fig. 4. Percentage removal of suspended solids has been plotted against suspended solids in the raw sewage. All of the values are clustered within fairly narrow limits throughout the whole range of the curve. On the plot above the main curve, the percentage removal by



FIG. 4.—Comparison of per cent removals of suspended solids by aeration and settling.

plain settling has been established as the standard. The results using the auxiliary methods in addition to settling indicate that no particular advantage accrued from the use of these auxiliary methods inasmuch as the per cent removals were only slightly different from those obtained by plain settling.

MECHANICAL AERATION

A number of plants which have been installed throughout the country for the treatment of sewage and industrial wastes have utilized me-

chanical aeration as an auxiliary means of grease removal (9). In most instances the grease separators involve the use of a recirculating pump located in a draft tube in the center of a tank. The flow through the tube may either be downward with a resulting upward motion of liquid in the tank proper or in the reverse direction.

At the Army post (Plant B) in which the experiments on this type of unit were conducted the mechanism provided for a downward movement of sewage in the draft tube as well as provisions for drawing in air to be mixed with the sewage in its downward path. It was noted that this mechanism gave many fine bubbles of air which brought considerable grease to the surface of the unit to be removed by the skimmer mechanism. After passing through primary settling tanks, the sewage was treated by high-rate trickling filters.

Experiments were conducted on a plant scale to determine the effectiveness of this grease separator unit on increasing the removals of grease over the results which would have been obtained by plain settling. The procedure adopted involved running the plant utilizing sedimentation alone for a week, and by-passing the aerator. The following week the grease separator was operated and was followed by the settling tanks. This was repeated for almost two months in order to obtain a sufficient amount of data for statistical averages which could be relied upon to give a fair analysis of the problem. Aero-chlorination was utilized during part of the experiments by adding 5 p.p.m. of chlorine gas to the air entering the down draft tube. Hourly composites were taken between the hours of 6 A.M. and 11 P.M. each day during the course of the experiments. Samples were not taken during the night hours inasmuch as very little flow went through the plant. Retention periods were so long that normal plant operating conditions would not

TABLE III.—*Removal of Grease by Settling—Plant B*

Raw Sewage Grease P.P.M.	Settled Sewage			
	Effluent P.P.M.	Removed		
		P.P.M.	Per Cent	
51	9	42	82	
56	12	44	79	
67	37	30	45	
67	27	40	60	
75	14	61	81	
82	20	60	73	
83	22	61	74	
102	41	61	60	
114	59	55	48	
125	28	97	78	
152	49	103	68	
161	45	116	73	
230	74	156	68	
233	44	189	81	

be represented in the samples taken during these hours. The composite samples obtained by this procedure represented the results obtained in a normal course of operation of this sewage treatment plant, with a nominal flow of 3 m.g.d. and approximately 15 minutes detention in the aeration tank.

The results of the settling tests are presented in Table III. The average grease removals in the settling tank, as obtained by the difference in the values of the grease content of the raw sewage and the clarifier effluent, were plotted against the value of grease in the raw sewage,



FIG. 5.—Removal of grease by settling—Plant B.

as shown in Fig. 5. Each of the points shown represents the composite of a day's run involving eighteen separate samples. The curve will be used later to compare results obtained through the use of the aerator.

TABLE IV.—*Grease Removal by Mechanical Aeration Plus Settling—Plant B*

Chlorine Dosage P.P.M.	Raw Sewage Grease P.P.M.	Grease Separator			Settling Tank		
		Effl. P.P.M.	Removed		Effl. P.P.M.	Removed	
			P.P.M.	%		P.P.M.	%
0	80	63	17	21	29	51	64
0	88	57	31	35	25	63	72
0	98	53	45	46	16	82	84
0	103	61	42	41	21	82	80
0	116	85	31	27	29	87	75
0	125	105	20	16	36	89	71
5	128	84	44	34	32	96	75
0	134	53	81	60	18	86	64
5	155	120	35	23	45	110	71
0	171	60	111	65	25	146	85
0	171	86	85	50	19	152	89
5	189	98	91	48	49	150	79
5	230	112	118	51	55	175	76
5	241	137	104	43	51	190	79

The values of grease removal versus grease in the raw sewage using the grease separator followed by the primary clarifiers are presented in Table IV. The average values have been plotted in Fig. 6. The



FIG. 6.—Removal of grease by mechanical aeration and settling.

squares represent the grease removed in the separator. It will be noted that an appreciable quantity was removed as scum in this unit. The circles represent removals obtained through the use of the separator and the settling tanks. The solid black squares and circles represent values obtained through the use of 5 p.p.m. of chlorine gas in the process. From Fig. 6, it will be noted that no increase in removals was obtained through the use of aero-chlorination.

In order to visualize the difference between the results obtained through the use of settling alone as against aeration plus settling, Fig. 7



FIG. 7.—Comparative grease removals by mechanical aeration and settling.

has been drawn, using the same curves as shown in Figs. 5 and 6. It will be noted that when the grease content in the raw sewage rises above 100 p.p.m. there is a slight difference in the removal of grease in favor of aeration plus settling.

Suspended solids analyses were also made at the same time as the analytical work was done for the determination of grease content of the raw sewage and effluents. The results of the removal of suspended solids versus the suspended solids content of the raw sewage by plain settling are indicated in Fig. 8. Similar results obtained through the



FIG. 8.—Removal of suspended solids by settling—Plant B.

use of the aeration tank followed by settling are plotted in Fig. 9. Tables V and VI present the tabulated data on which the curves are based. The results obtained through the use of aero-chlorination are shown in



FIG. 9.—Removal of suspended solids by mechanical aeration plus settling.

solid circles in the latter figure. It will be noted that these values confirm the previous findings with grease, namely that aero-chlorination with 5 p.p.m. of chlorine does not give any further removal of grease.

These curves have been transposed to Fig. 10. It will be noted that there is only a slight difference in the removal of suspended solids through the use of the aerator followed by settling.

TABLE V.—*Removal of Suspended Solids by Plain Settling—Plant B*

Raw Sewage Susp. Sol. P.P.M.	Settling Tank		
	Eff. P.P.M.	Removed	
		P.P.M.	Per Cent
220	97	123	56
224	98	126	56
229	123	106	46
249	139	110	44
271	111	160	59
280	88	192	68
283	119	164	58
300	106	194	65
338	180	158	47
374	136	238	64
388	126	262	68
454	158	296	65
504	164	340	67

TABLE VI.—*Removal of Suspended Solids by Aeration and Settling—Plant B*

Chlorine Dosage P.P.M.	Raw Sewage Susp. Sol. P.P.M.	Aeration Plus Settling		
		Eff. P.P.M.	Removed	
			P.P.M.	Per Cent
0	123	49	74	60
0	196	78	118	60
0	242	78	164	68
0	275	95	180	65
0	320	102	218	68
0	332	106	226	68
0	338	132	206	61
5	340	140	200	59
0	346	144	202	58
5	350	106	244	70
5	358	144	214	60
5	366	88	278	76
5	407	142	265	65
0	414	114	300	72
5	418	146	272	65
0	486	148	338	69
0	558	144	414	74



FIG. 10.—Comparative suspended solids removals by mechanical aeration and settling.

VACUUM FLOTATION

Of late years there have been a number of grease removal units installed at sewage treatment plants and in industrial plants employing the principle of vacuum flotation (10). A functional part of this apparatus is the pre-aeration unit in which sewage is aerated by a high speed mechanism for less than a minute to saturate the liquid with air at atmospheric pressure. The large air bubbles are released immediately, after which the sewage passes into the vacuum tank. This unit is comprised of a detention tank in which the sewage is retained for approximately 20 minutes. A rotating skimmer and sludge collecting mechanism are provided. The whole tank, either of steel or concrete, is inclosed and a vacuum of 10 inches applied over the surface of the sewage. A myriad of fine bubbles is released, inasmuch as the sewage is supersaturated with air at the decreased pressure. These bubbles attach themselves to particles of sewage containing grease and other organic matter. The buoyancy provided by the fine air bubbles carries the attached particles to the surface from which they are skimmed by a mechanism and swept to the scum trough. The skimmings pass through a barometric leg into a scum pit from which the material is pumped to the digester or other means of disposal. One of these units had been installed ahead of an activated sludge plant at an Army sewage treatment plant (Plant C) operated under the supervision of the authors.

Experimental procedure consisted of both plant and laboratory studies. In order to secure information over a wide range of grease contents in the raw sewages, samples were composited every 5 minutes over a period of an hour at various times of the day. The twelve samples which resulted comprised one run. Many of these runs were made during the course of the experiments. It was found that the best method of securing results worthy of interpretation was to collect large samples of raw sewage to obtain a composite over the course of an hour of approximately 20 gallons. The frequent addition of samples kept

the liquid in agitation. The composited raw sewage was settled for 30 minutes, after which samples were obtained for analysis of grease and suspended solids. These samples represented the overflow from a settling tank. This procedure was similar to that adopted for the experiments utilizing the diffused air method of grease separation. In a similar manner, the effluent from the vacuum flotation unit was sampled over the course of the same hour as above, with a time interval of 15

TABLE VII.—*Grease Removal by Vacuum Flotation and Settling—Plant C*

Raw Sewage Grease P.P.M.	Plain Settling			Flotation			Flot. Plus Settling		
	Effl. P.P.M.	Removed		Effl. P.P.M.	Removed		Effl. P.P.M.	Removed	
		P.P.M.	Per Cent		P.P.M.	Per Cent		P.P.M.	Per Cent
85	36	49	58	49	36	42	36	49	58
123	53	70	57	64	59	48	54	69	56
141	59	82	58	66	72	53	46	95	67
170	62	108	63	68	102	60	48	122	71
189	58	131	69	67	122	65	51	138	73

minutes to account for the flow-through time in the flotation tank. This material was allowed to settle for 30 minutes. Samples were then taken to represent the overflow from a settling tank following vacuum flotation. Samples of raw sewage and flotation tank effluent were also taken for analysis. Actual plant studies on settling tank effluent following the flotation unit paralleled the results obtained by the pilot plant studies



FIG. 11.—Grease removal by vacuum flotation and settling—Plant C.

and showed that the method adopted would give more consistent results and still represent an accurate picture of what was being accomplished in the plant itself.

The results of these experiments are given in Table VII. These results have been averaged and presented graphically in Fig. 11. It

will be noted that flotation removes a considerable portion of the grease without resorting to settling. However, plain settling will remove slightly more than flotation. Passing the flotation effluent through a settling tank does succeed in removing more grease. As with the other auxiliary methods of grease removal the overall removal of grease obtained through the use of the flotation unit followed by settling is only a few per cent greater than with settling alone, as will be seen from Fig. 11. Most of the grease was removed in the vacuum flotation tank and very little was left to be removed by settling. In the operation of the activated sludge plant in which the unit was installed, the grease load on the primary settling tanks was relieved greatly, but the overall removal of grease was not appreciable enough to relieve the grease load going to the activated sludge.

Aero-chlorination was tried with the use of this vacuum flotation unit. These studies were made on a laboratory scale to facilitate the addition of large quantities of gaseous chlorine to the aeration mechanism. The results of these experiments have been reported in a previous paper by the authors (11). In order to complete the picture of the work done in connection with grease separation at Army sewage treatment plants, it would be advisable to present Fig. 12 from the afore-



FIG. 12.—Grease removal by aero-chlorination and vacuum flotation.

mentioned paper. This illustrates the results obtained through the use of various dosages of chlorine ranging up to 25 p.p.m. in the aeration unit preceding vacuum flotation. It will be noted that chlorine had no effect on increasing the removal of grease by this unit.

DISCUSSION

These studies have covered experiments using various auxiliary methods applied ahead of primary settling tanks to assist in the removal of grease from sewage at Army sewage treatment plants. The plants at which the investigations were carried out utilized various biological

secondary treatment processes which would be adversely effected by grease in the effluent from primary settling tanks. No attempt was made in the course of these tests to evaluate the effect of pre-aeration on the supply of oxygen to the sewage to facilitate odor control or oxygenate the sewage. This is a different phenomenon from that involved in the separation of grease from sewage in that dissolved oxygen is of prime consideration, instead of the buoyant effect of air bubbles. Similarly, no evaluation was made of the effect of the addition of chlorine to sewage for the same purpose. These subjects have been the subject of much discussion in the literature and elsewhere. The studies were confined to the effect of the auxiliary method on increasing the removal of grease from that which was obtained in parallel studies utilizing plain settling tanks. The quality of the effluent from the primary settling tanks was used as the criterion of the effectiveness of grease removal.

Tests were not conducted on the effect of chemical precipitation on the removal of grease. This subject has been investigated by a number of authors (12). It is known that by the addition of chemicals in sufficient quantity, practically all of the grease could be removed from raw sewage. Cost is a major consideration. The methods being studied were only those involving air as the principal medium added to sewage, supplemented in some cases by chlorine gas.

In all the tests performed during the course of these studies, no distinct advantage was gained in increasing the effectiveness of grease removal through the use of either diffused air or mechanical aeration, aero-chlorination, or vacuum flotation. The quality of the primary clarifier effluent was virtually the same with or without these auxiliary methods of treatment. However, the units did succeed in taking grease out of the sewage and relieving the load on the skimmers of the primary settling tanks in all cases. This was particularly true when heavy slugs of grease were encountered. These slugs were removed to a great extent in the aeration unit. The need for additional methods of grease removal must be based on the desire to relieve the load on the primary settling tanks. These experiments indicated maximum effectiveness in this direction.

The opinions expressed in this article are those of the authors based upon the results of their research on grease removal. They are not to be construed as indicative of War Department policy in these matters.

Conclusions

1. Diffused air aeration had no appreciable effect on increasing grease removal over the removal accomplished by plain settling.

2. Aero-chlorination with 5 or 10 p.p.m. of chlorine gas added to the air being diffused into the sewage had no effect on increasing grease removal.

3. Mechanical aeration increased the removal of grease a few per cent when grease was present in the raw sewage in concentrations over

100 p.p.m. Approximately 50 per cent of the grease was removed in the aeration unit.

4. Aero-chlorination with 5 p.p.m. of chlorine gas showed no further increase in grease removal over that obtained by the mechanical aeration.

5. Vacuum flotation increased the removal of grease a few per cent when the grease in the raw sewage was over 150 p.p.m. Over 75 per cent of the grease was removed in the flotation unit.

6. Aero-chlorination with chlorine up to 25 p.p.m. added in the aeration stage preceding flotation showed no effect on increasing the removal of grease.

7. Plain settling is one of the most effective means of removing grease from raw sewage.

REFERENCES

1. C. E. Keefer and H. Kratz, Jr., SEWAGE WORKS JOURNAL, 3, 50 (1931).
2. H. Heukelekian, SEWAGE WORKS JOURNAL, 15, 499 (1943).
3. E. Wright, *Civil Engineering*, 5, 435 (1935).
4. R. Eliassen and H. B. Schulhoff, SEWAGE WORKS JOURNAL, 16, 56 (1944).
5. Standard Methods for the Examination of Water and Sewage, A. P. H. A., 8th Ed., 1936.
6. R. Eliassen and H. B. Schulhoff, SEWAGE WORKS JOURNAL, 15, 491 (1943).
7. F. C. Roe, *Public Works*, 64, 15 (July 1933).
8. H. A. Faber, *Water Works and Sewerage*, 84, 171 (1937).
9. Bulletin 260, American Well Works, Aurora, Ill.
10. A. J. Fischer, *Engineering News Record*, 130, 297 (1943).
11. R. Eliassen and H. B. Schulhoff, SEWAGE WORKS JOURNAL, 16 (1944).
12. H. W. Gehm, SEWAGE WORKS JOURNAL, 13, 927 (1941).

DISCUSSION OF PAPER BY ELIASSEN AND SCHULHOFF

BY W. S. MAHLIE

Not much attention was given to grease removal methods until the army camp plants were put into operation, and then the operators became "grease conscious." Kessler and Norgaard in their study of army camp plants (SEWAGE WORKS JOURNAL, July 1942) pointed out the need for better grease removal methods, and this paper appears to be an answer to the question confronting army camp plant operators as to what can be done to improve grease removal methods. The title of this paper would, in a measure, exclude any discussions from one who has no contact with army camp treatment plans; hence the following remarks must be accepted with that in mind.

In view of the amount of publicity various methods of grease removal have received, the conclusions reached by the authors may bring forth some discussion.

An excellent paper "The Grease Problem in Sewage," by Messrs. Fales and Greeley, in *Trans. A. S. C. E.*, Vol. 108 (1943), p. 507, gives some results obtained at various plants. I have taken their figures and platted them to the same scale as in the authors' Fig. 1 and it is surprising to see the close agreement as to grease removal by plain settling.

On examining the results shown in Table I which covers about the range of grease quantities as are usually found in sewage, we find that when the grease content is below 97 p.p.m. a removal of 40 per cent is obtained by plain settling, and when the grease is in excess of this the removal is somewhat greater, *i.e.*, 61 per cent. In the data submitted in the Fales and Greeley paper, on sewage containing up to 80 p.p.m., the average removal is 39 per cent. In analyzing the results on Table III, Plant B, the percentage removed is somewhat higher than that of Plant A. For sewages up to 100 p.p.m. the removal is 71 per cent, while for sewage from 100 to 233 p.p.m. the removal is 68 per cent.

The fact that no appreciable difference in grease removal between plain settling and aeration before settling was found will come as a surprise to most of us as this method has been widely exploited. The experiments show results from 43 to 69 per cent removal, while results reported from actual plant operations run from 34 to 75 per cent.



FIG. 1.—Comparison of grease removal by plain sedimentation as determined by Fales and Greeley (*Trans. A. S. C. E.*, Paper 2187, 1943) and by Eliassen and Schulhoff.

Gehm (*this Journal*, July 1942), however, points out that aeration and settling does result in greater removals than by settling alone. However, his experiments were conducted under different conditions than the authors' in that he aerated for longer periods of time. The amount of air was not given. Gehm used three liter samples of sewage—the authors used 20 gallons.

I have been informed that at several large packing house waste treatment plants where grease recovery is practiced, that when the aeration was discontinued no appreciable change in the amount recovered was noticed, and as a result aeration was discontinued. It should be mentioned, however, that a flocculator was used in combination with aeration, and that flocculation was not discontinued.

The conclusions drawn by the authors regarding the ineffectiveness of aero-chlorination will no doubt bring forth some discussion in view of the results reported by Weist at Lancaster, Pa. (*Water Works and Sewerage*, Dec. 1938), who reports 38 per cent removal by settling alone, 50 per cent removal by aeration and settling, and 80 per cent by aero-chlorination and settling.

The authors are to be complimented on their approach to this study. In all sewage experiments the difficulty of sampling is considerable and with the use of large quantities of sewage, the errors are minimized. Unless one has actually done so, no one can fully realize the time consuming methods of accurate grease determination, and I would like to take this opportunity to express my appreciation of their efforts.

In view of the shortage of fats at present and the fat saving program, some of us no doubt will wonder why we are not giving more study to the recovery of fats at sewage disposal plants. It must be remembered that the grease received at the ordinary sewage treatment plant is not nearly as pure as that recovered from the kitchens. It contains large quantities of mineral oils. True fats consist of a glycerine base united to a fatty acid constituent. During saponification in the manufacture of soap these two constituents are separated from each other, and the glycerine is set free, while the fatty acids combine with the lye to form a soap, and it is here that the glycerine is recovered. We are saving fats not for the fatty acids but for the glycerine which can be converted to explosives. Soaps either used or unused have no value for glycerine recovery. As a consequence grease removed from ordinary sewage has generally little value in the fat recovery program.

In normal times we might say that in soap manufacture the glycerine is a by-product and the soap is the more important, but in war times the situation is reversed and glycerine becomes the more important and the soap of lesser importance. Then, too, greases recovered from sewage present a most difficult refining problem.

Discussion of Paper by Major Rolf Eliassen Entitled "Grease Removal at Army Sewage Treatment Plants"

By Harry W. Gehm

The justification of units providing very short detention periods (15 min. or less) for the purpose of grease removal, placed prior to primary sedimentation tanks, has never been proved. Before evaluating such a device it is necessary to decide what its function in operation is and what results may be expected. We may formulate the function in the question: Is such a device intended to produce in conjunction with the clarifier an effluent decidedly lower in grease content or to remove only a very small part of the grease, easily separated, which causes rapid scum formation in the clarifier? If it is the function to produce an

effluent lower in grease content, it may immediately be concluded that such devices, as have been common in the past will not appreciably aid the overall removal of grease because they were never effective in lowering the suspended solids content (of which the grease is part) of the effluent of clarifiers materially. Devices employing detention periods of greater duration (30 min. or more) have been able to reduce the suspended solids, hence the grease content of clarifier effluents. Aerators and flocculators are examples of these.

Major Eliassen's work thoroughly covers this phase of grease removal and definitely shows again that short detention devices do not increase appreciably the quantities of grease removed by normal periods of sedimentation.

Major Eliassen's observation concerning the failure of aeration and aerochlorination to remove grease as measured by analysis of the sewage is easily understandable. When we consider grease removal figures observed by others who collected, weighed and analyzed the grease separated and reported the results in terms of pounds per million gallons of grease collected and convert the data into parts per million, we find:

	P.P.M. Grease Removed	
	by Aeration	by Aerochlorination
Kieffer	0.1	0.4
Gehm	5	7

The magnitude of these figures is well within the sampling and analytical error dealt with in sewage. Expressed in this way, the removal effected by the combination of aeration or aerochlorination and settling is no greater than that by settling alone. This issue has been clouded by the use of percentage increase removal figures. For instance: Four-tenths p.p.m. removal of grease is three hundred per cent higher than one-tenth p.p.m. but despite this it is still only four-tenths of one p.p.m.

It has been noted, however, that by separating the easily removable portion devices for the removal of grease have aided plant operation by taking the load off the skimming devices of the sedimentation tanks. As most of these are tied in with the sludging mechanism it is necessary to run both at the same time. Thus it is often impossible to skim the tanks frequently enough to prevent surface accumulation without interfering with sludge compaction.

Considerable doubt may be expressed concerning the economy of separate devices for removal of this relatively small quantity of grease. Independently operated skimming devices of efficient design embodied in the clarifier appear to be a more logical answer to this problem. Such devices exist and probably could be used to better advantage. Oxidation devices of adequate capacity, treating domestic or institutional sewage, will not be overloaded or upset if adequate sedimentation and skimming facilities precede the oxidation device. In some instances observed, as in the case of the sewages dealt with in Army camps, the grease content of the sewage was high and no difficulties resulted.

To produce clarifier effluents lower in grease content than normally obtained, some of the newer mechanical devices show distinct promise. Fine-bubble aerators and vacuum flotation devices are examples of these new developments. The ability of chemical treatment to remove practically all the grease from sewage should be kept in mind when grease removal is discussed. Some data published on the removal of grease by copperas alone is interesting enough to bear repetition:

Grease Removed by Copperas

Sample	P.P.M. Grease in Settled Sewage	P.P.M. Iron (Copperas)	P.P.M. Grease in Treated and Settled Sewage
1	50	15	12
2	20	10	6
3	29	5	13
4	31	15	5
5	33	15	8
Average	35	12	9

These results show that with a very low copperas dosage it was possible to remove an average of more than two-thirds of the grease present in the same sewage treated by settling alone. Such pretreatment might provide a solution at a relatively low cost where grease actually interferes with secondary treatment.

Added weight is given Major Eliassen's work by the fact that he dealt with sewage of high initial grease content. If high removals could be produced by aeration, aerochlorination, or chlorination followed by aeration as practiced at present, they would certainly have shown up in the large number of data collected. The writer was privileged to be in close contact with this work and feels that it was carefully executed in every way possible. In a most convincing manner, Major Eliassen has indeed filled a gap in our knowledge of this subject.

Sewage Works Design

SEWAGE TREATMENT PRACTICE—STANDARDS FOR MUNICIPAL SEWAGE TREATMENT PLANTS*

By Arthur S. Bedell

Chief, Bureau of Sewage and Waste Disposal, Division of Sanitation, New York State Department of Health, Albany, New York

In discussing the standards for the design of municipal sewage treatment plants and more particularly as concerns the practice in the New York State Department of Health, it seems desirable to spend a few moments on the background of the standards, especially as to the purpose and need for such standards. Although neither the Federal Government of the United States of America nor New York State has promulgated any laws or published any standards on the quality of sewage effluents, such as has been done by the Royal Commission on Sewage Disposal in England, nevertheless the Federal Government maintains jurisdiction over all waters insofar as interference with navigation is concerned and limits its activities in general to problems involving deposits in navigable channels and the problem of oil pollution. It is true that in very recent times the Federal Government has taken an active interest in pollution of waters from a public health point of view and probably will become increasingly active in this regard.

Until quite recently it has not generally been the custom for State governments to establish definite standards on the quality of sewage effluents on a state-wide basis. There has been a tendency and, I believe, wisely so, to consider each case of stream pollution or sewage disposal on its own merits. This broad view and to some a haphazard policy gives a very necessary flexibility in considering stream pollution cases since there are so many factors to be considered other than volumetric dilution and dissolved oxygen content in the receiving stream. During the past fifteen years there have been promulgated a number of Interstate Compacts on regulating the cleanliness of various streams or bodies of water in the U. S. A. Also in recent years there has been a tendency to classify streams on the basis of their present or potential purity and use. The State of Pennsylvania and, more recently, the New England States have taken definite steps in this direction. In New York State the Interstate Sanitation Commission acting under a tri-state compact to which New York, New Jersey and Connecticut are signatory has classified the metropolitan tidal waters in the vicinity of New York City into Class A and Class B waters, the former being waters to be used primarily for recreational purposes, shellfish culture and development of fish life.

* Presented on October 28, 1943, at the Tenth Annual Convention of the Canadian Institute on Sewage and Sanitation, Niagara Falls, Canada.

Although hard and fast standards have not been formally adopted in most states, it is the custom to follow "good sanitary engineering practice" in the endeavor to secure the common law rights of riparian owners. Fortunately there is a good deal of unanimity of opinion in the States so that the consulting engineers and the state authority usually see "eye to eye" in these matters.

Although somewhat apart from this discussion, I would like to call your particular attention to two references to a topic that is closely allied; namely, the matter of stream pollution and stream standards without which, of course, there would be no point in setting up standards for sewage treatment effluents. I have in mind particularly a paper prepared by George J. Schroepfer, Past President of the Sewage Works Federation, the paper being entitled "An Analysis of Stream Pollution and Stream Standards" which appeared in the September, 1942, issue of SEWAGE WORKS JOURNAL, pages 1030 to 1063. The paper contains a compilation of data on the hourly, daily and other variations in stream conditions, in addition to an admirable summary of standards throughout the United States and an excellent bibliography. The second article appears in the same JOURNAL and it is by Warren J. Scott, Director of the Bureau of Sanitary Engineering of the Connecticut State Department of Health, the paper being entitled "Classification of Inland and Shore Waters" and appears on pages 1064 to 1073. Here we have probably the most recent attempt at interstate cooperation on stream pollution matters.

Restricting our field now to New York State practice, which we believe is a reasonable reflection of American practice, we find first the authority of the State Department of Health dates back to 1889 when the Village Law required that sewer systems for villages should be comprehensive in scope and the plans must be approved by the State Department of Health before construction was commenced. This law is still in force although it has been amended several times. It has proven of great value to the people of the State in providing for intelligent planning for the future.

Actual legal control over stream pollution in New York State would appear to date from the year 1903 when the so-called "Anti-Pollution Law" was passed. This law in addition to setting up the modus operandi for the protection of the watersheds used as sources of water supply for New York City required that any person, corporation or municipality discharging wastes into the waters of the State in quantities injurious to public health must secure a permit from the State Commissioner of Health and in the granting of such permit the State Commissioner of Health might stipulate the conditions under which such sewage or waste discharge might be permitted. It might safely be said that since that time the State Department of Health has approved no plans for new public sewer systems unless adequate treatment of the sewage has been provided. It is true that from time to time plans have been approved for lateral sewer extensions to *existing sewer systems* in a number of communities not provided with sewage treatment works.

However, in such approvals we have always reserved the right to require treatment whenever we deem it necessary and in many instances have set definite time limits or specified dates on which plans should be submitted and the works constructed.

To complete the legal picture it might be well to note that in addition to requirements of the Public Health Law and the Village Law sewerage matters are also governed in unincorporated places by the provisions of the Town Law, which provide for setting up sewer districts, and furthermore before any sewer district can be formed plans for the sewer system and sewage treatment works must first receive the approval of the State Commissioner of Health. The question of the approval of plans for the interception and treatment of sewage in cities is adequately covered in the Public Health Law. It might be well to add at this point that this law also provides for the formation of sanitary sewer districts where in the interest of public health contiguous areas might profit by joint collection and disposal of their sewage irrespective of their form or lack of incorporation. Thus far the difficulties of formation and financing have been such that no advantage has been taken of the provisions of this law. However, special legislation has enabled two counties to establish trunk sewer systems and treatment works to serve large areas, including incorporated cities and villages as well as unincorporated places. Likewise in the case of the City of Buffalo a special act of the legislature enabled the formation of the Buffalo Sewer Authority, which in many respects is independent of the city government and depends on sewer rentals for its operating income and for the interest and amortization of its bonded indebtedness. This authority also has the power to provide trunk sewer capacity for and to treat the sewage from adjacent areas outside the city limits.

Shortly after the passage of the Anti-Pollution Law in 1903, it became evident that it would be desirable to establish definite requirements regarding the preparation and submission of plans for sewers and sewage and waste treatment works and to set up certain standards for the design of the different units of treatment. The following quotation from one of the earlier bulletins setting up these requirements is of general interest:

> "The Department will in general approve only of plans which include disposal works for such complete purification as will produce a clear and 'stable' effluent. This requirement may be increased or diminished according to local conditions, the volume and use of the stream below the discharge and the necessity for protecting water supplies, bathing, etc."

From this, it would appear that in the early part of this century the Department was willing only to consider plans for sewage treatment that provided some form of secondary treatment. However, the regulations also provided for the temporary omission from construction of certain portions of the works provided for the complete purification of the sewage. In other words, the Department then felt and still does feel that adequate forethought should be given to the ultimate needs of the community as to population growth, strength of sewage, decreasing

dilution in the receiving body of water and change in use of the water in the receiving body. It is interesting to note that 40 years after the establishment of most of these standards or criteria for design we find that essentially while our modern methods of approach to the problem may vary somewhat owing to our greater knowledge of the processes at work in the treatment of sewage, nevertheless the standards then established are still considered good sanitary engineering practice not only in New York State but throughout the United States. It is also interesting to note that with the passing of time these regulations have become more and more detailed and yet are still basically broad enough to be generally applicable throughout the State.

In discussing this general topic of standards for sewage treatment in New York State I feel constrained to discuss not only the standards and criteria but also the so-called rules and regulations set up by the State Department of Health as a basis on which plans for sewage treatment are reviewed by the engineering personnel of the Department, since the rules and regulations cover considerably more than merely the standards which some might conclude refer only to the biology and chemistry of sewage treatment. At the present time considerable thought is given in the review of plans to plant operation, not only as to provisions for the safety and health of the operator himself but also for ease in operation.

I referred above to the remarkable foresight of the engineer who originally drafted the rules and regulations, yet after all, this may be due in large part to the fact that so far as degree of treatment required for sewage is concerned, it is largely a matter of the available dilution in the receiving stream and the use to which the water in the receiving stream is put. The fundamental work done at the Lawrence Experiment Station in the State of Massachusetts on the efficiency of various types of sewage treatment and the measure of dilution required in the stream to prevent conditions of nuisance established more or less at the same time our basic standards of treatment plant design which still seem to hold true even though in those remote days very little was known about B.O.D.

While the rules and regulations of the Department do not definitely set forth any basic standards in terms of B.O.D. or suspended solids, the Department follows what is generally considered good sanitary engineering practice and frequently, where there is no existing sewer system and the treatment works are designed simultaneously with the sewer system, it is necessary to proceed on purely theoretical grounds. On this basis it is considered that the flow of sewage in a municipal system will be 100 gallons per capita per day and, unless there are some industrial wastes which are unusual in quantity or quality, the sewage should have a strength of 250 parts per million of suspended solids and a 5 day B.O.D. of 0.17 pounds per day, which is approximately 200 parts per million of B.O.D. So far as dilution in the receiving stream is concerned, purely on a basis of preventing nuisance conditions, it is generally considered that settled effluent can be discharged into a normal

stream without creating conditions of nuisance if there is dilution water to the extent of at least 4 c.f.s. per 1,000 population. In general this minimum flow is based on the average flow for the minimum two weeks where the records extend over a considerable period of time. It is felt that the above criteria are somewhat close to the margin in dealing with unknown factors so that frequently in considering the design of smaller plants a factor of safety should be introduced, particularly since one cannot expect the perfection in operating technique in a small community that one could expect in a larger one. In a similar way we have found through experience that, even where consulting engineers have spent considerable time in the careful consideration of the quantity and strength of a known sewage and planned for reasonable efficiencies of the various units of sewage treatment, nevertheless the actual operation of the plant after construction has indicated that all expectations could not be realized and the plant did not have the anticipated capacity. This, however, is seldom catastrophic since it frequently means merely that the anticipated life of the plant has been decreased and that additions will have to be made at an earlier date than anticipated.

With the above fundamentals in mind I would like to hastily run through some of the New York State requirements and standards that have proven desirable to secure expected efficiencies and to provide ease of operation. Although population estimates are now rather uncertain and our conception of them has undergone a fundamental change in the past decade, we expect that the capacity of the treatment plant should provide for an estimated future population 10 to 15 years hence. The plant site in general should provide sufficient area so that not only can the plant be enlarged to take care of the probable ultimate quantity of sewage but also an increased degree of treatment can be provided should this prove necessary. Although we understand some large municipal sewage treatment works are odorless in their operation, nevertheless, we feel that isolation of the site is extremely important.

With regard to main sewage pumping plants, at least three pumping units are desirable and the total capacity of the pumping station should be such that if the largest pumping unit is out of service the remaining units could pump the maximum flow of sewage. The pump sizes should be proportionate to the varying rates of flow and frequently an extra pump will greatly increase the efficiency of the plant by providing greater uniformity of flow. All pumps should be protected by screens and suitable ventilation should be provided both in the wet well and the pump room.

Screens

Bar screens should be provided at the entrance of all sewage treatment works, and in all but the smallest treatment works mechanically cleaned screens or their equivalent are now found desirable. Frequently the screenings are ground or shredded and returned to the sewage flow where they are removed with the settled sludge and the troublesome problem of handling screenings is eliminated.

Grit Chambers

Although somewhat contrary to the general opinion, our Department has found it desirable to require grit chambers even on separate sanitary systems. Experience has shown that grit does find its way into most sanitary sewage systems and its presence in the settled sludge always gives considerable trouble in the digestion compartments and in the handling of the sludge.

Sedimentation Tanks

While the septic tank was once considered a marvelous discovery in the treatment of sewage, advance in the art of sewage treatment has definitely indicated its deficiencies, so that in New York State we no longer will approve septic tanks for municipal sewage treatment plants. A two story Imhoff tank still has many things in its favor in spite of the popularity of sedimentation tanks with mechanical removal of sludge and separate sludge digestion. Two hour sedimentation is generally considered adequate and in recent years we have found it necessary to increase the capacity of the sludge digestion chambers in Imhoff tanks, particularly for the smaller populations. In general, for populations less than 5,000 we require 3 cu. ft. per capita for sludge digestion. A minimum of 2 cu. ft. per capita is permitted for populations over 10,000. In sedimentation tanks with mechanical removal of sludge two hour detention is generally considered satisfactory and the optimum depth of 8 feet provides an overflow rate of approximately 700 gallons per sq. ft. per 24 hrs. More and more attention is being given to the design of inlets and outlets and the Department is always open to conviction on this until some large body of experience will prove that one arrangement is superior to another in securing effective sedimentation. In separate sludge digestion tanks a digestion capacity of from 3 to 4 cu. ft. per capita is required, and where the design population exceeds 2,500, it is generally anticipated that heating of the sludge will be provided, in which case the cubic content is reduced in proportion to the increasing populations ranging from three cubic feet per capita for populations of 3,000 to two cubic feet per capita for populations greater than 10,000. Adequate safety precautions are required for the collection and utilization of the gas, and provisions for auxiliary heat in case of emergency are usually required.

No fixed standards have been adopted regarding chemical precipitation and there are only a very few installations in the State.

In the design of units for the secondary treatment of sewage, careful consideration must be given to the organic strength of the sewage in terms of the five day biochemical oxygen demand. The following standards are based on a sewage flow of 100 gallons per capita per day having a B.O.D. of 0.17 pounds per capita per day. Within reasonable limits, therefore, the size of the units depends almost entirely on the basis of the population tributary.

Intermittent Sand Filters

General good engineering practice is followed in the design of sewage sand filters and a depth of 3 feet of sand is expected, the sand having an effective size of between 0.25 and 0.5 mm. with a uniformity coefficient preferably not over 4.0. The rate of application of the effluent to the sand bed should not exceed 100,000 gallons per acre per day based upon a per capita flow of 100 g.p.d. In cases where a settled trickling filter effluent is applied to the sand filter, the rate of application may be increased four times, while on limited watersheds used as sources of public water supply only 50 per cent of the above rates is permitted.

Trickling Filters

Trickling filters should in general have depths between 6 and 10 feet, a filter medium of carefully selected material of fairly uniform size between the limits of 1 and 2½ inches and an area sufficient to give a rate of filtration of 300,000 gallons per acre per day per foot of the effective depth (based upon a per capita flow of 100 g.p.d.). It is always required that the trickling filter effluent be passed through a final settling tank before discharge into a stream and a detention period of an hour and a half is required. Provisions for frequent and regular removal of the sludge are required and the sludge is usually carried to the inlet of the primary sedimentation tank or to the separate sludge digestion tank, and 25 per cent additional sludge digestion capacity is required. No standards have as yet been adopted for high capacity filters, although two types of such filter are now in operation at municipal plants in the state and the results of operation are being carefully studied.

Activated Sludge

Activated sludge treatment may be either of the diffused air or mechanical aeration type. The aeration tank should have an aeration period of not less than six hours for the diffused air type and an aeration period of not less than eight hours for the mechanical aeration type. The capacity of these tanks is based on the daily flow of sewage plus 25 per cent for returned activated sludge. At least 1 cu. ft. of air for a gallon of sewage, with a pressure of 5 to 10 lbs. per sq. in. must be provided. Primary sedimentation tanks preceding the aeration tanks should have capacities equivalent to 30 to 60 minutes average daily flow of sewage. Tanks for the digestion of the excess activated sludge must have capacities of not less than 5 cu. ft. per capita unless provision is made for heating and conditioning the sludge. The effluent from the aeration tank should be passed through final settling tanks having a two hour detention period before discharge into the receiving stream.

Sludge Beds

Lines carrying sludge must be so arranged as to permit draining and flushing after use and the invert of the pipe discharging onto the sand

bed must be at least 12 inches above the surface of the sand and a suitable splash plate must be provided to prevent scouring the sand. The sand bed should have about 6 inches of sand on 6 inches of graded gravel and must be constructed of specification sand since otherwise there is a tendency to use run-of-bank sand and frequently even ordinary soil for such purposes which, of course, is entirely unsatisfactory. Where the bed is surrounded with a wall to support a glass superstructure the top of the wall must not be more than 18 inches above the sand surface and adequate provisions for ventilating with the side sash opening inward should be made. The beds must be divided into small units to permit flexibility of operation and suitable facilities must be provided for the removal of the dried sludge.

Disinfection

Chlorination by means of chlorine gas in water solutions or hypochlorite solutions is the only means of disinfection used in New York State; the latter because of expense is rarely used in municipal plants. A contact period of at least 15 minutes under maximum flow conditions is required for adequate disinfection and it is usually required that 0.5 p.p.m. of chlorine residual be maintained in the effluent. Ordinarily where the discharge of a chlorinated, settled effluent is permitted, it is expected that pre-chlorination will be practiced since in this way a longer period of contact is possible and any irregularities in flow will be taken care of. Application of chlorine through solution feed apparatus is generally required since the direct feed of chlorine gas in sewage is not generally satisfactory. The chlorine apparatus is required to be placed in a separate room with an outside entrance only and with provisions for heating during the winter season where year round chlorination is practiced. In checking the capacity of chlorine apparatus and based on the average sewage flows, we expect the apparatus to have a capacity of 18 p.p.m. for sedimentation tank effluent, 12 p.p.m. for trickling filter effluent and 6 p.p.m. for sand filter effluent. In the disinfection of trickling filter effluents the chlorine solution is generally applied to the inlet of the final settling tank and in the case of sand filter effluents a special reaction tank of at least 15 minutes detention period is required.

Bypasses

In the past the Department was very loath to approve bypasses around the sewage treatment plant because of the possible abuse of the use of such devices. However, with the increasing mechanization of treatment works and the need for temporarily shutting down certain portions of the works for repairs, it is now generally deemed advisable to provide bypasses around various units of the plant, provided they are safeguarded against unauthorized and unwarranted operation. In certain critical cases we have gone so far as to require that the gate valves on bypasses be locked and the key be kept in the possession of either the chief operator or some other municipal official.

It is now generally recognized throughout the State that the State Health Department is interested in a sewage treatment works even after it has passed upon the design as adequate. To this end, it is required, therefore, that every plant be provided with some means of measuring sewage flow and, if possible, to have some recording and integrating device to provide a continuous record. In the moderate sized plants Venturi flumes have been installed immediately after the grit chamber, and in this way we secure the means not only of measuring the flow but of controlling the velocity through the grit chamber so that the deposition of grit will be most efficient. In addition all new plants must be provided with adequate laboratory space and equipment for the laboratory control of the operation of the plant. The number and type of tests, of course, vary in accordance with the needs of each individual case. Furthermore, it is expected that all necessary operating tools be provided at the time the plant is built and not leave to the operator the unhappy necessity of securing this equipment from the municipal government when they are in a less complaisant mood.

Industrial Wastes

While the treatment of industrial wastes is not a part of the topic under discussion, nevertheless due consideration should be given to the problem of industrial wastes in a municipality when the sewage treatment plant is being designed and the importance of making a careful study of the industrial wastes tributary to the sewage treatment works and their probable effect on the operation of the plant cannot be overemphasized. In a number of instances, these wastes are of such a character that they can be discharged into the plant with the domestic sewage and the only thought that need be given to them is to provide adequate volumetric capacity. On the other hand there will be in many instances wastes that will require pre-treatment at the industry before they should be discharged into the sanitary sewer system. In this connection we have in mind such matters as pickling liquids from steel plants, which unless neutralized at the industry might seriously damage not only the sewer system and other structures but would seriously interfere with the operation of secondary devices such as trickling filters. To this end the Department usually includes among the conditions in its permits to municipalities for the discharge of sewage effluent into the waters of the State, one requiring that all industrial wastes shall be adequately pre-treated before discharge into the sewer system.

Reference has been made above to the necessity for providing for the health and safety of the operators. Among other points, there is the matter of water supply that in the past was probably overlooked and we feel that not only should the public water supply be protected from pollution but also the health of the operator should be safeguarded. Therefore in order to protect the public water supply from backsiphonage of polluted water from the sewage treatment works, the public water supply line should be provided at the point of entrance with an

approved installation of double check valves of the Special Factory Mutual type. Furthermore, within the plant itself all small service lines in lavatory basins, or at other points where drinking water might be obtained, should be on a separate line from the main plant supply in order that they may not be contaminated by backsiphonage.

While I have gone into the above matters in some considerable detail, it is not at all a comprehensive statement and I have endeavored to emphasize the more important points that might be considered somewhat controversial or novel. Again it might be considered that these standards and regulations set up by the State must perforce be of such universal application that either they cannot be detailed to any extent or that, if so detailed, frequent deviations from the standard would have to be permitted. Such, however, is not the case, largely due perhaps to the fact that although some of the standards or regulations appear very detailed in statement, nevertheless they are based on sound fundamental principles and little deviation from them is found to be necessary. The Department has always been open-minded when an engineer has made a very careful study of the problem and presents a sound rational analysis of the situation and in a number of instances under such conditions reasonable allowances have been made to fit the local conditions.

I have known several cases, however, where experience later showed that the Department might have been well advised to have held to the original standards.

In closing I wish to say that in the application of these standards and regulations in our review of plans we have always found the consulting engineers not only in our own state but from other states to be most cooperative and open to suggestion especially where such suggestions have been based on our own observation of operation of sewage treatment plants in our own state. Furthermore, we owe a great deal to the sewage treatment plant operators in our state for keeping accurate records of operation of their plants and making timely observations, not only enabling them and our district engineers to spot the cause of operating troubles but frequently such observations have resulted in modifying practices in design. Furthermore, such records of operation in a number of instances have proven invaluable in permitting economy in design of future additions to the plants in question since we had exact operating experience upon which to base our new design.

SEWAGE TREATMENT FOR HOMES AND INSTITUTIONS *

By A. E. Berry

Ontario Department of Health, Toronto

Public sewerage systems now serve about 150 urban communities in Ontario. This represents approximately 60 per cent of the entire population. A substantial percentage of the total number of citizens reside in rural and in semi-urban centres. While it is anticipated that the postwar development will extend these services considerably there will still remain many sections which can be served only by private sewerage works. The expansion of hydro-electric power to the rural areas and to villages will do much to enable home owners to secure these sanitary facilities, even when neither water works nor sewers has been constructed as a public enterprise.

In addition to private residences there is being continuously constructed buildings of various kinds so far removed from public sewers that they must provide for their own disposal works. These include schools, colleges, institutions, industries, war and peace-time camps, hospitals, and small groups of houses. In this paper there will be considered only water carried sewage systems.

Engineer's Responsibility

The municipal engineer has not always been directly associated with the installation of sewage disposal works for private residences or for small institutions. This work is more frequently supervised by the local health officer or his representative, such as the plumbing inspector or sanitary officer. It is believed that the local engineer can play a more useful part in this field, and that his assistance is likely to be sought to a greater extent in the future, even for work at private residences. For larger systems his guidance becomes a necessity.

Legislation

The Ontario statutes contain references to non-municipal sewerage works. Two of these are in the Public Health Act. The first in Schedule B, Section 14, requires that the approval of the local medical officer of health be obtained before septic tanks, cesspools and similar systems are installed.

The other section is a recent amendment to the Public Health Act, Section 101, which requires the approval of the Provincial Department of Health for all sewerage projects whether they be undertaken by public bodies or private parties.

* Presented at Tenth Annual Meeting of Canadian Institute on Sewage and Sanitation, Niagara Falls, Canada, October 28, 1943.

Private Residences

For private dwellings the septic tank installation is almost the universal choice when no public sewers are available. They have been used for many years with no major change in design or operation. Their success depends on proper design to meet local conditions. There appears to be considerable misunderstanding in respect to the functioning of these systems, and since they are built by many who are inexperienced, and under varying conditions, this is not surprising. It seems desirable, therefore, to discuss some of the factors involved, both in the construction and operation, in these septic tank systems.

Design of Septic Tanks

Operating experience seems to indicate that design features are of major consideration in the success or failure of a septic tank unit. This must be correlated to local requirements. These tanks are similar to those used in the past for municipal purposes with the exception that they are smaller, and the flow of sewage is likely to be more variable. Yet this fact appears to be overlooked all too frequently, and the septic tank is regarded as a mysterious device for producing an effluent of superlative quality.

The function of this tank, as in the case of the larger one, is the separation of the solids by sedimentation in order to permit the disposal of the liquid by filtration and to prevent choking of the pores of the soil. The deposited solids must digest in order to prevent an excessive accumulation in the tank and frequent cleaning.

The size of the tank is determined by the flow of sewage to be treated. A liquid capacity equal to a 24-hour flow is generally recognized as satisfactory for the small tank, with this decreasing to 12 hours for larger units.

Sewage flow of approximately 50 gallons per capita per day may be assumed as an average for private residences, and to this may be added an allowance for sludge accumulation. A figure of 15 to 20 gallons per person per year for this is often suggested as reasonable, and with an allowance being made for two years storage. This volume for a settling tank may seem high, but it is necessary in order to provide for the wide fluctuations in sewage flow reaching the tank. As the size increases less provision is necessary and the flow will be more uniform.

A minimum size of tank should be specified for residences where only a few persons are using the system. This minimum is set at different figures by various authorities. It is suggested as between 300 and 500 gallons. This volume is designed to overcome the problem of intermittent excessive flow in comparison with the volume of the tank.

Baffles on both the inlet and outlet of the tank are required. For small units a Tee section of pipe is sufficient, but for larger units a baffle board across the full width is desirable. The inlet pipe should be kept about 3 inches above the flow line in the tank.

Dosing Chambers

Dosing tanks, with siphons for intermittent discharge of the settled sewage to the field bed, are generally included in the designs of septic tanks, but there is some question as to their necessity for small units. The loss in head where one is used, makes them workable chiefly where the ground is sloping. For small tanks the rate of discharge at one time will be large in respect to the volume of the distributing tiles, and a proportion of the bed can be filled accordingly.

When dosing tanks are employed they should be sufficient to fill the tiles about three-quarters full at one time. The frequency of operation of the siphon should not be too great. Three or four times a day is a suitable objective but this will be influenced by the nature of the soil.

Subsurface Disposal Field

The liquid discharged from the septic tank still contains finely divided solids and it is offensive. This should not be discharged to a ditch or to a storm sewer. In most cases it must be further treated in a sub-surface filter bed.

The efficiency of these beds is dependent to a major degree on the absorptive qualities of the soil. They cannot function where this is heavy clay, or where inadequate drainage is provided. The laterals are best made of 4 in. tile, either farm drain tile or bell and spigot pipe. The joints should be left one-half inch apart in order to permit the free escape of the liquid. The use of stone or gravel around the joints is preferred to tar-paper covering. The tiles should be laid in rows of equal length, and generally should not exceed 100 ft. in length. Otherwise, even distribution is less likely to take place. The tiles can be laid practically flat where a siphon is used—or about 2 to 4 inches per 100 ft. where no siphon is used. This slope can be increased to about 6 in. per 100 ft.

The rows of tiles are spaced about 4 or 5 ft. apart, or at least three times the width of the trench. Where space is available it is desirable to use more land for distribution of the tank effluent. The depth of the tiles can be controlled by available drainage. If these are placed 18 to 30 in. below the surface better results are likely to be obtained in most situations. This arrangement also is less likely to pollute the underground water. Where, however, frost penetrates some distance, or where the grade does not permit of shallow trenches the tiles can be laid at depth, and if drainage from the area is good, little trouble is likely to develop.

Amount of Tile Required

The amount of tile required for distribution of sewage is a problem in most places. This depends largely on the porosity and drainage properties of the soil. The length required is generally given as about 20 to 50 feet per person. This, however, is more an approximation than an accurate estimate. Much information on requirements can be

obtained by percolation tests on the area in question. This is done by excavating a hole 1 foot square to the depth of the tile trenches, adding water to a depth of about 6 inches and observing the time required for the water to seep away. The time for the water to fall 1 inch may be correlated to the rate of sewage loading per square foot per day on the bottom of the sewage trench. The following figures are suggested:

Time for Water to Fall 1 Inch	Sewage Loading per Sq. Ft. of Trench per Day
1 min.	3.5 gal.
2 min.	3.0 gal.
5 min.	2.0 gal.
10 min.	1.5 gal.
30 min.	0.7 gal.
60 min.	0.5 gal.

Some judgment is necessary in making this test to ensure that the condition of the soil is not abnormally dry or wet, but is representative of average conditions.

Where soil is excessively dense, it may be necessary to use sand filter trenches. These consist of a bed of sand placed between the distributing tiles and the underdrains. Difficulties may be experienced in the operation of these, but they may be the only alternative. Care is essential to ensure that the bed is not overloaded.

Similarly cesspools may be used in some places instead of tiles, but these will choke in time unless the soil is quite porous.

Operation of Septic Tanks

Considerable confusion exists in respect to the operation of septic tank systems. It is well to keep in mind that these tanks are quite similar to the larger municipal units. Their size makes them subject to the effects of variation in the contents of the sewage. In general it may be said that all household wastes may be discharged into these systems. Their successful operation over many years is sufficient proof of this.

The cleaning of sludge from tanks is usually neglected, and so long as the system continues to operate at all they are given little attention. Unless this sludge is removed it may be carried into the tiles and result in choking. Removal of sludge about every two years is considered desirable.

Grease, laundry waters and other wastes may be handled readily in these tanks. Where grease is excessive, as in the case of dining rooms, it is desirable to use grease traps to prevent choking of the sewer, as well as too frequent removal of the accumulation from the septic tank. These grease traps, to be of value, must be cleaned regularly, as required.

Institutional Plants

When sewage must be treated from premises involving larger flows than in private residences, it is necessary to consider the feasibility of other methods. Septic tanks with subsurface filter beds are not in-

tended for very large flows. The cost of such an installation may also exceed that of others which will give equally good results.

The flow of sewage must first be estimated as closely as feasible. These flows will vary considerably, but the following daily figures are given as suggestions only:

Schools	15 gallons per person
Hospitals	100 to 175 gallons per person
Institutions	75 to 100 gallons per person
Factories	20 to 30 gallons per person
Camps (civil)	25 to 50 gallons per person
Military Camps	75 gallons per person
Hotels	75 gallons per person

While it is possible to construct septic tank systems using large amounts of field tile it is not considered a desirable project unless the soil is quite porous and the whole area can be drained readily. If more than 1,500 to 2,000 feet of tile is needed it is well to study relative costs of other methods of treatment. In several school systems in this province cesspools or leaching wells have been used in conjunction with tiles, and in this way the length of the latter is curtailed. This is recommended only for porous soils.

For institutional use the trickling filter can be employed with satisfaction, and with the assurance that a minimum of expert attention will be required. The modern method of recirculating part of the treated effluent increases the efficiency, and extends the application of this to conditions where a higher degree of treatment may be essential.

Similarly the intermittent sand filter, while an old method, can be employed under some conditions for larger units. The effluent is a most satisfactory one.

In summarizing sewage treatment methods for homes and institutions, it may be emphasized that they are not greatly unlike the municipal systems, but on a smaller scale. For this reason, however, care is necessary in the application of these methods to the treatment of small quantities of sewage. It is hoped that municipal engineers will assist health officers in the supervision of these systems within their territories.

THE OPERATOR'S CORNER

THE VALUE OF OPEN DISCUSSIONS ON OPERATION PROBLEMS

The entire *Operator's Corner* in this issue comprises only the edited transcript of the Breakfast Forum discussion which was a part of the program of the Second Wartime Conference held at Chicago last October. We have always been a proponent of such open discussions of operation problems but have not yet encountered a transcript record which better justifies them than the one which is presented here.

Our reaction, while engaged in the somewhat arduous task of editing, was that the material was refreshingly frank and untempered by the conservative qualification of opinion that is so evident (and properly so) in written manuscripts. When one is faced with a problem which is common to many others, there is much satisfaction in "taking down the hair" and in listening while his contemporaries do the same. Furthermore, there is a surprisingly valuable exchange of ideas and viewpoints which leads to a better understanding between those engaged in the various phases of the sewage works field.

The success of these discussions is in direct ratio to the manner in which they are handled by the leader or chairman. We feel that Chairman John C. Mackin and Messrs. Niles, Bedell, Downer and Nelson, who directed the Forum, should be credited with a task well done. Chairman Mackin is due additional recognition for his planning of the entire symposium.

Here's to more open forum discussions of similar character. May you find the transcript as interesting and informative to read as we found it to be while preparing it for publication.

W. H. W.

THE OPERATOR'S FORUM *

JOHN C. MACKIN, *Chairman*

I. USE OF SLUDGE IN THE VICTORY GARDEN CAMPAIGN

LEROY W. VAN KLEECK, DAVID A. BACKMEYER, HENRY A. RIEDESEL, P. W. RIEDESEL, AND A. H. NILES, *Leader*

Mr. Niles: When Pearl Harbor came, we immediately had a demand for nitrogen for war purposes and that meant, of course, a shortage of

* Symposium presented at Federation's Second Wartime Conference on Sanitation, Chicago, Illinois, October 21–23, 1943.

nitrogen for the growing of foodstuffs. We were certainly limited as to the total amount of nitrogen available. Then, with the tremendous impetus that was given to Victory Gardens, the interest in sewage sludge increased by tremendous percentages. I don't think there is a sewage plant operator who has not been almost swamped with sludge business, if he put it out at all for consumption.

The interest aroused has led to this panel discussion. We shall begin with a few papers and then open the topic to general discussion from the floor. The first speaker will be Mr. LeRoy W. Van Kleeck, of the Connecticut State Department of Health.

Mr. Van Kleeck: Mr. Niles, gentlemen, I am not going to read a paper. I have six items here that I will discuss very briefly. On all of them I hope there will be discussion from the floor.

In regard to the success of our own Victory Garden program in Connecticut this year, we produce in Connecticut roughly 18,000 tons of digested sludge cake a year. In spite of concerted efforts for the last 13 years to get that sludge back on the land, where I think it belongs, farmers and others have probably not used more than a third of our output up to this year. This year, it is estimated that we are using at least half of the output.

One thing that helped a great deal was to get the Connecticut Agricultural Station interested. I went down and talked with Dr. Lunt, the head of the Soils Department. He didn't know a great deal about sludge although he had heard about it. The Director of the Station often wondered why sanitary engineers hadn't pushed it's use and asked the doctor to work along with me. Dr. Lunt ran experiments this summer on cabbage, string beans, and so on. He is behind the movement now and the Station has been releasing newspaper publicity to which garden supervisors will give far more attention than to me or any other sanitary engineer. It is the old story, that if the agricultural department says it is good, it must be good.

My advice and my number one point would be to see the local county agents or agricultural men in your own states. Get them interested in pushing the program and advising the farmers how to use it. It will help a great deal.

The second item I have is not to expect heavy yields from heavy applications of sludge. It has been my experience in experimenting with various sludges in my own garden, and I have also seen references in the literature, particularly by Dr. Rudolfs, pointing out that frequently the heavier the application, the lower the yield. This is also borne out in the statement you hear, "Well, my potato crop did a lot better the second year than the first year, when I used sludge on the soil." There is a reason behind that. I didn't understand it until Dr. Lunt explained it to me. He says any humus material low in nitrogen —cow manure, sludge or anything—must first undergo further breaking down of the organic matter to bring it to the humus form. While the microorganisms are breaking down and oxidizing this organic matter in the sludge, they are robbing the soil of nitrogen, which the roots

of the crop require. Until this process is fairly completed, sufficient nitrogen isn't available to the plants. Therefore, there is a retardation of the growth of the early spring crops.

The third point involves my impression of refuse incinerators built in conjunction with a sewage plant, and utilizing the waste heat from the incinerator to dry sludge. We have one fairly large plant of this type in Connecticut that is about to go into operation. It is designed for an average flow of 10 m.g.d. and comprises the common plain sedimentation and separate sludge digestion system. The vacuum filter cake goes to a flash dryer and the heat to operate that system will be taken from the refuse incinerator. After drying down to a five per cent moisture content, they can either burn the sludge in their refuse incinerator or by-pass and bag it for use as fertilizer, which I certainly hope they will do.

This practice impresses me because in the past we have rather felt that ordinary primary digested sludge did not have enough fertilizing value to warrant expensive equipment for drying, but here is a means of getting waste heat for practically nothing and it looks as though it would really be an economical plan.

In this connection, Mr. McDonald, Supt. of the Springfield, Massachusetts plant, tells me that enough sludge gas is produced by his digestion tanks to provide all the fuel he needs for drying sludge without burning any of it.

My fourth item is of interest in connection with vacuum filtration of sludges conditioned with lime and ferric chloride. As you know, if you are conditioning digested sludge with lime, the pH is pretty certain to be at least 10; the usual range will be 10 to 11. It occurred to me that such a high pH in the sludge cake might adversely affect the soil over a period of time. In New England at least, most crops do best with a soil pH between 6 and 7. Dr. Lunt undertook some work on this problem and the first thing he found was that sludge cake having a pH of 11 at the time of collection, dropped to about pH 7.5 after 2 or 3 days. All the samples that were selected did likewise and he attributed it to the loss of free ammonia in the cake. After the initial drop, most of them seemed to average around pH 7.5. He mixed various amounts of soil with the cake, some acid, some neutral, and some a little on the alkaline side, and he found most of the overall mixtures to be near the neutral point. He found all of the mixtures to be suitable for growing crops.

I obtained a similar answer to this question in talking with Mr. Bauer, the superintendent of the Middletown, Connecticut, plant. He has a garden about 30 feet wide by 150 feet long and has been growing crops on it for about 10 years. He has never used anything but sludge and has applied it at about 1¼ cubic yards per 1,000 square feet. If you figure that out on an acreage basis you will find it is a pretty high application. He has been doing this for five years on this garden plot, and the sludge is lime-conditioned with a high pH. I took samples around his garden before any crops were planted, with a core bore, and of the six samples collected, the average pH was 6.9, which is perfect.

Thus it would appear from this limited information that lime-conditioned sludges will not have the effect of making soils too alkaline.

Incidentally, you would be amazed at the kill of bacteria in these lime-conditioned sludge cakes of high pH. Both the plate counts and coli counts are reduced enormously by the high pH. I have taken samples directly from the filter aprons (using sterilized forceps) in a number of plants and have not found a really bad sample yet. Of course, we can not depend on a high pH at all times. I am not trying to tell you that such sludge is sterile but there is a marked reduction of bacteria.

Had I not heard Dr. Cram's remarks * yesterday, my fifth point would have been that the fall is the time to put sludge on the land to avoid health hazards. I will modify this statement to this extent: The above recommendation applies for the present only to the northern part of the United States. Apparently, if I understand Dr. Cram correctly, the eggs of parasitic worms have not been isolated as yet in municipal sludge but we may have this problem after the war or as the soldiers return. I hope Dr. Cram will enter the discussion this morning.

I have wondered what would happen if such infected sludge is spread over the land, and allowed to stay on through the winter, as a great many health departments recommend. After spring plowing and mixing of this sludge with the soil, would there still be a possibility that parasitic eggs would be present after the crop is grown and the vegetables prepared by the usual methods for eating?

The other worm hazard, as I understand it, is that of infection through personal contact with the sludge. I haven't personally come to the point of going into the garden in my bare feet so as to get hook worm. Could one become infected with these worms by having sludge on his hands for a few hours? I am interested in what chance there is of getting infection in that way.

One thing we have learned about the application of sludge to avoid health hazards. It does little good to tell the Victory gardener with a small garden plot to avoid putting sludge on crops that are going to be eaten raw—to leave the sludge off those crops and put it only on corn or other vegetables that will be cooked. For that reason, from a practical standpoint, our Connecticut Agricultural Experiment Station is putting on a campaign to get digested sludge on the land now and let it stay there over the winter. We feel it will be safe next spring for anything that the ground might be used to grow.

My sixth and last point is a question I would like to put to the Minneapolis-St. Paul plant personnel. I know they have had experiments underway on the use of their raw primary sludge as a fertilizer. I believe their agricultural station is working with them on this. It has always been my understanding that raw sludge, because it is not humified, will not be a satisfactory fertilizer, and I am wondering whether their material is sufficiently humified to do a good job.

* See article by Dr. Cram, *This Journal*, Nov. 1943, Vol. 15, No. 6, page 1119—Ed.

With your permission, I would like to read a very short excerpt from an article by Sir Albert Howard who has written several articles on the use of sludge for the British Institute of Sanitary Engineers. These articles have been published in their *Journal* and if you want some good reading, you should review them. He is rather rabid on this subject of getting sludge into use on the land. He says in respect to the usage of humified material:

"The utilization of vegetable and animal wastes in crop production involves two definite steps: One, the formation of humus and its incorporation in the soil, and two, slow oxidation of this product accompanied by the production of available nitrogen. Both of these stages are brought about by microorganisms for which suitable environmental conditions are essential. The requirements of the first phase, the preparation of humus and its incorporation in the soil, are so intense that if the process takes place in the soil itself rather than in a digestion tank, it is certain to interfere with the development of the crop."

That is more or less what I meant under my second point, and I think the better digested the sludge the heavier the application that can be made to the soil.

"The soil, in fact," continues Sir Albert Howard, "gets indigestion. This explains to a large extent why crude sewage, crude refuse and some of the sewage and refuse derivatives have been found wanting or even harmful by cultivators. In some places, worse has happened but it is clear in many cases that the first phase has not been sufficiently prolonged to allow the second to come into operation before the stuff was offered to the crop."

Mr. Niles: We shall defer discussion of the matters that Mr. Van Kleeck has brought up until we conclude the rest of the scheduled program.

I would like to take my prerogative as chairman to offer a few remarks. Mr. Van Kleeck's point about the interest of state and county agents is extremely important and one that Ohio neglected in the early days of the preparation and sale of sludge. As a result, much prejudice developed on the part of the Agricultural Department. This was difficult to overcome.

Now, due to the fact that a shortage of nitrogen exists, the county agents are actually beginning to admit that sewage sludge has value. They put it in a negative manner rather than a positive one because we made a poor beginning with the State Department of Agriculture.

Speaking of fall applications, it is extremely good practice to put a chunky sludge or partially dried sludge out in the fall, because the weathering of the elements certainly helps break it down and make it much more usable in the spring.

The next part of the program pertains to a topic of considerable interest at present—the use of sludge in a liquid state. We are fortunate in having with us Mr. David A. Backmeyer of Marion, Indiana, who has had a lot of experience in this practice.

Mr. Backmeyer: When Mr. Mackin asked that I take part in the discussion on fertilizing Victory gardens with sewage sludge, I prepared a short questionnaire on the subject and mailed copies to several of our

Indiana sewage treatment plants. Replies were received from eleven plants, and the data herein given is primarily from their reports.

The cities contacted are geographically distributed throughout the entire state. They range in population from 11,000 to 130,000, and the volume of sewage treated from 1.4 m.g.d. to 26.5 m.g.d.

All of the sewage plants disposing of sludge for garden use were digesting the sludge prior to disposal on the land. One plant reported a digestion period as short as 10 days, while several of the plants were able to hold the sludge from 40 days up to 100 days. None of our Indiana plants are equipped for complete drying of the sludge and sale of same as a commercial fertilizer.

Very few plants in Indiana are making a charge for the sludge other than the cost of removing the fertilizer material from the plant grounds. In most cases the sludge is dewatered on sand beds (covered or open) or stored in a lagoon until dry enough for removal. At present there are no vacuum filters being operated in the state. Muncie, Richmond, La-Porte, Anderson, Marion, and several other plants have used liquid disposal methods of one kind or another within the past year.

Very little advertising in newspapers or bulletins has been used to date. When interested customers call for the sludge, the plant superintendent usually points out that the sludge fertilizer is an excellent soil conditioner as well as an economical source of essential plant food. He might also add that it is not a "world beater." It will not make potatoes grow on a concrete slab or beans thrive in a rock pile. As proof that one cannot use too much of the stuff he will probably show the prospective customer the remains of the thousands of tomato plants that grew in the sludge stock pile the previous season. Well kept lawns about the plant grounds are another good means of advertising the sludge.

Muncie, Indiana, population 50,000, average sewage flow 8.0 m.g.d., dries its digested sludge on glass covered beds. In 1942, all the sludge was removed from the beds (without charge) as it became sufficiently dry for handling. This year, due to labor and hauling shortage, only 50 per cent was removed from the drying beds in the corresponding period of time. Superintendent Paul White has equipped two tank trucks for hauling the liquid sludge that must be removed from the digesters when the drying beds are loaded full. Superintendent Ross of Richmond uses a similar system, and reports good results with the liquid disposal method.

At Marion, Indiana, population 28,000, average sewage flow 4.2 m.g.d., liquid disposal of digested sludge has entirely replaced the vacuum filtration method of sludge treatment. In February, 1943, the first liquid sludge was removed by hauling in a dump body type truck outfitted with a reinforced wooden tank of 1,000 gallons capacity. A portable pump was mounted on the end gate of the truck, and the sludge could be unloaded either by gravity or by pumping. This method has proven satisfactory and is being used at the present time. It shows some economy over the former method of dewatering the sludge on the

vacuum filter and subsequent disposal of the filter cake by spreading on farm and garden land. During the past spring months of March, April, and May, more than 50 Victory gardens were treated with liquid sludge in Marion. A full tank, comprising 930 gallons of sludge, was delivered and applied to the garden plot at a charge of from $1.00 to $2.50, depending upon the distance the sludge had to be hauled. The average distance traveled per round trip was five miles, and the average cost per load was $1.50. Revenues received from liquid disposal for the period from March 15 to April 30 totaled $215.00.

What was the customer getting for his money? Since the sludge averaged 8.6 per cent total dry solids, a tank load contained 667 lbs. of dry solids. Tests of the sludge made at Purdue University show the nitrogen content to be 2.0 per cent and the phosphorous content to be 2.4 per cent. Each truck load, therefore, contained about 16 lbs. of phosphate and 13 lbs. of nitrogen. The combined value of these elements is $2.62 when nitrogen is figured at 14c per lb. and phosphate at 5c per lb. Incidentally, our sludge is a mixture of primary and activated sludge with ground garbage.

It is apparent from the above figures that even if the soil conditioning value of the sludge is disregarded, its application in a concentrated liquid form to farm and garden land makes an attractive bargain for the purchaser.

Two of the three larger plants reported upon, Ft. Wayne and Hammond, showed a definite increase in the amount of sludge put on Victory gardens in 1943 as compared to the previous year. Mr. Brunner at Ft. Wayne reports an increase of 50 per cent, while Mr. Carpenter at Hammond reports an increase of approximately 900 per cent. Mr. Mathews at Gary reports a slight decrease in the amount of sludge taken from the drying beds which he attributes to labor and hauling difficulties.

A special committee of the Indiana State Sewage Works Association is now at work preparing some literature for publication that is intended to stimulate the sale and disposal of sludge fertilizer throughout the state. A better Victory garden market is therefore expected for 1944 than was experienced in this past year.

I might add that we had the cooperation of our county farm agent in establishing the fertilizing value of the sludge. He was of great assistance in getting the farmers, especially those in the vicinity of our plant, interested in using it.

Mr. Niles: I am sure that many of you would be interested in asking questions of Mr. Backmeyer, but we shall defer open discussion until we hear from the next two speakers.

May I say in passing, that if any of you wish to do some experimenting with different kinds of sludge, try some of the filtrate from your open sludge drying beds and see what it will do. We know; we have tried it.

We shall next hear from Mr. Henry A. Riedesel, Superintendent of the Rockford (Illinois) Sanitary District. Mr. Riedesel has been

through the business of fertilizer production and marketing and then gone out of it, so his remarks should be interesting.

Mr. H. A. Riedesel: The need for utilization of all of our natural resources in the winning of the war is recognized as paramount. Any campaign to use sewage sludge in Victory Gardens is, for that reason, a timely subject.

The Sanitary District of Rockford, however, has been very cautious about recommending dried sludge for garden purposes. We recommend it for lawns, golf courses and the like, and it has been used very extensively and successfully in this way. Yet, while we recognize its fertilizing values for home gardens and truck gardens and know of no disease being traceable to its use, we have desisted in recommending it generally, because of the possibility of passing on pathogenic bacteria in certain vegetables.

We continue to encourage its use as a grass conditioner and are now working with the Winnebago County Farm Advisor's office in the disposal of it for pasture lands. Pasture lands, seldom fertilized, are one place where more emphasis could, and should, be placed in the winning of the war and, in the opinion of Mr. Brunnemeyer, our Farm Advisor, it is especially true in this particular area, since we dwell in a large milk shed ourselves and border on a much larger one. The need for more milk is quite apparent in view of our present shortages and the many ration points needed to secure some of its by-products. Hence, we are hoping to help increase the yield by supplying "bossy" with more grass.

In the September, 1943, issue of *Sewage Works Engineering*, the "Round Table" editor comprehensively explored the use of sewage sludge for Victory gardens. From this reference, one receives some very enlightening information as to the extent to which sewage sludge as a fertilizer is being used in this country for Victory gardens and the ways and means developed in disposing of it. Mr. N. G. Damoose, Director of Public Service, Battle Creek, Michigan, replied at length concerning the topic and the campaign his Victory Garden Committee put on in getting the material moving. For further detailed information on this subject, I refer you to Mr. Damoose or the article. He also indicated another very interesting point—"liquid fertilizer." To quote Mr. Damoose, "I again urge you to do what you can to increase interest in this liquid material." In this connection, Mr. Phil Schriner, Superintendent at Kankakee, Illinois, has, for some years, been advocating using liquid fertilizer. At the Battle Creek plant they recently provided suitable connections easily available to the public wanting "liquid fertilizer" (liquid digested sludge). In this same Round Table discussion, the remark of Mr. James M. Glynn, Superintendent, Sewage Treatment Plant, Reno, Nevada, is mentioned particularly for the contrast. I quote: "Our sludge is not fit for fertilizer."

Sears, Roebuck and Company has sampled and tested our product and has surveyed the possibilities of packaging it in small bags and selling it through their national chain, as have others with a similar view

in mind, but as yet, at least as far as we are concerned, without any tangible results.

Some years ago, the Sanitary District of Rockford undertook the drying and sacking of sludge in one hundred pound bags. Financial success, although theoretically apparent on paper, did not crown the venture, as successive difficulties placed stones in its pathway. Our sludge comes from a primary treatment plant with two-stage digestion units and has a large and varied amount of industrial waste in it. As a fertilizer, it does not compare favorably, when prepared and marketed, with commercial fertilizers.

Our problem in recent years has been providing adequate means for making the material rather than marketing it. At present, we have expanded our sludge-handling facilities to meet the increasing load placed upon them and, of course, have, in turn, increased our yield. We have been able, however, to dispose of the sludge easily as it is free of charge, f.o.b. plant, for those desiring it, with the understanding aforementioned as to its use.

Part of this previous and present history on sludge use in Rockford digresses somewhat from the subject at hand but, nevertheless, is related to it. The fact that limestone outcroppings throughout the county are in abundance and pulverized limestone is used extensively in the area is another tangent which could be developed further.

I might mention one other matter. We are working with the Midwest Extraction Company, Rockford, Illinois, manufacturers of vitamins and chlorophylls, in the extraction of a hormone, a trace compound, from the scum or the supernatant. All that we have done so far in this connection is to start laying the ground work for continuing the research.

Digressing as I have brings to mind the story of the mother who, upon hearing unusual noises in the living room called to her small son, "Johnny, Johnny." "What, Ma?" "Johnny, are you spitting in the goldfish bowl?" "No, Ma, but I'm comin' close."

Recent analysis of our sludge, in accordance with the method suggested by Mr. Harry W. Gehm, Associate, Department of Water and Sewage Research, New Jersey Agricultural Experiment Station, New Brunswick, New Jersey, indicates that we have upwards of one-third grease in our raw sludge. It is to this end: the extraction of the grease, and recommending the dried sludge for pasture lands, that we have been bending our thoughts and efforts in the utilization of the sludge to help win the war.

Mr. Niles: We shall now be pleased to hear from Mr. P. W. Riedesel of the Division of Sanitation, Minnesota State Department of Health.

Mr. P. W. Riedesel: The Minnesota Department of Health is often called upon for information relative to the health aspects involved in the use of sludge obtained from human sewage as fertilizer. Some tests have been made by the Division of Preventable Diseases in regard to the presence and viability of pathogenic organisms in raw and stored sludge cake which has been conditioned with lime and ferric chloride. The Division of Sanitation of the Minnesota Department of Health has

also carried on some tests on the most probable number of coli-form organisms remaining in piles of stored sludge which had been conditioned with ferric chloride at the sewage treatment plant to improve drainage. Little or no information has been secured on other types of sludge.

Studies on the most probable number of coli-form organisms in raw, undigested sludge as compared to sludge conditioned for dewatering with ferric chloride and stored in piles on garden plots showed 28,700,000 coli-form organisms per gram dry weight for the raw sludge, and 22,900,000 per gram dry weight after conditioning with ferric chloride. This same sludge stored in piles on garden plots during the winter showed 800 most probable number of coli-form organisms per gram dry weight when tested early the following spring. The stored sludge was frozen and undigested. Putrefaction and further multiplication of organic life could be expected with the advent of warmer weather.

The Division of Sanitation sampled sludges in various stages of storage as deposited on the stock pile at the Minneapolis-St. Paul plant and the laboratory work was done largely in the Division of Preventable Diseases of the State Health Department. In the experiments, the sludges were mixed with a saline solution and centrifuged, followed by attempts to reproduce disease in guinea pigs. It was demonstrated that sludge stored a longer period than one week did not show any positive results in causing typhoid, paratyphoid or tuberculosis. I believe that it was from six samples of very fresh sludge that tuberculosis was developed in the guinea pigs.

Because of the limited amount of information on conditioned sludge, and with little or no information available on other types of sludge, no attempt has been made by the Minnesota Department of Health to prepare a bulletin on health aspects involved in the use of sludge as fertilizer. The policy has been to recognize the value of sludge and to recommend it as a fertilizer and soil conditioner for ordinary farm crops and for some vegetable and truck crops, the edible portions of which do not come in contact with the soil. Its use as a fertilizer for vegetable and truck crops which are eaten raw is not recommended.

Mr. Van Kleeck mentioned that it is impractical to expect the Victory gardener to apply sludge only to the parts of his garden in which cooked vegetables will be grown. Perhaps the user could be induced to avoid planting raw-edible vegetables in sludge treated soil until a year had elapsed, after which time I feel it would be quite safe.

Mr. Niles: This concludes the prepared papers and we shall now have open discussion on this topic. I am sure that enough thoughts have been given out to provoke some good questions and answers.

Dr. Eloise B. Cram: I have been wanting to talk to Mr. Van Kleeck about some of these matters. I am fully in accord with him in his enthusiasm for the use of this reservoir of good material, but I am interested in seeing that the public health aspects are taken into consideration, and this situation is still a big question mark. The work that I did was the first of its kind and still leaves many questions unanswered.

As to the concentration of this parasitic material, it was, of course,

much more concentrated in my tests, which was necessary under experimental conditions, in order to recover a sufficient number of the organisms to make a study of the effect of the treatment processes on them. I don't think ordinarily you would ever get any such concentration in municipal sewerage systems. We might in epidemics. Anybody who was at all connected with the Chicago situation here during the outbreak of amoebic dysentery and saw the large percentage of people in certain hotels that were affected, must realize it doesn't take much polluted material to start an epidemic.

As to infection of the hands, I think that hookworm might easily be acquired that way in the south or any place where you might get sufficient concentration.

In going back to the matter of concentration in the army camps that we examined, we only examined a five-gram sample, which is very small and found these parasite eggs in a large percentage. This was really astonishing to us in 1941 when the incidence of this large intestinal parasite was fairly low in this country. So with the greatly increased incidence, especially in camps or hospitals where food is coming back from epidemic areas in which these parasites are prevalent, there is going to be a huge increase in numbers contained in the sewage.

Mr. Van Kleeck: Dr. Cram, just how does hookworm infection occur? Do the eggs in the sludge hatch and the worms then go into the skin?

Dr. Cram: I think so but it would depend a little on the conditions. The large intestinal round worm doesn't hatch. That would have to be a hand-to-mouth thing. There are some interesting observations in the tropical countries. In Africa in the prisons there was such a high incidence of these worm parasites among the prisoners and yet the sanitary conditions were relatively good and they weren't out in contact with the soil at all, yet they had a much higher incidence than the general population. It was found here that the cooks and people handling the vegetables in the kitchen became carriers just from washing the vegetables. In that case, fertilizer wasn't being used on the vegetables. They were not eaten raw, but the food handlers had to wash the fresh vegetables before they were cooked. They became so heavily infected they acted as carriers to the other people in the prisons.

Of course, it isn't perhaps the worm parasites that one would become so worried about as amoebic dysentery, especially in connection with the use of the wet sludge.

I was very interested to hear that one plant reported using sludge after only 10 days digestion, because that would be in a period in which I still found amoebae exists and infects. I understand that sludge should be digested for at least 30 days. We don't know the upper limit of the infectivity. I think we are now in our studies about where the typhoid people were about 20 years ago as far as being able to culture the amoeba, and the typhoid methods of study have improved so greatly that it has made a very different situation in being able to do really comprehensive work now.

I am very hopeful that these remarks will arouse your interest and

that anyone who has a chance to make any studies, either in universities or elsewhere, will do so, so there will be supplementary work to answer some of these questions.

Mr. W. W. Mathews (Gary, Ind.): I would like to ask if any experiments have ever been made by anyone as to the condition of the soil after using sludge for a year or six months or three months, knowing that there is a destructive effect from the soil on the pathogenic bacteria. As far as I know, there have been no studies of the soil itself after the use of sludge as a fertilizer for any length of time.

Mr. L. H. Enslow (New York): I would like to ask a question along the same line as Mr. Mathews'. I am thinking of the primitive practice in China, and I just wonder what the history may be in China after all these thousands of years of using this material, not digested either, as I understand it.

Another question is, do I understand the amoebas were found in the digested sludge as well as raw sludge?

Dr. Cram: I will answer the last question first. The amoebas were only in experimental, inoculated sludge. There hasn't been any real study in this country as to amoeba in the natural state in sludge but the experiments did not include inoculation of digesting sludge, and I felt that there was a considerable safety factor in that the limit of time in which I could recover the effective amoeba was only about 12 or 14 days in digesting sludge, so I felt it would not survive the digestion process up to a really ripe sludge (30 days or more—Ed. note). So if the sludge were used before that period there might be a real danger.

As to the other question concerning the destruction of pathogenic bacteria in the soil, I am not sure that much is known on that as yet. I think the recommendation, at least in the north, that the sludge be put on in the fall is very good, because the low temperatures, especially freezing temperatures, would be very deleterious to a high percentage of organisms. It would also mean the sludge would not be handled or put on vegetables during the early stages.

Mr. Morris M. Cohn (New York): Does that apply to sludge that might be stored in the open during the winter months and applied to the soil in the spring?

Dr. Cram: I would think so if it was stored where it actually froze. Of course, spreading would be even better because drying is a good control factor, especially with amoeba, and spreading it in thin layers would mean better drying.

Mr. Cohn: How about the other parasitic organisms?

Dr. Cram: The same would certainly be true of hookworm. As for the other parasites, I think they would also be reduced to fairly low numbers. Drying is one of the best control factors.

Mr. Mathews: How about applying the sludge in a finer state, as with limestone? The government requires, say 70 per cent to pass through an eighth-mesh screen. If we pulverize the sludge to that extent and then spread it, we can distribute it better and expose it to the extreme

temperatures which help destroy the bacteria and parasites. Also, the sludge would dry out better if in a fine state.

Dr. Cram: I agree that such preparation of the sludge would be a wise measure.

Mr. C. C. Larson (Springfield, Ill.): We have a splendid group of guinea pigs in the operators who work around our plants. One cannot work around a sewage plant without getting into the sewage, yet we have never had any infections among our men. Has anyone here any information as to infections among men working in contact with sewage?

Mr. Niles: This is a very good question. While we can't go into it like we should, I would like to ask for a showing of hands. Does anyone in the room know of any instance of infection by pathogenic bacteria that came from sewage sludge or sewage itself? (One hand; Mr. McGuire—Ed.)

Mr. C. D. McGuire (Columbus, Ohio): We use a grab bucket with an electric hoist to remove the sludge cake in excess of our incinerator capacity from a pit near the incinerator. One day a man who was excited (and slightly intoxicated, we found out afterward) grabbed the open edge of the bucket to guide it. When he tried to let loose he couldn't and it closed and cut off several fingers. His hands were covered with sludge, of course, and tetanus developed in about 6 or 8 hours. He had a desperate time and finally lost the arm just below the elbow. That is our only experience with such infections and it, as you can see, was a result of an unusual exposure.

Dr. Cram: May I mention that the reason we made some of these tests in municipalities in California was because an operator contracted amoebic dysentery and thought he got it from the sludge. As I said, we did not recover them in that case. I do not believe that the negative results should be stressed as much as they have. As all of you know, the fact we do not find anything in a few samples of sludge does not mean we can generalize and say there is no hazard. It would be a very interesting survey to see if any more cases were found.

Mr. Cohn: Mr. Niles, I wonder if I can bring this discussion down to a practical level. Many of you who have been marketing sludge for a long time and then listened to Dr. Cram's talk may think you were in a very unfortunate situation.

I don't mind taking myself for a specific example; I have been marketing sludge for 19 years. You can imagine my reaction when I got this repetition of a previous warning we had received in a chapter of a manual prepared by Mr. Gilcreas.* Therefore, I felt very unfortunate in that I was an operator who had been marketing something that was potentially hazardous by analysis. But to cap the situation, the Sewage Works Practice Committee of the Federation has been preparing its first chapter of our proposed manual of practices, and the first chapter carries the title "The Use of Sludge as a Fertilizer," exactly the same

* F. W. Gilcreas (New York).

title as is carried in this important panel discussion. We are now faced with the publication of that manual.

One of the sections of the manual deals with the health hazards involved in the use of sludge as a fertilizer. That section was prepared by Mr. Gilcreas, who reviewed the literature and pointed out the possibility that parasitic infections may be spread by the use of sludge as fertilizer.

I do wish to raise this hypothetical question. I hope you can answer it. If it is embarrassing to you, please don't, but if we can get an answer it would help our committee tremendously in addition to helping those of us who are caught on the horns of a very serious dilemma.

In view of the present interest in the use of sludge as a fertilizer; in view of all the past negative experiences regarding the transmission of diseases or parasitic infections as a result of the use of sludge as a fertilizer; in view of your own studies as they relate to theoretical infections or infusions, if I may use that word; in view of the fact there have been no studies made of soil which has been treated with sludge; would you advise the discontinuance of the use of sludge as a fertilizer?

May I say one thing more, please? I am groping for guidance or some ray of sunshine in this rather dark picture that has suddenly appeared on our horizon. You see my point?

Dr. Crane: I do not care to make a blanket endorsement or condemnation one way or the other, because I do not feel, with the present status of our knowledge, one could say. I think one should advance cautiously and should be familiar with the possibilities of potential danger to the public health. Under the present conditions or the past conditions where infections were so light, I think it was a minor matter. That is my personal opinion. But with increasing severity of infections and with the returning military and civilian personnel, we do get a condition that is comparable to those in Germany and Russia and some other European countries, to say nothing of China where infections are so frequent. If we are in for a comparable situation in relation to parasitic infections, then I think that one could come to the conclusion there was a real menace. At this time, however, I do not think we know enough about it and should give more consideration to the future than the present.

Mr. Cohn: May I ask a supplementary question now which may help the situation? I consider it very important for the guidance of the committee as well as everyone here. In view of these doubts, in view of the fact that there may be a possibility of infection, are there a set of regulations or protective rules which we might set up? For example, we have already said that the spreading of sludge on land over the winter months should diminish greatly the dangers involved. Is that right? Is there further possibility that we could cut down again the hazards involved by setting up regulations about keeping sludge off crops that go on the table uncooked or do you feel that the possibility of infection through the hands by working in the garden is sufficient hazard to put up the warning sign for us?

Dr. Cram: I feel that we are hardly in a position to make any such definite set of rules. I think the observations are too limited, both as regards experimental work and actual practice. I think it would be good to aim toward conditional investigations but I doubt if at present one could lay down hard and fast rules.

Mr. Gilcreas: Mr. Chairman, I have two comments. I would first like to thank Dr. Cram for her unqualified support of my chapter in the manual. Second, because I do think there is a potentiality, and that the Federation of Sewage Works Associations should realize there is a potentiality, and we can't ignore it. Dr. Cram has again brought that to you.

It seems to me in one way we are losing sight of the fact that our primary job is to take care of sewage and that getting rid of the sludge is only one part of that task.

Mr. Niles: Surely some of you must have questions you would like to ask Mr. Backmeyer on the use of liquid sludge. Perhaps we are treading on dangerous ground, but I, for one, know we have had some very interesting experiments and work in Toledo, and I know they have had some in Battle Creek. I know Mr. Backmeyer would be glad to answer your questions.

Mr. Euslow: I would like to ask Mr. Backmeyer for a little more detail about the quantities of liquid sludge applied.

Mr. Backmeyer: On Victory gardens, we put on a truckload, that is, 930 gallons to a 40 by 40 foot area. On farm land the application is quite a bit lighter than that. We put it on by gravity and apply about 7 to 12 truckloads to an acre of ground. Just about two weeks ago we put 26 truckloads on a five-acre plot of ground which had been sowed with wheat and will have a good chance to see what that will do. Some of the other farmers are applying about 5 to 7 truckloads, the equivalent of about 930 gallons of it to the acre.

Mr. McGuire: That is 8 per cent total solids?

Mr. Backmeyer: It varies from 8 to 10 per cent. There is an important comparison when you are hauling out filter cake which runs about 27 per cent solids. When we are hauling liquid, we are hauling 9 per cent solids but it is cheaper for us to make three times as many trips with the truck hauling 9 per cent solids than it is to produce the 27 per cent solids and haul it out as filter cake.

Mr. W. A. Allen (Pasadena, Calif.): Mr. Chairman, I would like to ask Dr. Cram if she ever ran any tests on heat-dried, ground sludge, either digested or activated.

Dr. Cram: Heat dried sludge? No, I have not.

Mr. W. A. Moore (Cincinnatti, Ohio): Our laboratory performed a small experiment using pulverized sludge of 30 per cent moisture content and we found that the organisms were killed in about three minutes by a temperature of about 100° C. I feel sure that heat-dried sludge, which is dried at a much higher temperature would involve no danger at all.

Chairman Mackin: I would conclude from this discussion that it would be wise to take all the precautions that have been mentioned and

I also feel that, if you are not now practicing liquid application of sludge, I could recommend it only as a future development. I think we might conclude in a practical way that the status quo should be observed until some further information is obtained along these lines. Many questions have been brought up and we have not had the time to answer them, but I am sure that you have all received a letter from the Research Committee of the Federation asking for projects that could well be undertaken or that were in progress. I suggest that you list some of the questions that have come to your mind this morning. This discussion may leave you feeling just a little bit guilty perhaps, as Mr. Cohn suggested, so be sure the questions that would make good research projects are transmitted to the Research Committee.

II. SECONDARY TREATMENT—PRESENT AND FUTURE

DONALD W. WALKER, A. W. WEST, LINN H. ENSLOW, AND ARTHUR S. BEDELL, *Leader*

Mr. Bedell: Although our title provides only for the present and future of secondary treatment, I have no doubt but that we shall delve into its past also, before we conclude this discussion. Perhaps we should begin with a definition. What do we mean by "secondary treatment"? In kindergarten, we learn that two comes after one, but this is not necessarily true in sewage treatment because we do have secondary treatment without any primary treatment. I have in mind that in primary treatment of sewage we usually expect the removal of suspended solids by physical and mechanical deposition, while secondary treatment connotes to most of us the further removal of suspended solids, with some of the colloids and dissolved solids, by oxidation, coagulation and adsorption. Physical, chemical and biological forces are all strongly at work in the secondary processes.

If we hold to this definition, we find there are a number of so-called secondary treatment methods and processes used without benefit of primary treatment. We immediately think of the sand filtration as practiced early in England and in New England in the early part of the century, where raw sewage was applied directly, and treated quite satisfactorily within our conception of what we expect of secondary treatment.

On this basis we might include the treatment of sewage by chemical precipitation, although to many of us chemical precipitation is an adaptation or extension of primary treatment by sedimentation. Plain flocculation is also considered as an augmentation of primary treatment by sedimentation.

To get the perspective, I think it is well to look back and see how we have developed the art of sewage treatment. Our advancement has been by surges. We have advanced not only in the technique of treatment but also in our ideas and ideals regarding stream pollution. I can remember when in school I had a course in the purification of water and

sewage, and we meant *purification* of the sewage. In other words, one of our usual inspection trips was to go to the Lawrence Experiment Station and be offered a glass of the filtered effluent. We rather suspected it might have been disinfected. It was supposed to have been sand filtered.

I think it is well from some of the questions that were raised in our preliminary correspondence regarding this panel discussion to examine a few statistics on what we have in the way of secondary treatment in the country. Unfortunately, due to the lack of personnel and time on my own part, I was unable to make a review of the splendid census of treatment works in the U. S. made by the United States Public Health Service and would have brought us up to date. I had to limit myself for most recent statistics to the *Engineering News-Record* census of 1938.

In that 1938 census there were 4,667 treatment plants listed in the United States. Of those 4,667 there were 2,110, or 45 per cent, provided with secondary treatment devices. It was rather a surprise to me at that time to note the high percentage of secondary treatment plants. Of the 1,773 communities employing filtration in its various forms, there were 1,140 trickling filter, 109 contact bed and 524 sand filter plants. There were 223 activated sludge plants and 114 chemical precipitation plants.

In New York State I have made a comparison of conditions at several stages. The first attempt by the State Health Department to require municipalities to install sewage treatment plants and to submit plans of them was made in 1903. This might be taken as the inception of our present anti-pollution program. At that time we had four public sewage treatment plants in the state, a rather astounding condition. In 1917 we had 47 sewage treatment plants serving about a quarter of a million population. Of the 47 plants, 33 employed secondary devices, including 15 contact beds, 8 trickling filters, 7 sand filters, and 3 chemical precipitation plants.

In 1940, the total population of the state exclusive of New York City, was 6,200,000 people. Sewage treatment was provided for just half of that, and there were 269 treatment works in the state, of which 103 or 35 per cent used secondary devices. In contrast to that, we have the State of Massachusetts, where in 1918 they had 33 sewage treatment plants, all of which provided secondary treatment. Most of us are familiar with the fact that natural sand beds are readily available in Massachusetts and also that, with certain minor exceptions, there are no large streams or bodies of water within the state in which disposal by dilution would be possible.

In 1938 there were 79 sewage treatment plants in the State of Massachusetts and here again 39 of these, or half of them, included secondary treatment. Apparently nearly all of the plants built in the interim 20-year period provided only primary treatment.

Fundamentally, we have seven types of secondary treatment, *i.e.*, broad irrigation, fish ponds (which we do not have in the U. S.), bio-

logical filters, contact beds, activated sludge, chemical precipitation, and finally, disinfection.

As to broad irrigation, it was interesting to me to note the extent to which it is used in certain places, as in the western states where we have arid and semi-arid conditions. In 1938 we had 113 places using broad irrigation as a method of sewage disposal in this country. As a rule, preliminary sedimentation is provided. At San Antonio, Texas, 20,000,000 gallons a day is sold to a private company which disposes of the sewage on 4,000 acres. In the winter time, it is necessary to store the sewage so they have a pond or a lake of 1,000 acres in extent, which serves as a reservoir during the winter, and allows them to carry on the rest of the year. In Europe, of course, sewage farms are quite common, large ones being located adjacent to Paris and Berlin.

Fish ponds, the next type of secondary treatment on my list, are employed along the Elbe River in Europe with fairly satisfactory results. The removal of organic matter and reported nitrification is surprisingly good. In general, very shallow ponds 1.0 to 1.5 feet deep are used except that deeper ponds are necessary for the protection of the fish in winter when they hibernate. The ponds are stocked in the spring with fish, clams and, sometimes, ducks. As applied to the ponds, the sewage is diluted with one to four volumes of water—otherwise offensive conditions would result. It is reported that 88 per cent of the organic matter is removed and that the bacterial count is reduced to about 10,000 per ml. by the treatment. A clear effluent is claimed. The fish yield is said to be about 500 pounds per acre, which is interesting from a commercial standpoint.

Coming to filters, we have three general types: the contact bed, the intermittent sand filter and the trickling filter. The contact bed might be considered as a separate process and I shall discuss it first, although contact beds are now largely replaced by more efficient and economical methods.

The application rate for contact beds is about 400,000 gallons per acre per day. Ordinarily, contact beds are about four feet deep and have an efficiency of 60 to 70 per cent of B.O.D. removal, if operating satisfactorily. In all of these discussions we are trying to think of the future and it is my opinion that contact beds have no future.

The sand filters, of course, are best justified where there are natural sand beds. We cannot very well afford to build up a large, artificial bed of sand to take care of large quantities of sewage. The usual loading is about 500 to 1000 population per acre for a settled effluent. Rest periods are necessary, so additional beds must be provided. Sand filters give excellent results with B.O.D. and suspended matter removals in the order of 95 and 99 per cent, respectively. Bacterial removals are also very good.

This brings us to present day methods of secondary treatment of sewage and I shall ask you to take over the discussion from here.

Chairman Mackin: Thank you very much, Mr. Bedell. I shall now

call on J. D. Walker, Sanitary Engineer of the American Well Works, to continue this discussion.

Mr. J. Donald Walker: I trust that you will permit me to speak more or less freely and without the necessity of backing up my remarks with a great array of scientific data, if any such thing can be gathered in this field. I shall speak briefly on the various devices that are used for secondary treatment, confining myself mostly to trickling filters and activated sludge and combinations, and if there are any questions, I shall be pleased to answer them if I can.

In the first place, I would like to define secondary treatment. There has always been a question in my mind as to what we mean by secondary treatment, and in order to confine this discussion to one channel, I will define secondary treatment as Wisely did a few years ago when he suggested that the effluent of an activated sludge plant should contain not more than 10 or 15 parts per million of B.O.D. which means 85 to 95 per cent removal of B.O.D.; also, that it should show at least a positive trace of nitrification. I presume by that he meant to spot the point on the curve at which the plant was operating, so that the 5-day B.O.D. could be correlated in terms of total B.O.D. In other words, you had some definite idea as to the degree of stability being obtained.

Accordingly, I shall discuss the secondary treatment units on the basis that they are capable of producing nitrification, in other words, stabilized effluents. I think there has been a great deal of discrepancy. I talked to a sewage plant operator a few days ago and he had a low rate filter and a high rate filter of common design in his plant. The low rate filter was producing about 85 per cent removal of B.O.D. and the high rate unit was effecting slightly greater removal, say, 86 or 87 per cent removal. The operator was very confused because the relative stability samples would stand up approximately ten days on the low rate filter and would only stand up five or six days on the high rate filter. Even though the high rate filter was giving a greater removal of B.O.D., he was using the stability results as an index to illustrate that the low rate filter was doing better work.

I think that requires some clearing up, because the point has been frequently brought up to a good many consulting engineers, and I think that if we understand the difference between 5-day B.O.D. when there is nitrification present and when there is not, we can have a better understanding between the equipment manufacturer, the designing engineer and the plant operator.

Let me make it clear at this point that even though some secondary treatment units may not be producing an effluent containing nitrates, it does not mean that the unit or plant is no good. Neither does it mean that the unit, be it trickling filter or activated sludge, would not be capable of producing nitrification if designed a little more liberally. It is up to the engineer to decide whether he wants nitrification or whether he does not. At the same time he should clearly decide whether he wants B.O.D. removal on the stabilization end of the curve or the other end.

In speaking of high capacity filters, I would like to put, if I may, high capacity filters and activated sludge in the same classification, because I think they more or less follow along the same general lines. For instance, I noticed in Mr. Larson's report of the Springfield plant, when they have a protracted dry period he often puts down a memorandum on the day it rains and how the activated sludge plant operation has improved thereby. We are led to believe that the rainfall carried down dissolved oxygen and created better operating conditions in his plant and allowed him to have a much happier activated sludge. If that is true, it seems that some form of recirculation is quite desirable for the satisfactory operation of most sewage plants. I wouldn't care to make the statement that it is necessary for the operation of all sewage plants, but I do think that all sewage plants should have recirculation so that, if necessary, the operator could call upon recirculation to freshen up the primary settling tank or otherwise improve operating conditions. Recirculation seems to give us more consistent operation.

Activated sludge can be operated with little or no nitrification or it can be operated with long detention periods and high mixed liquor solids to effect a high degree of nitrification and stability.

High-capacity filters can be operated in the same fashion notwithstanding the fact that there will be a lot of argument to the contrary. As I said, I again take the privilege of making my statements subject to your challenge. High-capacity filters can be operated with a relatively small amount of media present for the amount of organic load being applied to obtain a given result, and then, of course, the filter can be more liberally designed to increase the nitrification within the unit and give more stable operating characteristics.

I feel that this same thought can be carried on to all of the other types of secondary treatment, which might be combinations of trickling filters and activated sludge or combinations of trickling filters and slow sand filters or slow sand filters alone. Incidentally, I would like to challenge a remark that Mr. Bedell made. I do not agree that slow sand filters domestically require a tremendous amount of sand. I think that by applying more modern methods of design, or, to be specific, by using rotary distributors, better underdrains and smaller dosing tanks, that a small amount of sand will yield a very high degree of efficiency. The use of a washed sand, screened to a given specification, might even be justified. I have seen a sand filter in Michigan used in that fashion, and it has proved to be very economical. The operation has been just as good as the old-fashioned, conventional sand filters which were loaded only about 30 per cent of the time because of the inability to distribute all of the load over the entire surface of the unit.

I suggest that this same line of reasoning will apply to the newer processes such as the Emscher filters that we saw tried in connection with a Dow Chemical Co. problem at Midland, Michigan, and I believe the failure there was probably due to trying to work the filters too hard. It also applies to the Hays process, concerning which I would like to add the comment that the best Hays plants, and I have seen some doing

a very good job, seem to be those plants which were more liberally designed, or to say it conversely, those which were not being loaded to such a great extent.

Chairman Mackin: Thank you very much, Mr. Walker. To continue with the discussion, I shall now call upon Mr. A. W. West, former sanitary engineer with the Board of Health of the State of Wisconsin, who is now associated with Mr. E. B. Mallory.

Mr. A. W. West: We are privileged characters up here, so I am again going to take advantage by dragging out an old horse, and you will excuse me, I hope. I refer to the absolute need for the collection of complete and comprehensive operation data in sewage treatment plants. I can think back to a number of cases, sometimes the smaller communities, more particularly in Imhoff tank installations, primary treatment plants, and some of the grossly overloaded complete treatment plants, in which the operators have discontinued collecting some of this vitally important data. This was done by them with the firm conviction that their particular treatment plant was, shall we say, inflexible or overloaded to such an extent that no amount of records could help them to improve the efficiency of their process or to obtain a better effluent.

As we all know, they are overlooking one very important factor, that such a situation means that some day they are going to have additional treatment facilities or a new plant. If they have neglected to gather this information very conscientiously, they are doing a disservice to the community, because the lack of such information may lead to additional difficulties when the new structures are in, and might even be responsible for the waste of public funds on the construction of a sewage treatment plant that does not fit the needs of that community.

We have seen in the past some of the results from lack of such data. In the rush days of PWA many plants had to be constructed hurriedly without adequate consideration of flow and other factors of loading. The census figure was often used and sometimes we used population equivalents of industrial waste. May I say a very unkind word about population equivalents? It is, we believe, a very loose term and suggest that it is much better to consider the B.O.D. and flow separately and not to incorporate them into a single statistic such as population equivalent. The B.O.D. and the flow each exert their individual and correlated influence on the design of new structures.

It is axiomatic that we cannot design one plant that will take care of any and all conditions. If you have a sewage treatment plant receiving a high B.O.D. and a low flow, it must be designed altogether differently than if these characteristics were reversed.

Let us consider some activated sludge treatment plants. I believe one thing that is general is that when the design or the operating characteristics of some of these activated sludge plants are examined in the light of present knowledge on what that plant can handle and how it must operate, we find that the majority are capable of producing the optimum results for a primary effluent B.O.D. in the range of 200 to 250 parts per million. For average figures, I believe it is pretty well

known that most of our domestic sewage after primary treatment average about 150 parts per million B.O.D. In other words, the plant is designed to handle one type of sewage and it must operate on another type of sewage.

We mentioned something about the high rate processes before, and I would like to speak of the activated sludge process as a very high rate process also. It is a most efficient one if we understand the underlying principles and the fixed physical relationships that really govern the operation of such a plant.

We are fortunate at present in that we can eliminate trial and error groping for the exact method by which activated sludge plants must be operated. That has been illustrated time and time again where operators have gone over many years of trial and error operation in order to find the point at which their plant can do a decent job and, unfortunately, some operators have not as yet found that point. In the light of present day knowledge, it is necessary that we recognize one important factor which is that the relationship between the aeration holding capacity and the final clarifier holding capacity is one of the important things that governs the method by which that plant must be operated. When the plant is set down in front of you to be operated, that relationship is fixed and nothing you can do can change the method by which that plant must be controlled. Therefore, in the past you could find the optimum conditions if you had enough time to do it, but now it is possible to actually predict, evaluate and compute within a matter of minutes how the plant must be operated. You don't have to grope around.

Take our old friend the 20 or 25 per cent return sludge. We know that is not the factor in all sewage treatment plants. Plants have been found where an attempt was made to operate at that ratio when they required 50, and at one place 100 per cent return sludge to get proper operation. When those values are fixed, the plant must be operated in accordance with the physical principles that govern, and the same thing goes back to the plant design. You must have the basic information on B.O.D. and flow so that you can design a particular plant that will stand up and produce the best under those particular conditions, and not be limited by a characteristic of the sewage that is not most readily amenable to treatment in that particular cycle.

I would like to say something about final effluent quality. I think a high quality effluent can be considered that which has a B.O.D. and suspended solids of around 2, 3, or 5 parts per million, say, an average of 5, and never exceeding 10. That is what we consider to be a high quality effluent.

May I go back? We were talking about each plant having to be operated according to a definite set of rules. Have any of you ever operated an activated sludge plant with a high suspended solids condition? There is one plant of which I know that is operating between 3,500 and 9,500 parts per million of suspended solids in the mixed liquor and on one occasion they had to increase the suspended solids content to 13,000 parts per million because the conditions of load demanded that.

I think my time is up. I just wanted to introduce some of these remarks and hope that it will bring about discussion from the floor.

Chairman Mackin: Thank you very much, Mr. West. I am happy to call on Mr. L. H. Enslow, Editor of *Water Works and Sewerage*, to conclude the discussion of this subject, and then I shall call for questions and comments from the floor.

Mr. L. H. Enslow (New York City): Mr. Chairman, members and guests: I was specifically told to talk a bit about chlorination as secondary treatment. I told Mr. Mackin I had not thought of chlorination as a secondary treatment, but he said it was an adjunct, and therefore, I should cover that part of the topic.

We are running behind time and I can see faces in this audience of men who have heard me speak on this same topic so often that I am going to hurry through it, because it is somewhat repetitious.

Now, of course, as an adjunct to secondary treatment, we are all familiar with the use of chlorine in conjunction with trickling filters for a multiple purpose; for controlling odors as the first and primary use, for eliminating or controlling ponding and also for control of fly breeding. In some plants fly breeding is not controlled to the extent that it should be by chlorination alone, the reason being, I think, largely because of inadequate coverage of the filter media by the spray. In other words, this fly breeding control, as Morris Cohn pointed out long ago, is due apparently to the elimination of the thicker film which forms around the upper stones. Unless you can have some method of eliminating that film, the flies will breed in those areas where the film persists. I have seen filters which were very effectively controlled by chlorination.

When it comes to ponding, there seems to be a good deal of success in that direction and every now and then we hear of a new case where chlorine has been effective.

Now I might say too that chlorination at trickling filters has an effect somewhat along the line of high rate filtration. That is, it does keep the film on the filter moving out and, therefore, keeps a thinner film which apparently is a much healthier film, as Morris Cohn expressed, in oxidation and nitrification.

Therefore, when you chlorinate, instead of getting a deficiency in effective oxidation, you actually get an increased efficiency in most cases. Of course, that was quite revolutionary at the time we discovered it and hardly anyone believed it. Everybody does know chlorine does kill bacteria and they do not know how chlorination on top of a biological film would be helpful anyway.

Messrs. Bedell and Walker both mentioned sand filters. It might interest you to know that I have seen plants in New Jersey chlorinating ahead of the slow sand filters. That really is a little upsetting to most of us but it actually improved the effluent of the plants, but more interesting, I think, was the fact that most of the filters took a much higher volume loading due to the fact that the zoögleal film on the sand seemed to be kept in a granular condition rather than a gummy con-

dition. I was rather impressed with Mr. Walker's idea of going back a bit in re-establishing, you might say, the slow sand filter and I think of this only for small plants. I don't think there is anyone in the room who will not agree with me that when you observe a slow sand filter plant you are rather disturbed to see that in most cases the sewage does not reach thoroughly over the sand bed. The settled sewage being applied does not get good distribution and that means that part of the area is loaded until it clogs. When you get clogging, that part is dead and suffers from oxygen deficiency while the other part is put to work naturally because the sewage runs onto it. So at no time, then, do you have 100 per cent of the sand bed operating effectively. You have half the bed unused and the other half over-used and then you get putrefaction in the clogged part while the other half becomes overloaded. It leaves you between two horns of the dilemma at all times.

It strikes me that Mr. Walker reached a logical conclusion when he pointed out that slow sand filters still have a place in small plants if provided with efficient distribution facilities. Everyone here knows that it is hard to beat a slow sand filter in the production of a good effluent when it is operated correctly and given good care.

Speaking of high rate filters, we all know that the argument as to the stability versus B.O.D. of the effluent is one that could last all night, but I look at it this way. The stability test is a very useful index, particularly where we do not have the more scientific B.O.D. test, but all that the stability test tells you is how far down the stream the effluent will go before it becomes devoid of oxygen, providing that there is no natural reaeration in the stream. Unless I am badly mistaken that is all it does show.

Now we know we don't usually have covered streams. Out in Iowa, there was a covered stream which acted as a wonderful septic tank because it was sealed over from any air. Ordinarily, we have reaeration going on, so I don't know why we get excited about the stability number on any effluent except to predict as to about how far down the stream that would go if it had no aeration whatever. I do not see that it has a real practical application. I would like to hear discussion on that. I think it is an interesting subject and a lot of these plant operators are very much confused, especially the uninitiated ones as to the stability number versus B.O.D.

When it comes to secondary treatment and chlorination, I have one more application and the effectiveness of it is exhibited right here in the State of Illinois at Downer's Grove. I understand that for 12 years or so at Downer's Grove the effluent of a heavily overloaded sprinkling filter is being chlorinated every summer, primarily for the purpose of raising the stability number. It does it. It increases the stability number so that instead of going bad in five days it will only go bad in 10 days, as shown by a survey of the small brook which receives that effluent. I examined the stream about a year and a half ago in the late summer when conditions were proper for showing up bad results, if

ever, because it was dry and had been a very hot period, and I did find the brook to be remarkably clean and also free of odors.

The same thing has been done at any number of places and more scientifically where there are industrial wastes involved, canning wastes in particular. I know plants that have been treating canning wastes without chlorination of the effluent; naturally, they do get a putrid condition which seems very bad in the eyes of the farmers. These nasty looking slime growths lead the farmer to think that the stream is dirty as soon as he sees them. If he does not see the growth but sees clean sand and clean branches along the stream instead, he is not so excited. It reminds me of the fellow who smells a sewage treatment plant through his eyes. That is just the case in this situation. There are cases, in other words, where you can use chlorination as a palliative, as a temporary relief measure, and in the case of Downer's Grove they have never yet seen fit to add more to that plant as long as chlorination is doing the job it has been doing.

Chairman Mackin: Thank you very much, Mr. Enslow. I shall now ask for discussion from the floor on the topic of secondary treatment.

Mr. C. A. Emerson (New York City): Mr. Chairman, I would like to ask Mr. Enslow the question, bearing in mind that the progress of sewage treatment for the past 30 or 40 years has been uniformly toward more intensive methods without full development of standards, are we in danger of running into a condition wherein we are going too fast? We are told in these days of rubber and gasoline shortage that 35 miles an hour is two or three times as easy on the car. It cuts the death rate down. The car operates more efficiently. What is the speed limit?

Chairman Mackin: Mr. Emerson poses a very interesting question. What is the speed limit? I shall ask Mr. Enslow to answer it when he sums up this discussion later.

W. D. Hatfield (Decatur, Illinois): I would like to comment upon something I have read between the lines in a good deal of this secondary treatment discussion. It seems to me if we look back into the history of the activated sludge process we find it to be one of the first processes in which we returned a considerable quantity of the effluent back into the process. We happened to return solids along with about 95 per cent of the effluent back into the sewage and we had the activated sludge process. Then more recently we have started pumping the effluent from the trickling filter back to the head end of the plant with some rather astonishing loading results.

Now there are any number of different processes proposed in which we are going back to the original activated sludge plant practice of pumping back still larger volumes and getting much better operation. Two or three different processes use 50, 100, 200, 300 or 400 per cent return. What I am thinking of is final effluent rather than sludge. I am wondering if the keynote of the future in this secondary treatment is not some form of recirculation.

Major Rolf Eliassen: One thing I wanted to bring up. When Mr.

West mentioned the very high concentration of solids in the mixed liquor you would also bring in power consumption or air consumption, because I have noticed a number of times in Mr. Mallory's paper in New York he was very evasive about air requirements, and that is what costs the money. As far as we are concerned, we have to remember that we can get treatment but we have to realize economy in some of those things.

There is just one more point. We can still have our slide rule and our tables but we still need the operators to pull us out of difficulty!

Mr. Van Kleeck: Mr. Chairman, a question for Mr. Walker. Could you give us any figure, Mr. Walker, as to how high the rate could be on the slow sand filter, using the rotary distributor? We usually think of the rate as 100,000 gallons per acre per day. Could you offer 200,000 or 500,000 g.a.d. or aren't you prepared to say?

Mr. Walker: I would rather answer that by saying I don't think that it should be rated in terms of flow. It should be in terms of pounds of B.O.D. or some other measure of the amount of organic matter being applied to the filter.

Chairman Mackin: Mr. Walker, what do you mean by the amount of organic matter?

Mr. Walker: Go back to the B.O.D. Rated in terms of B.O.D. applied to the filter or, if you please, with apologies to Mr. West, population equivalent. It is my belief that with better primary treatment, such as preliminary treatment on high capacity filters, or some other form of removal of the more dense solids, that you could increase the loading probably six or seven or eight times. I have seen work done where the loads were increased ten times over and above the standard as set up as a point of departure for the Illinois Department of Health, which I think compares favorably with the other Boards of Health.

Operator (Camp Breckenridge, Ky.): I would like to ask what figure Mr. West uses to determine the best operation for an activated sludge plant. He spoke of a measure which operators should use to govern the rates of return sludge to the mixed liquor and the solids content. Which figure does he prefer to use as the best measure?

Mr. West: You must use both. As far as the percentage of return sludge, that is governed solely by the relationship between the holding capacity of the aeration tanks and final settling tanks. In other words, if you have one combination, if I may just go back, the formula is 2A over C minus 1. In using that, K, the return would be the actual sewage flow divided by 2A over C minus 2. May I say that this value is fixed and that the conditions in your plant will govern the percentage of circulation you must use to keep the optimum. As far as the B.O.D. loading, that will be shown by the other simple tests in the process, the centrifuge, the settleometer, and your sludge blanket. The conditions in your tank will show the magnitude of the loading and what effect it has on the process and will tell you what should be done to bring that process back into equilibrium.

Chairman Mackin: Is that of some help? The latter part of his

discussion I think is the part that related to the specific prescription for suspended solids.

Are there any other questions? Does anyone have any comments to make about the future of secondary treatment?

Mr. W. W. Mathews (Gary, Ind.): Mr. Chairman, I haven't heard anyone say what he thought was going to be the next advance in sewage treatment, with these processes coming out that guarantee such a high reduction. They leave only one or two parts per million to go. Where do we go from that?

Chairman Mackin: When we get there I don't think we will have much to worry about from that point on. The only basic thing to seek then will be a bacteria-free effluent.

Mr. W. A. Allen (Pasadena, Cal.): Mr. Chairman, I would suggest that sewage plants ought not be burdened with water treatment.

Mr. Emerson: What I had in mind when I asked about the speed limit was that it is all very well to sit down with a slide rule and plotting paper and get your A times C, divided by X equation, or something like that, but that we cannot just ignore some 30 or 40 years of sewage treatment experience.

When we set the plant up we try to know in advance just what we are going to get but often find the sewage isn't that way, which puts the poor operator in a position where he has to handle that sewage in the summer and the fall and the winter, each season differently. The thing we must bear in mind is to always provide a factor of safety but you cannot get these things down to the nth degree of accuracy.

Mr. McGuire: Who is going to pay for the factor of safety?

Mr. Emerson: The point was raised, where do we go from here. You have to look at it from a practical standpoint, to which the State Departments of Health are coming more and more as to how much purification is required for the particular needs of each stream. We must develop first a means of determining a safe measurement for the particular method of treatment which is under consideration. We must estimate what it will do, and then apply that to the requirements of the stream, because most assuredly we are going to have to design in the future more on a dollar basis than we have. It certainly is a waste of public funds to provide a higher degree of treatment or purification than is required for the specific stream conditions. If old Dame Nature will pick up where you leave off and continue things nuisance free and without a menace to health, that is the cheapest way in the world to get that 2, 5, 10, or 20 p.p.m. effluent, or whatever the local conditions demand. You operators don't have to fight with the council to get the appropriation for the initial design as the engineer sometimes must do. That is the difficulty tomorrow.

Chairman Mackin: I think we appreciate your point of view, Mr. Emerson, but it is my feeling that perhaps we haven't done quite as much as we could. As sanitary engineers, we have been too willing to accept "no we can't afford it." I wonder if in the future it isn't going to be scrutinized pretty carefully as to whether or not some such im-

proved form of treatment for almost every community in the country is indicated if they wish to keep their self-respect in our society. The discussion yesterday brought out the fact that our national income may level off at around 125 billion dollars, and I could conceive that even if the job is expensive, as long as it isn't out of line with our pocketbooks, it would be desirable to go much further in treatment. It has been done in the past, because communities often feel much better about doing a job to a greater extent even though it might not be absolutely essential. I feel that with high quality effluents going into most of our streams, the fauna and flora of those streams would change almost completely and certainly for the better. I make these remarks freely and without inviting any questioning of them, and you are all free to do likewise, but my mind just runs along those idealistic lines.

The pocketbook isn't so important as long as you don't go too far, and I am sure we have not gone far enough nor has the proper share of the tax dollar been spent for sanitary improvements that will produce the high quality effluent that science is capable of giving us in these days.

Mr. Morris M. Cohn: Mr. Chairman, I rise because yesterday afternoon I propounded a philosophy that with a national income of 125 billion dollars a year and with 100 billion dollars a year now being expended for the job of human slaughter, that there will come a time when we can expend a reasonable percentage of the national income for the job of protecting our nation's greatest asset, which is human public health. But if you recall, I tempered that idealistic viewpoint with one statement that attracted some attention and which caused people to buttonhole me last evening. I said this, "that the idealistic viewpoint as far as I was concerned was treatment for every gallon of sewage and industrial waste," and if I had said period thereafter, that would have been, in my opinion, an improper statement. But I went on and said, "commensurate with the needs of the stream," and I merely rise to second the feeling of Mr. Emerson that we must temper our idealistic viewpoints on treatment of sewage and industrial wastes by an intelligent appraisal of the needs of the stream into which these wastes are going.

In fact, I have often propounded the philosophy of fitting the stream to the effluent when we cannot fit the effluent to the stream. I have talked before several communities in the country where engineers with good intelligence have actually diverted more diluting water to a stream in order to permit the treatment plant to do a lesser job of purification. I speak particularly now of an interesting experience at Lockport, New York, where the diversion of water from a canal permitted the use of a primary treatment plant rather than a complete treatment plant. I merely offer this as further proof that the engineering intelligence of the future will prevent the wastage of public funds for the carrying out of treatment beyond the actual needs of the stream.

Mr. Wm. A. Allen: I think that we have heard this morning all the more reason why this group and the Federation should sometimes come

out to the west and the southwest. All we hear about is diluting streams. We have no streams.

Chairman Mackin: That brings a thought to mind. We should look to the west for the future of secondary treatment.

Mr. Allen: I was about to mention that it is predicted that our whole climate is going to change. Perhaps some day you will have arid conditions. You may not have the streams and we will have them, and we will be fortunate and that will be your hard luck. I think perhaps we should look at the matter of sewage treatment not so much in the light of the receiving stream because there are some localities that do not have any.

Mr. Lloyd Nelson (Washington, D. C.): I am afraid Mr. Emerson and Mr. Cohn are perhaps not looking far enough ahead into the future in the attitude they are taking at present. I am very much in disagreement with the thinking we have had in our ears for a decade or more, that we are coming to a part of the development of our country at which we are leveling off. For example, that we are going to round off at perhaps 150,000,000 population. I think that is a very foolish idea and I think that by carrying on with the best known methods of sanitation, we can support a much larger population satisfactorily and look forward to a period of development as great as any we have had in the past in the United States.

Dr. Hatfield: May I support the proponents of more complete treatment? While costs may be higher, some figures I compiled several years ago showed that in Illinois we were completely treating sewage at about $1.00 to $2.00 per capita or about $3.00 or $4.00 per family per year. At that time I figured out that it did not equal the cost of toilet paper for a family for the whole year. Now we talk about these tremendous figures, thinking of how many million dollars it costs to build the plant, but we can certainly spend as much money for sewage treatment as for toilet paper!

Chairman Mackin: That, perhaps, suggests a new basis for the engineers to use.

I certainly want to thank you all for your attendance here this morning and your splendid attention. I shall now call upon Mr. Enslow to summarize this discussion.

Mr. Enslow: I will comment on two or three highlights of the remarks made and will begin with Mr. Walker's statement about dilution with recirculated effluent. I would like to consider dilution with stream water also. As I have often said, if I were a sewage plant operator and had a sewer going under a creek, I would punch a nice hole in the sewer and fix it so I could turn the creek into the sewer whenever I felt pleased to do so. I think 90 per cent of the sewage plant operators I have met would be pleased to do it at certain times of the year.

Mr. Walter Sperry has been doing that very thing for several years at Aurora, Illinois, and my guess is that he will continue doing it. It has helped him out a great deal by winning a $10,000 odor nuisance suit-

and in producing a better effluent from his sprinkling filters. I think that is a highlight.

Mr. Cohn mentioned the diversion of stream water for dilution of partially treated sewage as an adjunct to the sewage treatment plant. This might be done by developing reservoirs for that purpose. Pennsylvania is working in that very direction. It not only applies to domestic sewage but to industrial pollution also, in this case mine drainage in Pennsylvania.

Speaking on Mr. West's topic, I do not think anyone can help but be very highly impressed when they go to these plants that are using the Mallory method of control and finding out that they really are getting pretty good results. Here is something that has upset most of you here. It did me. You go to the Ann Arbor plant and you find a bulking sludge condition, the sludge going over the effluent weirs. The operator would then immediately test A to Z to determine if he had any dissolved oxygen in his aeration tanks. If he did not do this as a regular routine test, he probably would in any event just to make sure. We find four or five parts of dissolved oxygen. You say: "I have plenty of air. What could this be? The sludge is poisoned. What am I going to do about it?" He tries as many things as he knows how. The sludge continues to bulk. It may take three or four days to get it back on an even keel. As I understand, what they do when they have such a condition is to take as much sludge out of the process as possible, and get rid of that, they reduce the sludge blanket in the final tank to the minimum at which they can safely operate and increase the air. There you are. You have already four parts per million of dissolved oxygen and still in this case the remedy seems to be increasing the air and within an hour and a half the sludge in the final settling tank was down and well behaved, and the effluent was clear and you could see the sludge blanket. I must say when people can do something of that nature it is something to look at. You can't ignore it.

On the other hand, you heard Mr. West mention one case of 13,000 p.p.m. aeration solids. Well, that is an awful load of sludge, much more than we ordinarily conceive of but it worked in that particular case. We are a long way from solving the riddle of activated sludge plant control.

I can certainly appreciate the position of the operator from Camp Breckenridge. I realize his situation even though I have never seen his plant. His case is additional proof that there is much more studying to be done in activated sludge control methods.

We come to this critical question that Emerson proposed. I think we can look to operators like Mackin and Hatfield as the very life savers of sewage treatment, as we now know it today. I am telling you that if some of the expensive plants that have been built over this country had not had operators like Hatfield and Mackin, our hides would have been nailed to the door a long time ago as sanitary engineers. The plant would have been on the junk heap and our reputations would have been lost.

The public can be sold on good sewage treatment, but Emerson has a very important point, particularly at this time when we are talking about doing something tomorrow, and trying to do it right. That is to say, if you will take Schroepfer's plant up at Minneapolis, that is to my mind an outstanding plant. There was a place where all the evidence would seem to indicate activated sludge treatment or some secondary treatment, whether it be trickling filter or activated sludge. On the other hand, there was one original thought brought into the picture and the State Board of Health and the United States Public Health Service said, "We will try chapter one first," and chapter one was primary treatment. However, the design also provided for chemical treatment, and if this proved inadequate, secondary treatment was to be provided later. The answer is that the plant has been operated several years and they have not found it necessary to go beyond good primary treatment. That is good common sense and economics and it should be good sanitary engineering. I leave it to you gentlemen if we haven't got to think in those terms from here on.

III. WARTIME OPERATING PROBLEMS IN MUNICIPAL AND ARMY SEWAGE TREATMENT PLANTS

MAJOR ROLF ELIASSEN, MARTIN A. MILLING, EDWARD C. CALDWELL, AND WILLIAM J. DOWNER, *Leader*

Chairman Mackin: This topic will be of unusual interest. I take pleasure in presenting its leader, Mr. Wm. J. Downer, Chief Sanitary Engineer of the Illinois Department of Public Health and Technical Secretary of the State Sanitary Water Board.

Mr. Downer: My remarks will pertain mainly to the sewage treatment problems that have confronted the Department of Public Health in the past year. Owing to the fact that we have only two men in the central office who specialize in sewage treatment work and that they are unable to spend appreciable time in the field, we are not nearly as well informed on present day problems as we would like to be. Previous to the war, we had ten men engaged in sewerage and stream pollution work along with 32 district engineers, so our present situation will be apparent.

Accordingly, most of my remarks will be based on what we have heard, what has come to us by correspondence or what our two remaining sewage works engineers have learned in their very infrequent trips to the field.

The first and primary problem that we are up against in wartime operation is that of personnel. You heard something about it last Thursday afternoon. We have it here in Illinois. We have lost several of our good operators to the Army, the Navy, the Marine Corps, and the Coast Guard. We have lost them also to industry and to those war industries that pay much higher salaries. It has been necessary to replace these men to keep the plants going and you know as well as I what

the replacements are to a large extent. A lot of the replacements need training in order to operate the plants satisfactorily and they look to the State Department of Health to give them the training. What can we do with only two trained men on our staff? So the plants must get along as well as possible under existing conditions.

Not only have many good operators left for more lucrative positions and for military service, but some cities and municipalities have felt free to make changes because of political reasons, which is to be deplored at this time.

From our standpoint, we are trying to do the best we can to train these new men but we just do not have the personnel ourselves to do it. We have been very fortunate, in some instances to be able to call upon some of our better sewage plant operators to give us a helping hand and they have kindly consented to do it and helped us greatly in this emergency.

I also do not overlook the point that many of our equipment companies have been very gracious and gone out into the field, especially where they have had equipment installed, and have helped operators in the proper operation of their plants.

Now the second item, besides personnel, is the general wear and tear and deterioration of equipment and of the plant structures. That would come whether we have a war or not, but probably more so because of the type of personnel we are getting into our plants who cannot appreciate what should be done to keep these structures in proper condition and the machinery properly repaired, lubricated and adjusted. A sewage plant operator, we will all agree, should have some mechanical ability, and a lot of the men that are being placed now know nothing about mechanical equipment or its proper care.

The third thing, and I am being very brief, is the problem of introduction of industrial wastes to many of our sewage treatment plants, such as oil, the by-products from cheese and milk products and also other war industries, as Dr. Mohlman described in his paper. You can appreciate how some of these problems would trouble even a good operator, and what happens when we have a poor operator!

As to the Army camps here in Illinois, I can give you no information because they give none to us. The only time we hear from the Army camp plants is when something goes radically wrong and they need some help. As far as Army camp plant operation is concerned, I will leave that to two of the other speakers on this panel.

I shall now call upon Major Rolf Eliassen of the Corps of Engineers, U. S. Army.

Major Eliassen: To everything that Mr. Downer has said, we can say amen, because the same things happen in Army plants but in a different way, perhaps.

In the first place, personnel is critical. Yes, we have a manpower shortage and Congress is clamping down on our expenditures to a considerable extent. We cannot pay the salaries that some of the industrial plants can pay to attract employees. Furthermore, we have been cut

considerably in the number of personnel available for operation of utilities. This is the same story that is found in municipal operation.

We have had to solve the problem by holding a number of training schools at local universities. We have also recruited men from all over, many of whom had never before seen a sewage treatment plant. As Mr. Downer said, if we can get a man with some mechanical background and give him a little bit of training, we can make a good operator out of him in a reasonable length of time. We still have to exercise considerable supervision over a man of this type because he does not have the outlook of the person associated with the sewage treatment field for a number of years.

Our problems at some of these posts have been similar to those in municipalities on account of the increase in population. However, our population rises have been meteoric in nature at various times. As was mentioned the other day, very frequently higher authority makes a decision to double-bunk the barracks which means that twice the population can be accommodated almost over night. No time is available for increasing utilities facilities and, therefore, twice the load occurs on the water and sewage treatment plants.

Industrial wastes have been quite a problem at a number of posts. This is not ordinarily thought of in connection with Army wastes but some posts have special missions particularly those engaged in manufacturing. A number of different problems confront us from time to time.

One of the most interesting and the most perplexing of these problems was that encountered at an activated sludge sewage treatment plant. Large photographic laboratories were connected to the sewer. These laboratories discharged wastes containing silver and other reducing compounds such as hyposulphites. Efforts were made to blow air into the sewage to increase the dissolved oxygen content. At the same time these reducing compounds would utilize all of the dissolved oxygen with the result that no residual oxygen could be maintained in the mixed liquor for utilization by the bacteria in the activated sludge. We were applying as much as 4 cu. ft. of air per gallon of sewage and still getting nowhere. The net effect was to decrease the treatment on all of the organic wastes coming into the plant. It was felt better to give adequate treatment to this organic matter and by-pass the industrial waste entirely. The biological treatment plant would in no way treat these wastes except to decrease the oxygen demand. As a result, the stream took care of the photographic laboratory wastes and the activated sludge plant took care of the organic wastes.

All of the wastes were disconnected from the sewage except the X-ray laboratory at the hospital and the Post Exchange photographer. The quantity of photographic wastes from these two sources was so small that it did not effect the oxygen demand of the sewage to any appreciable extent. Everything went along smoothly until graduation of the Officers Candidate School when all of the proud mothers and fathers

came to see their offspring with new gold bars on their shoulders. I do not know how many dozens of photographs were taken to the Post Exchange for developing at that time, but we do know that for several days following graduation no dissolved oxygen was found in the mixed liquor of the aeration tanks and the sludge bulked excessively. When these pictures were all developed, the plant operated to satisfaction again.

At another plant TNT wastes were discharged into the sewers causing some difficulties with the trickling filter plant. The wastes were diverted into a nearby lake and fish were killed near the outfall sewer. Experiments were conducted and it was found that activated carbon would remove the organic matter from these explosive wastes. However, for the sake of economy, the activated carbon had to be regenerated. This was done in a closed cell and worked fine until it was found that for complete regeneration the temperature had to be run so high that the whole mass exploded. Another method of carbon recovery had to be developed.

You see that problems of industrial wastes do come into the Army camp waste treatment picture as well as with all municipalities. No mention has been made of laundry wastes and grease which have created quite a problem at many posts. The amount of grease discharged at times has made the sewage look almost like packing house wastes. This is a familiar situation which has been spoken of by many people interested in the treatment of Army camp sewage.

Sludge drying beds have given us considerable difficulty. Some of the camps in the East have been located rather close to barracks and with limited room for expansion. Thus, we have not been able to resort to lagoons or other emergency methods of sludge disposal. The method developed by Mr. Sperry of Aurora, Ill., has been used with a great deal of success at a number of Army camps. That is, the addition of alum to the sludge as it is drawn to the beds. It does a remarkable job of drying and increasing sludge bed capacity and it has been a life saver to us until we could get additional sludge beds constructed.

You may not be very much interested in the subject of septic tanks and tile drain fields, but the Army has hundreds of these installations serving small outposts. Many of these tile fields have been installed in practically impervious soil and have had to be redesigned in order to accommodate the posts. Although we may be prone to think of large cities like Chicago and others, the sanitary engineer must be in a position to pay attention to sewage disposal facilities both large and small and to be able to dispose of the sewage without creating a nuisance under all conditions.

Conservation of critical materials has led to the use of wooden tanks in a number of instances. The shortage of seasoned lumber has led to embarrassing situations when trying to make tanks watertight. The use of green lumber did not permit necessary expansion to close all construction joints. Consequently much leakage occurred until the joints could be caulked with colloidal clay, oakum and asphaltic compounds.

On the whole, in spite of the many emergencies which have arisen, the Army has paid a great deal of attention to the treatment of sewage so that in most instances the receiving streams have not been damaged and we can point with pride to a number of streams which have been improved through the treatment of Army camp sewage.

Mr. Downer: Thank you, Major Eliassen. Now I wish to call upon Mr. Martin A. Milling, Senior Sanitary Engineer of the State Board of Health of Indiana.

Mr. Martin A. Milling: In order to understand better wartime operating problems at Indiana municipal and Army camp sewage treatment plants one must first know something about the number of sewage treatment plants, the kind of plants, and the population served by these plants. There are 126 sewage and industrial waste treatment plants in Indiana. They may be divided into three classes, namely, industrial and institutional plants, plants for Army camps and air bases, and municipal plants. There are 31 plants for institutions and for the treatment of industrial waste, 14 for Army camps and air bases and 81 for municipalities. There are 22 activated sludge type plants, 60 standard trickling filter type, 6 high capacity filter type, 22 plain sedimentation, 4 biochemical, 1 bio-activation, 6 sand filters, 1 magnetite filter, 2 contact beds, 1 neutralization plant and 1 with only coarse screens, making a total of 126.

About 1,127,640 people in the State are served by the municipal sewage treatment plants. This is 59.8 per cent of the urban population.

Classification of Sewage and Waste Treatment Plants

Type of Plant	Number of Plants			Population		
	Industrial Institutional	Sanitary Sewage		1940 Census	*Served by Plants 1943	Urban Pop. Served by Municipal S.T.P.
		Army and Air Bases	Municipal			
Activated Sludge	6	2	14	884,278	794,500	42.1%
Biochemical	1	—	3	107,122	49,500	2.6%
Bio-Activation		1	—	—	—	—
High Capacity Filters	2	4	—	—	—	—
Trickling Filters	15	3	42	224,770	187,050	9.9%
Sand Filters	4	2	—	—	—	—
Magnetite Filters	—	—	1	11,375	11,000	0.6%
Contact Beds	1	—	1	3,075	2,000	0.1%
Plain Sedimentation	1	2	19	54,748	33,590	1.8%
Coarse Screens	—	—	1	97,062	50,000	2.6%
Neutralization	1	—	—	—	—	—
Total	31	14	81	1,382,430	1,127,640	59.7%

* Includes only the population served by plants now in operation.

Urban population	1,887,712
Rural population	1,540,084
Total	3,427,796

About 42 per cent of the urban population is served by activated sludge plants and about 10 per cent by trickling filter type plants.

At the beginning of World War II we found ourselves confronted with a number of problems without any past experience to fall back on for information and guidance. During World War I there were only five sewage treatment plants in Indiana and these were only of the septic tank variety. It is, therefore, understandable why, at the beginning of the war, many sewage works men were doubtful as to what would happen to the State's stream pollution abatement program.

One of the first problems at the beginning of the war was to come to an understanding with officials of army camps, air bases and ordnance plants as to what type of plant would be required to meet State laws and as to operating supervision of these plants. This problem was not found to be very difficult. In the first place local consulting engineers were employed to design most of the plants, and these engineers were sympathetic with the State's stream pollution abatement program.

After the plants were built the State was fortunate in being able to help place many locally trained operators in the plants to supervise their operation. It can now be said that very little additional stream pollution has been caused as a result of the discharge of sewage and industrial waste from war plants and camps into State streams.

Another problem that arose soon after the war started was that the construction on sewage treatment plants, which were not considered essential to the war effort, was stopped even though the construction on several of them was nearing completion.

There has been no real solution to this problem as yet. However, interested contractors and engineers are beginning to become active and it is hoped that at least some of the plants will be completed so that they can be placed in operation.

Another problem that came up soon after the war started was the demand on the part of some city officials to shut down their sewage treatment plants in order to economize by saving labor, electricity and the cost of operation. A newspaper in one of the larger cities came out with an editorial recommending that the sewage treatment plant be shut down. To combat this problem a publicity campaign was undertaken by plant superintendents, the State Sewage Works Association, and the State Board of Health, to impress upon the city officials and the public the importance of sewage treatment to the health and welfare of the people. Many plant superintendents distributed to the public small booklets describing their sewage treatment plants and the benefits derived therefrom. Sewage works meetings were also held in various parts of the State, all of which helped to acquaint the public as to the importance and necessity of sewage treatment. There have been no plant shutdowns in the State.

One of the biggest problems, at least worries, that we have had in Indiana has been about critical materials. The purpose of priorities is to distribute critical materials where they are most needed.

In order to find out the quantity of critical materials that have been

purchased in the State since the beginning of the war, questionnaires were sent out to the superintendents of all the larger sewage treatment plants in the State. There were 54 of these questionnaires sent out to plants serving a population of 1,128,987, which is 63 per cent of the urban population of the State. Reports were received from 35 superintendents of plants serving a population of 969,622, which is 85 per cent of the population questioned. The results of these questionnaires showed that $36,937 has been spent for critical materials since the war started. This is less than 4 cents per person and, considering that Indiana has invested some $15,000,000 in sewage treatment plants, this is a very low figure.

There are a number of objections that have been raised to the priority system of distributing critical materials. One is that the regulations are too complicated and that there are too many changes. Another is that it works a hardship on the small plant operator who has no engineering and legal talent at his command for making out complicated application forms. Another objection is that the man who passes on the application is too far away and is not personally familiar with the need for the materials requested.

The critical material problem has been solved in several cases by the use of local machine shops for making machine parts and welding broken parts. This practice, however, has not always proven satisfactory. For example, in one city a machine shop attempted to make a bearing ring for a rotary distributor. This bearing ring was made out of soft material and was not in use but a few weeks until it was worn out. The part finally had to be ordered from the manufacturer and the outcome of it was that the plant was out of operation for a period of time. It was also a waste of material and labor.

Early in the war a Mutual Aid Plan was organized primarily for the purpose of listing surplus repair parts which could be used where needed in order to avoid the purchase of new critical materials. We have not had any major catastrophes in Indiana; however, Mutual Aid has already helped to a limited extent in at least one city. In this case a trained mechanic from one sewage treatment plant was loaned to another city for the purpose of making necessary repairs on a machine.

One solution of the critical material problem has been better maintenance. Machinery is gone over more often to see if it is properly greased and in good operating condition.

In some cases where the particular machine or part could not be purchased a substitute machine or part was used. This practice has not always proven satisfactory. In fact in many cases it has proven a gross waste of critical materials. In one instance that came to our attention only a small part was needed, but, not being able to get this part, it was necessary to purchase the entire machine, which by the way, was far inferior to the old one.

Indiana enjoys the distinction of having the third highest per cent employment increase in the country, being exceeded only by Michigan and Washington. This has resulted in many Indiana sewage works

operators leaving their jobs for higher pay work in war plants. To help solve this problem the Indiana State Board of Health has acted somewhat as an employment agency in locating available operators. Valuable assistance in locating operators has also been received from the Central States Sewage Works Association through Mr. Mackin. Women have been employed in several of Indiana's sewage treatment plants as chemists, bookkeepers and secretaries.

It is hoped that out of the many operating problems that have arisen during World War II that we will at least have learned some lessons which we can pass on to future wartime sewage works operators of World War III. Some of these lessons are listed briefly as follows:

1. That sewage treatment is classified as one of the essential industries.

2. That complicated priority regulations are just so much scrap paper so far as the small sewage treatment plant operator is concerned. Large plants with highly skilled technical staffs, engineers, lawyers and maybe politicians, are likely to get more than their share of the critical materials.

3. That the useful life of machines, pumps, etc., can be extended several years if they are given proper care.

4. That it does not pay to make specialized machine parts in local machine shops. Such parts should be purchased from the company that manufactures the machine.

5. That better distribution of critical materials could be made if regulations were simplified and if Washington would work more through State and local governments.

6. That failure to make available repair machine parts often results in a waste of plant efficiency, labor and even of critical materials.

7. That women have proven to be good substitutes for men at sewage treatment plants as chemists, bookkeepers and secretaries.

Mr. Downer: Thank you Mr. Milling. At this time I would like to call on Mr. Edward C. Cardwell, Associate Sanitary Engineer, Truax Field, Madison, Wisconsin.

Mr. Edward C. Cardwell: Members of the Federation: I am a pretty small cog here after listening to these gentlemen, one covering all the camps from a particular Service Command and the other two gentlemen covering all the non-military camps in Indiana and Illinois. All I have is a small sewage treatment plant located at Madison, Wisconsin and Madison is part of the "Land of Lakes" which no one shall pollute. Therefore, we are forced to turn out a pretty good effluent—at least, we think it is.

Major Eliassen gave you a composite picture of interesting problems throughout his Service Command. I shall discuss a single plant of the trickling filter type.

Our flows are considerably over the per capita figures used in design and the sewage concentration is low for an Army camp but a little higher than domestic sewage. The B.O.D. ranges from 250 to 300

p.p.m. and the suspended solids from 200 to 250 p.p.m. The raw sewage contains about 1,800 pounds per day of B.O.D.

Our primary tanks are hopper bottomed. I have found that the hoppers must be pumped frequently for short periods. The primaries remove about 400 pounds of B.O.D. and about 800 pounds of solids daily. Our filters operate well, removing about 1,200 pounds of B.O.D. daily, although they are not heavily loaded. Due to the shortage of critical materials, we have no sludge collecting mechanisms in the flat-bottomed final settling tanks and we must pump them down at least weekly. Despite this, about 600 pounds of solids daily are removed by the final tanks. Our B.O.D. removals average about 22 per cent through the primary treatment, 91 per cent through the filters and 93.4 per cent through the plant. We are never below 90 per cent any more.

So much for the figures. Characteristic of a lot of army camps, we started operation in the middle of winter, in the month of December. It was a renovated plant and we had a hard time getting started. Sometimes we were getting only 80 per cent removal. As all operators know, you must take the plant as designed and make it operable and this is often not easy. I am not criticizing—merely pointing out that you may get many unexpected problems.

One of the features that we have found best was a change to a more rapid dosing cycle. As designed, the filter was dosed about 25 minutes each time but we have reduced the dosing tank until we now have a 5-minute dosage.

Another change was made in the post-chlorination procedure. We formerly applied about 100 pounds daily to the final tank effluent. Now, we chlorinate ahead of the final tank which has helped overcome the lack of sludge collection equipment.

Reducing the dosing tank cycle has helped to eliminate sedimentation in the dosing tank and has minimized septicity in the sewage. The original part of our plant is the old Burke plant built in 1914 and it comprised two stages of primary settling, a colloidal chamber and contact beds, all in series ahead of the trickling filters. You can see why it is important that we keep the sewage fresh.

We have not met very many pitfalls except we have fallen into the pitfall of grease, and we had grease in the digester, which caused much trouble. We had not heard about "super-heating" the digester at that time. It sounds very good, but we had to practice what we called a "flushing" policy and that consisted of building a raft inside the digester and scooping the scum out with pails. Anyway, we got it out and immediately the gas was released and the problem was over.

In conclusion, I would say that operation of the Army camp plants in our particular area was very comparable to municipal plants. I think we are doing our share in our part of the country to keep the effluents as clean as possible.

Mr. Downer: Thank you, Mr. Cardwell. Since the hour is late we must dispense with any discussion from the floor, which is regrettable. Before restoring the chair to Mr. Mackin, however, may I pass on a com-

ment about grease control in Army camps that I heard this morning. It was suggested that automatic control would result if the mess sergeant were paid a few cents per pound for the grease that he salvaged in the kitchen. This might solve the problem to a surprising degree.

Mr. Mackin, the chair is yours.

Chairman Mackin: Thank you, Mr. Downer, for a most interesting discussion. We shall now hear from Mr. Lloyd Nelson of the War Production Board regarding a very significant topic of the times.

IV. THE BROAD CONSERVATION PROGRAM OF THE WAR PRODUCTION BOARD

By Lloyd Nelson

Special Consultant, WPB, Washington, D. C.

Mr. Nelson: While sewage works are not directly involved in our conservation program, they can certainly be of help.

As the tempo of our war effort is increasing, demands for fuel and materials and equipment and manpower likewise increase, and to my mind, all of these things go back to that one question of manpower. It takes manpower to produce our fuel and transport it, to produce our equipment and process our materials. As the draft calls go out month after month, the manpower problem will be increasingly difficult, probably at least until the middle of the next year.

I was very much interested in some of the suggestions here. I know that in filter plant operation in the water industry, they are using quite a number of women operators and I presume the same could be done in sewage works. As men are called, in some cases their wives have been called in to help out under supervision, of course.

This broad conservation program is asking every citizen of the United States to stop waste and to conserve so as to save that fundamental manpower, to make our situation that much better. This might sound like a small program, but believe me, when you add up the savings through stoppage of waste in 30,000,000 homes in the United States, you will give a tremendous impetus to the war effort. It is estimated that if 18,000,000 homes which are heated with coal alone in the United States, would put into practice such simple "stop waste" conservation measures as learning how to fire the furnace properly, not overheating and opening the windows to cool the rooms off, as much as 18,000,000 or 20,000,000 tons of coal could be saved in home heating alone!

In the sewage works field your main use of electricity is in pumping, I presume. May I suggest that you call in the manufacturer's representative of the equipment you use and have him to check your method of operation to see if it can be operated more efficiently. Simple things, such as replacing the wearing rings in pumps at the proper time enable quite a large saving in power cost. This is money in your pockets and it is also a help to the war effort.

Might I also say that the War Production Board, in asking for conservation, is not asking anyone to stop necessary uses—only to stop unnecessary and wasteful uses. Certainly no one in the United States wants to use up something to no real purpose, just waste it. All that is being sought at the present time is that everyone co-operate in that type of program.

Turn out electric lights when you do not need them. It is estimated that such a simple thing as this will save as much as 75,000,000 light bulbs a year, and that means a saving in tungsten, which is extremely critical and is vitally needed in the manufacture of radar equipment for our armed services.

There are many other things you know about your own plants in which you can co-operate in the program better than I can tell you. I merely want to bring the program to your attention and ask your co-operation. Thank you.

Chairman Mackin: Thank you very much, Mr. Nelson. If there is nothing further to come before the meeting, I will declare it adjourned.

Editorials

THANKS TO THE CHEMICAL FOUNDATION

This issue of the *Journal* is notable for the fact that it is the *first* issue to be produced without some degree of participation by The Chemical Foundation of New York City, the institution which brought the Federation and the *Journal* into being. In view of the intensely important service rendered by Chemical Foundation and its modest, "behind-the-scene" role, a suitable acknowledgment is very much in order.

In March, 1928, the embryo Federation consisted of an Organization Committee headed by Charles A. Emerson, Jr., supplemented by a Committee of One Hundred comprising interested individuals from all parts of the United States. Progress was good until an impasse was encountered in the search for a publisher to undertake the printing and distribution of the proposed *Journal*. Then, through the good offices of Dr. Willem Rudolfs, Mr. W. W. Buffum became interested in the foundation of the Federation as a project for The Chemical Foundation and in May, 1928, a most unrestricted and liberal offer to underwrite the *Journal* was extended President Emerson and immediately accepted. Mr. Buffum was associated with Mr. Frances P. Garvan who served as Alien Property Custodian in World War I and the early funds made available for the sponsorship of the *Journal* by The Chemical Foundation came largely from the Imhoff patents which had been taken over by the Federal Government and assigned to the Foundation for the support of worthwhile scientific activities. Thus, Chemical Foundation takes a prominent place with such personages as C. A. Emerson, Jr., Willem Rudolfs, F. W. Mohlman, W. J. Orchard, Langdon Pearse, H. P. Eddy, George W. Fuller, John R. Downes, H. W. Streeter, John H. Gregory and others who were directly instrumental in bringing the Federation and its *Journal* into existence.

The generosity of the Foundation's original subsidy is apparent when the set-up of the first business office of the *Journal* is considered. Office facilities were provided in the Foundation headquarters and Mr. Buffum assumed the duties and responsibilities of Business Manager of the *Journal*. These duties included solicitation of subscriptions, solicitation and production of advertising, maintenance of mailing lists and financial accounts, and printing and mailing of the *Journal*. Finally, and of utmost importance, the Foundation undertook the obligation of meeting any deficit incurred in the entire venture. It may be of interest that the original agreement covered a period of but one year; yet Mr. Buffum continued to serve as Business Manager from May, 1928 to the time of his death in June, 1940, while the Foundation extended its participation to January, 1944.

At the death of Mr. Buffum in 1940, Dr. Rudolfs wrote fittingly of the work Mr. Buffum had performed in behalf of the Federation and the *Journal* (Volume 12, page 816; July, 1940):

"Those who have come in contact with Mr. Buffum can appreciate his work and encouragement to stimulate the development and research in sewage treatment. His identification with the *Journal* made it financially possible to reach a large number of sewage plant operators. His interest was an important factor in the rapid growth of sewage research, which had made this country the leader in the world. He was always ready to support any movement to fight diseases and secure cleaner streams. In the earlier years of the Federation his advice and help was an important factor in the rapid growth of Sewage Works Associations in this country. His business-like manner in handling the affairs of the *Journal*, his sympathy and support carried the *Journal* over several difficult periods."

The Foundation continued its service to the Federation and the *Journal* after Mr. Buffum's death, designating Mr. Arthur A. Clay to serve as Business Manager. Mr. Clay worked zealously and enthusiastically in the position and was particularly successful in giving impetus to the use of advertising facilities offered by the *Journal*. The first *Convention Number* was attempted at his suggestion and, under his guidance, proved to be an outstanding success.

In January, 1941, after Chemical Foundation had carried the *Journal* through its first twelve years of existence, the opening move was made to relieve the Foundation of this burden. It was then that the Federation Secretarial office was expanded to assume the bulk of the responsibilities of business management, but the Foundation was still retained to provide assistance in the mechanical production of *Journal* advertising. Mr. Clay's title was changed to Advertising Manager and the work was carried on under his supervision by Miss Gertrude R. Horan, his capable and efficient assistant. It is significant that more than 200 pages of paid advertising were carried in the *Journal* in 1943, an all-time high. Henceforth, all advertising functions associated with the *Journal* will be handled in the new Secretarial office of the Federation but Mr. Clay and Miss Horan kindly extended their assistance to include production of the January, 1944 issue in order that a minimum disruption of service would result during the transfer of the work.

At best, the writer can but echo the expressions of gratitude to The Chemical Foundation which are in the thoughts of Messrs. Emerson, Mohlman, Orchard, Rudolfs and others who have been so intimately familiar with the part taken by that agency in the development of the Federation. The writer can and does offer sincere thanks in his own right, however, for the courteous and complete cooperation that he has enjoyed during the past three years in his gradual assumption of the functions formerly provided so efficiently and unostentatiously by the Foundation. Every member of the Federation should likewise be grateful for the progress in the sewage works field that has come through such participation.

Chemical Foundation, the Federation thanks you, deeply and sincerely!

W. H. W.

PAUL HANSEN (1879–1944)—IN MEMORIAM

Paul Hansen was born at Arlington, Va., on August 9, 1879, the only son of John and Pauline (Meyenberg) Hansen. His early education was in the public schools of Washington, D. C. In 1903 he was graduated from the Massachusetts Institute of Technology with the degree of B.S. in Sanitary Engineering.

After a year with the Massachusetts State Board of Health, he joined the Improved Water and Sewerage Work at Columbus, Ohio, and later, the Pittsburgh Filter Co. He was first Assistant, and later Chief Engineer of the Ohio State Board of Health, from 1906 to 1910. From August, 1910 to October, 1911, he was State Sanitary Engineer of Kentucky. From 1911 to 1915, he was Chief Engineer of the Illinois State Water Survey, lecturing also at the University of Illinois. In 1915, he became Chief Engineer of the Illinois State Board of Health, serving until 1920. During the first World War he served for 19 months (1917–1919) with the A. E. F. as a staff officer with General Pershing, on water supply.

In May, 1920, he became a member of the firm of Pearse and Greeley, later known as Pearse, Greeley and Hansen, and since 1930 as Greeley and Hansen. In the course of his professional work he was engaged in the design and construction of numerous water supply and sewerage works, including projects for New York City; Boston, Mass.; Chicago, Ill.; Buffalo, N. Y.; Toledo, Ohio; Peoria, Ill.; and Philadelphia, Pa. He specialized in water purification and became an expert witness on water rates and valuation of water works. During the present World War he was concerned with consulting work for the War Department.

In 1905, he was married to Alison May Scott. He is survived by his widow, a daughter, Elizabeth Scott (Mrs. Henry Pope), and a son, Dr. Paul Scott Hansen, together with five grandchildren.

Among the earlier achievements of his career, he esteemed highly the organization of the public health engineering work for the State Boards of Health in Kentucky and Illinois. In the 40 years of his professional life he accomplished his ambition and became one of the prominent sanitary engineers in the United States. He was a skillful and resourceful engineer, and withal a student of human relations. Traveling widely in his professional work, he possessed a large circle of friends. He was helpful in the technical societies and presented papers which attracted attention. His works will live after him as a worthy monument.

Those of us who knew him well mourn the loss of a firm friend. His kindly humor enlivened many a meeting. To his wife and children, who survive, we extend heartfelt sympathy in their bereavement.

LANGDON PEARSE

Proceedings of Member Associations

NEW YORK STATE SEWAGE WORKS ASSOCIATION

Sixteenth Annual Meeting

New York City, January 20–21, 1944

The sixteenth annual meeting of the NYSSWA was held in New York City on January 20–21, 1944, with headquarters at the Hotel McAlpin. About 245 members and guests were registered at what turned out to be a most interesting and well attended meeting.

On January 20, 1944, the members of the NYSSWA were guests at the Sanitary Section meetings of the ASCE. The program for the ASCE included committee reports on "Sewerage and Sewage Treatment," "The Advancement of Sanitary Engineering," "Operations of the Committee for Sanitary Engineering of the Natural Research Council," a paper on "Plans for Post War Sanitary Engineering Works by the City of New York," an address on the work of the Committee on Water and Sewage Works Development, a symposium on engineering phases of Malaria Control in War Areas, the challenge to the sanitary engineer in regard to the return of tropical diseases and a paper on the "Impact of War on Chicago's South District Filtration Plant."

At the Executive Committee meeting of the NYSSWA the evening of January 20, 1944, William H. Larkin, District Sanitary Engineer, New York State Department of Health, was elected president for the year 1944 and Dr. George E. Symons, Associate Editor of *Water Works and Sewerage*, was elected vice-president. A. S. Bedell of the New York State Department of Health, Albany, New York, was reappointed secretary-treasurer. J. C. Brigham also from the Department of Health, Albany, New York, was reappointed assistant treasurer and A. W. Eustance, district sanitary engineer of the New York State Department of Health, Geneva, New York, was reappointed assistant secretary for the year 1944.

Charles L. Walker, Professor of Sanitary Engineering, Cornell University, Ithaca, New York; Uhl T. Mann, Superintendent, Sewage Treatment Plant, Cortland, New York; and Henry M. Rath, Chief Operator, Tallmans Island Works, New York City, were elected to the Executive Committee of the NYSSWA for a term of three years. Retiring members from the Executive Committee are W. L. Malcolm, Ithaca, E. C. McKeeman, Freeport, and Charles R. Velzy, New York City.

At the general business meeting on Friday, it was noted that the association now has an active membership of 590 with five local sections whose members number 180. The reports of the activities of these local sections, as well as of the various standing committees of the Association, were presented and discussed at the meeting.

W. H. Wisely, the Secretary, Editor and Advertising Manager of the Federation of Sewage Works Associations, spoke on Federation Affairs. Mr. Wisely advised that Dr. F. W. Mohlman, former editor of the *Journal*, has agreed to continue in an advisory capacity and that there will be no change in the policy of the *Journal*. The Federation, according to Mr. Wisely, is not just a journal publishing association but a service agency with its meetings, committees, etc., and his office is ready and willing to serve in any capacity within his power.

Mr. Wisely also spoke on the war time responsibility of the members of our profession advising that we should not lower standards because of present conditions but should take a lead in postwar planning work and maintain pride in our work now more than ever before.

The first paper to be given at the technical session on Friday morning was entitled, "Sewerage Developments and Prospects in Canada," and was presented by Albert E. Berry, Director, Sanitary Engineering Division, Provincial Department of Health, Toronto, Ontario, Canada. In this exceedingly interesting paper, Dr. Berry outlined methods of sewage disposal employed in Canada. He stated that there were some 1,300 water systems and 500 sewer systems in Canada but only 115 sewage treatment works. He is anticipating major developments in sewage disposal systems and expects that water and sewerage developments will take first place in the postwar planning program. Dr. Berry estimated that about forty million dollars are needed for new works in Ontario province alone. The method of financing these postwar projects whether by the local governments or by the provinces has not as yet been decided.

In the discussion of this paper, Mr. Donaldson of New York City, asked whether Canada had a definite target for the postwar program. Dr. Berry stated that the answer was unfortunately no. They had not as yet reached that stage. The question of the use of sludge was discussed and at several places in Canada the wet sludge is carted from the plants in tank trucks and spread over the ground for the use of field crops. No sludge has been used for gardens. Mr. Welsch of Nassau County asked Dr. Berry concerning the method of proportioning costs if several municipalities were served together by one system. Dr. Berry advised that the division was made on the basis of assessments. In answer to a question concerning water use, Dr. Berry answered that the maximum consumption was about 200 gallons per capita per day, the average being about 100 and the minimum being about 20 to 30 gallons. In Canada the provinces have the power to require municipalities to provide necessary sanitary installations and the question was asked whether this power could be used to require municipalities to provide plans for such installations under the postwar set-up. Dr. Berry stated that this power had not been used to that end because normally the cost of the plans are sufficiently low so that the municipality could finance that cost without any difficulty.

At the end of his paper Dr. Berry stated that this, to him, was a return engagement because President Smith and Secretary Bedell had

attended the meeting of the Canadian Sewerage Works Association last summer.

The second paper in the morning session was on "Controlled Digestion," and was given by Harry E. Schlenz, Pacific Flush Tank Company, Chicago, Illinois. In this paper, Mr. Schlenz pointed out the results of experiments using ammonia nitrogen in the control of sludge digestion. There was considerable discussion of this paper and Dr. Rudolfs stated that the supernatant liquor concentration depended on the time and material in the sludge digestion tank. He thought it would be better to increase the digestion capacity and do away with numerous gadgets because in his opinion poor supernatant was caused by inadequate digestion space. Another comment from the floor was that the addition of ammonia might have a good deal of effect in certain industrial wastes but that sewage sludge was an entirely different story. A description was given of the operation of the digestion tank at Jamaica where excellent digestion was obtained without the addition of any chemicals, except a very little lime. Professor Fair stated he did not believe that now is the time to use nitrogen for this purpose because of the critical need of nitrogen in the war effort. In answer to the comment on lack of sludge digestion capacity, Mr. Schlenz stated he did not believe that adequate digestion capacity was the answer because one of the plants where he experimented had adequate sludge digestion capacity with no active digestion prior to the adding of the ammonia nitrogen.

The afternoon session opened with a symposium on grease removal. The first paper on this symposium was entitled, "Grease Interceptors for Use in or near Houses and Restaurants," and was given by F. M. Dawson, Dean of Engineering, University of Iowa, Iowa City, Iowa. This paper outlined the results of experiments undertaken by the writer to test various types of grease traps. The speaker pointed out that a successful grease trap must have adequate capacity, be properly baffled and be so placed as to be readily cleanable because unless a grease trap is cleaned, it is of absolutely no use.

The next paper was entitled, "Experiences of a Large City with the Grease Removal Problem," written by C. E. Keefer, Associate Engineer, Bureau of Sewers, Baltimore, Maryland, but given by Albert L. Genter, Consulting Engineer, Baltimore, Maryland.

The third paper was entitled, "Grease Removal Ordinances and Grease Problems in Sewer Maintenance," prepared by Morris M. Cohn, Sanitary Engineer, City of Schenectady, New York. In the absence of Mr. Cohn, this paper was read by A. W. Eustance, Assistant Secretary.

The last paper of the symposium entitled, "Utilization of Sewage Grease," was given by Wellington Donaldson, Chief, Bureau of Sewage Disposal Design, Department of Public Works, New York, New York. Mr. Donaldson described the method of grease utilization in the City of New York. Grease collected from the tops of settling tank is being sold to a rendering plant and such grease is used in the manufacture of soaps and similar products.

Following these papers, Messrs. Dawson, Genter and Donaldson acted as a board of experts to answer questions from the audience.

Doctor Rudolfs asked Mr. Dawson why he had chosen a fat content of 2½ per cent for his tests and Mr. Dawson replied that was just an arbitrary figure but was somewhere near the fat content in the wastes from restaurant dishwashing equipment. Mr. Dawson had given a figure of 90 per cent removal of floating material and Doctor Rudolfs desired to know whether this was 90 per cent of the total grease content. The answer to this question was that it was 90 per cent of the total grease added in their experiments. Major Eliassen stated that Army installations affected about 50 per cent removal of the grease. The main trouble with such installations has been that they have either not been properly cared for and were neglected, or else they were cleaned out too thoroughly, the grease being dumped down the sewer. Mr. Enslow stated that he had never until recently seen a grease trap which was at all satisfactory but at last he had found one which worked fairly well. In describing this, he stated that it was simply a cistern built into the ground, shaped something like a milk bottle, but egg shaped at the bottom. This type of trap seemed, to him, particularly good, especially because of the small neck which made it easy to remove the floating grease. Mr. Pineus of New York City discussed the danger in the transporting of the liquid grease from the New York City plants through the streets and stated that his department was recommending the processing of the grease at the various sewage plants. This subject of grease was further discussed by Mr. Van Kleeck, Major West, Dr. Gehm and Professor Fair.

This symposium on grease removal turned out to be a most interesting affair and it was regretted that Mr. Cohn of Schenectady was unable to be there to participate.

The final paper of the technical session was entitled, "The Determination of Grease in Sewage," prepared jointly by W. D. Hatfield, Superintendent Sanitary District of Decatur, Illinois, and George E. Symons, Associate Editor, *Water Works and Sewerage*, New York, New York, and was given by Dr. Symons. In giving this paper, Dr. Symons stated that it was more of a report of the committee's work in selecting a standard method for grease determination to be included in the ninth edition of Standard Methods. He stated that the comparative data of the several tests did not yield results which would make a definite selection of one method unquestionable but the committee was obligated to choose one method which they did, namely, the Hurwitz-Ludwig of grease determination.

There was considerable discussion on this paper because present in the audience were Major Eliassen, Mr. Schulhoff and Dr. Gehm, all three of them having done considerable work on this problem.

The technical session was adjourned at 4:40 P.M.

On Friday evening the members of the NYSSWA and the ASCE enjoyed the usual annual banquet and were greeted by Malcolm Pirnie, President-Elect of the American Society of Civil Engineers. Since the

noon luncheon meeting of the NYSSWA was not held this year, the presentations of the NYSSWA awards were made at the banquet.

The Kenneth Allen Memorial Award, for the most meritorious paper of an engineering or research nature, was awarded jointly to Major Eliassen and H. B. Schulhoff for their work on determination of grease in sewage which was set forth in a paper, "Grease Extraction from Sewage and Sludge." The award was made by George E. Symons, a member of the Kenneth Allen Award Committee and Vice-president of the NYSSWA, and the acceptance was made by Major Eliassen, who introduced Mr. Schulhoff.

Edward J. Smith, the retiring President, was presented with the gold key bearing the emblem of the Association by Mr. William H. Larkin, President-Elect.

The guest speaker of the evening was Edward J. Cleary, Managing Editor, *Engineering News Record*, New York, New York, who spoke on "Wartime Engineering in South America." This was an exceedingly interesting discussion and was illustrated by numerous slides. In his paper, Mr. Cleary praised the work of the engineers from the United States who are now in South America, particularly those engaged in sanitary work. He pointed out that the problem of sanitation in South America is entirely different from the problem in this country and that much simpler methods of sewage disposal are employed. He also mentioned the problem of construction in South America where much of the work is still done by hand labor, which required that engineers from this country make considerable adjustments in their mode of thinking in order to successfully work in South America.

William J. Orchard as a master of ceremonies very graciously introduced the various speakers and provided some very enjoyable entertainment in the typical "Bill" Orchard manner.

As was the case last year, the Saturday inspection trip was not undertaken because of transportation difficulties.

The next meeting of the association will be held in Syracuse at the Hotel Syracuse on June 16 and 17, 1944.

A. W. EUSTANCE, *Assistant Secretary*

MEMBER ASSOCIATION MEETINGS

Association	*Place*	*Date*
Michigan Sewage Works Association	Michigan State College, East Lansing	Apr. 5–6
Pacific Northwest Sewage Works Association	Olympia, Washington	May 11
Florida Sewage Works Association	Daytona Beach, Fla.	May 17–19
Maryland-Delaware Water & Sewage Association	Lord Baltimore Hotel, Baltimore, Md.	May 19–20
Central States Sewage Works Association	Oshkosh, Wis.	June 20–22
California Sewage Works Association	Fresno	June 22–25
Iowa Wastes Disposal Association		June
Federation of Sewage Works Associations	Wm. Penn Hotel, Pittsburgh, Pa.	Oct. 12–14
Pennsylvania Sewage Works Association	Wm. Penn Hotel, Pittsburgh, Pa.	Oct. 12–14

Federation Affairs

MILLING AND DE MARTINI WIN 1943 MEMBERSHIP PRIZES

For sterling service in the enrollment of new members in their respective Member Associations during 1943, Martin A. Milling (Central States Sewage Works Association) and Frank E. De Martini (Federal Sewage Research Association) have each been awarded a $25.00 denomination, Series E, War Bond as joint winners of the Federation's 1943 membership contest. Rules of the contest, which closed on December 31, 1943 (see *this Journal*, May, 1943, page 532), provided that duplicate prizes were to be awarded in case of a tie. Messrs. Milling and De Martini each secured 35 new members during the year.

Mr. Milling's efforts were in large measure responsible for the advance of the Central States Association into first place as the largest Member Association in the Federation in 1943. He, together with several other workers under the leadership of Secretary John C. Mackin, boosted that organization from a total of 426 members in 1942 to 510 in 1943, a gain of 84 for the year.

Mr. De Martini's accomplishment is remarkable in that he almost singlehandedly increased the membership of the Federal Sewage Research Association from 48 members in 1942 to 88 members in 1943, a gain of 82 per cent. As Secretary-Treasurer of his Association, he is to be further commended for the fact that only one of the 48 members in 1942 failed to renew for last year.

Honorable mention to other contestants goes to J. M. Schirk of the Rocky Mountain Sewage Works Association and A. W. Eustance of the New York State Sewage Works Association.

FIFTH ANNUAL MEETING TO BE HELD AT PITTSBURGH

Preliminary arrangements for the Fifth Annual Meeting of the Federation to be held at the Hotel William Penn, Pittsburgh, Pa., on October 12–14, 1944, were recently completed by the Hotel Arrangements Committee, comprising F. S. Friel, Arthur T. Clark and W. H. Wisely. Precautions have been taken to preclude any conflict with other conventions such as occurred at Chicago in 1943.

The Pennsylvania Sewage Works Association will be host to the Federation. Mr. L. S. Morgan, District Engineer of the Pennsylvania State Department of Health, stationed at Greensburg, Pa., has accepted appointment as Chairman of the General Arrangements Committee.

WANTED—SEWAGE WORKS ACCIDENT REPORTS

The Sewage Works Practice Committee, under chairmanship of Morris M. Cohn, has appointed a sub-committee to prepare a Chapter on "Occupational Health Hazards in the Operation of Sewerage Systems," for the Manual of Practice now under preparation.

This committee is very desirous of obtaining information on serious accidents in sewers, in sewage pumping stations and in sewage treatment plants occurring in recent years, especially those which resulted in the death or permanent disability of workers or which resulted in a fire or explosion.

Will any member of the Federation having information on such accidents send at once the name of the community, the nature of the accident, the approximate date of the mishap, and its cause, if known, to the committee's chairman: LeRoy W. Van Kleeck, Senior Sanitary Engineer, Connecticut State Department of Health, State Office Building, Hartford, Connecticut.

Reviews and Abstracts

H. Gladys Swope

T.N.T. WASTE

By Stuart Schott, C. C. Ruchhoft, and Stephen Megregian

Industrial and Engineering Chemistry, 35, 1122–1127 (Oct., 1943)

Liquid waste from the manufacture of T.N.T. is made up of the acid waste from the washing processes, sellite waste from the sulfite treatment and washing and cooling water. The table shows analysis of waste from three sources:

Plant	Color P.P.M.	Odor Conc.	pH	Parts Per Million									
				Acidity Methyl Red	Nitrogen			SO_4	Solids				Oxygen Cons.
					NH_3	NO_2	NO_3		Total		Susp.		
									Vol.	Ash	Vol.	Ash	
A	7,100	70	2.4	291	5.3	15	107	672	1,004	1,273	22	144	795
B	6,300	16	2.7	134	—	20	—	604	868	1,123	14	15	551
C*	34,000	11	1.2	3,230	2.8	62	310	2,923	5,490	4,685	17	0	1,057

* No cooling water included.

The analyses indicate that the mixed composite waste has a low pH and is relatively high in total solids, sulfates and oxygen consumed (acid dichromate method). Red water (sellite waste) has a pH of 8.0 or higher, no odor, and is 3 to 6 times as concentrated in total solids, oxygen consumed, nitrites and nitrates. The color of the red water waste ranges from 100,000 to 300,000; that of the mixed composite waste ranges from 7,000 to 35,000.

Treatment Processes

Biological Treatment.—Biochemical oxygen demand measurements to determine the extent to which these wastes can be purified in a stream or in a biological treatment plant resulted in no oxygen depletions during the 5-day, 20° C. test in concentrations up to 8 per cent of waste. In concentrations of 10 per cent the depletion obtained in 5 days was less than that of the control. These observations indicate that 10 per cent or more of the waste interferred with normal biochemical reaction. Furthermore, long-time studies (129 days) indicated that the salts of the nitrotoluene sulfonic acids in these wastes cannot be oxidized biochemically and that therefore self-purification of such wastes cannot be expected following discharge into a stream.

Effect of Waste on Activated Sludge Purification.—Tests to show the effect of these wastes on the activated sludge process indicated that they interferred definitely in sewage-waste mixtures containing 5 per cent or more of T.N.T. waste. The data collected showed a decrease in solids content of the sludge, a reduction in B.O.D. removal efficiency and loss of nitrification qualities of the sludge.

Effect of Waste on Trickling Filters.—Trickling filters were capable of handling up to 10 per cent of T.N.T. waste without appreciable loss in efficiency. When dosed with sewage containing 25 per cent waste, there was a marked decrease in B.O.D. removal.

In neither the trickling filter nor the activated sludge process was the color of the waste reduced appreciably.

Chemical Treatment.—Dosage with copperas, lime and caustic soda in amounts as high as 58 grains per gallon failed to show any satisfactory reductions of oxygen consumed, or color. Activated carbon up to 2,000 p.p.m. produced no reduction in oxygen consumed values. Ozonation for color removal failed to produce any significant effect. Distillation experiments indicated that a large percentage of the oxygen consuming organic matter remains in the residue regardless of the pH to which the waste is adjusted.

Reduction of Nitro Compounds

Reduction of nitro compounds to amino sulfonic acids with acid and zinc, followed by biological treatment, indicated that the compounds formed by reduction were no more amenable to biological attack than the original material. Also chemical treatment of the reduced material showed no improvement over treatment of the original material with chemicals.

Electrolytic reduction for 24 hours did effect a 50 per cent removal of color and suggested possibility of greater removal with prolonged electrolysis.

Color Removal

Attempts to extract the color from T.N.T. wastes with organic solvents were unsatisfactory in both acid and alkaline solution. Amyl and butyl alcohols extracted some color from the acid wastes but not from the red water.

Large doses of activated carbon (5 to 10 grams per liter) when boiled for 15 minutes with red water effected a satisfactory removal of color. The dose and treatment however are impractical. In doses of 10 grains per gallon, activated carbon was effective in removing the color from the combined waste diluted to 0.5 per cent. Suspensions of the carbon and waste were mechanically stirred for 15 minutes and filtered.

Chlorination or bromination of wastes offers the only satisfactory and economical means of color reduction. Extinction values obtained by spectrophotometric method showed definite decrease between treated and untreated dilutions. Chlorine was added in amounts up to 18 p.p.m.

Tastes

Cincinnati water containing as much as 1,000 p.p.m. of combined T.N.T. waste tasted no different than tap water. Water containing 1,000 p.p.m. of waste and 1 p.p.m. of chlorine showed a definite enhancement of taste.

E. Hurwitz

GLUTAMIC ACID CONTENT OF STEFFEN'S WASTE

By David O'Day and Edward Bartow

Industrial and Engineering Chemistry, 35, 1153 (Nov., 1943)

Studies to determine the variations in the glutamic acid content of Steffen's waste and the reasons for these variations yielded no definite results but indicated that variations may be due to geographical locations and seasonal changes in temperature which effect the quality of the beet crop and to slight operational difficulties in the beet sugar refineries.

Steffen's waste from 22 sources in California, Colorado, Wyoming, Idaho, Iowa, Michigan, Montana, Nebraska, Ohio and Utah were analyzed. Yields of glutamic acid varied from 1.21 per cent to 6.13 per cent (1938 campaign) with the highest yields from factories in the midwestern states and California.

The method of recovery of glutamic acid from Steffen's waste was improved over that suggested by Benninghoff and Redmanbby using an extraction process to remove glutamic acid hydrochloride from the crude inorganic salts without the excessive use of water.

Steffen's waste is the waste water formed by the precipitation of tricalcium saccharate and the decomposition of this precipitate to sugar in the process of manufacturing sugar from beets. It contains several organic compounds extracted from the beets and some inorganic material originating both from the beets and from the manufacturing process. The amount of valuable constituents is low and this is recoverable only after the removal of large volumes of water.

E. HURWITZ

DISPOSAL OF CITRUS WASTES

By Howard W. Hall

Civil Engineering, **14**, 15–17 (Jan., 1944)

The production of citrus fruits has increased materially during the past twenty years, resulting in greater quantities available for processing. During the past ten years large plants for processing have been built. It is estimated that more than 800,000 tons of fruit are processed each year at the present time. The processing results in over 400,000 tons of waste products plus the water used in their disposal.

In canning, the waste products amount to approximately 60 per cent of the total weight of fruit. A typical analysis of citrus peel is shown in the following table.

Analysis of Waste Citrus Peel, Dry Basis

Material	Crude Protein	Crude Fiber	Ether Extract	Nitrogen Free Extract	Ash
	Per Cent				
Grapefruit-canning waste	5.3	13.0	1.2	75.9	4.6
Lemon residue	9.87	16.7	0	68.5	4.9
Orange residue	5.8	10.0	2.4	77.7	4.0

In recent years some of the larger canneries have installed facilities for drying citrus peel and converting it into stock feed. Others have discharged the liquid and solid wastes to large storage beds. Here the liquid portion was allowed to evaporate or seep away, and the residue material was removed for use as fertilizer when partially dry.

Cannery wastes disposal is discussed in a bulletin of the Department of Agriculture, Bureau of Agricultural Chemistry and Engineering, "Experimental Treatment of Citrus-Cannery Effluent in Florida," subtitle, "Food Research Unit Contribution No. 513." Five methods are discussed, as follows: (1) Emptying into lakes, (2) handling by city sewerage systems, (3) primary settling tanks, (4) flooding on waste lands, and (5) disposal in tidewater rivers. It is pointed out that when handled by city sewerage systems, such wastes have caused damage to pumps and piping, foaming in Imhoff tanks, and clogging of sand beds. Most municipalities are reluctant to handle these wastes. It was noted in the use of primary settling tanks that the material showed little tendency to flocculate and settle. Addition of chemicals to help flocculation was not helpful. No significant improvement in the 5-day B.O.D. value is shown by filtering the wastes.

In the manufacture of chemicals there are end liquors that must be disposed of, in addition to the peel and fiber. As with canning wastes, drying of the material for use

as stock feed has reduced quantities for disposal. The following table shows a typical analysis of liquid effluent from a chemical manufacturing plant.

Analysis of Liquid Effluent from Plants Manufacturing Chemicals from Citrus Fruits

	Per Cent of Total Solids	P.p.m.
Total solids	100.00	18,918
Total solids ash	18.85	3,566
Dissolved solids	81.74	15,464
Dissolved solids ash	16.33	3,090
Suspended solids	18.26	3,454
Suspended solids ash	2.52	476
Total nitrogen	1.48	280
Crude protein (N × 6.25)	9.26	1,750
Nitrogen free extract	60.90	11,522
Pectin (dispersed in filtered portion)	10.68	2,020
Crude fiber	10.98	2,077
Oxygen consuming		4,800

A typical method of disposal consists of screening all wastes through rotating screens (0.050-inch mesh) and depositing the screened solids in storage tanks where they are allowed to disintegrate. Liquid resulting from the disintegration process is pumped to settling beds along with the screened effluent. The beds, large natural sand and gravel filters, are filled to a depth of about 2.5 feet. When the water has seeped away and deposited solids, largely cellulose, have dried they are raked off and burned.

T. L. Herrick

SLUDGE DISPOSAL AT HORSHAM

By P. S. Browne

The Surveyor, 102, xii (Oct. 1, 1943)

The article describes the operation of a Porteous sludge disposal plant at Horsham. (For description of the plant see *The Surveyor*, June 3, 1938.) The plant has a capacity to treat 6,000 gallons per day of raw sludge.

Treatment consists of heating the sludge, which has previously been disintegrated by a mechanical device known as a Hathorn Davey disintegrator, to a temperature of 360° F. for half an hour, decanting the supernatant and pressing the residue without the aid of chemicals in sludge presses. The resultant sludge is stated to contain about 40 per cent moisture.

Raw sludge is pumped to an overhead supply tank, being disintegrated on the way to the tank. A second pump takes sludge from the supply tank and forces it through a heat exchanger into sludge heaters. The raw sludge passes through the outer tube of the exchanger; the inner tube of the exchanger contains sludge from the sludge heaters. Heat from the heated sludge is thus transferred to the raw sludge. The process of exchange preheats the raw sludge to 310° F. and cools the heated sludge to 150° F.

There are three sludge heaters, each designed to treat 250 gallons per batch, and each heated by a steam jet. As one heater is being filled, another is being emptied through the heat exchanger, and the third is being heated. The heated sludge is forced through the exchanger by the steam pressure in the heater.

The filter press cake is further air dried and then used as fuel in the boiler along with coke.

K. V. Hill

FROM WATER LIQUORS TO WAR ALCOHOL

By John R. Callaham

Chemical and Metallurgical Engineering, 50, 104–107 (December, 1943)

The first successful plant in North America to produce alcohol from waste sulfite liquor is located at Thorold, Ontario, Canada, and is operated by the Ontario Paper Company. The plant was originally designed for an annual output of 600,000 U. S. gallons of 190 proof alcohol but process improvements have increased this to 800,000 gallons. This is enough alcohol to produce two million pounds of Buna S rubber.

The process involves the following steps: (1) waste sulfite liquor from the pump mill is cooled, aerated for SO_2 removal and neutralized with lime to a degree suitable for subsequent fermentation (pH = 6.5); (2) lime sludge is separated and the liquor is pumped to the fermentation tanks where yeast and a trace of nutritive salts are added; (3) the fermented liquor is run through centrifugal separators which remove the yeast; and (4) the clarified liquid contains about 1 per cent alcohol which is recovered by fractional distillation.

The yeast recovered from the separators is re-used in the next fermentation cycle.

Projected manufacturing costs for alcohol production employing this process indicate an approximate direct cost 12.4¢ per gallon for plants of average size.

There are three photographs of the alcohol plant and one flow sheet.

Paul D. Haney

PREDICTING FLOW-FRICTION DATA FOR SLUDGES

By Joseph D. Parent

Chemical and Metallurgical Engineering, 51, 101–103 (January, 1944)

Two methods of correlating plastic flow data are presented. One method involves the use of tabulated data or graphs showing the relationship between velocity of flow and apparent viscosity for both streamline and turbulent flow. For each range the viscosity may be expressed as a function of velocity and simple equations derived for both types of flow. The usefulness of this method is limited by the fact that it is necessary to have viscosity and velocity data before friction losses may be computed and by other factors. Hatfield has reported viscosity data on sewage sludges in the Sewage Works Journal, **10**, pp. 3 and 272 (1938).

A second method of attack leads to a complex equation for evaluating friction loss which, however, can be solved graphically. This equation is limited to the laminar flow range. For the turbulent range the author recommends the use of the method described by Babbitt and Caldwell in *Bulletin* 323, Illinois University Engineering Exp. Station or "The Flow of Muds, Sludges, and Suspensions in Circular Pipe," *Trans.* Am. Inst. Chem. Engrs., **37**, 237 (1939).

Paul D. Haney

REFERENCES TO SEWAGE LITERATURE

July–December, 1943

American City. Volume 58.

July, 1943 (No. 7).

"Outgrowing an Activated Sludge Plant" (Lawton, Okla.). Wyatt B. Hendrick, pp. 44–45.

"So You Don't Think It Pays" (Winnemucca, Nevada, Sewage Plant). Henry P. Berk, pp. 56–57.

August, 1943. (No. 8).

"Pryor, Oklahoma, Meets a Sewerage Emergency." Rex Collins, pp. 56–58.

September, 1943 (No. 9).

"Sewerage in San Diego for National Defense." Harold Keen, pp. 56–58.

October, 1943 (No. 10).

"About High Rate Filters." Henry W. Taylor, p. 79.

"What Elutriation of Sewage Sludge Can Do." C. G. Weber, pp. 91–93.

November, 1943 (No. 11).

"Army and City Collaborate" (Walla Walla, Wash.). Emil C. Jensen, pp. 42–43.

"How New York City Utilizes Sewage Scum." Nathan I. Kass, pp. 56–57.

December, 1943 (No. 12).

"Can Sewage Pumps Be Trusted?" Russell Riker, pp. 43–44.

Engineering News-Record. Volume 131.

July 15, 1943 (No. 3).

"Sewage Plant Operation Taught with a Model." pp. 146–48.

October 7, 1943 (No. 15).

"Treatment Plant Built of Local Materials" (El Salvador). A. N. Carter, pp. 529–30.

"Sewage Disposal Post War Prospects." pp. 544–45.

"Sewer Charts Based on Scobey's Formula." Paul E. Whittington, pp. 548–50.

"Sewage Disposal in South America." Edward J. Cleary, pp. 551–52.

November 4, 1943 (No. 19).

"War Sanitation Problems in Massachusetts." p. 675.

December 16, 1943 (No. 25).

"City Upheld by Courts in Refusal to Handle Industrial Wastes." p. 901.

Public Works. Volume 74.

July, 1943 (No. 7).

"Solving Boom Town San Diego's Sewage Problem." B. D. Phelps, pp. 14–19.

"Lubrication of Machinery in Water and Sewage Treatment Plants." pp. 22–23.

"The Sewerage Digest." pp. 40–43.

August, 1943 (No. 8).

"Treatment of Supernatant Digester Liquor." Willem Rudolfs and L. L. Faulk, pp. 13–15.

"Screening, the Solution of a Troublesome Trade Waste Problem." Arthur L. Boley, pp. 20–21.

"The Sewerage Digest." pp. 46–48.

September, 1943 (No. 9).

"Englewood's (N. J.) Sewage Pumping Station." Russell Hartley, pp. 11–13.

"Two-Step Lime Addition for Sewage Coagulation and pH Control." Willem Rudolfs and G. B. Nickol, pp. 30–32.

"The Sewerage Digest." pp. 50–54.

October, 1943 (No. 10).

"Landscaping Sewage Treatment Plants and Sewers." Russell Riker, pp. 17–18.

"The Sewerage Digest." p. 57.

November, 1943 (No. 11).

"Treatment of Cherry Waste Waters." C. H. Young, pp. 25–26.

"The Sewerage Digest." pp. 36–40.

December, 1943 (No. 12).

"Operating Results of the Minneapolis-St. Paul Sewage Treatment Plant." pp. 13–15.

"Recovery of Grease from Sewage." pp. 21–22.

"The Sewerage Digest." pp. 39–42.

Sewage Works Engineering. Volume 14.

July, 1943 (No. 7).

"Rendering of Sewage Grease at Civilian and Army Plants." C. P. Gunson, pp. 329–30.

"Effect of War and Post-War on Sewage Treatment." Part IV. V. M. Ehlers, p. 332.

"Sewage Treatment Plants in U. S. A." pp. 335–36.

August, 1943 (No. 8).

"Pickle Liquors Fail to Upset Activated Sludge Operation." pp. 364–66.

"Validity of Sanitation Laws." Leo T. Parker, pp. 370–72.

"Effect of War and Post-War on Sewage Treatment." Part V. Clarence W. Klassen, pp. 372–75.

"Oregon Urges Cities to Finance Post-War Work." Kenneth H. Spies, pp. 374–75.

"Sewage Treatment Plants in U. S. A." pp. 381–82.

September, 1943 (No. 9).

"50,000 Hours of Gas Engine Service." William H. Gottlieb, pp. 412–14.

"Fish Ladder Aerator Improves Supernatant Liquor." Bernard Rowntree, pp. 415–16.

"Hints on Care and Operation of Small Treatment Plants." pp. 417–18.

"Validity of Sewer Laws." Leo T. Parker, pp. 422–23.

"Sewage Treatment Plants in U. S. A." pp. 427–28.

October, 1943 (No. 10).

"Equipment Maintenance in Time of War." Morris M. Cohn, pp. 469–78.

"Gas Engineer Operation at Aurora, Illinois." Walter A. Sperry, pp. 479–81.

"Modern Litigations Simplified." Leo T. Parker, pp. 482–85.

"Sewage Treatment Plants in U. S. A." pp. 489–90.

November, 1943 (No. 11).

"Dual Disposal at Two Midwestern Cities." S. L. Tolman, pp. 529–33.

"Equipment Maintenance in Time of War." Morris M. Cohn, pp. 534–39.

"Electrolysis and Corrosion Damage Digester Heating Coils." V. R. Schick, p. 540.

"Blasting Damages from Sewer Construction." Leo T. Parker, pp. 541–42.

December, 1943 (No. 12).

"Sewage Treatment Plants in U. S. A." pp. 545–46.

"Effluent Used for Chlorinator." L. B. Barnes, pp. 578–79.

"Plant Manual Explains pH in Theory and Practice." p. 579.

"Validity of Legal Procedure." Leo T. Parker, pp. 583–84.

"Equipment Maintenance in Time of War." Morris M. Cohn, pp. 585–90.

"Sewage Treatment Plants in U. S. A." pp. 591–92.

Water Works and Sewerage. Volume 90.

July, 1943 (No. 7).

"Enlargement of Disposal Plant of Spartanburg, S. C." George W. White, pp. 241–45.

"Control of Micro-Organisms and Aquatic Vegetation." L. F. Warrick, H. E. Wirth and W. Van Horn, pp. 267–72.

"How's Your Supernatant?" E. Arthur Bell, p. 281.

August, 1943 (*No. 8*).

"A Rapid Method for Determining Grease in Sewage and Sludges." Harry W. Gehm, pp. 305–8.

"The Mathematics of B.O.D. Determinations." H. M. Gifft, pp. 313–16.

September, 1943 (*No. 9*).

"The Use of Liquid Chlorine in the Treatment of Water and Sewage." E. Sherman Chase, pp. 345–46.

"The Application of Ferric Salts in Water and Sewage Treatment." Francis K. Burr, pp. 347–51.

October, 1943 (*No. 10*).

"Ventilation Features of the Minneapolis-St. Paul Sewage Treatment Plant." George J. Schroepfer, pp. 353–58.

"The Cokato Sewage Disposal Plant." W. E. King, pp. 359–65.

"A Revenue Plan for Sewage Works Financing." John A. Goetz, pp. 366–68.

"Disposal of Sludge in Small Plants." G. A. Parkes, pp. 384–85.

"An Easier Method For Determining Suspended Solids." Alice L. Mathis, pp. 386–87.

November, 1943 (*No. 11*).

"Laundry Waste Treatment by Flotation." Rolf Eliassen and Henry B. Schulhoff, pp. 418–21.

"Through These Portals Passed the World's Most Beautiful Sewage." Jack Kreismer, pp. 422–23.

December, 1943 (*No. 12*).

"Recirculating Filters for Treatment of Slaughterhouse Wastes." E. F. Eldridge, pp. 449–51.

"The Little Rock Sanitary Sewer System." T. W. Clapham, pp. 459–62.

Federation of Sewage Works Associations

1943–44 OFFICERS OF MEMBER ASSOCIATIONS

Arizona Sewage and Water Works Association

President: H. H. Idle, Globe
First Vice-President: E. S. Borquist, Tucson
Second Vice-President: Geo. W. Marx, Phoenix
Secretary-Treasurer: Richard Bennett, Phoenix
Director, Board of Control: P. J. Martin, Tucson

California Sewage Works Association

President: Richard D. Pomeroy, Pasadena
First Vice-President: Frank S. Currie, San Bernardino
Second Vice-President: Keeno Fraschina, San Francisco
Secretary-Treasurer: J. A. Harmon, Los Angeles
Director, Board of Control: William A. Allen, Pasadena

Central States Sewage Works Association

President: Don E. Bloodgood, West LaFayette, Indiana
First Vice-President: Dr. W. D. Hatfield, Decatur, Illinois
Second Vice-President: Capt. E. J. Beatty, U. S. Army
Third Vice-President: P. W. Riedesel, Minneapolis, Minnesota
Secretary-Treasurer: J. C. Mackin, Madison, Wisconsin
Director, Board of Control: Major B. A. Poole, Chicago, Illinois

Dakota Water and Sewage Works Conference

North Dakota Section

President: Dave MacDonald, Bismarck
Vice-President: F. W. Pinney, Fargo
Secretary-Treasurer: K. C. Lauster, Bismarck
Director, Board of Control: K. C. Lauster, Bismarck

South Dakota Section

President: C. A. Polley, Lead, South Dakota
Vice-President: M. J. Hoy, Watertown, South Dakota
Secretary-Treasurer: Glen J. Hopkins, Pierre, South Dakota
Director, Board of Control: K. C. Lauster, Bismarck, North Dakota

Federal Sewage Research Association

President: A. W. Fuchs, Washington, D. C.
Vice-President: Ralph E. Fuhrman, Blue Plains, D. C.
Secretary-Treasurer: F. E. DeMartini, Washington, D. C.
Director, Board of Control: J. K. Hoskins, Washington, D. C.

Florida Sewage Works Association

President: Chas. E. Fiveash, Fort Lauderdale
Vice-President: J. B. Miller, Jacksonville
Secretary-Treasurer: J. R. Hoy, Jacksonville
Director, Board of Control: Joe Williamson, Jr., Jacksonville

Georgia Water and Sewage Association

President: T. A. Jones, Fort Valley
First Vice-President: H. Grady Wylds, Augusta
Second Vice-President: W. G. Bryant, Griffin
Secretary-Treasurer: Van P. Enloe, Atlanta
Director, Board of Control: Van P. Enloe, Atlanta

Iowa Wastes Disposal Association

President: T. R. Lovell, Marshalltown
Vice-President: Paul Winfrey, Des Moines
Secretary-Treasurer: Lindon J. Murphy, Ames
Director, Board of Control: A. H. Wieters, Des Moines

Kansas Water and Sewage Works Association

President: W. O. Myers, Ottawa
First Vice-President: J. P. Morris, Council Grove
Second Vice-President: V. E. Hoagland, Beloit
Third Vice-President: H. H. Kansteiner, Leavenworth
Fourth Vice-President: Wesley Cochran, Winfield
Secretary-Treasurer: Paul D. Haney, Lawrence
Director, Board of Control: Paul D. Haney, Lawrence

The Maryland-Delaware Water and Sewage Association

President: R. V. Stewart, Edgewood, Maryland
First Vice-President: E. C. Cromwell, Colgate, Maryland
Second Vice-President: John W. Alden, Wilmington, Delaware
Secretary-Treasurer: Miss E. V. Gipe, Baltimore, Maryland
Director, Board of Control: A. L. Genter, Baltimore, Maryland

Michigan Sewage Works Association

President: C. P. Witcher, Ann Arbor
Vice-President: H. M. Leonhard, Trenton
Secretary-Treasurer: R. J. Smith, East Lansing
Director, Board of Control: E. F. Eldridge, East Lansing

Missouri Water and Sewerage Conference

President: Roger Higgins, Hannibal
Vice-President: John Sanders, Boonville
Secretary-Treasurer: Warren Kramer, Jefferson City
Director, Board of Control: William Q. Kehr, Jefferson City

New England Sewage Works Association

President: Joseph A. Muldoon, Bridgeport, Conn.
First Vice-President: Frank L. Flood, Boston, Mass.
Second Vice-President: George H. Craemer, Hartford, Conn.
Secretary-Treasurer: LeRoy W. Van Kleeck, Hartford, Conn.
Director, Board of Control: J. H. Brooks, Jr., Worcester, Mass.

New Jersey Sewage Conference

Chairman: H. Van Der Vleit, Maywood
Vice-President: John Collom, Bordentown

Second Vice-President: L. J. Fontenelli, Rashway
Secretary: J. R. Downes, Plainfield
Treasurer: Edward P. Molitor, Chatham
Director, Board of Control: Edward P. Molitor, Chatham

New York State Sewage Works Association

President: W. H. Larkin, New York City
Vice-President: G. E. Symons, New York City
Secretary-Treasurer: A. S. Bedell, Albany
Assistant Treasurer: J. C. Brigham, Albany
Assistant Secretary: A. W. Eustance, Geneva
Director, Board of Control: C. G. Andersen, Rockville Centre

North Carolina Sewage Works Association

Chairman: J. R. Purser, Jr., Charlotte
Vice-Chairman: E. M. Johnson, Raleigh
Secretary-Treasurer: R. S. Phillips, Durham
Director, Board of Control: W. M. Franklin, Charlotte

Ohio Sewage Works Conference Group

Chairman: R. F. Snyder, Massillon
Vice-Chairman: J. R. Turner, Mansfield
Secretary-Treasurer: D. D. Heffelfinger, Alliance
Director, Board of Control: C. D. McGuire, Columbus

Oklahoma Water and Sewage Conference

President: L. H. Scott, Oklahoma City
Vice-President: H. M. Frye, Pryor
Secretary-Treasurer: H. J. Darcey, Oklahoma City
Director, Board of Control: M. B. Cunningham, Oklahoma City

Pacific Northwest Sewage Works Association

President: M. S. Campbell, Seattle, Washington
First Vice-President: C. V. Signor, Grants Pass, Oregon
Second Vice-President: C. M. Howard, Seattle, Washington
Secretary-Treasurer: W. P. Hughes, Lewiston, Idaho
Director, Board of Control: C. D. Forsbeck, Tacoma, Washington

Pennsylvania Sewage Works Association

President: T. S. Bogardus, Berea, Ohio
First Vice-President: L. D. Matter, Harrisburg, Pennsylvania
Second Vice-President: Wm. J. Murdock, Pittsburgh, Pennsylvania
Secretary-Treasurer: B. S. Bush, Wilkes-Barre, Pennsylvania
Director, Board of Control: F. S. Friel, Philadelphia, Pennsylvania

Rocky Mountain Sewage Works Association

President: Frank C. Hill, Montrose
Vice-President: Dana E. Kepner, Denver
Secretary-Treasurer: Carroll H. Coberly, Denver
Director, Board of Control: Dana E. Kepner, Denver

Texas Sewage Works Section

Chairman: E. J. M. Berg, San Antonio
Vice-Chairman: Capt. R. M. Dixon, Dallas
Secretary-Treasurer: V. M. Ehlers, Austin
Assistant Secretary and Treasurer: Mrs. Earl H. Goodwin, Austin
Director, Board of Control: W. S. Mahlie, Fort Worth

The Canadian Institute on Sewage and Sanitation

President: R. H. Parsons, Peterborough
Vice-President: R. J. Desmarais, Windsor
Secretary-Treasurer: A. E. Berry, Toronto
Director, Board of Control: Stanley Shupe, Kitchener

The Institute of Sewage Purification (England)

President: William T. Lockett, Hampton-on-Thames
Secretary-Treasurer: W. F. Freeborn, Hampton-on-Thames
Director, Board of Control: W. F. Freeborn, Hampton-on-Thames

The Institution of Sanitary Engineers (England)

President: Guy Howard Humphreys
Vice-President: C. B. Townend
Acting Secretary: E. M. Kerry, Westminster
Treasurer: J. W. Hammond
Director, Board of Control: D. M. Watson, Gerrards Cross, Bucks.

FEDERATION OF SEWAGE WORKS ASSOCIATIONS

SECRETARIES OF MEMBER ASSOCIATIONS

Any individual desiring to affiliate with the Federation as an Active Member, may do so by joining one of the Member Associations listed below. Write to the Secretary for particulars.

Association	*Secretary*	*Address*
Arizona Sewage and Water Works Association	Richard Bennett	City Water Dept., Phoenix, Arizona
California Sewage Works Association	J. A. Harmon	703 California State Bldg., Los Angeles 12, Calif.
Central States Sewage Works Association	John C. Mackin	c/o Nine Springs Sewage Treatment Plant, Route No. 4, Madison 5, Wisconsin
Dakota Water and Sewage Works Conference		
(North Dakota Section)	K. C. Lauster	c/o State Dept. of Health, Bismarck, South Dakota
(South Dakota Section)	Glen J. Hopkins	Div. of San. Engr., State Bd. of Health, Pierre, South Dakota
Federal Sewage Research Association	Frank E. DeMartini	U. S. P. H. S., 2000 Mass. Ave., N.W., Washington, D. C.
Florida Sewage Works Association	J. R. Hoy	404 Hildebrandt Bldg., Jacksonville, Fla.
Georgia Water and Sewage Association	V. P. Enloe	R. F. D. No. 5, Box 363, Atlanta, Ga.
Iowa Wastes Disposal Association	L. J. Murphy	Iowa State College, Ames, Iowa
Kansas Water and Sewage Works Association	Paul D. Haney	Room 2, Marvin Hall, University of Kansas, Lawrence, Kansas
Maryland-Delaware Water and Sewerage Association	Miss E. V. Gipe	State Dept. of Health, 2411 N. Charles St., Baltimore, Md.
Michigan Sewage Works Association	R. J. Smith	Michigan Dept. of Health, State Office Bldg., Lansing, Michigan
Missouri Water and Sewerage Conference	Warren Kramer	State Board of Health, 200 Monroe St., Jefferson City, Mo.
New England Sewage Works Association	LeRoy W. Van Kleeck	State Dept. of Health, State Office Bldg., Hartford, Conn.
New Jersey Sewage Conference	John R. Downes	P.O. Box 11, Dunellen, N. J.
New York State Sewage Works Association	A. S. Bedell	c/o State Dept. of Health, Albany, N. Y.
North Carolina Sewage Works Association	D. M. Williams	P.O. Box 1170, Durham, N. C.
Ohio Sewage Works Conference Group	D. D. Heffelfinger	1101 E. Walnut, Alliance, Ohio
Oklahoma Water and Sewage Conference	H. J. Darcey	State Dept. of Health, Oklahoma City, Okla.
Pacific Northwest Sewage Works Association	W. P. Hughes	City Engineer, Lewiston, Idaho
Pennsylvania Sewage Works Association	B. S. Bush	Pa. Dept. of Health, Kirby Health Center, Wilkes-Barre, Pa.
Rocky Mountain Sewage Works Association	Carroll N. Coberly	1441 Welton St., Denver, Colo.
Sewage Division—Texas Section, S. W. W. A.	V. M. Ehlers	State Dept. of Health, Austin 2, Texas
The Canadian Institute on Sewage and Sanitation	A. E. Berry	Sanitary Engr. Division, Ontario Dept. of Health, Toronto, Ontario, Canada
Sanitary Engineering Division of Argentine Society of Engineers	Carlos Santos Rossell	Centro Argentino de Ingenieros, Cerrito, 1250, Buenos Aires, South America
The Institute of Sewage Purification—England	J. H. Garner	28 Aberford Road, Wakefield, Yorks, England
The Institution of Sanitary Engineers—England	Mrs. E. M. Kerry	118 Victoria St., Westminster, S.W. 1, London, England

Directory of Members

Federation of Sewage Works Associations
December 31, 1943

HONORARY MEMBERS

Bedell, Arthur S. (1942), Div. of Sanitation, State Dept. of Health, Albany, N. Y.

Bugbee, Julius W. (1942), Supt., Sew. Disp. Wks., 25 New York Ave., Providence, R. I.

Emerson, Charles A. (1941), Havens & Emerson, Woolworth Bldg., New York, N. Y.

Hyde, Charles Gilman, Prof. (1943), Rm. 11, Engr. Bldg., Univ. of Calif., Berkeley, Calif.

Moses, H. E. (1943), 1522 N. Second St., Harrisburg, Pa.

Pearse, Langdon (1942), Chicago San. Dist., 910 S. Michigan Ave., Chicago, Ill.

ASSOCIATE MEMBERS

Aluminum Co. of America, 2110 Gulf Building, Pittsburgh, Pa., Rep. C. E. Magill

American Brass Co., Waterbury, Conn.

American Cast Iron Pipe Co., Birmingham, Ala.

American City Magazine, 470 Fourth Avenue, New York, N. Y., Rep. Edgar J. Buttenheim, Pres. & Mgr.

American Well Works, Aurora, Ill., Rep. J. D. Walker, Sanitary Div.

Armco Drainage Products Assn., Middletown, Ohio, Rep. W. H. Spindler, Publicity Mgr.

Automatic Control Co., 1005 University Ave., St. Paul 4, Minn., Rep. J. S. Williams

Builders-Providence, Inc., Div. of Builders Iron Foundry, P. O. Box 1312, Providence, R. I., Rep. C. G. Richardson

Cambridge Instrument Co., 3732 Grand Central Terminal, New York City, Rep. F. G. Paully

Carter, Ralph B., Co., 192 Atlantic St., Hackensack, N. J., Rep. J. W. Van Atta

Chain Belt Company, Milwaukee, Wisc., Rep. W. B. Marshall, Sales Promotion Manager

Chapman Valve Manufacturing Co., 203 Hampshire St., Indian Orchard, Mass.

Chicago Pump Company, 2300 Wolfram St., Chicago, Ill., Rep. Milton Spiegel, Vice-Pres. & Gen. Mgr.

Clay Products Assn., 111 W. Washington St., Chicago, Ill., Rep. J. D. Cook, Sec'y.

Crane Company, 836 South Michigan Ave., Chicago, Ill., Rep. G. W. Hauck, Mgr., Eng. Sales Section

Dickey, Clay Mfg. Co., W. S., 607 Commerce Trust Bldg., Kansas City, Mo., Rep. A. G. Frerking, Vice Pres.-Sales Mgr.

Dorr Co., Inc., 570 Lexington Ave., New York, N. Y., Rep. D. S. McAfee

Dow Chemical Co., Midland, Mich., Rep. Ralph B. Ehlers, Industrial Sales

Eimco Corporation, 111 W. Washington St., Chicago, Ill., Rep. Paul O. Richter, Mgr. Central Div.

Electro Rust-Proofing Co., 1026 Wayne St., Dayton, Ohio, Rep. E. H. Ingle, Gen. Mgr.

Engineering News-Record, 330 W. 42nd St., New York, N. Y.

Everson Manufacturing Co., 214 W. Huron St., Chicago, Ill., Rep. A. B. Everson, Pres.

Flexible Sewer-Rod Equipment Co., 9059 Venice Blvd., Los Angeles, Calif., Rep. Peter L. Ciacco, Mgr.

Foxboro Company, Neponset Avenue, Foxboro, Mass.

Gale Oil Separator Co., Inc., 52 Vanderbilt Ave., New York City, Rep. Wm. A. Gehle, Pres.

General Chemical Co., 3357 West 47th Place, Chicago 32, Ill., Rep. L. I. Birdsall, Technical Service Div.

General Electric Co., 1 River Road, Schenectady, N. Y., Rep. H. V. Crawford

Glamorgan Pipe & Foundry Co., Lynchburg, Va.

Graver Tank & Mfg. Co., Inc., 4809 Tod Ave., E. Chicago, Ind., Rep. G. V. Malmgren, Vice-Pres.

Gruendler Crusher & Pulverizer Co., 2915 N. Market St., St. Louis, Mo., Rep. Wm. P. Gruendler, Secy-Treas.

Homelite Corporation, Port Chester, N. Y.

Infilco, Inc., 325 W. 25th Place, Chicago, Ill., Rep. H. W. Gillard

Iowa Valve Co., 812 Hubbell Bldg., Des Moines, Iowa, Rep. C. S. Howard, Vice-Pres. & Gen. Mgr.

Jeffrey Manufacturing Co., Columbus, Ohio, Rep. J. X. Farrar, Adv. Mgr.

Johns-Manville Corporation, 22 East 40th St., New York City, Rep. C. A. McGinnis, Mgr. Transite Pipe Dept.

Lakeside Engineering Corp., 222 W. Adams St., Chicago, Ill., Rep. R. O. Friend

Limestone Products Corp. of America, Newton, N. J., Rep. Peter J. Kelley, Service Representative

Link-Belt Company, 2045 West Hunting Park Ave., Philadelphia, Pa., Rep. M. B. Tark

Ludlow Valve Mfg. Co., P. O. Drawer 388, Troy, N. Y.

Lynchburg Foundry Company, Lynchburg, Va.

Mathieson Alkali Works, Inc., 60 East 42nd Street, New York, N. Y., Rep. R. J. Quinn

Monsanto Chemical Company, Merrimac Division, Everett Station, Boston, Mass.

Mueller Company, 512 West Cerro Gordo St., Decatur, Ill.

National Water Main Cleaning Co., 30 Church St., New York, N. Y., Rep. Clinton Inglee, Pres. & Gen. Mgr.

Nichols Engineering & Research Corp., 60 Wall Tower, New York, N. Y., Rep. R. W. Bowen, Vice-Pres.

Omega Machine Company, 3409 East 18th St., Kansas City, Mo., Rep. L. E. Harper, Pres.

Pacific Flush Tank Co., 4241 Ravenswood Ave., Chicago, Ill., Rep. L. E. Rein, Pres.

Pennsylvania Salt Mfg. Co., 1000 Widener Building, Philadelphia, Pa., Rep. L. L. Hedgepeth, Mgr.

Pittsburgh-Des Moines Co., Neville Island Branch, Pittsburgh, Pa.

Pittsburgh Equitable Meter Co., 400 N. Lexington Ave., Pittsburgh, Pa., Rep. R. S. Reed, Jr., Advtg. Mgr.

Proportioneers, Inc., P. O. Box 1442, Providence, R. I., Rep. L. M. Bullock

Public Works Magazine, 310 East 45th St., New York, N. Y.

Quigley Company, Inc., 56 West 45th St., New York City, Rep. H. L. Stelfeld, Adv. Mgr.

Royer Foundry & Machine Co., 158 Pringle Street, Kingston, Pa., Rep. S. B. Davies, Pres. & Gen. Mgr.

Sewage Works Engineering, 24 West 40th St., New York, N. Y., Rep. Karl M. Mann

Simplex Valve & Meter Co., 68th & Upland Sts., Philadelphia, Pa., Rep. Everett M. Jones, Sales Mgr.

Smith Manufacturing Co., A. P., East Orange, N. J., 545 N. Arlington Ave., Rep. W. P. Baerenrodt, Treas.

Stuart-Brumley Corp., 516 N. Charles St., Baltimore, Md.

United States Pipe & Foundry Co., Burlington, N. J.

Vapor Recovery Systems Co., 30 Church St., New York City, N. Y., Rep. Frank M. Holloway, Eastern Sales Mgr.

Wailes Dove-Hermiston Corp., Westfield, N. J., Rep. W. H. T. Thornhill, Vice-Pres.

Wallace & Tiernan Co., Inc., Newark, N. J., Rep. B. M. Lindsay

Water Works & Sewerage, 155 East 44th St., New York, N. Y.

Wood, R. D., Co., 400 Chestnut St., Philadelphia, Pa., Rep. Chas. Becker, Sales Mgr.

Worthington Pump & Machy. Corp., Harrison, N. J.

Yeomans Bros. Co., 1433 Dayton St., Chicago, Ill., Rep. Chas. Yeomans, Pres. & Treas.

MEMBER ASSOCIATIONS

Arizona Sewage and Water Works Association

Mr. Richard Bennett, *Secretary-Treasurer*, City Water Dept., Phoenix, Ariz.

Bejcek, Otto, P. O. Box 1486, Coolidge, Ariz.

Borquist, E. S., Prof., Head Dept. of Civil Engr., University of Arizona, Tucson, Ariz.

Cook, John O., Sanitary Inspector, U. S. Dept. of Interior, Grand Canyon Nat'l Park, Grand Canyon, Ariz.

Cushing, Robert, 948 Ash Ave., Tempe, Ariz.

Gilbert, A. J., Water Service Foreman, So. Pacific R. R., Tucson, Ariz.

Johannessen & Girand, Consulting Engineers, Ellis Bldg., Phoenix, Ariz.

Jones, A. N., Upper Verde Utilities Co., Clarkdale, Ariz.

Ludlow, John, Box 1784, Phoenix, Ariz.

Lewis, Mr. E. S., Non-Corrosive Products Co., 611 N. 19th Ave., Phoenix, Ariz.

Marx, Geo. W., State Sanitary Engr., State Bd. of Health, Phoenix, Ariz.

Mathis, Alice, Engineering Dept., City Hall, Phoenix, Ariz.

Miller, Alden W., 1833 North 13th Avenue, Phoenix, Ariz.

Prendergast, John W., Box 736, Ajo, Ariz.
Travaini, Dario, 69 W. Wilshire Dr., Phoenix, Ariz.
Yost, Harold W., Yost Engineering Co., Heafd Bldg., Phoenix, Ariz.

California Sewage Works Association

Mr. J. A. Harmon, *Secretary-Treasurer*, 703 Calif. State Building, Los Angeles 2, Calif.

Adams, J. J., 3959 Everest Arlington St., Riverside, Calif.
Adolphe, Robt. C., 985 Atking Ave., Salt Lake City 5, Utah.
Albers, J. C., City Engr. & Street Supt., 120 N. Howard St., Glendale, Calif.
Aldrich, Lloyd, City Engineer, Room 600, City Hall, Los Angeles, Calif.
Alexander, Louis J., 1206 Maple Ave., Los Angeles, Calif.
Allen, William A., City Hall, Pasadena, Calif.
Allin, Claud R., 931 Highland Ave., Buena Park, Calif.
Anaya, Marvin, Sanitary Engr., Designer, 367 City Hall, San Francisco, Calif.
Arnold, G. E., Regional Sanitary Engr., U. S. Public Health Service, 477 Colon Ave., San Francisco, Calif.
Avis, R. L., Green Village, N. J.
Bacon, Vinton, 836 W. Slauson Ave., Los Angeles 44, Calif.
Banks, Harvey O., Capt., Corps of Engineers, 1628 N. Roosevelt Ave., Pasadena, Calif.
Banta, A. Perry, Major, Corps of Engineers, U. S. Army, General Delivery, Springhill, Ala.
Bargman, R. D., Ensign, USNR., Naval Eng. Experimental Sta., Annapolis, Md.
Barnard, Archer F., Partner Leeds, Hill, Barnard & Jewett, 601 W. 5th St. (Suite No. 1000), Los Angeles, Calif.
Batty, Frederic A., Supt. of Sewers, 231 S. Cliffwood Ave., Los Angeles, Calif.
Becker, Fred G., Opr. Azusa Sew. Treat. Plant, 909 San Gabriel Ave., Azusa, Calif.
Belt, Elmer B., Owner, Squires-Belt Material Co., 153 12th St., Box 1097, San Diego, Calif.
Bennett, S. G., c/o City Hall, Santa Paula, Calif.
Berlin, A. Martin, Engr., American Crystal Sugar Co., Clarksburg, Calif.
Besselievre, E. B., The Dorr Co., Inc., 811 W. 7th St., Los Angeles, Calif.
Bishop, H. N., City Engr., P. O. Box 333, Sunnyvale, Calif.
Borland, Victor J., Engineer-Chief Draftsman, Co. Sanitation Distrs. of L. A. County, 110 S. Broadway, Los Angeles, Calif.
Bowen, M. R., 205 N. Greenleaf St., Whittier, Calif.
Bowlus, Fred D., Box 443, San Fernando, Calif.
Boyle, J. R. Lester, 430 Bent St., Laguna Beach, Calif.
Brown, Kenneth W., P. O. Box 1150, San Jose, Calif.
Brown, R. F., Asst. Supt. of Sewer Maintenance, City of Los Angeles, 1220 Colorado Blvd., Los Angeles, Calif.
Buckman, Millard E., 832 53rd St., Sacramento, Calif.
Burnson, Blair L., Asst. Sanitary Engr., East Bay Municipality Dist., 512 16th St., Oakland, Calif.
Bush, A. F., 2002 Acton St., Berkeley 2, Calif.
Bybee, J. F., 347 Alma St., Palo Alto, Calif.
Caldwell, David H., 1396 So. 15th East, Salt Lake City, Utah
Cardillo, Wm. V., Sanitary Inspector, Calif. State Dept. of Pub. Health, 10413 Oro Vista Ave., Tujunga, Calif.
Cary, Edmund S., 560 Chaucer St., Palo Alto, Calif.
Casey, John J., City Hall, City Engr., San Francisco, Calif.
Castello, W. O., Supt. of Sewer Dept., City Hall, Sacramento, Calif.
Carter, Alton B., 515 Broadway Bldg., San Diego, Calif.
Ceriat, Eugene, Construction Engr., 1220 S. Lake St., Los Angeles, Calif.
Chanlett, Emil T., 434 Bronx Park Ave., New York City
Chutter, W. H., Sec.-Mgr., Jourdan Concrete & Pipe Co., P. O. Box 152, Fresno, Calif.
Clark, J. C., Chief Opr., Sewage Treatment Plant, City Hall, Huntington Beach, Calif.
Cole, Hawley M., Jr., Civic Center Bldg., San Diego, Calif.
Collins, A. Preston, Civil Engr., Sanitation Div., Los Angeles County Engrs. Office, 700 Union League Bldg., Los Angeles, Calif.
Compton, C. R., Asst. Chief Engr., L. A. Co. Sanitation Distr., 110 S. Broadway, Los Angeles, Calif.
Cook, Lawrence H., Box 696, Menlo Park, Calif.
Cook, Max E., 100 Bush Street, San Francisco, Calif.
Cooley, E. C., 625 Market St., Rm. 1414, San Francisco, Calif.
Cortelyou, H. P., Engr., Director of Bureau of Maintenance & Sanitation, City of Los

Angeles, Room 700, City Hall, Los Angeles, Calif.

Crane, H. R., Owner, Flexible Sewer Rod Equip. Co., 9059 Venice Bldg., Los Angeles, Calif.

Crecars, T. H., 1824 S. Hope St., Los Angeles, Calif.

Currie, Frank S., Consulting Engr., 219 Anderson Bldg., San Bernardino, Calif.

Davey, H. W., Plant Mechanic, Bakersfield Treatment Plant, 1021 Q Street, Bakersfield, Calif.

Davids, E. M., Vice-Pres., Gladding, McBean Company, 2901 Los Feliz Boulevard, Los Angeles, Calif.

Davidson, J. R., Davidson & Fulmor, 3646 Seventh St., Riverside, Calif.

DeMartini, Frank E., USPHS, 2000 Massachusetts Ave., N.W., Washington, D. C.

Deming, P. H., Owner, The Deming Company, 817 Yale St., Los Angeles, Calif.

Derby, Ray L. Major, 111 South Pomona Ave., P.O. Box 4, Brea, Calif.

Dewante, Randolph H., 1st Lt., Force Hospital, APO 729, Seattle, Wash.

Doane, C. C., 487 Mark West Springs Rd., Santa Rosa, Calif.

Duell, Garth H., City Hall, Monrovia, Calif.

Dunstan, Gilbert H., Asst. Prof. San. Engineering, University of Alabama, Box 1996, University, Ala.

Early, Fred J. Jr., Owner, Fred J. Early Jr., Co., 369 Pine St., San Francisco, Calif.

Easley, G. E., Chief Operator, Camp Roberts Sewage Disposal Plant, P. O. Box 443, Atascadero, Calif.

Egan, J. H., c/o Crane Company, 321 E. Third St., Los Angeles, Calif.

Elder, Leiton J., 56 Scenic Ave., San Rafael, Calif.

Fairbanks, E. G., Commissioner of Health & Safety, 233 Sycamore St., Manteca, Calif.

Farrar, J. H., Chief Opr., City Hall, Ontario, Calif.

Fink, Wm. Kenneth, 79 West St., Salinas, Calif.

Finley, Dexter L., 3567 Hoover St., Riverside, Calif.

Fitch, T. A., 826 Yale St., Los Angeles, Calif.

Fitzmaurice, E. W., Engr., Pacific Foundry Co., 3100 19th St., San Francisco, Calif.

Flannery, Harold J., City Engineer, City Hall, San Jose, Calif.

Foreman, Merle S., Bacteriologist, State Dept. of Pub. Health, 15 Shattuck Square, Berkeley, Calif.

Foster, Herbert, Jr., Captain, Plymouth, Calif.

Foster, William Floyd, Eng., 333 W. 2nd St., Rm. 711, Los Angeles, Calif.

Fraschina, Keeno, Asst. Supt. & Technician, Richmond Sunset Sewage Tr. Plant, 4545 Lincoln Way, San Francisco, Calif.

Fraters, E. W., Calif. Corrugated Culvert Co., 7th & Parker Sts., Berkeley, Calif.

Frick, A. L., Jr., 2311 East 8th St., Los Angeles, Calif.

Frickstad, Walter N., 803 City Hall, Oakland, Calif.

Froehde, F. C., City Engr. & Supt. of Streets, City Hall, Pomona, Calif.

Garnder, R. T., Wallace & Tiernan, 2311 E. 8th St., Los Angeles, Calif.

Gilkey, A. E., 332 Pleasant St., Roseville, Calif.

Gill, John B., 116 New Montgomery St., San Francisco, Calif.

Gillespie, C. G., 15 Shattuck Square, Berkeley, Calif.

Gladding, Charles, Pres., Gladding Bros. Mfg. Co., Third & Keyes Sts., San Jose, Calif.

Goodridge, Harry, City Engineer, City Hall, Berkeley, Calif.

Goudey, R. F., Water & Power Dept., Box 3669, Terminal Annex, Los Angeles Calif.

Gray, Harold F., Sanitary & Hydraulic Engineer, 2540 Benvenue Ave., Berkeley, Calif.

Gregory, The John H. Sanitary & Nun. Ref. Lib., Rm. 229, City Hall, Columbus, Ohio

Gregory, Ted R., Chief Engr., Flotation Systems, Inc., 1112 Wellington Ave., Pasadena, Calif.

Gruss, A. W. Agent, The American Brass Co., 235 Montgomery Street, San Francisco, Calif.

Gwin, Thomas, Supt., Treatment Plant, Box 49, Repress, Calif.

Hammond, Robt., Associate Engineer, Water & Sewerage Section, U. S. Engineers Dept., 1072 West 7th St., Los Angeles, Calif.

Hanes, Gilbert C., 75 "H" Street, Salt Lake City, Utah

Hapgood, E. P., City Hall, Anaheim, Calif.

Harmon, Judson A., 703 California State Bldg., Los Angeles 12, Calif.

Harper, Travis C., P. O. Box 34, Lompoc, Calif.

Harrison, John B., Capt., Ordinance Dept., U. S. Army, 505 Central Ave., Palo Alto, Calif.

Hilton, E. M., Capt., U. S. Army, C. E., U. S. Army, c/o Post Engineer, Camp Roberts, Calif.

Hoag, Henry J., Box 66, Oro Grande, Calif.

Hommon, H. B., Bureau of San. Engineering, Calif. State Dept. of Public Health, 15 Shattuck Sq., Berkeley, Calif.

Hoskinson, Carl M., Chief Engr. & Acting Supt., Div. of Water & Sewers, No. 112 City Hall, Sacramento, Calif.

Howell, Eugene M., Lt., 107 W. Stadium Drive, Stockton, Calif.

Huebner, Ludwig, Chief Opr., Palo Alto Sew. Treatment Plant, Box 52, Station A., Palo Alto, Calif.

Huffman, Fred, 422 University St., Healdsburg, Calif.

Humphreys, Walter, 633 W. Fern Drive, Fullerton, Calif.

Hunt, Geo. W., Engr. & Field Mgr., Lakewood Public Utility Distr., 2539 East 2nd St., Long Beach, Calif.

Hurst, Howard M., Acting Director, Div. of Public Health Engr. & Sanitation, State Dept. of Health, 130 State Capitol, Salt Lake City, Utah

Huth, Norman A., City Engineer, City Hall, Visalia, Calif.

Hyde, Chas. Gilman. Prof., Rm. 11, Engr Bldg., Univ. of Calif., Berkeley, Calif.

Ingram, Wm. T., P. A. San. Engr. (R) PHS, 9th Regional Off., Civilian Defense, 1355 Market St., San Francisco, Calif.

Jeffrey, H. H., City Hall Rm. 112, Sacramento, Calif.

Jenks, Harry N., 345 Madrono Ave., Palo Alto, Calif.

Jessop, A. H., 224 N. Segovia Ave., San Gabriel, Calif.

Jewell, H. W., Engr., Pacific Clay Products, 306 West Ave., 26, Los Angeles, Calif.

Johnson, Verner C., 128 N. Greenwood St., Motebello, Calif.

Jones, Wayland, Supt., South Disp. Plant, Rt. 2, Box 182, Stockton, Calif.

Jorgensen, Homer W., 1st Lt., Sanitary Corps, U. S. Army, 3948 Albatross St., San Diego, Calif.

Keirn, Kenneth A., Div. Manager, Wallace & Tiernan Sales Corp., 171 Second St., San Francisco, Calif.

Keller, H. James, Chief Chemist & Bact., Water & Sewage Plants, Basic Magnesium, Inc., Box 1150, Los Vegas, Nev.

Kelly, Earl M., Commander Officer in Charge 8th N. C. B., U. S. N., 1014 So. Orange Grove Ave., Los Angeles, Calif.

Kempkey, A., Cons. Engr., Room 409, 593 Market, San Francisco 5, Calif.

Kennedy, C. C., Atlas Bldg., 604 Mission St., San Francisco, Calif.

Kennedy, D. R. Supt., Pipe Lines Div., 502 City Hall, Long Beach, Calif.

Kennedy, R. R., 604 Mission St., San Francisco, Calif.

Kimball, Jack H., 6845 58th, N.E., Seattle 5, Wash.

Kivari, A. M., 811 W. 7th St., Los Angeles, Calif.

Kizler, Wilfred C., P. O. Box 508, Arroyo Grande, Calif.

Kjellberg, G., Supt. of Sewers, 4411 Roubidoux, Riverside, Calif.

Knapton, Wm., Post Plumber, McClelland Field, Box 173, Auburn, Calif.

Knoedler, H. A., Inertol Co., 64 South Park, San Francisco, Calif.

Knowlton, W. T., Cons. Engr., 1632 S. Van Ness Ave., Los Angeles, Calif.

Koebig, A. H., Jr., Koebig & Koebig, Cons. Engrs., 458 S. Spring St., Los Angeles, Calif.

Kolb, Fred W., District Sales Representative, Proportioneers, Inc., 598 Monadnock Bldg., San Francisco, Calif.

Kressly, Paul E., Cons. Engr., City Hall, Azusa, Calif.

Lak, Gerard J., P. O. Box 27, Aromas, Calif.

Langelier, W. F., Prof. San. Engr., 213 Engr. Materials Lab., Univ. of Calif., Berkeley, Calif.

Lederer, K., Director & Gen. Mgr., Mercury Technical Cloth & Felt Corp., 1265 Broadway, New York, N. Y.

Lee, Charles H., Cons. Engr., 58 Sutter St., San Francisco, Calif.

Lemcke, Ewald M., Maintenance Engr., Orange County Joint Outfall Sewer, City Hall, Anaheim, Calif.

Lemon, Paul R., Asst. Supt., Sewage Treatment Plant, Calif., State Prison at Folsom, P. O. Box 572, Folsom, Calif.

Livingstone, Bard, Supt. Water Dept., City Hall, San Bernardino, Calif.

Long, Frank V., President, Vapor Recovery Systems Co., 2820 N. Alameda St., Compton, Calif.

Los Angeles Public Libr., Municipal Reference Lib., 300 City Hall, Los Angeles, Calif.

Los Angeles Public Libr. Serials Division, 530 South Hope Street, Los Angeles, Calif.

Lowe, Robt., Sanitary Engr., War Relocation Authority, 1015 N. Kensington St., Arlington, Va.

Lowther, Burton, Consulting Engr., 710 Colorado Bldg., Denver, Colo.

Ludwig, Harvey F., Asst. San. Engr., USPHS, Office for Malaria Control in War Areas, 605 Volunteer Bldg., Atlanta, Ga.

Ludwig, Russell G., 1014 Harbor View, San Pedro, Calif.

Luebbers, Ralph H., Capt. Sn-C., SCU 1947, Station Hospital, Camp San Luis Obispo, Calif.

Luippold, G. T., Luippold Engineering Sales Co., 1930 W. Olympic, Los Angeles, Calif.

Martin, Chas. P., City Hall, San Leandro, Calif.

McBride, J. L., Cons. Engr., 1110 Spurgeon, Santa Ana, Calif.

McIntosh, Pierce B., P. O. Box 1739, Sacramento, Calif.

McMorrow, B. J., San. Engr., Island of Hawaii, Bd. of Health, Territory of Hawaii, P. O. Box 916, Hilo, Hawaii

Macabee, Lloyd C., Cons. Eng., 156 University Ave., Palo Alto, Calif.

Maga, John A., Ensign, U. S. Navy Reserve, 316 El Camino Real, San Mateo, Calif.

Maldonando, Ardis, Sales Engr., Pacific Clay Products, 306 West Ave., 26, Los Angeles, Calif.

May, Harold L., Water & Sewer Div., Palo Alto, Calif.

McKeen, William H., Rt. 1, Box 330, San Luis Obispo, Calif.

McKinlay, Daniel, Field Engr., Infilco, Inc., 611 Howard St., San Francisco, Calif.

McLaren, Alfred M., Sales Engr., Fairbanks Morse & Co., 3772 Dublin Ave., Los Angeles, Calif.

McMillan, Donald C., City Mgr., 1225 Bay St., Alameda, Calif.

McRice, Donald J., 9931 Dante, Oakland, Calif.

Mechler, L. W., Chief. Engr., Camarillo State Hospital, Camarillo, Calif.

Medbery, H. Christopher, Purification Engineer, Water Department, San Francisco, Millbrae, Calif.

Meyer, Louis P. H., Insp. of Police, Rm. 401, Hall of Justice, Washington & Kearny Sts., San Francisco, Calif.

Miick, Fred E., Asst. Mgr., Link-Belt Co., Pacific Div., 361 S. Anderson St., Los Angeles, Calif.

Miles, Henry J., College of Engr., Univ. of So. California, Los Angeles, Calif.

Mills, J. Ralph, P. O. Box 825, Palm Springs, Calif.

Montgomery, James M., 306 W. Third St., Los Angeles, Calif.

Morris, Arval, Sales Engr., Sterling Electric Motors, Inc., Telegraph Rd. at Atlantic Blvd., Los Angeles, Calif.

Munson, Laura A., Mrs., 746 E. Gorham St., Madison, Wisc.

Nasi, Kaarlo W., Asst. San.Engr., U. S. P. H. S., Plague Suppression Measures Lab., 14th & Lake, San Francisco, Calif.

Norfleet, Clark T., Pacific Clay Products, 306 W. Avenue 26, Los Angeles, Calif.

Nugent, Lee M., Rt. 1, Box 56, Manteca, Calif.

O'Connell, Wm. J., Jr., Technical Consultants, 525 Market St., San Francisco, Calif.

Ogle, Harry B., Sales Mgr., Valley Conc. Pipe & Products Co., P. O. Box 402, Chico, Calif.

O'Neill, Ralph W., 520 Avenue L., Boulder City, Nev.

Ongerth, Henry J., Assoc. San. Engr., U. S. E. D., 1911-B Berryman St., Berkeley, Calif.

Painter, Carl E., Water Works Equipment Co., 149 West Second South, Salt Lake City, Utah

Palmer, Harold K., Office. Engr., Los Angeles Co. Sanitation Dist., 110 S. Broadway, Room 400, Los Angeles, Calif.

Parks, G. A., Civil Engr., City of Los Angeles, 1725 Virginia Place, So. Pasadena, Calif.

Peightal, Wm. H., Chief Opr., Sewage Treatment Plant, U. S. N. R. Air Base, Los Alamitos, 2233 255th St., Lomita, Calif.

Peirson, Henry C., Sales Engineer, Gladding, McBean & Co., 521 S. Parish Place, Burbank, Calif.

Peterson, J. H., 116 New Montgomery St., San Francisco 19, Calif.

Pfiffer, Fred, Supt., Disposal Plant, P. O. Box 35, Ojai, Calif.

Phelps, B. D., Asst. City Engr., Rm. 266, Civic Center, San Diego, Calif.

Pierce, C. L., District Representative, Great Western Div., The Dow Chem. Co., 4151 Bandini Blvd., Los Angeles, Calif.

Pisano, Frank, Chief Opr., Sew. Treatment Plt., City Hall, Santa Clara, Calif.

Pomery, Richard, Consultant, Rm. 639, 117 E. Colorado St., Pasadena, Calif.

Poole, Wm. A., 227 S. Hollenbeck St., Covina, Calif.

Porter, H., Asst. City Engr., Civic Center, San Mateo, Calif.

Pratt, Jack W., Ensign (C. E. C.) U. S. N. R., 23rd U. S. Naval Construction Battalion, 1425 Santa Ynez Way, Sacramento, Calif.

Quartly, Eric V., 806 Adella Ave., Coronado, Calif.

Ramseier, Roy E., Sr., San. Engr., Pacific Div., U. S. Engineering Dept., 852 So. 19th East, Salt Lake City, Utah

Rantsma, W. Frank, Deputy Commissioner, Pub. Wks., City Hall, Fresno, Calif.

Rawn, A. M., Los Angeles Co. Sanitation Dists., 110 S. Broadway, 4th Floor, Los Angeles, Calif.

Reeves, C. F., Dist. Manager, DeLaval Steam Turbine Co., 410 Rialto Bldg., San Francisco, Calif.

Reidell, Alfred G., 1st Lt., Sanitary Corps, Sanitary Officer, U. S. Army, 139 W. 62nd St., Los Angeles, Calif.

Reinhardt, Arthur W., 1561 Euclid Ave., Berkeley 8, Calif.

Reinke, E. A., Senior Sanitary Engr., Bureau of San. Engr., State Dept. of Public Health, 15 Shattuck St., Berkeley, Calif.

Reinoehl, Don, Civil Engr., Box 1150, Las Vegas, Nev.

Reynolds, Leon B., Prof., Hydraulic & Sanitary Engr., Rm. 275, Stanford Univ., Stanford, Calif.

Ribal, Raymond Robt., 3889 Lyman Rd., Oakland, Calif.

Riffe, Norman T., San. Engr., City of Richmond, 105 Parkside Dr., Berkeley, Calif.

Roberts, F. C., Jr., 5645 Cherry St., Kansas City, Mo.

Roberts, W. C., Director, Pacific Engineering Lab., 604 Mission St., San Francisco, Calif.

Robertson, John, Box 249, Rt. 2, Oakdale, Calif.

Robinson, W. S., 152 E. Louise St., Long Beach, Calif.

Rowntree, Bernard, Asst. Secy., Sewage Treatment Wks., P. O. Box 83, Carmel, Calif.

Rudolph, R. L., Sewage & Water Treatment Plant Operator, Sonoma State Home, P. O. Box 211, Eldridge, Calif.

Sanchis, Joseph M., Water Lab., Principal, Div. of San. Engr., Dept. of Water & Power, 207 S. Broadway, Los Angeles, Calif.

Sauer, Victor W., 701 City Hall, Oakland, Calif.

Schott, Edgar C., City Hall, Santa Clara, Calif.

Schuck, H. W., Supt., Water & Sewer Plt., City Hall, Burlingame, Calif.

Schureman, A. L., 563 W. 24th St., Apt. H, Ogden, Utah

Segel, A., Cons. Engr., 817 Mattei Bldg., Fresno, Calif.

Senseman, Wm. B., Pacific Coast Manager, 406 S. Main St., Los Angeles, Calif.

Shaw, Paul A., Toxicologist, Division of Fish & Game, Ferry Building, San Francisco, Calif.

Shearer, A. B., 11 Library Place, San Anselmo, Calif.

Shelton, M. J., 1935 Goldfield St., San Diego, Calif.

Shook, H. E., Dow Chemical Co., 10th Floor, 310 Sansome St., San Francisco, Calif.

Siegel, John A., Asst. City Engr., Newport Beach, 718 Jasmine Ave., Corona Del Mar, Calif.

Silberbauer, Walter R., Inspector, Campbell San. District, Box 614, Campbell, Calif.

Silverts, S. A., 222 S. W. Temple, Salt Lake City, Utah

Skinner, John F., 1610 Idlewood Rd., Glendale, Calif.

Skinner, W. V., Supt. of Public Wks., P. O. Box 668, Escondido, Calif.

Smith, C. A., Cons. Engr., 300 Carmen's Bldg., 107 W. Linwood Blvd., Kansas City, Mo.

Smith, Charles L., 1259 Harris Ave., Fresno, Calif.

Smith, Frank E., Operator, Santa Ana, 1100 East Broadway, Anaheim, Calif.

Smith, H. G., Eng. of Sewer Design, City of Los Angeles, 708 City Hall, Los Angeles, Calif.

Smith, J. F., Sales Mgr., Great Western Div., Dow Chem. Co., 10th Floor, 310 Sansome St., San Francisco, Calif.

Snyder, John A., Jr., Opr., Sewage Disposal Plant, Hammer Field, Fresno, 3350 Nevada Ave., Fresno 2, Calif.

Souther, Fred L., 4580 Edgeware Rd., San Diego, Calif.

Sperbeck, George E., City Engineer, City of Alameda, City Hall, Alameda, Calif.

Stevenson, Ralph A., 641 Gibbons St., Los Angeles, Calif.

Stewart, Morgan E., 1st Lt., Sn C., 0-517573, Surgeon's Office Hq. W. B. S., APO 515, c/o Postmaster, New York, N. Y.

Stites, H. L., City Mgr., Box 231, Burbank, Calif.

Stowell, E. Ralph, Lt., Sanitary Corps, c/o Chas. E. Bigelow, Rt. 1, Box 224, Hughson, Calif.

Strangard, Edward L., Opr., Disposal Plant, c/o Public Works Dept., U. S. Naval Air Sta., Alameda, Calif.

Strotkamp, Charles E., Sr. Opr. Sewage Plant, Camp Cooke, P. O. Box 1004, Guadalupe, Calif.

Stunkard, C. R., Capt., Corps of Engrs., Army Engr., Office of Pacific Div., 19 West South Temple, Salt Lake City, Utah

Talbot, Frank D., 3256 S. E. Burnside, Portland 15, Oregon

Taylor, Arthur, 725 S. Spring St., No. 310, Los Angeles, Calif.

Teel, Jess W., P. O. Box 828, Tracy, Calif.

Thews, Vernon W., Terminal Island Sewage Plant, City of Los Angeles, 2300 S. Pacific Ave., San Pedro, Calif.

Thoits, Edw. D., Sanitary Engr., San Joaquin Local Health Dist., 130 S. American St., Stockton, Calif.

Todd, J. L., Field Engr., Sanitation Div., Los Angeles Chemical Co., Inc., 2903 W. Vernon Ave., Los Angeles, Calif.

Tolagson, Clarence F., 616 N. Stanley, Hollywood, Calif.

Toone, Dean Wm., 370 Bryam Ave., Salt Lake City, Utah

Trotter, Roy M., Asst. San. Engr., 1551 Sonoma Avenue, Berkeley, Calif.

Ullrich, C. J., Cons. Engr., 422 Ness Bldg., Salt Lake City, Utah

University of California, Division of Serials and Exchanges, Berkeley, Calif.

University of Southern Calif., General Library, University Park, Los Angeles, Calif.

Updegraff, W. R., Western City Magazine, 458 So. Spring St., Los Angeles, Calif.

Vaughan, E. A., Mgr., Lompoc Light & Water Dept., P. O. Box 456, Lompoc, Calif.

Vensano, H. C., Director, San Francisco, City & County, Department of Public Works, Room 260, City Hall, San Francisco, Calif.

Von Pelt, Richard, 577 Butler St., Grass Valley, Calif.

Waggoner, E. R., 306 West Ave., 26 Los Angeles, Calif.

Walker, Walter J., Opr., Sewage Treatment Plant, 409 Railroad Ave., Decoto, Calif.

Walters, Grover L., 123 W. Wilshire Ave., Fullerton, Calif.

Webb, Rollin D., SDP Chief Opr. Disp. Plt. Camp Q.M. Maintenance, Marine Camp Elliot, San Diego, Calif.

Weed, Sam A., Assoc. Engr., U.S. E. D., Pacific Div., 279 2nd Ave., Apt. 1, Salt Lake City, Utah

White, George C., Div. Engr., Wallace & Tiernan Sales Corp., 171 2nd St., San Francisco, Calif.

White, R. E., Consulting Engineer, 2617 20th St., Bakersfield, Calif.

White, W. W., State San. Engr., Nevada State Bd. of Health, Fordonia Bldg., Rm. 20, Reno, Nev.

Wilkins, George F., 235 Montgomery St., San Francisco, Calif.

Wintersgill, A. T., 306 W. Ave., 26 Los Angeles, Calif.

Woo, Francis H., 1253 16th Ave., Honolulu, T. H.

Woodward, R. D., Chief Opr. & Mechanic, 463 Myrtle St., Laguna Beach, Calif.

Wright, L. R., Supt., L. A. Co. Sanitation Dist., Sew. Treatment Plt., 815 N. Chester Ave., Compton, Calif.

Wyatt, Bradley W., Supt. N. Clark & Sons, 401 Pacific Ave., Alameda, Calif.

Yaeger, Oscar G., Controller, City of Covina, 125 E. College St., Covina, Calif.

Yoder, M. Carleton, Ensign, USNR, Engineering Officer, 610 S. El Dorado St., San Mateo, Calif.

Zuckweiler, G. C., Chief Div. of Sanitation, County Health Dept., Civic Center Bldg., San Diego, Calif.

Central States Sewage Works Association

Mr. John C. Mackin, *Secretary-Treasurer*, c/o Nine Springs Sewage Treatment Plant, Rt. 4, Madison, Wisc.

Abplanalp, C. C., Wallace & Tierman Co., 809 W. Washington Blvd., Chicago, Ill.

Adams, Charles L., Major, 202 Elks Bldg., Joliet, Ill.

Adams, Frank, Opr., 2100 South J St., Elwood, Ind.

Algonquin, Village of McHenry County, Algonquin, Ill.

Alikonis, J. J., Chemist, Bloomington & Normal San. Dist., Bloomington, Ill.

Anderson, Geo. H., Annex Bldg., Herrin, Ill.

Anderson, Herbert A., 1st Lt., Sn. C., c/o Hortan, Nashville, Ind.

Anderson, Norval E., Engr. of Treatment Plant Design, Sanitary District of Chicago, 910 S. Michigan, Chicago, Ill.

Antl, John C., 1141 8th Ave., So. St. Paul, Minn.

Arbogast, Joseph, 117 N. Ellsworth St., Naperville, Ill.

Arnold, Geo., Engr., 5036 Kingsley Dr., Indianapolis, Ind.

Ashdown, W. L., P. O. Box 158, Chicago Heights, Ill.

Babbitt, H. E., Sanitary Engineer, 204 Engineering Hall, University of Illinois, Urbana, Ill.

Backmeyer, David, 1520 W. Fourth St., Marion, Ind.

Baer, Arlie, Supt., (Mun. Water Dept.) Lawrenceburg, Ind.

Baetz, C. O., Box 51, Appleton, Wisc.

Baillie, E. P., 1st Lt., Battery I, 211th C. A. (A. A.) Hamilton Field, Calif.

Baker, C. M., 1 West Main St., Madison, Wisc.

Barnet, G. R., 519 Commercial Bank Bldg., Peoria, Ill.

Bartz, Erwin A., 2806 West St., Two Rivers, Wisc.

Bass, Jerry Connor, Plant Opr. (Gulfport Field), R. F. D. No. 2, Gulfport, Miss.

Baxter, R. R., Supt., Sewage Treatment Wks., 204 W. 10th St., Anderson, Ind.

Bayliss, John R., 1643 E. 86th St., Chicago, Ill.

Beatty, E. J., Capt., Station Hospital, AAB Sioux City, Iowa.

Beaudoin, Robert E., 3424 Arden Ave., Hollywood, Ill.

Beck, A. J., 215 Southcote Rd., Riverside, Ill.
Belaskas, Anthony J., Research & Technical Dept., Wilson & Co., Inc., 4100 S. Ashland Ave., Chicago, Ill.
Bender, Dwight O., 932 N. Hawthorne Lane, Indianapolis, Ind.
Bergman, O. O. City, 522 Jefferson Ave., Sparta, Wisc.
Bernauer, Geo. F., San. Engr., 713 Chapman St., Madison, Wisc.
Berry, Geo. A., R. R. 2, Box 440, Indianapolis, Ind.
Bers, G. D., Pres., Chicago Pump Co., 2336 Wolfram St., Chicago, Ill.
Besozzi, Leo, 314 Hammond Bldg., Hammond, Ind.
Bessert, J. Ervin, 138 Conde St., West Chicago, Ill.
Bird, Neal, Supt., 752 Glendale Dr., Frankfort, Ind.
Birdsall, L. I., P. O. Box 75, Glencoe, Ill.
Birkeness, O. T., 809 W. Washington Blvd., Chicago, Ill.
Bjelajac, Vaso, Capt., Sn. C., Brookley Field, Mobile, Ala.
Black, Hayse H., Capt., Corps of Engineers, The Engineer Board, Fort Belvoir, Va.
Black & Veatch, 4706 Broadway Bldg., Kansas City, Mo.
Bloodgood, Donald E., 5545 Guilford, Indianapolis 5, Ind.
Boeke, Harley C., Capt., Sn. C., Hubbard, Iowa
Bogema, Marvin, R. No. 2, Forrest Home Drive, Ithaca, N. Y.
Boley, Arthur L., Asst. City Engr., Sheyboygan, Wisc.
Borchardt, Jack A., Hydraulic & Sanitary Lab., University of Wisconsin, Madison, Wisc.
Bosch, Herbert M., Lt. Col., Morris Apt. Hotel, 18th & Dodge, Omaha, Nebr.
Botkin, Gilbert E., Jr., 2609 S. Bootes, Marion, Ind.
Bott, Roderick, F., San. Engr., State Board of Health, Box 36, Chippewa Falls, Wisc.
Bradney, Leland, Engineer's Office, Sioux Falls, S. Dak.
Bragg, Robert E., 5859 N. New Jersey St., Indianapolis, Ind.
Bragstad, R. E., City Engr., City Hall, Sioux Falls, S. Dak.
Brensley, A. A., 940 S. Poplar St., Kankakee, Ill.
Brody, James, 417 Melrose Avenue, Glen Ellyn, Ill.
Brook, Harry L., 313 N. Maple St., Osgood, Ind.
Brower, James, 3021 N. 36th St., Milwaukee, Wisc.
Bruden, C. O., 21 E. Gorham St., Madison, Wisc.
Brunner, Paul L., 1229 Swinney Avenue, Fort Wayne, Ind.
Bruss, O. E., Asst. Chemist, 310 12th Ave., S.E., Minneapolis, Minn.
Buck, Ross J., Chief Engr., 308 E. Main Cross St., Edinburg, Ind.
Burger, Arnold W., Supt., 1315 11th St., Menominie, Wisc.
Burgeson, J. H., 1st Lt., Corps of Engineers, 101 Tudor St., Apt. B., Pineville, La.
Burrin, Thomas J., 111 E. Main St., Lebanon, Ind.
Burt, Gordon M., (Rose Polytechnic Inst.) 123 Jackson Blvd., Terre Haute, Ind.
Bushee, Ralph J., 2225 Ardmore Ave., Villa Park, Ill.
Calder, Charles L., San. Engr., 3812 W. Beach, Gulfport, Miss.
Caldwell, H. L., 803 W. College Ave., Jacksonville, Ill.
Callen, Loy A., Capt., Sn. C., M. D. R. P. A. S. F. W. T. C., Camp Ellis, Ill.
Callon, Harry A., Muscatatuck State School, Butlerville, Ind.
Calvert, C. K., Box 855, Indianapolis, Ind.
Capraro, Paul E., c/o Sanitary Dept., Two Rivers, Wisc.
Cardwell, Edw. C., 1523 Spaight St., Madison, Wisc.
Carey, Wm. N., Col., C. E., 8414 Manchester Rd., Silver Spring, Md.
Carpenter, Carl B., San. Distr. of Hammond, 5135 Columbia Ave., Hammond, Ind.
Carson, R. G., Chem. Engr., Sales Rep., Solvay Sales Corp., 5052 N. Kent Ave., Milwaukee, Wisc.
Carter, Earl, Supt., P. O. Box 543, Henning, Minn.
Caster, Arthur, San. Engr., 318 S. Main St., Franklin, Ind.
Cheadle, Wilford G., 4224 42nd Ave., So., Minneapolis, Minn.
Christensen, Gordon R., Asst. Engr. (R), U. S. Public Health Service, Apt. No. 148, 4440 March Lane, Indianapolis 5, Ind.
Church, Dean F., Supt., Water & Sew. Plants, 513 Second Ave., So., Saint James, Minn.
Clark, Arthur T., Secy., Water & Sewage Works Mfgrs. Ass'n, 12 E. 41st St., New York 17, N. Y.
Clarke, Samuel M., Cons. Engr., 6 N. Michigan Ave., Chicago, Ill.
Clem, Curtis B., Supt., 114 E. Ames St., Anderson, Ind.
Clore, L. B., City Hall, Crawfordsville, Ind.
Cole, Charles W., 220 W. LaSalle Avenue, South Bend, Ind.

Condrey, Lawrence M., Professional Engr., 3436 N. Temple Ave., Indianapolis, Ind.
Consoer, Arthur W., 211 W. Wacker Dr., Chicago, Ill.
Cornell, R. M., Instructor, Civil Engr., Dept., University of Minnesota, Minneapolis, Minn.
Cornilson, C. K., 509 Chicago Ave., Savanna, Ill.
Corrington, Kingsley, Chemist, 8109 E. Jefferson Ave., Detroit, Mich.
Couch, L. I., Civil Engr., R. R. 4, Box 771, Indianapolis, Ind
Covert, Henry Rew, Supt., Sewage Treatment Plant, 3410 10th St., Gulfport, Miss.
Craig, Clifford, 310 Humiston St., Pontiac, Ill.
Crask, Rex, Board of Public Works, Greencastle, Ind.
Cropsey, W. H., c/o Sewage Disposal Commission, South St. Paul, Minn.
Cushman, S. P., 1256 Eleanor Avenue, St. Paul, Minn.
Czerepinski, Henry Peter, Chemist, 119 S. Hancock St., Madison, Wisc.
Daley, Stanley J., 1515 Munroe St., c/o Y. M. C. A., Chicago, Ill.
Davidson, Philip, Raymond Pulverizer Div., Combustion Engr. Co., 1319 N. Branch St., Chicago, Ill.
Davis, D. A., Chief Opr., 210 Morgan St., Crawfordsville, Ind.
Davis, F. R., Jr., 45 Halleck St., Newark, N. J.
Davis, Frederick E., 245 E. Keefe St., Milwaukee, Wisc.
Davis, Howard A., Sew. Treat. Plt., Camp Ellis, Ill.
Dawson, Norman, 104 South Taylor Avenue, Oak Park, Ill.
Day, L. A., 4456 Florriss Place, St. Louis, Mo.
DeBerard, W. W., Mgr., 402 City Hall, Chicago, Ill.
DeBrun, John W., Jr., Resident Engineer, Taylorville, Ill.
Decker, Walter G., Maj., C. E. Blue Grass Ordnance Depot, Richmond, Ky.
Deckert, Christ, 602 S. 6th St., Dekavan, Wisc.
DeLeuw, C. E., 20 N. Wacker Drive, Chicago, Ill.
DePoy, A. G., 117 6th Ave., So. South St. Paul, Minn.
Depp, David, Public Health Sanitarian, Versailles, Ind.
Deuchler, Walter E., 63 So. LaSalle St., Aurora, Ill.
Dick, Robert, Jr., 267 Columbia Ave., Elmhurst, Ill.
Dietz, Jess. C., Capt., Brooklyn, Wisc.
Dietz, John, Plant Opr., Mundelein, Ill.
Diller, Walter W., 1009 W. Main St., Decatur, Ill.
Dimmitt, Bruce S., Distr. San. Engr., 409 E. Walnut St., Green Bay, Wisc.
Domke, L. C., Waukegan Water Works No. 2, Waukegan, Ill.
Domogalla, Bernhard, Dr., City Board of Health, 110 N. Hamilton St., Madison, Wisc.
Donohue, Jerry, P. O. Box 489, Sheboygan, Wisc.
Downer, Wm. J., Principal San. Engr., State Dept. of Public Health, Springfield, Ill.
Doyle, Wm. H., P. O. Box 270, Wisconsin Rapids, Wisc.
Drake, James A., 6164 Old Town, Detroit, Mich.
Dreier, D. E., Div. of San. Engr., State Dept. of Public Health, Springfield, Ill.
Dudley, D. E., Mechanical Engr., 1909 Regent St., Madison 3, Wisc.
Dundas, Wm. A., Chicago Sanitary Dist., 910 S. Michigan Ave., Chicago, Ill.
Dunmire, E. H., Lt. Comdr., Principal Materials Engr., Ninth Naval Distr., 175 W. Jackson Ave., Chicago 4, Ill.
Dust, Joseph V., R. F. D. No. 1, Effingham, Ill.
Duvall, Arndt J., 1391 Fairmount Ave., St. Paul, Minn.
Dwyer, John W., Opr., Box 157, Lawrence, Ind.
Egger, Oscar O., 130 E. 9th St., Fond du Lac, Wisc.
Elgin, San. Distr. of, Box 92, Elgin, Ill.
Epler, J. E., P. O. Box 724, Danville, Ill.
Erichson, Roy H. (Student, Univ. of Wisconsin), 17 N. Mills St., Madison 5, Wisc.
Erickson, Carl V., 521 Gunderson Ave., Oak Park, Ill.
Evans, R. W., Versailles, Ind.
Everson, R. B., Everson Mfg. Co., 214 West Huron St., Chicago, Ill.
Farnsworth, George L., Jr., 230 Christie St., Ottawa, Ill.
Fassnacht, George G., San. Engr., 5901 E. Washington St., Indianapolis 1, Ind.
Feltz, Fred C., Supt., Sewage Treatment Plant, Box 261, West McHenry, Ill.
Ferebee, James L., P. O. Box 2079, Milwaukee, Wisc.
Figeley, Paul, Supt., 404 Galt Ave., Rock Falls, Ill.
Finch, Lewis S., Consulting Engr., 115 Penway St., Indianapolis, Ind.
Finch, R. M., 416 Flour Exchange, Minneapolis, Minn.
Fiskett, F. J., Chemist, Twin Cities Ordnance Plant, New Brighten, Minn.
Fitzgerald, Edw. P., Supt. (Truax Field), 317 Norris Court, Madison 4, Wisc.
Fitzgibbons, F. C., 116 W. Cook Ave., Libertyville, Ill.

Flatt, Truman L., District Engr., R. R. No. 5, Box 154, Springfield, Ill.

Ford, J. R., San. Engr., 1112 Twenty-Third St., Columbus, Ind.

Foster, Charles, Cons. Engr., 316 Medical Arts Bldg., Duluth, Minn.

Foth, Herbert S., 225 Columbus Bldg., Green Bay, Wisc.

Frazier, Ernest, Supt., Sewage Treatment Plant, Court House, Greenfield, Ind.

Frazier, R. W., City Hall, Sewerage Commission, Oshkosh, Wisc.

Frederich, Hoyt A., P. O. Box, Herrin, Ind.

Freeland, B. H., Supt. of Utilities, Bluffton, Ind.

Fulmer, Frank E., Capt., R. F. D. No. 2, Mishawaka, Ind.

Gail, A. L., North Shore Sanitary Distr., 1015 St. Johns Ave., Highland Park, Ill.

Gause, Frank, Dept. of Sanitation, Marion Sew. Treatment Plant, Marion, Ind.

Gelston, W. R., 415 Hampshire St., Quincy, Ill.

Gerard, F. A., Asst. Civil Engr., 242 Columbia Ave., Park Ridge, Ill.

Getz, Murray A., Distr. San Engr., 111 Dean St., Woodstock, Ill.

Giesey, J. K., 2121 Glenwood Ave., Toledo, Ohio

Gifford, Earl W., Project Maintenance Engr., Kingsford Heights, Ind.

Gifford, J. B., Chemist, Sew. Disp. Plant, 1125 Maple St., Michigan City, Ind.

Golly, M. R., 1st Lt., Gunnery Dept. Field Artillery School Staff, Fort Sill, Okla.

Goodman, Arnold H., 363 Downing Rd., Riverside, Ill.

Gordon, Arthur, 7743 N. Hermitage Ave., Rogers Park Sta., Chicago, Ill.

Grabbe Construction Co., H. A., 500 Belle Street, Alton, Ill.

Graden, Paul W., 11007 Bell Place, Hillsboro, Ill.

Grantham, G. R., 1st Lt., Box 1857, Portland, Mich.

Greeley, Samuel A., 6 N. Michigan Ave., Chicago 2, Ill.

Gross, Carl D., Engr., State Dept. of Health, Springfield, Ill.

Grosshans, Edward W., 1011 Water St., Baraboo, Wisc.

Haag, Gerald, Plant Opr., c/o Walter E. Kroening, Village Manager, Greendale, Wisc.

Hager, Fred, Operator, 123 North Avenue, Barrington, Ill.

Hagestad, Herman T., Consulting Engr., 513 E. Elm St., River Falls, Wisc.

Hale, Frank C., C. W. O., U. S. A., Asst. Medical Inspector, Hdqrs. I Troop Carrier Command, Stout Field, Indianapolis, Ind.

Halff, Albert H., Lt., 4345 Normandy, Dallas, Tex.

Hall, George M., Professional Engr., 3358 N. 51st Blvd., Milwaukee, Wisc.

Hall, S. P., 418 Lincoln Ave., Eau Claire, Wisc.

Halvorson, H. O., Prof. Bacteriology, 215 Millard Hall, University of Minnesota, Minneapolis, Minn.

Hamilton, Loeman A., 4316 Upton Ave., So. Apt. 305, Minneapolis 10, Minn.

Hammond Board of Sanitary Commissioners, Anne Baciu, Secy., 5135 Columbia Ave., Hammond, Ind.

Hansen, Paul, 6 N. Michigan Ave., Chicago 2, Ill.

Harbin, Wm., Asst. Chemist, 1046 S. Pershing Ave., Indianapolis, Ind.

Hardman, Thomas T., 2100 South Center St., Terre Haute, Ind.

Harmeson, D. K., R. F. D. No. 1, c/o R. B. Harmeson, Mattoon, Ill.

Harmon, Jacob A., Cons. Engr., 144 Fredonia, Peoria, Ill.

Harper, Charles E., City Light & Water Plant, North 5th St., Goshen, Ind.

Harris, George C., 127 S. State Road, Arlington Heights, Ill.

Harris, T. R., President, Engineering Service Corp., Decatur Club Bldg., Room 106, Decatur, Ill.

Harshbarger, J. R., Supt., 509 W. Water St., Fairfield, Ill.

Hartman, B. A., Engr., 608 N. 8th St., Sheboygan, Wisc.

Hartman, Byron K., 300 W. Pershing Rd., Chicago, Ill.

Hartung, N. E., 627 Seminary St., Richland Center, Wisc.

Hasfurther, Wm. A., 1st Lt., Sn. C., 7723 Ada St., Chicago, Ill.

Hatfield, W. D., Dr., 249 Linden Ave., Decatur, Ill.

Hattery, Charles E., Chief Chemist, 191 Ewing St., Peru, Ind.

Hay, T. T., 21 Street & Grand Ave., Racine, Wisc.

Heider, Robert W., 1098 W. Michigan Ave., Indianapolis, Ind.

Heiple, Loren R., 1st Lt., Sn. C., Off. of the Post. Engr., O'Reilly Gen. Hospital, Springfield, Mo.

Heisign, Henry M., Sewerage Commission, Box 2079, Milwaukee, Wisc.

Henn, Donald E., 517 S. 4th St., Dekalb, Ill.

Hensel, Eugene C., Asst. San. Engr., 318 W. Main St., Sparta, Wisc.

Hermann, F. X., Asst. Opr., 3152 40th Ave., So. Minneapolis, Minn.

Herrick, T. L., 717 N. Washington St., Park Ridge, Ill.
Herzig, S. B., Renville, Minn.
Hicks, George W., Capt., c/o Carl Hicks, R. R. No. 2, Benton Harbor, Mich.
Hill, K. V., c/o Greeley & Hansen, 6 N. Michigan Ave., Chicago 2, Ill.
Hodkinson, C. T., Asst. Opr., 908 Grand Ave., St. Paul, Minn.
Hoganson, Lester O., Capt., c/o City Hall, Burlington, Wisc.
Holderby, J. M., Capt., Box 498, Appleton, Wisc.
Holderman, John S., 491 N. Union, Kankakee, Ill.
Holt, Clayton M., 2400 Oliver Bldg., Pittsburgh, Pa.
Holway, O. C., 209 E. Seventh St., Superior, Wisc.
Hott, Ralph A., Sewage Treatment Works, Ft. Wayne, Ind.
Hoth, Fred, Bartlett, Ill.
Howe, W. A., Illinois Ordnance Plant, Carbondale, Ill.
Howland, W. E., Assoc. Prof., Civil Engineering, Purdue University, West Lafayette, Ind.
Howson, L. R., Alvord, Burdick & Howson, Suite 1401, 20 North Wacker Drive, Chicago, Ill.
Hromada, Frank M., Filtration Plant Supt., Box 782, El Reno, Okla.
Hudson, L. D., Lt., 333 E. 4th St., Flora, Ill.
Hunt, Henry J., 2440 Commonwealth Ave., Madison 5, Wisc.
Hunt, L. W., Box 403, Galesburg, Ill.
Hupp, John E., Jr., 720 Weller Avenue, La Porte, Ind.
Hurd, Charles H., 333 North Pennsylvania St., Indianapolis, Ind.
Hurd, Edwin C., 5821 Washington Blvd., Indianapolis, Ind.
Hurst, Charles, Opr., Sewage Treatment Plant, City Hall, Princeton, Ind.
Hurwitz, Emanuel, 5013 N. Francisco Ave., Chicago, Ill.
Hussong, Ernest W., 520 Christy Street, Marion, Ind.
Hutchins, Will A., Freeport, Ill.
Illinois Dept. of Public Health, Division of Sanitary Engineering, Sixth Floor, North Wing, State House, Springfield, Ill.
Indiana State Board of Health, Bureau of Sanitary Engr., 1098 W. Michigan Ave., Indianapolis, Ind.
International Filter Co., 325 W. 25th Place, Chicago, Ill.
James, Glenn, Supt., Sewage Treatment Wks., 529 E. Lincoln-Way, Morrison, Ill.
Jeup, Bernard H., 1098 W. Michigan St., Indianapolis, Ind.
Johnson, Arthur N., 944 24th St., Moline, Ill.
Johnson, Floyd E., 471 Barrett St., Elgin, Ill.
Johnson, Jess B., Supt. of Utilities, 309 Maple Ave., Sturgeon Bay, Wisc.
Johnson, L. M., Comm. of Streets & Electricity, City Hall, Chicago, Ill.
Johnson, R. J., 1st Lt., U. S. P. H. S. Eng., c/o State Health Dept., Capitol Bldg., Salt Lake City, Utah
Jonas, Milton R., 5496 Cornell Avenue, Chicago, Ill.
Jones, Frank O., Civil Engr., Fairmont, Minn.
Jones, John N., 803 Central Ave., Columbus, Ind.
Jones, Martha A., Miss, Chemist, Sewage Treatment Plant, Richmond, Ind.
Kaar, G. C., Engineer, The Door Co., Inc., LaSalle-Wacker Bldg., 211 N. LaSalle St., Chicago, Ill.
Kafka, John, Sewage Treatment Plant, Clintonville, Wisc.
Kearney, John J., 1320th Engr. General Service Regt., Camp Swift, Tex.
Kendrick, George L., 113½ E. Wash. St., Pittsfield, Ill.
King, Henry R., 2661 Asbury Ave., Evanston, Ill.
King, Richard, Capt. Sn. C., P-444407, c/o 13th Malaria Control Unit, APO 503, Unit 1, c/o Postmaster, San Francisco, Calif.
Kingsbury, Harold N., 1st Lt., Sn. C., 38 Signal Hill Blvd., East St. Louis, Ill.
Kingston, Paul S., Public Health Engr., Minn. Dept. of Health, City Hall, Room 212, Rochester, Minn.
Kinney, E. F., 2204 E. Kessler Blvd., Indianapolis, Ind.
Kirchoffer, W. G., 22 N. Carroll St., Madison, Wisc.
Kirn, Matt, Sewage Treatment Plant, Dahringer Rd., Waukegan, Ill.
Klein, J. A., Supt. of Treatment Plant, Sheboygan, Wisc.
Kleiser, Paul J., 424 N. 2nd St., Clarksville, Tenn.
Knechtges, O., 2222 Hollister Ave., Madison, Wisc.
Koch, Phillip L., 3423 Viburnum Dr., Shorewood Hills, Madison, Wisc.
Koeckeritz, R. C., Asst. Opr., P. O. Box 3598, St. Paul, Minn.
Kramer, Harry P., 825 Oakland, Joliet, Ill.
Kraus, L. S., 510 Albany, Peoria, Ill.
Kuhl, F. A., Supt., Water and Light Dept., Breese, Ill.
Kuhner, Frank G., P. O. Box 871, Muncie, Ind.

Lakeside, Engr. Corp., 222 W. Adams St., Chicago, Ill.
Lamb, Miles, Supt., City Hall, Belvidere, Ill.
Langdon, L. E., Pacific Flush-Tank Co., 4241 Ravenswood Avenue, Chicago, Ill.
Langdon, Paul E., 6 N. Michigan Ave., Chicago 2, Ill.
Langwell, Louie, 305 W. Market St., Salem, Ind.
Larsen, Stanley J., 1st Lt., A. C., Lowry Field, Denver, Colo.
Larson, C. C., Springfield Sanitary Distr., R. R. No. 5, Springfield, Ill.
Larson, Keith D., Lt., Sewage Treatment Plant, South St. Paul, Minn.
Larson, L. L., 1705 Kentucky Ave., Fort Wayne, Ind.
Lautz, Harold L., State Board of Health, Madison 2, Wisc.
Lee, Oliver, 102 N. 4th St., Mt. Horeb, Wisc.
Leland, Raymond L., Capt., Station Hospital, AAB, El Paso, Tex.
Leland, Benn. J., San. Engr., 737 S. Wolcott St., Chicago, Ill.
Lentfoehr, Charles E., Plant Operator, 228 Allen St., Mayville, Wisc.
Lessig, D. H., 110½ E. Center St., Warsaw, Ind.
Lewis, R. K., 5009 Park Ave., Indianapolis, Ind.
Lind, A. Carlton, Chain Belt Co., 1600 W. Bruce St., Milwaukee, Wisc.
Linderman, Irving E., 2nd Lt., San. C., 57th Malaria Control Unit, APO 603, c/o Postmaster, Miami, Fla.
Link-Belt Co., 300 W. Pershing Rd., Chicago, Ill.
Long, H. Maynard, 309 Dearborn St., Hillsboro, Ill.
Lourinch, Louis B., Chief Opr., 2319 New York St., Whiting, Ind.
Love, James C., Opr., Sewage Plant, 337 S. Franklin St., Greensburg, Ind.
Lovett, Frank W., 300 W. Pershing Rd., Chicago, Ill.
Lubratovich, M. D., 840 Grandview Avenue, Duluth, Minn.
Ludzack, F. J., 6060 E. Washington St., Indianapolis, Ind.
Lueck, Bernard F., 540 E. So. River St., Appleton, Wisc.
Lundstrom, Karl A., Sewage Treatment Plant, South St. Paul, Minn.
Lupher, Leon P., Jr., Plant Opr., Box 389, Gulfport, Miss.
Lustig, Joseph, City Eng., Janesville, Wisc.
Lux, Kathleen, Ens. U. S. N. R., 1713 Rhode Island Ave., N.W., Washington 6, D. C.
McCall, Robert G., 1st Lt., San. C., A. U. S., Station Hosp., Camp Myles Standish, Taunton, Mass.
McCaslin, Walter R., Consulting Engr., 218 N. Spruce St., Nokomis, Ill.
McClenahan, W. J., 910 S. Michigan Ave., Chicago, Ill.
McClure, Ernest, Galva, Ill.
McCoy, Ted, Supt., Sewage Treatment Plant, 935 S. Chicago Ave., Brazil, Ind.
McDaniel, C. C., Sanitary Engr., Chicago Bridge & Iron Co., Seneca, Ill.
McGurk, Sam R., Jr., San. Engr., 2206 N. 10th St., Terre Haute, Ind.
McIlvaine, Wm. D., Jr., Electrical Engr., Minn.-St. Paul San. Dist., Box 3598 Childs Road, St. Paul, Minn.
McIntyre, John C., Sanitary Engineer, Sewage Treatment Plant, Cedar Rapids, Iowa.
McKee, Frank J., 1st Lt., 1110 Harrison St., Madison, Wisc.
McMahon, A. E., Civil Engineer, 305 Cleveland St., Menasha, Wisc.
McMullen, Wm., 1214 Constance, Collinsville, Ill.
McRae, John C., Chemist, Vermont, Illinois (Camp Ellis, Ill.)
Mabbs, John W., Mabbs Hydraulic Packing Co., 431 S. Dearborn St., Chicago, Ill.
MacDonald, J. C., 404 Stillwell Court, Del Paso Heights, Calif.
Mackin, J. C., Nine Springs Sew. Treatment Plant, Route 4, Madison 5, Wisc.
Mallory, E. B., Director of Research, Lancaster Research Laboratories, 85 Zabriskie St., Hackensack, N. J.
Manteufel, Lawrence A., 622 Henrietta St., Wausau, Wisc.
Margrave, C. E., Assistant Sanitary Engr. (State Health Dept.), 2015 Dial Court, Springfield, Ill.
Martens, Myron M., Supt., Sewage Treatment Plant, Office of Post Engr., Headquarters, Camp Breckenridge, Morganfield, Ky.
Martin, George W., Sew. Treatment Plt., Route 1, Green Bay, Wisc.
Martin, Sylvan C., 1st Lt. San. C., Internal Security Div., HNSC, Ft. Douglas, Utah
Mathews, W. W., P. O. Box 388, Gary, Ind.
Merrick, Ray, Asst. Supt., Kokomo Sew. Treat. Plant, 1244 S. Ohio St., Kokomo, Ind.
Merz, H. Spencer, 3227 W. Gate Parkway, Rockford, Ill.
Mick, K. L., 1st Lt., 0503385, San. C., P. O. Box 3598, St. Paul 1, Minn.
Mickel, Charles T., 804 N. 7th Ave., LaGrange, Ill.
Miller, Basil, Supt. Box 141, Fennimore, Wisc.

Miller, David R., Engr. in-Charge, Sewage Treatment Plants, Quarters 48 A. North Area, Great Lakes, Ill.
Miller, L. A., Box 206, Streator, Ill.
Miller, Maurice L., 408 McDowell Bldg., Louisville, Ky.
Miller, Noble, Supt., Sew. Treat. Plt., City Hall, Orleans, Ind.
Milling, Martin A., 3931 Lomond, Indianapolis 1, Ind.
Minneapolis-St. Paul San. Distr., Box 3598, St. Paul, Minn.
Moeller, Carl, Plt. Main Eng. H, Indiana State Farm, R. R. No. 2, Greencastle, Ind.
Mohlman, F. W., Dr., 910 S. Michigan, Chicago, Ill.
Monfried, Leon, Chemist, 2108 Indiana Ave., LaPorte, Ind.
Moore, Herbert, 1742 N. Prospect, Milwaukee 2, Wisc.
Moore, Lee S., Public Health Sanitarian, 35 Valley View Court, New Albany, Ind.
Moore, R. B., 1456 N. Delaware St., Indianapolis, Ind.
Morgan, Philip F., 356 N. York St., Elmhurst, Ill.
Morkert, Kenneth, 562 Roanoke Rd., Kingsford Heights, Ind.
Morris, D. K., Chemical Salesman, 2303 Hampden Ave., St. Paul, Minn.
Muegge, O. J., Room 462, State Office Bldg., Madison 2, Wisc.
Murphy, John A., 117 W. Blair St., West Chicago, Ill.
Myers, Harry L., 8152 Merrill Ave., S. Chicago Sta., Chicago, Ill.
Nauer, Louis A., Jr., 357 18th Ave., South, So. St. Paul, Minn.
Neiman, W. T., Cons. Engr., 10 W. Douglas St., Freeport, Ill.
Nelle, Richard S., Major 807 W. Grove St., Bloomington, Ill.
Nelson, D. H., Dr., Chemist, Industrial Waste Treatment Wks., Oscar Mayer & Co., 157 Division St., Madison 4, Wisc.
Neumann, Geo. B., Supt. & Opr., Bethalto, Ill.
Newton, Donald, San. Engr., 1319 Rutledge St., Madison 4, Wisc.
Nicholas, Forrest A., 7235 Jarnecke Ave., Hammond, Ind.
Nichols, M. Starr, Chemist, Wis. State Lab. of Hygiene, Madison, Wisc.
Nickel, Jack B., 96 E. Andrew Dr., Atlanta, Ga.
Niemi, Arthur G., 142 W. Howard St., Hibbing, Minn.
Niles, Thomas M., San. Engr., 6 N. Michigan Ave., Chicago 2, Ill.
Nold, Vern, Operator, Sewage Treatment Plant, 909 Bond Ave., Marion, Ind.
Nordell, Carl H., 190 E. Chestnut St., Chicago, Ill.
Norman, G. A., 1107 Penn Ave., Columbus, Ind.
Nutter, Frank H., Consulting Chemist, 1200 2nd Ave., S., Minneapolis, Minn.
Obma, Chester A., Captain, C. E., 2421 Whitmore St., Omaha, Nebr.
Odbert, Eugene, Jr., Professional Engr., City Hall, Sturgeon Bay, Wisc.
Oeffler, W. A., 120 S. Lawton St., Jasonville, Ind.
Okun, Daniel A., 1st Lt., San. C., 42 Livingston St., Brooklyn, N. Y.
Olson, Frank W., 16 S. Mallory St., Batavia, Ill.
Pacific Flush Tank Co., 4241 Ravenswood Ave., Chicago, Ill.
Palmer, John R., 1321 Monroe St., Evanston, Ill.
Parsons, Chase, Supt., Elwood Sew. Treat. Plant, 710 Main St., Elwood, Ind.
Pearsall, Ted., Opr., Sewage Treatment Plant, 305 Johnson St., Elroy, Wisc.
Pearse, Langdon, Chicago Sanitary Dist., 910 S. Michigan Ave., Chicago, Ill.
Peaslee, George A., 905 Wolcot St., Sparta, Wisc.
Peirce, W. A., Racine Water Dept., City Hall, Racine, Wis.
Pence, Irel V., Supt., Public Works, 25 W. Third St., Peru, Ind.
Perry, J. S., 2204 E. Kessler Blvd., Indianapolis, Ind.
Peterson, Ivan C., 130 N. Wells St., Chicago, Ill.
Peterson, Myhren C., Dist. Public Health Engineer, Box 308, Bemidji, Minn.
Peterson, Ralph W., Lt., 9141 Bishop St., Chicago, Ill.
Pett, K. M., Utility Opr., 2638 Garfield St., N.E., Minneapolis, Minn.
Pierce, George O., Asst. Prof. of Public Health Engr., University of Minnesota, Rm. 112, Millard Hall, Minneapolis, Minn.
Plummer, Raymond B., 4827 Chevy Chase Blvd., Chevy Chase 15, Md.
Poindexter, G. G., 231 S. Elmwood Ave., Oak Park, Ill.
Poole, B. A., Major, San. C., Medical Branch, Hq. 6th Service Command, Chicago, Ill.
Quinn, Joseph L., Jr., 1098 W. Michigan St., Indianapolis, Ind.
Racek, L., Jr., Sauk City, Wisc.
Rankin, R. S., Engr., 570 Lexington Avenue, New York, N. Y.

Read, Homer V., R. R. No. 1, Lawrenceville, Ill.
Reardon, Wm. R., 1036 North 17th St., Manitowoc, Wisc.
Redmon, Polk, Maintenance Man, Kokomo Sew. Treat. Plant, 1006 S. Courtland Ave., Kokomo, Ind.
Rees, N. B., 1609 E. Washington, Bloomington, Ill.
Rein, L. E., Pacific Flush Tank Co., 4241 E. Ravenswood Ave., Lakeview Station, Chicago, Ill.
Reynoldson, C. G., Chief Engr., Industrial Waste Treatment Wks., c/o Oscar Mayer & Co., 910 Mayer Ave., Madison 4, Wisc.
Richards, Paul W., 1st Lt., Sn. C., 3935 Graceland Ave., Indianapolis, Ind.
Richgruber, Martin, 420 E. Oak St., Sparta, Wisc.
Richman, W. F., 111 E. 8th St., Winona, Minn.
Richter, James B., Op., Industrial Waste Treatment Wks., Oscar Mayer & Co., 2557 Upham St., Madison 4, Wisc.
Richter, Paul O., 111 W. Washington St., Rm. 548, Chicago, Ill.
Riedesel, Henry A., Spring Creek Road, Rockford, Ill.
Riedesel, P. W., Dept. of Health Bldg., University of Minnesota Campus, Minneapolis, Minn.
Roab, F. H., Mgr., Water and Light Dept., Columbus, Wisc.
Roahrig, Henry L., 5608 Howard St., Omaha, Nebr.
Robins, Maurice L., P. O. Box 3598, St. Paul, Minn.
Robinson, Fred M., Opr., 211 S. West Street, Tipton, Ind.
Rodwell, Robert D., 4303 Dodge St., Omaha, Nebr.
Roe, Frank C., c/o Porous Products & Lab. Ware Dept., Carborundum Co., Niagara Falls, N. Y.
Rogers, Harvey G., Lt. Col., A.P.O. 828, c/o Postmaster, New Orleans, La.
Rogers, W. H. Supt., Downers Grove Sanitary Dist., Downers Grove, Ill.
Rohlick, Gerard A., 17 Gallatin St., Northwest, Washington, D. C.
Roll, A. H., Supt., 316 E. Main St., Chilton, Wisc.
Romaine, Burr, 237 Vincent St., Fond du Lac, Wisc.
Romeiser, C. H., 211 W. Fourth St., Auburn, Ind.
Rosemeyer, Alfred, Box 155, Red Bud, Ill.
Rosen, Milton, Commissioner of Public Works, 234 City Hall & Court House, St. Paul 2, Minn.
Ross, Herman M., 1st Lt., Sn. C., Station Hosp., Camp Hale, Pando, Colo.
Ross, W. E., Supt., 221 S. 21st St., Richmond, Ind.
Rowen, R. W., Vice-Pres., Nichols Engineering & Research Corp., 60 Wall Tower, New York, N. Y.
Ruchhoft, C. C., U. S. P. H. S., East 3rd & Kilgour Sts., Cincinnati, Ohio
Rudgal, H. T., Supt., 6530 Sheridan Rd., Kenosha, Wisc.
Ruhmann, Ovid G., Supt., 3205 Roland Ave., Belleville, Ill.
Ryan, Joseph P., 7746 Coles Avenue, Chicago, Ill.
Sager, John C., Capt., Sn. C., Station Hosp., Fort Ord, Calif.
Sala, David W., Operator, Camp Ellis, 513 S. McArthur St., McComb, Ill.
Sander[illegible], M. D., Res. Chemist, Swift & Co., Chemical Lab., Union Stock Yards, Chicago, Ill.
Saunders, E. F., c/o L. K. Cecil, 732 Kennedy Bldg., Tulsa, Okla.
Sawyer, C. N., Dr., Director, Madison Lakes Investigation, 2010 University Ave., Madison 5, Wisc.
Scheidt, Burton A., 1700 W. 91st Place, Chicago, Ill.
Schier, Lester C., 206 W. Saveland Ave., Milwaukee, Wisc.
Schlenz, Harry E., Pacific Flush-Tank Co., 4241 Ravenswood Ave., Chicago, Ill.
Schneller, M. P., Sales Engineer, Aurora Pump Company, 319 BeVier Place, Aurora, Ill.
School, Clarence E., Chemist-Engineer, 314 N. Drexel Ave., Indianapolis, Ind.
Schriner, P. J., 382 S. Lincoln, Kankakee, Ill.
Schroeder, Arthur W., Chemist, 137 Tennyson Court, Elgin, Ill.
Schroepfer, George, Box 3598, St. Paul 1, Minn.
Schubert, Frank J., U. S. N. T. S., P. O. Box 4, Round Lake, Ill.
Schwartz, Oswald, Street Commissioner, Cederburg, Wisc.
Scott, Clifton A., The American Well Works, 100 N. Broadway, Aurora, Ill.
Scott, Ralph, 1st Lt., Sn. C., Station Hospital, Camp Tyson, Tenn.
Scott, Roger J., 3522 Jackson Blvd., Chicago, Ill.
Shaw, Morton, Opr., Sewage Treatment Plant, Marion, Ind.
Shaykin, Jerome D., Chemist, 165 N. Central Ave., Chicago 44, Ill.
Shipman, R. H., State Dept. of Health, County Court House, Mankato, Minn.
Shodron, John M., Engr., 1652 Monroe St., Madison 5, Wisc.

Simpson, Maynard, Maintenance Mgr., Crane Housing Project, Crane, Ind.
Slagle, Elmer C., Room 115, Court House, Duluth, Minn.
Smith, Gilbert M., c/o Post Engineer, Camp Breckenridge, Ky.
Smith, J. Irwin, 15031 Vine St., Harvey, Ill.
Smith, R. L., Cons. Engr., 2083 Wellesley Ave., St. Paul, Minn.
Smith, R. Trumbull, 9818 N. E. Mason St., Portland 13, Ore.
Smith, Ralph A., 1st Lt., 1763 N. 75th St., Wauwatosa, Wisc.
Sneed, Glenn J., Opr., 60 Gilbert Ave., Terre Haute, Ind.
Snow, Donald L., 2013 Mayview Ave., Cleveland, Ohio
Somers, Verne, 219 N. Third St., Stevens Point, Wisc.
Sowden, Howard J., Twin Cities Ordnance Plant, Zone 13, Bldg. 116, New Brighten, Minn.
Spaeder, Harold J., Major, Hq. 2nd Army, Memphis, Tenn.
Sperry, Walter A., P. O. Box 241, Aurora, Ill.
Spiegel, Milton, 575 Drexel Ave., Glencoe, Ill.
Spitzer, Elroy F. (Student, Univ. of Wisconsin), 17 N. Mills St., Madison 5, Wisc.
Spurgeon, Ralph, 124 Cavin St., Ligonier, Ind.
Stauff, Paul V., Park Hotel, Eveleth, Minn.
Steffen, A. J., Capt., 1348 Glenlake Ave., Chicago, Ill.
Steffes, Arnold M., 821 Fairmount Ave., St. Paul 5, Minn.
Steindorf, R. T., Chain Belt Co., 20 N. Wacker Dr., Chicago, Ill.
Storey, Benjamin M., 2240 Edgecomb Rd., St. Paul, Minn.
Strickland, Raymond, Asst. Plant Opr., 525 Christy St., Marion, Ind.
Stroessenreuther, G. A., 785 Ashland Ave., St. Paul, Minn.
Stutz, C. N., 314 Unity Bldg., Bloomington, Ill.
Sund, Gutorm, Plant Opr., Altoona, Wisc.
Suter, Max, 405 W. Elm St., Urbana, Ill.
Swope, Gladys, Sewage Treatment Works, Dahringer Road, Waukegan, Ill.
Tapleshay, John A., 4102 Harwood Rd., South Euclid, Ohio
Tapping, C. H., 7718 Cornell, Chicago, Ill.
Tempest, W. F., Portland Cement Association, 33 W. Grand Blvd., Chicago, Ill.
Tennant, H. V., Cons. Engr., City Bank Bldg., Portage, Wisc.
Thalheimer, Marce, E. Pearl St., Batesville, Ind.
Thayer, Paul M., 3933 No. Prospect Ave., Milwaukee, Wisc.
Thierman, Frank, Opr., Sewage Treatment Plant, 313 Jackson St., Sheyboygan Falls, Wisc.
Tholin, A. L., Lt. (C. E. C.) U. S. N. R., 32 U. S. N. Constr. Battalion, Fleet P. O., San Francisco, Calif.
Thomas, Ariel A., 1st Lt., Sn. C., 4 Butler St., Blackstone, Mass.
Thompson, H. Loren, Asst. Prof. of Civil Engr., Northwestern Technological Institute, Evanston, Ill.
Timm, Arthur, Asst. Supt., 222 W. William St., Michigan City, Ind.
Tomek, A. O., 926 17th St., S. Arlington, Va.
Townsend, Darwin W., 2219 E. Belleview Place, Milwaukee, Wisc.
Troemper, Paul A., 1st Lts., Sn. C., Hq. 7th Service Command, Omaha, Nebr.
Trulander, Wm. M., 1316 7th St., South, Minneapolis, Minn.
Tuhus, Kenneth, c/o Knute Posselt, Kendall, Wisc.
Turpin, U. F., 2518 Ridgeway Ave., Evanston, Ill.
Twin City Testing & Engr. Lab., Galen J. Jasper, Engr. & Partner, 2440 Franklin Ave., St. Paul, Minn.
Van Praag, Alex, Jr., 447 Standard Office Bldg., Decatur, Ill.
Veatch, F. M., Jr., 1st Lts., Sn. C., c/o Black & Veatch, 4706 Broadway, Kansas City, Mo.
Wade, Clarence, Supt., Sewage Treatment Plt., City Hall, Princeton, Ind.
Wade, W. J., 1722 Fremont Ave., North, Minneapolis, Minn.
Wahlstrom, Carl A., 419 North 23rd St., La Crosse, Wisc.
Walbridge, Thornton, Supt., Lake Bluff, Ill.
Walker, J., Donald, American Well Wks., Sanitary Div., Aurora, Ill.
Walton, Graham, U. S. Public Health Service, District No. 8, 617 Colorado Bldg., Denver 2, Colo.
Ward, C. N., 550 State St., Madison, Wisc.
Ward, Oscar, Operator, 1500 S. Cedar St., Marshfield, Wisc.
Warden, Lotus A., City Engr., 821 S. Armstrong, Kokomo, Ind.
Wardwell, T. M., City Manager, Rhinelander, Wisc.
Warrick, L. F., Rm. 458, State Off. Bldg., Madison, Wisc.
Waters, George E., Asst. Op., Minn.-St. Paul San. Dist., 2130 Princeton Ave., St. Paul, Minn.
Watters, T. G., 824 E. Washington St., Hoopeston, Ill.
Weasner, Leo, Asst. Chemist, 2016 S. Belmont Ave., Indianapolis, Ind.

Weeber, Wm. Keith, 1st Lt., Sn. C., Hq. MRTC-Sanit. Tech. School, Camp Barkeley, Tex.

Wells, E. Roy, 11 N. LaSalle St., Ill. Post-War Planning Comm., 11 N. La Salle St., Chicago 3, Ill.

West, A. W., 2621 Van Hise Ave., Madison, Wisc.

Westfall, Milton, Opr., 455 N. Court St., Sturgeon Bay, Wisc.

Wheeler, C. E., Jr., 11127 Homewood Ave., Chicago, Ill.

White, Paul R., 505 Alameda Ave., Muncie, Ind.

Whitney, Col. Alfred C., Twin Cities Ordnance Plant, 1841 Dayton Ave., St. Paul, Minn.

Whittaker, H. A., Chief San. Engr., Minnesota Dept. of Health, Div. of Sanitation, Minneapolis, Minn.

Wiegert, Lester O., 118½ N. Andrews St., Shawano, Wisc.

Willett, C. K., Engr., City National Bank Bldg., Dixon, Ill.

Williams, C. C., Ill. Dept. Public Health, 21 E. Van Buren St., Joliet, Ill.

Williams, Charles W., 59 Ewing St., Peru, Ind.

Williams, Clyde E., 2180 Hollywood Place, South Bend, Ind.

Williams, Leon G., 1309 Westover Ave., Norfolk 7, Va.

Williamson, F. Martin, Capt., 1171 Wesley Ave., Oak Park, Ill.

Wilson, Harry L., 3634 47th Ave., So., Minneapolis, Minn.

Wilson, J. B., Cons. Engr., 512 K of P Bldg., Indianapolis, Ind.

Wilson, John, 901 Alworth Bldg., Duluth 2, Minn.

Wilson, Robert A., Dist. San. Engr., 325 Gooding St., La Salle, Ill.

Wilson, R. D., Consulting Engineer, Christie Clinic Building, Champaign, Ill.

Windell, Talmage, Supt., Sewage Treat. Plt., Corydon, Ind.

Winter, Orvan V., Opr., Sewage Treatment Plant, Clifford, Ind.

Wirth, Harvey E., 1st Lt., Sn. C., Base Sanitary Office, Station Medical Detachment, Baton Rouge, La.

Wisely, F. E., 5049a, Oleatha Ave., St. Louis, Mo.

Wisely, W. H., Executive Sec.-Editor, F. S. W. A., 325 6 Illinois Bldg., Champaign, Ill.

Wisniewski, Theo, R., 458 State Off. Bldg., Madison 2, Wisc.

Wittenborn, E. L., 904 W. Lawrence, Springfield, Ill.

Woltmann, J. J., Consulting Engr., 314 Unity Bldg., Bloomington, Ill.

Wright, George I., Opr., Sewage Treatment Plant, 1108 W. New York St., Indianapolis, Ind.

Wurtenberger, Helen, Chemist, 309 West 10th St., Anderson, Ind.

Yeager, Bert T., City Hall, Engineer's Office, Sioux Falls, S. Dak.

Yeomans Brothers Co., 1433 Dayton St., Chicago 22, Ill.

Zeldenrust, Albert T., Lt. Post Engr., Ft. Wm. Henry Harrison, Mont.

Zetterberg, Edw., Chemist & Chemistry Teacher, 1101 N. Jefferson, Muncie, Ind.

Zoglmann, Martin, Opr., General Delivery, Shawano, Wisc.

Zurbuch, N. F., 204 S Utility Bldg., Fort Wayne 2, Ind.

Dakota Water and Sewage Works Conference

(North Dakota Section)

Arnold, Earl H., Asst. San. Engr., State Dept. of Health, Bismarck, N. Dak.

Bavone, A. L., Sanitary Engr., City-County Health Unit, Minot, N. Dak.

Clark, L. K., Major, 0-27577, Det. 22nd Post Hq., A.P.O. 713, c/o Postmaster, San Francisco, Calif.

Gilbertson, W. E., Asst. San. Engr., U. S. Public Health Service, Volunteer Bldg., Atlanta, Ga.

Hanson, Harry G., P. A., San. Engr., U. S. Public Health Service, Volunteer Bldg., Atlanta, Ga.

Kleven, John, Sewage Works Supt., Grand Forks, N. Dak.

Lauster, K. C., State Dept. of Health, Bismarck, N. Dak.

Lindsten, H. C., Wallace & Tiernan Co., Winnipeg, Manitoba, Can.

Pinney, F. W., 1413 8th St., No., Fargo, N. Dak.

Svore, Jerome H., Senior Sanitary Engr., State Dept. of Health, Bismarck, N. Dak.

Tarbell, Park, City Engineer, Fargo, N. Dak.

(South Dakota Section)

Bielmaier, Joe, Water Works Supt., Wall, S. Dak.

Bowman, C. R., Asst. Engr., State Bd. of Health, Pierre, S. Dak.

Campbell, A. S., Supt. Water Treatment Plant, Chamberlain, S. Dak.

Cochrane, W. F., U. S. Engineer Office, 1709 Jackson St., Omaha, Nebr.

Colahan, J. G., Superintendent of Water Works, Aberdeen, S. Dak.

Dixon, F. S., Midwest Equipment Co., 1624 Harmon Place, Minneapolis, Minn.

Holst, J. E., City Chemist, Mitchell, S. Dak.

Hopkins, Glen J., Div. of San. Engr., State Bd. of Health, Pierre, S. Dak.

Hoy, M. J., Supt. Water & Sewers, Watertown, S. Dak.

Jacobson, Geo. L., Civil Engr., Dept., South Dakota State School of Mines, Rapid City, S. Dak.

Lacey, Howard E., Asst. San. Engr., 210 West 21st St., Sioux Falls, S. Dak.

Mailloux, Wm., Sewage Plant Opr., Sturgis, S. Dak.

Mather, Edward K., Dakota Engineering Co., 309 Western Bldg., Mitchell, S. Dak.

Mathews, E. R., Div. of San. Engr., State Bd. of Health, Pierre, S. Dak.

Mitchell, Robert D., 114 Spring St., Falls Church, Va.

Morris, Lee, Box 606, Provo, S. Dak.

Murschel, Jacob, Supt. Water & Sewage, Webster, S. Dak.

Nangle, B. A., Pub. Health Engr., State Bd. of Health, Pierre, S. Dak.

Pierce, H. M., City Engr., Huron, S. Dak.

Poston, R. E., Sanitary Engineer, 428 San Antonio St., Santa Fe, N. Mex.

Price, Charles R., Supt. Sewage Treatment Plant, Box 590, Rapid City, S. Dak.

Schroeder, W. L., Water & Sewer Commissioner, Miller, S. Dak.

Sorbel, J. L., Associate Engr., State Bd. of Health, Pierre, S. Dak.

Spicker, Roy G., c/o State Bd. of Health, Pierre, S. Dak.

Spies, Kenneth H., 1617 N.E. 65th Ave., Portland 17, Ore.

Stapf, R. J., State Bd. of Health, Pierre, S. Dak.

Towne, W. W., Capt., Sn. C., Station Hospital, Camp Lee, Va.

Federal Sewage Research Association

Mr. Frank E. DeMartini, *Secretary-Treasurer*, U. S. P. H. S., 2000 Massachusetts Ave., N.W., Washington, D. C.

Agnano, Paul, U. S. Public Health Service, 2000 Massachusetts Ave., N.W., Washington, D. C.

Aldridge, Frederick F., Asst. San. Engr., 4055 Grant St., N.W., Washington, D. C.

Anderson, Lewis D., P. O. Box 424, Hampton, Va.

Andrews, John, U. S. Pub. Health Service, 2000 Massachusetts Ave., N.W., Washington, D. C.

Arnold, G. E., Regional Sanitary Engr., U. S. Public Health Service, 477 Colon Ave., San Francisco, Calif.

Berry, C. Radford, 1215 North Second St., Harrisburg, Pa.

Blew, M. J., Lieut. Col. Sanitary Corps, U. S. A., Hdg. Fourth Service Command, Old Post Office Bldg., Atlanta, Ga.

Boyce, Earnest, U. S. Pub. Health Serv., 2000 Massachusetts Ave., N.W., Washington, D. C.

Browning, Claud F., U. S. Public Health Service, 2000 Massachusetts Ave., N.W., Washington, D. C.

Butterfield, C. T., U. S. Public Health Service, Third & Kilgour Sts., Cincinnati, Ohio

Calderara, O. J., Public Roads Administration, Alaska Highway Project, Medical & Sanitary Program, Whitehorse, Yukon Territory, Can.

Capone, Domenic, 342 Hollingsworth Manor, Elkton, Md.

Carlson, H. R., Rm. 1223, Flood Bldg., San Francisco, Calif.

Carnahan, Chas. T., Lt., U. S. N. R., Malaria Control, Hadnot Point, Marine Barracks, Camp LeJeune, New River, N. Car.

Castagna, Samuel C., Sussex-Prince George-Dinwiddie Health District, Dinwiddie, Va.

Chapman, Howard W., 33 Lee Drive, Lake Forest, Wilmington, N. Car.

Coffey, Joseph H., Wayne County Health Dept., Goldsboro, N. Car.

Crockett, Vernon P., 619 Ann Ave., Kansas City 16, Kans.

Crohurst, Harry R., 6504 Park Lane, Mariemont, Ohio

Dashiell, Walter N., Apt. 383, Guatemala City, Guatemala

Decker, Herbert M., Lt., Sn. C., AUS 159-02 84th Ave., Jamaica 2, N. Y.

DeMartini, F. E., U. S. P. H. S., 2000 Massachusetts Ave., N.W., Washington, D. C.

Dopmeyer, A. L., U. S. Public Health Serv., 1223 Flood Bldg., San Francisco, Calif.

Ettinger, M. B., U. S. Public Health Service, East Third & Kilgour Sts., Cincinnati, Ohio

Feldhake, C. J., Kentucky State Health Dept., 620 S. Third St., Louisville, Ky.

Fischback, Hyman S., Lake Eagle County Health Unit, Leadville, Colo.

Fisher, Lawrence M., U. S. Public Health Service, 852 U. S. Customs House, Chicago, Ill.

Fittro, Louis L., 1409 West Pike St., Clarksburg, W. Va.

Fletcher, Cecil C., U. S. Pub. Health Service Dist. No. 2, National Institute of Health, Bethesda, Md.

Freeman, A. B., Asst. Pub. Health Engr., U. S. Public Health Service, 1223 Flood Bldg., San Francisco, Calif.

Fuchs, Abraham W., U. S. Public Health Service, 2000 Massachusetts Ave., N.W., Washington, D. C.

Fuhrman, Ralph E., Sewage Treatment Plant, Blue Plains, D. C.

Garthe, E. C., U. S. P. H. S., Sub. Treasury Bldg., Wall, Pine and Nassau Sts., New York, N. Y.

Gordon, Jr. B., Room No. 309, District Building, Washington, D. C.

Graber, Ralph Carl, U. S. Public Health Service, Gulf Health Department, El Campo, Tex.

Grimsley, J. T., City Health Dept., City of Houston, Houston, Tex.

Hamblett, W. C., 1st Lt., Station Hospital, B. A. A. F., Bainbridge, Ga.

Hansen, Chris A., Asst. San. Engr., Malaria Control in War Areas, U. S. Public Health Service, 605 Volunteer Bldg., Atlanta, Ga.

Hanson, Harry G., P. A., San. Engr., U. S. Public Health Service, Volunteer Bldg., Atlanta, Ga.

Hommon, H. B., Bureau of San. Engineering, Calif. State Dept. of Pub. Health, 15 Shattuck Sq., Berkeley, Calif.

Hope, Malcolm C., Assistant Sanitary Engineer, U. S. Public Health Service Dist. No. 7, 603 B. M. A. Bldg., Kansas City 8, Mo.

Hopkins, Omar C., U. S. P. H. S., 603 B. M. A. Bldg., Kansas City, Mo.

Hopler, Harold S., Charleston Co. Health Dept., Rm. 322 Old Citadel, Charleston, S. Car.

Hoskins, J. K., U. S. Public Health Service, 2000 Massachusetts Ave., N.W., Washington, D. C.

Jones, S. Leary, Health & Sanitation Section, Tennessee Valley Authority, Wilson Dam, Ala.

Kachmar, John F., 979 Neptune, Akron, Ohio

Kochtitzky, O. W., Jr., c/o Health and Sanitation Section, TVA Examining Bldg., Fontana Dam, N. Car.

Lambert, Lowell E., Jr., Public Health Engineer, U. S. Public Health Service, Clark County Dept. of Public Health, 217 Carson Ave., Las Vegas, Nev.

Lamoureux, Vincent B., 1652 Adams St., Denver, Colo.

Lang, Sheldon L., State Health Dept., Rm. 307, Little Rock, Ark.

Langdon, B. J., P. O. Box 47, Olathe, Kans.

LeBosquet, M. L., U. S. Public Health Service, E. Third & Kilgour Sts., Cincinnati, Ohio

LeVan, James H., U. S. Public Health Service, Dist. No. 1, Sub-Treasury Bldg., Wall, Nassau & Pine Sts., New York, N. Y.

Lewis, G. M., 1314 High St., Williamsport, Pa.

Linders, Edward, Gordon Hotel, 916 16th St., N.W., Washington, D. C.

Ludwig, Harvey F., Asst. San. Engr., USPHS, Office for Malaria Control in War Areas, 605 Volunteer Bldg., Atlanta, Ga.

McAuley, John Dennis, Mobile County Health Dept., Mobile, Ala.

McCallum, G. E., Office of Civilian Defense, Du Pont Circle Bldg., Washington, D. C.

McNamee, Paul D., Sewage Treatment Plant, Blue Plains, D. C.

MacKenzie, Vernon G., U. S. Public Health Ser., 2000 Massachusetts Ave., N. W., Washington, D. C.

Maier, F. J., USPHS, Subtreasury Bldg., Wall, Pine and Nassau Sts., New York, N. Y.

Mark, Richard S., 2023 Patterson Rd., West Hyattsville, Md.

Meckler, Wm. G., U. S. Public Health Service, E. Third & Kilgour Sts., Cincinnati 2, Ohio

Middleton, Francis M., U. S. Public Health Service, E. Third and Kilgour Sts., Cincinnati, Ohio

Mfller, A. P., U. S. Public Health Ser., Subtreasury Bldg., Wall, Pine and Nassau Sts., New York City, N. Y.

Moore, W. A., Chemist, U. S. Public Health Service, E. 3rd and Kilgour Sts., Cincinnati, Ohio

Moss, F. J., U. S. Public Health Service, 8th Floor Mercantile Bank Bldg., Dallas, Tex.

Nasi, Kaarlo W., Asst. San. Engr., USPHS, Plague Suppression Measures Lab., 14th & Lake, San Francisco, Calif.

Nesheim, Arnold, 924 Elm St., Salt Lake City, Utah

Norris, Francis L., Jr., Chemist, U. S. Public Health Service, East Third & Kilgour Sts., Cincinnati, Ohio

Old, N. N., USPHS, 2000 Massachusetts Ave., N.W., Washington, D. C.

Palange, Ralph C., U. S. Public Health Service, 605 Volunteer Bldg., Atlanta, Ga.

Pirnie, Malcolm, Jr., U. S. Public Health Service, Alaskan Road Project, Public Roads Administration, 302 Hoge Bldg., Seattle, Wash.

Porges, Ralph; USPHS, 41 Exchange Place, Atlanta, Ga.

Rice, John E., 161 Chesapeake St., S.W., Washington 20, D. C.

Roberts, F. C., Jr., 5645 Cherry St., Kansas City, Mo.

Rogers, Jack C., Norfolk City Health Dept., Norfolk 10, Va.

Ruchhoft, C. C., U. S. Public Health Service, E. Third & Kilgour Sts., Cincinnati, Ohio

Scott, Guy R., Sanitation Section, Tennessee Valley Authority, Wilson Dam, Ala.

Shaw, Frank R., U. S. Pub. Health Ser. Dist. No. 2, Bethesda, Md.

Sloan, Garrett, U. S. Public Health Service, Dist. No. 11, Office, Juneau, Alaska

Smith, Russell S., c/o U. S. Public Health Service, E. Third & Kilgour Sts., Cincinnati, Ohio

Solander, Arvo, Lt., Surgeon's Office, Camp Robinson, Ark.

Spencer, Charles C., c/o Pan American Sanitary Bu., Washington, D. C.

Stevens, Donald B., 18 Highland Ave., Newburyport, Mass.

Streeter, H. W., USPHS, E. Third & Kilgour Sts., Cincinnati, Ohio

Tarbett, R. E., U. S. Public Health Ser., 2000 Massachusetts Ave., N.W., Washington, D. C.

Tetzlaff, Frank, 4060 Walsh St., Chevy Chase, Md.

Theriault, E. J., U. S. Pub. Health Ser., National Institute of Health, Bethesda, Md.

Udell, Harold, Lt. (Sn. C.), 24 Lafayette St., Dracut, Mass.

Walker, Wm. W., Dr., U. S. Public Health Service, E. Third & Kilgour Sts., Cincinnati, Ohio

Wallach, Arthur, N. Y. State Dept. of Health, 411 Herald Bldg., Syracuse, N. Y.

Weibel, S. R., U. S. Public Health Service, E. Third & Kilgour Sts., Cincinnati, Ohio

Weiner, Daniel J., Local Health Dept., 803 N. Palafox, Pensacola, Fla.

Wiley, John S., 1307 Pere Marquette Bldg., New Orleans, La.

Woodward, R. L., USPHS, Malaria Control in War Areas, Rm. 6126, Municipal Bldg., 3rd and C Sts., N.W., Washington 1, D. C.

Wright, Charles T., U. S. Public Health Service Dist. No. 8, 617 Colorado Bldg., Denver, Colo.

Yaffe, C. D., U. S. Pub. Health Ser., c/o Tenn. Dept. of Pub. Health, Nashville, Tenn.

Florida Sewage Works Association

Mr. J. R. Hoy, *Secretary-Treasurer*, 404 Hildebrandt Bldg., Jacksonville, Fla.

Allen, Edw. H., 2611 Forbes St., Jacksonville, Fla.

Angas, Robt. M., 420 Hildebrandt Bldg., Jacksonville 2, Fla.

Brennan, Ralph F., Supt. Water Works, Daytona Beach, Fla.

Briley, Harold D., Apt. 5, 415 South Palmetto Avenue, Daytona Beach, Fla.

Carothers, Charles H., Route 1, Box 165, Arcadia, Fla.

Clifford, Gilbert W., 3903 Saint Johns Ave., Jacksonville 5, Fla.

Connell, Maurice H., Consulting Engineer, 816 Langford Bldg., Miami, Fla.

DeWolf, A. B., Mechanical Engr., Dept. of Water & Sewers, City of Miami, Dade County Court House, Miami, Fla.

Dodd, C. K. S., Consulting Engr., Sarasota, Fla.

Drew, Leland F., Apt. P 11, Lamer Heights, Camp Wheeler, Macon, Ga.

Eidsness, Fred A., Asst. San. Engr., Florida State Board of Health, Jacksonville, Fla.

Feltham, John C., 4513 Kingsbery St., Jacksonville, Fla.

Ferguson, Gerald W., U. S. P. H. S., Room 322, The Center, Charleston 29, S. Car.

Fiveash, Charles E., Supt. of Plants, City of Fort Lauderdale, P. O. Box 1113, Fort Lauderdale, Fla.

Garland, C. F., Captain, Apt. B-1, 3462 So. Stafford, St., Arlington (Fairlington), Va.

Gilbert, J. Miles, 325 E. Broadway, E. St. Louis, Ill.

Gillespie, Wylie W., Box 1048, Jacksonville, Fla.
Goicoechea, Prof. Leandro de, Escuela de Ingenieros Y Arquitectos, Universidad de la Habana, Habana, Cuba
Green, Wingate, Post Engineer's Office, Eglin Field, Fla.
Hanlon, D. A., Supt. Pub. Wks., 824 Newark St., West Palm Beach, Fla.
Harding, Carl G., Pompano, Fla.
Hartline, Wm. C., West First St., Sanford, Fla.
Hoy, J. R., Distr., Mgr., Wallace & Tiernan Co., Inc., 404 Hildebrandt Bldg., Jacksonville, Fla.
James, Norman S., Fla. State Hospital, Chattahoochee, Fla.
Jenson, Theodore B., Senior Engr., U. S. Engineers, P. O. Box 294, Jacksonville, Fla.
Jones, Arthur C., 1351 W. Arlington St., Gainesville, Fla.
Keller, S. K., General Supt., Pinellas County Water System, Clearwater, Fla.
King, L. H., c/o Florida Utilities Corp., Winter Park, Fla.
Lee, David B., Station Hospital, Camp Haan, Calif.
Marrs, Paul, General Delivery, Rockledge, Fla.
Michaels, A. P., Consulting Engr., P. O. Box 974, Orlando, Fla.
Miller, John B., Acting Director, Bureau of Sanitary Engineering, State Board of Health, Jacksonville, Fla.
Newman, Alfred C., City Manager, Leesburg, Fla.
Phelps, Ellis K., Live Oak, Fla.
Pizie, Stuart G., Sales Engineer, Chicago Pump Co., 223 S. W. 31st Road, Miami, Fla.
Powell, Reuben R., c/o Office of the Post Engineer, Avon Park Bombing Range, Avon Park, Fla.
Reid, George W., Prof., Hydraulics Lab., University of Florida, Gainesville, Fla.
Richheimer, Charles E., Consulting Engr., G. A. Youngberg & Assoc., Lynch Bldg., Jacksonville, Fla.
Ruge, J. Herman, Box 365, Dunedin, Fla.
Ruggles, M. H., 5608 Manning Ave., West Palm Beach, Fla.
Shapiro, Maurice A., P. O. Box 1228, Panama City, Fla.
Sperling, Elmer J., U. S. Engineers Office, Little Rock, Ark.
St. John, Conrad H., Box 1411, Pensacola, Fla.
Sweeney, J. Stanley, Supt. Sewage Treatment, City Hall, Pensacola, Fla.
Sweet, Theodore T., 148 Southeast 14th Terrace, Miami, Fla.
Taylor, D. R., Capt., 1112 Reading Drive, Orlando, Fla.
Timmons, Cyrus L., 1463 Talbot Ave., Jacksonville, Fla.
Tims, Wm. C., P. O. Box 108, Waldo, Fla.
Vickery, John U., 608 S. W. 7th Ave., Fort Lauderdale, Fla.
Wells, S. W., 1st Lt., Sanitary Corps, 700 Mississippi Ave., Greenwood, Miss.
Wild, Harry E., U. S. Engineer Office, Jacksonville, Fla.
Williamson, A. E., Major, Sn. C., c/o E. H. Mallonee, Laurel, Md.
Williamson, Joe, Jr., 415 S. Palmetto Ave., Daytona Beach, Fla.

Georgia Water and Sewage Association

Mr. V. P. Enloe, *Secretary-Treasurer*, R. F. D. No. 5, Atlanta, Ga.

Aldridge, M. G., Supt. of Water Supply, Camp Wheeler, Ga.
Baker, Hugh L., Gnome Trail, Lookout Mountain, Tenn.
Bean, Carl S., Capt., c/o Post Engineer, Key Field, Miss.
Bragg, J. M., Supt. Sewage Disposal Plant, Moultrie, Ga.
Bryant, W. G., Supt. Water and Sewage Dept., Griffin, Ga.
Chandler, John B., Asst. Sanitation Engineer, Bell Aircraft Corp., Dept. 36, Marietta, Ga.
Craig, J. D., Supt. Water Dept., Madison, Ga.
Davis, T. J., c/o Brighton Mills, Inc., Shannon, Ga.
De Jarnette, N. M., Associate Director, Public Health Engineering, 245 State Office Bldg., Atlanta, Ga.
Earl, Ralph, Sanitary Engineer, c/o Post Engineer, Moody Field, Valdosta, Ga.
Earnest, Lloyd, Sr., Sew. Plant Opr., Turner Field, 241 Broad St., Albany, Ga.
Edmond, H. P., City Engr., Valdosta, Ga.
Ehloe, V. P., Supt., R. M. Clayton Plant, R. F. D. No. 5, Box 363, Atlanta, Ga.
Frazier, Royall C., Chemist A. A. F., Leland, Miss.
Frith, G. R., Ga. Dept. of Health, 245 State Off. Bldg., Atlanta, Ga.
Gilman, Harry L., c/o Engineering Service, Asst. Toxicologist, Huntsville Arsenal, Ala.

Gran, Dr. John E., School of Chemistry, Univ. of Ala., University, Ala.
Handley, L. H., Supt. Water Works and Sewage, 110 Orion St., La Grange, Ga.
Hansell, Wm. A., Asst. Chief Const. & Engr. of Sewers, City Hall, Atlanta, Ga. (Deceased)
Hansell, Wm. S., Jr., San C-0521051, 96th General Hospital, Camp Moxey, Tex.
Hicklin, R. G., Consulting Engr., c/o Robert & Co., 706 Bona Allen Bldg., Atlanta, Ga.
Hobbs, Roy L., Assoc. Sanitary Engineer, Camp Rucker, Ala.
Houston, W. J., 610 Red Rock Bldg., Atlanta, Ga.
Humphries, J. I., Edgewood, Columbus, Ga.
Jacobs, L. L., San. Engr., Camp Gordon, 1510 Pendleton Rd., Augusta, Ga.
Job, Richard C., State Tuberculosis Sanatorium, Alto, Ga.
Kaiser, C. T., R & U Branch, 4th Service Command, U. S. Army Engineers, Atlanta, Ga.
King, Cooley B., Box 323, Flora, Miss.
Knapp, Henry A., Supt. Intrenchment Creek and South River Sewage Treatment Plants, R. F. D. Box 332, Route 3, Atlanta, Ga.
Koruzo, John E., R & U. Unit, 4th Service Command, U. S. A., Atlanta, Ga.
Lenneau, F. B., Supt. Water & Sew. Wks., Ashburn, Ga.
McAuley, Wm. F., Sanitation Engr., Bell Aircraft Corp., Dept. 36, Marietta, Ga.
Naehr, Harry F., P. O. Box 1523, Fort Benning, Ga.
Nixon, M. B., 301 City Hall, Atlanta, Ga.
Page, C. A., Supt. Water & Light Dept., Moultrie, Ga.
Ray, Clayton B., Clayton Sewage Treatment Plant, R. No. 5, Box 363, Atlanta, Ga.
Reaves, S. H., 4015 Wickam Terrace, Savannah, Ga.
Robinson, Philip L., 2815 Springhill Ave., Crichton, Ala.
Scales, E. P., Deer Park Circle, Nashville 5, Tenn.
Simmons, M. F., Supt. Water & Sewage, City of Douglas, Douglas, Ga.
Simonton, Lewis R., Supt. of Water Filtration and Sew. Treat., Griffin, Ga.
Singleton, M. T., C & S Bank Bldg., Atlanta, Ga.
Smith, W. Austin, Smith & Gillespie, P. O. Box 1048, Jacksonville, Fla.
Stringer, R. M., Asst. Engr., Mississippi State Bd. of Health, Jackson, Miss.
Sullivan, R. H., 229 E. Jefferson St., Thomasville, Ga.
Swenson, John P., 1st Lt., Sanitary Corps, Box 68, Station Hospital, Fort Jackson, S. Car.
Taylor, F. W., Branch Mgr., Chain Belt Co., 601 Mortgage Guarantee Bldg., Atlanta, Ga.
Weaver, W. H., City Engineer, City Hall, Decatur, Ga.
Weir, Paul, Asst. Gen. Mgr., Atlanta Water Works, 1 Boyd Road, N.W., Atlanta, Ga.
Whelchel, H. E., City Hall, College Park, Ga.
Wilbanks, Lowry G., Water and Sewage Plant Operator, Camp Toccoa, Toccoa, Ga.

Iowa Wastes Disposal Association

Mr. L. J. Murphy, *Secretary-Treasurer*, c/o Iowa State College, Ames, Iowa

Ahrens, G. C., 2115 S. 61st St., Omaha, Nebr.
Ames, City of, c/o Charles Alexander, Supt. of Water Works & Sewage Works, Ames, Iowa
Barklage, O. F., Sales Engr., 423 South 38th Ave., Omaha, Nebr.
Bartow, Edward, Prof., Chemistry Bldg., State Univ. of Iowa, Iowa City, Iowa
Bond, Richard C., Public Health Engineering Division, State Department of Health, Des Moines, Iowa
Buell, Walter E., Buell & Winter Engr. Co., Insurance Exchange Bldg., Sioux City, Iowa
Clear Lake, City of, c/o James A. Buck, Operator Sewage Works, Clear Lake, Iowa
Crawford, L. C., Distr. Engr., 508 Hydraulic Laboratory, Iowa City, Iowa
Dawson, F. M., Dean of College of Engineering, State Univ. of Iowa, Iowa City, Iowa
Des Moines, City of, c/o Paul Winfrey, Supt., Municipal Sewage Works, Des Moines, Iowa
Garwood, Kirk, Supt., Municipal Sew. Wks., R. R. No. 4, Grinnell, Iowa
Green Howard R., H. R. Green Company, 208-210 Bever Bldg., Cedar Rapids, Iowa
Hammer, Vernon Benjamin, Asst. San. Engr. (R), U. S. P. H. S. District No. 6, San Juan, Puerto Rico
Holtkamp, Leo, Supt. Sewage Works, Webster City, Iowa
Iowa City, City of, c/o Robert D. Mott, Supt. Sewage Works, Iowa City, Iowa
Johnson, Robert T., 522 Roche, Knoxville, Iowa
Klippel, Floyd, City Manager, 321 Stevens St., Iowa Falls, Iowa

Lovell, Theodore R., 210 N. 2nd St., Marshalltown, Iowa
Miller, Robert G., Supt. Sewage Plant, 807 Fourth Avenue, Vinton, Iowa
Mullinex, Charles D., Public Health Division, State Health Dept., Des Moines, Iowa
Murphy, Lindon J., 102 Service Bldg., Iowa State College, Ames, Iowa
Nessa, Herbert, Supt. Municipal Sew. Wks., Forest City, Iowa
Newell, Town of, c/o Frank W. Wilter, Supt. Sewage Works, Newell, Iowa
Newton, City of, c/o H. J. Lammers, City Clerk, Newton, Iowa
Osage, City of, c/o Richard Coonradt, Supt. of Sewage Works, Osage, Iowa
Pray, John W., Manager of Utilities, City Water Dept., Fort Dodge, Iowa
Pyle, Wm., Jr., City Hall, Oskaloosa, Iowa
Roach, Vincent, 117 N. Russell Ave., Ames, Iowa
Schenk, E. F., 214 Waterloo Bldg., Waterloo, Iowa
Schlickelman, R. J., 1st Lt., Sn. C., Station Hospital, Fort Riley, Kans.
Schrack, Bert, Supt., Sewage Works, Oelwein Iowa
Sedlacek, A. J., Supt. of Sew. Wks., Pocahontas, Iowa
Spencer, City of, c/o City Clerk, Spencer, Iowa
Spragg, H. J., Supt., Iowa Great Lakes Sewage Works, Box 187, Arnolds Park, Iowa
Stanley, C. M., Stanley Engineering Co., Box 807, Muscatine, Iowa
Strelow, J. L., 1616 Jersey Ridge, Davenport, Iowa
Swender, Harvey P., 2910 Easton Blvd., Des Moines, Iowa
Toledo, City of, c/o Ed. Stewart, City Engineer, Toledo, Iowa
Urick, R. H., 749 32nd St., Des Moines, Iowa
Waterman, Earle L., Prof., Civil Engineering Dept., 208 Engineering Bldg., State University of Iowa, Iowa City, Iowa
Wieters, A. H., Director, Public Health Engr., Div., State Dept. of Health, Des Moines, Iowa
Wilson, C. T., 620 W. Third St., Waterloo, Iowa
Woolley, B. C., City Engineer, Le Mars, Iowa

Kansas Water and Sewage Works Association

Mr. Paul D. Haney, *Secretary-Treasurer*, 1745 Louisiana St., Lawrence, Kans.

Boyce, Earnest, U. S. Public Health Service, 2000 Massachusetts Ave., N.W., Washington, D. C.
Brethour, Herman, 709 W. Crawford, Salina, Kans.
Cochrum, G. W., c/o City Clerk, Winfield, Kans.
Clark, Alfred, 218 N. Chestnut, Lindsborg, Kans.
Duffy, Ora, Supt., Holton, Kans.
Haney, Paul A., Acting Chief Engr., Room 2, Morvin Hall, Univ. of Kansas, Lawrence, Kans.
Harr, Neal, City Engr., McPherson, Kans.
Heinrikson, J. J., 3707 Madison, Kansas City 2, Mo.
Kaler, P. E., 1522 W. 16th, Topeka, Kans.
King, Wendell, 303 N. Main, Lindsborg, Kans.
Nixon, Ray, Water Supt., Herington, Kans.
Rector, K. E., 943 Mulvane St., Topeka, Kans.
Reeves, R. B., City Engr., Chanute, Kans.
Remsburg, W. N., c/o The American Well Wks., 400 B. M. A. Bldg., Kansas City, Mo.
Rogers, Milford E., Municipal Water Plant, Wichita, Kans.
Spaeth, Julius, Box 746, Salina, Kans.
Staley, H. H., 416 Woodlawn, Topeka, Kans.
Strang, J. A., Wallace & Tiernan Sales Corp., Board of Trade Bldg., Kansas City 6, Mo.
Sulentic, S. A., 327 New England Bldg., Topeka, Kans.
Wilson, Murray A., Wilson & Co., Engrs., P. O. Box 518, Salina, Kans.
Wyatt, Wendell C., 932 Sheridan, Salina, Kans.

Maryland-Delaware Water and Sewerage Association

Miss E. V. Gipe, *Secretary-Treasurer*, State Dept. of Health, 2411 N. Charles St., Baltimore, Md.

Armeling, George, 4031 Bonner Rd., Baltimore, Md.
Bingley, W. McLean, Lt., Headquarters, 8th Service Command, Dallas, Tex.
Enoch Pratt Free Library, Periodicals Dept., Cathedral, Franklin & Mulberry Sts., Baltimore, Md.
Finck, G. E., Bureau of Sewers, Municipal Building, Baltimore, Md.
Funk, John B., City Engineer, Brunswick, Md.
Genter, Albert L., Wyman Park Apartments, Baltimore, Md.
Geyer, John C., 1055 Pickwick St., Springfield, Mo.

Hall, Harry R., Chief Engr., Washington Suburban San. Distr., Hyattsville, Md.
Hodek, James J., 713 N. Rose St., Baltimore, Md.
Hopkins, E. S., Major, 4402 Roland Ave., Baltimore, Md.
Kaltenbach, Albert B., 4122 Kathland Avenue, Baltimore 7, Md.
Keefer, Clarence E., 408 Kensington Road, Baltimore, Md.
Kenney, Norman D., Assoc., Engr., Whitman, Requardt & Smith
Machis, Alfred, 867 Hollins St., Baltimore, Md.
Maryland State Dept. of Health, Bureau of San. Engr., 2411 N. Charles St., Baltimore, Md.
Munroe, W. C., Old High School Bldg., Green St., Annapolis, Md.
Owings, Nobie L., 4507 Oliver St., Riverdale, Md.
Powell, S. T., Professional Bldg., 303 N. Charles St., Baltimore, Md.
Regester, Robert T., Consulting Engr., Baltimore Life Bldg., Baltimore, Md.
Sklarevsky, Rimma, Back River Sewage Treatment Wks., Colgate, Md.
Smith, Paul L., 5404 Tramore Rd., Baltimore, Md.
Stevens, Harry, 7017 5th St., N.W., Washington, D. C.
Wolman, Abel, Prof. of San. Engr., Johns Hopkins Univ., Latrobe Hall, Homewood, Baltimore, Md.

Michigan Sewage Works Association

Mr. R. J. Smith, *Secretary-Treasurer*, Michigan Dept. of Health, State Office Bldg., Lansing, Mich.

Adams, Milton P., State Office Bldg., Lansing, Mich.
Anderson, R. A., Supt., Sewage Treatment Plant, Muskegon Heights, Mich.
Arnold, Everett W., 8818 Morley, Detroit, Mich.
Beukema, Robert, 370 Richard St., Zeeland, Mich.
Bower, Stanley, Supt. of Sewage Treatment, Ypsilanti, Mich.
Bowers, T. C., 202 East Ganson St., Jackson, Mich.
Boyd, J. W., 442 Grant St., Grand Haven, Mich.
Buckingham, C. E., 1236½ Turner St., Lansing, Mich.
Burley, Fred H., Capt., c/o Station Hospital, Avon Parly Bombing Range, Avon Park, Fla.
Cameron, N. B., 216 Steward Ave., Jackson, Mich.
Cary, Wm. H., 717 Arbor, Ann Arbor, Mich.
Chamier, Albert, 9300 West Jefferson, Detroit, Mich.
Clark, M. S., 1853 E. Beardsley, Elkhart, Ind.
Corson, H. C., City Engineer, Birmingham, Mich.
Crooks, Howard, Board of Public Works, Menominee, Mich.
DeHooghe, Bernard A., 212 S. 6th St., Gladstone, Mich.
DeLano, Huntley, 222 Sheridan, Fremont, Mich.
Demorest, S. L., 216 E. Cherry St., Mason, Mich.
Dennis, Carl E., City Manager, Rockford, Mich.
Dodge, H. P., 1632 Stark St., Saginaw, Mich.
Dorr, Fred, P. O. Box 17, Royal Oak, Mich.
Dowd, Ira, 1813 Belle Ave., Flint, Mich.
Doyle, Thomas J., 274 E. Boulevard N., Pontiac, Mich.
Durand, Edwin M., 724 Ethel Ave., S. E. Grand Rapids, Mich.
Eckelcamp, Joseph, P. O. Box 565, Spring Lake, Mich.
Eldridge, E. F., Eng. Exp. Sta., Mich. State College, East Lansing, Mich.
Erickson, E. J., 9300 W. Jefferson, Detroit, Mich.
Filkins, D. A., Sparta, Mich.
Fishbeck, Kenneth, 2117 W. St. Joseph St., Lansing, Mich.
Forton, R. G., 319 Barlow, Traverse City, Mich.
Foster, Richard G., Michigan Dept. of Health, Lansing, Mich.
Francis, George W., Francis Engr. Co., Eddy Building, Saginaw, Mich.
Gentsch, Edward, 3119 Harrison, Detroit, Mich.
Godfory, J. L., Sew. Plant, City Hall, Monroe, Mich.
Graham, James E., Berrien Springs, Mich.
Granger, George, City Mgr., Grayling, Mich.
Gray, Earl G., 1210 S. Harvey, Plymouth, Mich.
Green, R. A., 511 N. Elm Ave., Jackson, Mich.

Grinnell, Russell, Municipal Bldg., Birmingham, Mich.
Groen, Michael A., Chief Opr.; Div. of Sew. Treat., 7446 Ternes Ave., Dearborn, Mich.
Habermehl, C. A., 14521 Strathmoor, Detroit, Mich.
Hauer, Gerald E., 592 S. Third St., Middleport, Ohio
Hawken, Dalton, Rochester, Mich.
Hayward, Homer J., 227 N. Clay St., Delphos, Ohio
Herda, N., 224 Huron River Dr., Belleville, Mich.
Hicks, Cyril, Richmond, Mich.
Hillis, Leonard, Caro State Hospital, Caro, Mich.
Hubbell, Geo. E., 2640 Buhl Bldg., Detroit, Mich.
Hunt, H. S., c/o Fargo Engr. Co., 120 Michigan Ave., W., Jackson, Mich.
Jackson, R. B., 527 W. Ganson St., Jackson, Mich.
Jackson, T. L., St. Ignace, Mich.
Jennings, L. R., 509 E. Mason St., Owosso, Mich.
Jones, Frank E., Constantine, Mich.
Kammerling, Lane, 194 E. 7th St., Holland, Mich.
Kelley, R. E., M9 S. Maple St., Sturgis, Mich.
Klann, Martin C., City Hall, Bay City, Mich.
Kronbach, Allan, Capt., c/o Station Hospital, Selfridge Field, Mich.
Kunze, Albert T., 797 Central Avenue, Wyandotte, Mich.
Leemaster, J. F., Supt. Sewage Treatment, Jackson Prison, Jackson, Mich.
Leonhard, Harold M., 2333 W. Jefferson, Trenton, Mich.
McFarlane, W. D., 14365 Marlowe Ave., Detroit, Mich.
McGrath, C. P., 116 Clinton Street, Mt. Clemens, Mich.
McKenna, Harold K., 520 E. Third St., Flint, Mich.
Main, Ralph A., 1819 Fairview, Birmingham, Mich.
Mallmann, W. L., Dept. of Bacteriology, Mich. State College, E. Lansing, Mich.
Malloy, Howard M., Capt., 811 Barton Dr., Ann Arbor, Mich.
Marshall, J. C., Charlevoix, Mich.
May, D. C., Ayres, Lewis, Norris & May, Wolverine Bldg., Ann Arbor, Mich.
Metyko, Frank J., 12511 Rosemary, Detroit, Mich.
Miller, Norman A., 4733 W. Jefferson, Trenton, Mich.
Mogelnicki, Stanley J., R. F. D. No. 5, Midland, Mich.
Montgomery, J. R., c/o Sewage Treatment Plant, Pontiac, Mich.
Morrill, Arthur, 13563 Birwood Ave., Detroit, Mich.
Mudgett, C. T., Supt., Sewage Treatment Wks., Muskegon, Mich.
Musgrove, Robt., 701 Alger St., S. E., Madison Sq. Station, Grand Rapids, Mich.
Norgaard, John, 931 S. 18th St., Arlington, Va.
Oeming, L. F., c/o Mich. Stream Control Comm., Lansing, Mich.
Ohr, Milo F., 3824 Sequoyah Ave., Knoxville 16, Tenn.
Olson, Herbert A., 127 Grand View, Ann Arbor, Mich.
Orton, J. W., 18920 Sorrenton, Detroit, Mich.
Palmer, C. L., City Engineers Office, Rm. 400, City Hall, Detroit, Mich.
Pierce, W. E., Whitehall, Mich.
Pomeroy, Clarence, Hartford, Mich.
Potts, Harry G., Pennsylvania Salt Co., Wyandotte, Mich.
Powers, Thomas J., 1016 W. Park St., Midland, Mich.
Raymond, Nelson L., 610 Pine St., Owosso, Mich.
Reames, H. S., Village Clerk-Treasurer, Grand Ledge, Mich.
Reedy, Timothy D., Supt., Sew. Treatment Plant, 2422 Miller Rd., Flint, Mich.
Ridenour, G. M., Ph.D., Assoc., Resident Lecturer, School of Public Health, Univ. of Mich., Ann Arbor, Mich.
Ritter, Bruce, Lake Odessa, Mich.
Rumsey, James R., 1325 36th St., S. E., Grand Rapids, Mich.
Sawyer, Lee, 108 Lafayette, Hudson, Mich.
Schoeninger, C. J., 14587 Prevost, Detroit, Mich.
Shephard, W. F., Mich. Dept. of Health, Lansing, Mich.
Smith, Earl T., Steward, Lapeer State Home & Training School, Lapeer, Mich.
Smith, Harold L., 525 Center, Alma, Mich.
Smith, Robt. J., 545 Elizabeth St., E. Lansing, Mich.
Smith, S. H., Supt. Board of Public Works, South Haven, Mich.
Smith, Walter E., Wallace & Tiernan Co., Inc., 415 Brainard St., Detroit, Mich.
Sndedker, L. LaVerne, Sewage Treatment Plant, Adrian, Mich.
Stark, Louis, 434 Jackson St., Petoskey, Mich.
Stegeman, Paul, Water Dept., Midland, Mich.
Theroux, Frank R., Div. of Engineering, Michigan State College, E. Lansing, Mich.

Tomkins, Lloyd, 289 S. Jefferson, Coldwater, Mich.

Venn, Frank, Pentwater, Mich.

Wallace, W. M., 9300 W. Jefferson Ave., Detroit, Mich.

Weeber, Earl R., City Manager, East Grand Rapids, Mich.

Williams, W. B., Williams & Works, County Bldg., Grand Rapids, Mich.

Witcher, C. Preston, Sewage Treatment Plant, Ann Arbor, Mich.

Wolterink, Paul, c/o Mead-Johnson Co., Zeeland, Mich.

Wyllie, George F., 1625 Sunset Ave., Lansing, Mich.

Missouri Water and Sewerage Conference

Mr. Warren Kramer, *Secretary-Treasurer*, State Board of Health, 200 Monroe St., Jefferson City, Mo.

Bridges, F. B., Supt. Water & Sewage Works, Monroe City, Mo.

Brown, Cleo, Supt. Water Works, Harrisonville, Mo.

Carl, Charles E., 1st Lt., Sn. C., Station Hospital, Jackson Army Air Base, Jackson, Miss.

Collison, Okla. C., Chief Engr., Southwest Sewage Treatment Plant, Rt. No. 7, Box 406, Springfield, Mo.

Curtiss Wright Corp., Lambert Field, St. Louis, Mo.

Fuller, H. L., 420 E. 73rd Terrace, Kansas City, Mo.

George, J. E., Sewage Treatment Plant, Odessa, Mo.

Harwell, Glenn A., Laclede Co. Health Dept., Lebanon, Mo.

Haskins, Chas. A., Finance Bldg., Kansas City, Mo.

Hayob, Henry, Marshall Municipal Utilities, Marshall, Mo.

Hogan, M. S., Supt., Water & Light Dept., West Plains, Mo.

Homan, Arthur R., Associate Engineers, c/o Post Engineer, Camp Clark, Nevada, Mo.

Howard, R. R., Supt. Water Works, Slater, Mo.

Kehr, William Q., State Bd. of Health, Jefferson City, Mo.

Lindell, O. V., Dorr Company, The, 6315 Brookside Plaza, Kansas City, Mo.

Little, August, Supt. Municipal Utilities, Vandalia, Mo.

Loelkes, Geo. L., Supt., P. O. Box 267, Clayton 5, Mo.

Russell, George, 7112 Wydown Blvd., Clayton, Mo.

Russell, George S., Russell & Axon, Cons. Engrs., 229 Roosevelt Bldg., St. Louis, Mo.

Seaver, Wist D., Sanitary Engr., Post Engineer's Office, Fort Leonard Wood, Mo.

St. Louis County Health Dept., Box 267, Clayton, Mo.

St. Louis Public Library, Olive & 11th Sts., St. Louis, Mo.

Vogelbaum, Chas. J., Sewer District, R. F. D. No. 7, Overland, Mo.

New England Sewage Works Association

Mr. LeRoy W. Van Kleeck, *Secretary-Treasurer*, State Dept. of Health, State Office Bldg., Hartford, Conn.

Abrams, M. F., 17 Battery Place, New York City, N. Y.

Allen, Herbert B., Sewage Plant Opr., Treatment Plant, Fitchburg, Mass.

Baird, Charles O., Jr., Teacher, Northeastern University, 316 Huntington Ave., Boston, Mass.

Baldwin, C. W., 9 Middle St., East Weymouth, Mass.

Balmer, Robt. R., Jr., 74 Washington St., Marblehead, Mass.

Barbour, Frank A., Cons. Engr., 1120 Tremont Building, Boston, Mass.

Bauer, Henry W., Supt., 181 Ridge Road, Middletown, Conn.

Bogren, George G., 55 W. Plain St., Cochituate, Mass.

Bond, Eugen L., Dept. of Streets & Engineering, Town Hall, Greenfield, Mass.

Bond, Philip E., 189 High St., Holyoke, Mass.

Bowler, Edmond Wesley, Prof., University of New Hampshire, Durham, N. H.

Bradlee, Warren R., AAB-Bluethenthal Field, Wilmington, N. Car.

Britton, Benj. A., Jr., Hecker Avenue, Noroton Heights, Conn.

Brooks, John H., Jr., E. Worcester St., Worcester, Mass.
Brown, Edward S., Jr., Thayer School of Civil Engineering, Hanover, N. H.
Brown, Walter H., Jr., 12 Hersey Road, Cranston 10, R. I.
Brule, Abundius A., 157 Chestnut St., Central Falls, R. I.
Buck, Robinson D., 650 Main St., Hartford, Conn.
Bugbee, Julius W., 290 Massachusetts Ave., Providence, R. I.
Bugbee, Raymond, C., 17 Monument St., Groton, Conn.
Burden, Harry P., Dean of Eng. School, Tufts College, Medford, Mass.
Burden, Robert P., 18 Day St., Somerville, Mass.
Burdoin, Allen J., 85 Washington St., Wellesley Hill, Mass.
Burr, R. S., American Brass Company, Waterbury, Conn.
Burrell, Robert, Operator, 39 Howard Street, West Haven, Conn.
Camp, Thomas R., Assoc., Prof., Massachusetts Inst. of Tech., Cambridge, Mass.
Capwell, Walter, Disp. & Incinerator Plant, Trumbull St., New London, Conn.
Carpenter, Howard F., 2 Ernest St., Providence, R. I.
Carson, Caryl C., Box 1139, Hartford, Conn.
Cary, Willis E., 5 Chesterfield Rd., Worcester, Mass.
Casey, Albert E., 16 Pine St., Stoneham, Mass.
Cerny, Paul J., 441 Lexington Ave., New York City
Chase, E. Sherman, Metcalf & Eddy, 1300 Statler Bldg., Boston, Mass.
Chisholm, Henry, R. F. D. 125, Mansfield, Mass.
Clarke, V. B., Box 582, Ansonia, Conn.
Cobb, Edwin B., 34 Stevens Road, Needham 92, Mass.
Coburn, S. E., 1300 Statler Bldg., Boston, Mass.
Cohn, Morris M., 1101 Lexington Ave., Schenectady, N. Y.
Coltart, Rodney F., Link-Belt Co., 2045 W. Hunting Park Ave., Philadelphia, Pa.
Copeland, Wm. R., 887 Asylum Ave., Hartford, Conn.
Copley, Charles H., 49 Bedford Ave., Hamden, Conn.
Corbett, Walter E., 84 East Main St., Milford, Mass.
Coy, Arthur H., Water & Sewer Dept., Westerly, R. I.
Craemer, George H., Operator, Municipal Building, Hartford, Conn.
Damon, Nelson A., 34 Spring Street, Amherst, Mass.
Damon, Wayne F., 161 West St., Leominster, Mass.
Darby, George M., c/o The Dorr Company, Westport, Conn.
DeHass, Nicholas, Box 176, Linwood, Mass.
Dion, Clarence K., Post Road, Westerly, R. I.
Disario, G. M., Ave., Lost Pines 24, LaFlorida Caracas, Venezuela, So. Amer.
Doman, Joseph, Div. of Highways & Sewers, Room No. 7, Town Hall, Greenwich, Conn.
Domnini, Frank L., C. Mo. M. M., U. S. Coast Guard Training Sta., Staff Barracks, Groton, Conn.
Drew, Samuel T., Apartado No. 14, Guatemala City, Guatemala, Central America
Dudley, Richard E., Rm. 410, City Hall, Springfield, Mass.
Dyer, Samuel, Memorial Bldg., Framingham, Mass.
Easter, Charles W., Claremont Water & Sewer Dept., 7 Sullivan St., Claremont, N. H.
Eddy, Harrison P., Jr., 1300 Statler Bldg., Boston, Mass.
Ellsworth, Samuel M., Cons. Engr., 6 Beacon St., Boston, Mass.
Epstein, Herman, 18 Robert St., New Britain, Conn.
Fair, Gordon M., Prof., 7 Scott St., Cambridge, Mass.
Fales, Almon L., c/o Metcalf & Eddy, Statler Bldg., Boston, Mass.
Fenn, Ernest G., Fairfield State Hosp., Newtown, Conn.
Ferris, James E., Niagara Alkali Company, 60 E. 42nd St., New York, N. Y.
Fleming, Paul V., 1272 Massachusetts Ave., North Adams, Mass.
Flood, Frank L., U. S. Division Engineer's Office, 75 Federal St., Boston, Mass.
Foote, Kenneth E., 87 Fort Hale Rd., New Haven, Conn.
Gibbs, Frederick S., Wallace & Tiernan Co., Inc., 346-A Newbury St., Boston, Mass.
Gilcreas, F. Wellington, Div. of Laboratories & Research, New Scotland Ave., Albany, N. Y.
Giles, J. Henry L., State Dept. of Health, State Office Bldg., Hartford, Conn.
Gisborne, Frank R., Operator, Arcadia Road, Old Greenwich, Conn.
Gladue, Donat J., 210 High Street, Bristol, R. I.
Goff, James S., Sanitary Corps, Station Hosp., Camp Patrick Henry, Newport News, Va.
Gough, Andrew B., 37 Standard Ave., West Warwick, R. I.
Graemiger, Joseph A., 7 Earl St., West Warwick, R. I.

Greeley, Richard F., 34 Central St., Hudson, Mass.

Greenleaf, John W., Jr., American Embassy, Asuncion, Paraguay, So. Amer.

Griffin, Guy E., Major, Federal Engineer, 502 School St., Belmont, Mass.

Hanson, George L., Boston Post Road, Marlboro, Mass.

Harper, M. J., Mereo Nordstrom Valve Co., 50 Church St., New York City, N. Y.

Hartley, John R., Asst. Sales Mgr., Builders-Providence, Inc., 9 Codding St., Providence, R. I.

Hiller, Paul W., Innis Speiden & Co., 117 Liberty St., New York, N. Y.

Holmes, Harry E., Mass. State Dept. of Health, 511-A State House, Boston, Mass.

Holmes, Kenneth H., Municipal Bldg., New London, Conn.

Horgan, John J., 53 Park Place, New York, N. Y.

Horne, Ralph W., 11 Beacon St., Boston, Mass.

Houser, George C., 220 Clyde St., Brookline, Mass.

Howard, P. F., 138 Bartlett Rd., Winthrop, Mass.

Jackson, J. Frederick, 36 Cannon St., Hamden, Conn.

Jenckes, J. Franklin, Jr., Fields Point Mfg. Corp., Providence, R. I.

Johnson, Eskil C., 335 Thames Ave., Greenwood, R. I.

Joy, C. Fred, Jr., 50 Meredith Circle, Milton, Mass.

Kappe, S. E., 5230 Massachusetts Ave., Washington, D. C.

Kelsey, Walter, Lord & Burnham Co., Irvington On Hudson, New York, N. Y.

Kunsch, Walter, 1105 S. Race St., Urbana, Ill.

Lamb, Clarence F., Waterman Engineering Co., 86 Weybosset Street, Providence, R. I.

Lane, Calvin S., Box 1825, Portland, Me.

Langford, Leonard L., 141 Lexington Ave., New York City, N. Y.

Lannon, William, 21 Bridge St., Putnam, Conn.

Lanphear, Roy S., Worcester Sew. Treat. Plant, Post Office Sta. C., Worcester, Mass.

Locke, Edw. A., 21 Forster St., Hartford, Conn.

Lockwood, Bronson E., Municipal Engr., Watertown Fire District, Watertown, Conn.

McCarthy, Joseph A., Lawrence Experiment Station, 4 Island St., Lawrence, Mass.

McDonald, John, 67 Hartford Terrace, Springfield, Mass.

McKee, Jack E., Capt., 17 College Ave., Waterville, Maine

McMahon, Walter A., 76 Brookside Avenue, Torrington, Conn.

Maguire, Charles A., 1515 Turks Head Bldg., Providence, R. I.

Mannheim, Robert, The Mathieson Alkali Wks., Inc., 911 Hospital Trust Bldg., Providence, R. I.

Mariner, W. S., 225 Dedham St., Dover, Mass.

Merrill, Walter E., Major, War Dept., The Div. Engineer, P. O. Box 4541, Miami, Fla.

Mitchell, Burton F., P. O. Box 147, Foxboro, Mass.

Moore, Edward W., 7A Pierce Hall, Harvard University, Cambridge, Mass.

Morgan, Edward F., Jr., Supt. of Public Works, Hudson, Mass.

Morgenroth, Fritz, 156 Lake St., Brighton, Mass.

Muldoon, Joseph A., 849 Hancock Avenue, Bridgeport, Conn.

Naylor, William, Supt., Water and Sewers, Maynard, Mass.

Newlands, James A., Pres., Henry Souther Engineering Co., 11 Laurel St., Hartford, Conn.

Palmer, Benjamin M., 114 Thayer Bldg., Norwich, Conn.

Parker, L. K., Acting Supt., Auburn Sewerage Distr., 268 Court St., Auburn, Me.

Perry, Earl R., City Hall, Worcester, Mass.

Petrie, William P., Supt., Sewage Disposal Plant, Norwalk, Conn.

Pratt, Gilbert H., 346A Newbury St., Boston, Mass.

Proudman, Chester F., New Canaan Sewage Disposal Plant, New Canaan, Conn.

Puffer, Stephen P., Town Hall, Amherst, Mass.

Raisch, William, 227 Fulton St., New York City

Reed, Leon H., P. O. Box 81, Pittsfield, Mass.

Richardson, C. G., Builders-Providence, Inc., Div. of Builders Iron Foundry, Providence, R. I.

Rogers, John A., Operator, 6 Central Avenue, Milford, Conn.

Ryckman, Seymour J., Wingate Hall, University of Maine, Orono, Me.

Sanderson, W. W., c/o State Dept. of Health, Div. of Laboratories & Research, New Scotland Ave., Albany, N. Y.

Sawyer, Robert W., Jr., c/o Malcolm Pirnie, 25 W. 43rd St., New York City

Scott, Warren J., 34 Garfield Rd., West Hartford, Conn.

Shea, Walter J., 327 State Office Bldg., Providence, R. I.

Shepperd, Frederick, "Municipal Sanitation," 24 W. 40th St., New York City

Sherman, Leslie K., Capt., Command Med. Field Service, Carlisle Barracks, Pa.

Snell, J. R., 364 Lebanon, Melrose, Mass.
Snow, Willis J., State Water Comm., State Office Bldg., Hartford, Conn.
Stearns, Donald E., c/o Fay, Spofford & Thorndike, Engrs., 11 Beacon St., Boston, Mass.
Sterling, Clarence L., Office of Coordinator of Inter-American Affairs, 3624 Commerce Dept. Bldg., Washington, D. C.
Stock, Mitchell B., P. O. Box 804, Bridgeport, Conn.
Suttie, R. H., Prof., Dept. of Civil Engr., Yale University, New Haven, Conn.
Szymanski, John R., New Britain Treatment Plant, New Britain, Conn.
Tarlton, Ellis A., 34 Pleasant St., Danbury, Conn.
Thompson, E. H., 1318 Elm St., Stratford, Conn.
Thompson, Robert B., The Dorr Co., Inc., Westport, Conn.
Tierney, Lawrence J. Jr., 518 Rice Bldg., 10 High St., Boston, Mass.
Trager, Leonard W., N. H. State Board of Health, Concord, N. H.
Tuttle, Leon E., Mun. Engr., Town Hall, Stamford, Conn.
Van Atta, John W., Ralph B. Carter Pump Co., 53 Park Place, New York City
Van Kleeck, LeRoy W., State Dept. of Health, State Office Bldg., Hartford, Conn.
Wivier, Harvey, Sewage Treatment Plant, Ludlow, Mass.
Wadhams, Gen. S. H., State Water Commission, State Office, Bldg., Hartford, Conn.
Walker, Philip B., 18 Summit Street, Whitinsville, Mass.
Welsh, William J., Lenox, Mass.
Wentworth, John P., 569 Fellsway East, Malden 48, Mass.
Weston, Arthur D., Room 511, State House, Boston, Mass.
Weston, R. S., Cons. Engr., 14 Beacon St., Boston, Mass. (Deceased)
Whipple, Melville C., 112 Pierce Hall, Cambridge, Mass.
Whitlock, Henry C., City Hall, Waterbury, Conn.
Winch, Norman M., Lt., 0-461488, Station Hospital, A.P.O. 845, Postmaster, New York, N. Y.
Wright, Edw., State Engr., Mass. State Dept. of Health, 511-A State House, Boston, Mass.
Worthington, Erastus, Insurance Bldg., Dedham, Mass.

New Jersey Sewage Works Association

Mr. John R. Downes, *Secretary*, P. O. Box 11, Dunellen, N. J.

Abeles, Joseph C., 22 E. 40th St., c/o Faesy & Besthoff, Inc., New York City
Adams, J. K., 15 Ravine Rd., Tenafly, N. J.
Bell, E. Arthur, Box 41, Essex Falls, N. J.
Brunstein, Maurice, P. O. Box 622, Atlantic City, N. J.
Burack, W. D., 77 Sycamore Ave., Livingston, N. J.
Cameron, George, 1905 Kuehule Ave., Venice Park, Atlantic City, N. J.
Capano, Sam J., 27 Church St., Bound Brook, N. J.
Capen, Charles H., Jr., 8 Florence Place, West Orange, N. J.
Cenicola, Samuel, Sewage Plant Opr., 209 Huyler St., S. Hackensack, N. J.
Chamberlin, Noel S., 189 Liberty St., Bloomfield, N. J.
Cleary, Edw. J., Old Quarry Rd., Upper Montclair, N. J.
Corson, B. I., 120 Woodland Terrace, Oaklyn, N. J.
Cowles, M. W., Hackensack Water Co., Dept. Filtration & Sanitation, New Milford, N. J.
Daniels, P. N., 56 Maple Ave., Trenton, N. J.
Downes, John R., P. O. Box 11, Dunellen, N. J.
Decker, Edward P., 36 Midland Place, Newark, N. J.
Evans, F. M., Municipal Bldg., Glen Rock, N. J.
Farrant, James, 443 East 29th St., Paterson, N. J.
Fontenelli, Louis, 616 Center St., Garwood, N. J.
Friedman, S. N., 10 Co-operative Ext., Jersey Homesteads, N. J.
Frye, Jacob E., Longport, N. J.
Gadomski, Albert J., 709 Parker St., Perth Amboy, N. J.
Gatley, H. K., 26 Oakview Ave., Maplewood, N. J.
Gibbons, M. M., P. O. Box 162, Rahway, N. J.
Gehm, Harry Willard, Jr., 11 Ross Avenue, Metuchen, N. J.
Graul, Leroy H., Sewage Plant Operator, 4310 Hudson Ave., Wildwood, N. J.
Griffin, A. E., Sunset Rd., Pompton Plains, N. J.

Harley, Frank E., Fair Lawn Radburn Trust Co. Bldg., Fair Lawn, N. J.
Hartley, G. R., 415 Valley View Rd., Englewood, N. J.
Hartom, R. A., 29 Hudson St., Ridgewood, N. J.
Heukelekian, H., Short Course Bldg., Agricultural Experiment Sta., New Brunswick, N. J.
Holtje, Ralph H., c/o Rutan, 583 Mt. Prospect Ave., Newark, N. J.
Ingols, Robert, 2912 Avenue T, N. W. (R. D. No. 2), Winter Haven, Fla.
Jackson, John F., 2005 Sunset Ave., Wanamassa, N. J.
Kachorsky, M. S., P. O. Box 283, Manville, N. J.
Kaplan, Bernard, State Health Dept. Employee, Lovett Ave. & Orchard Rd., Little Silver, N. J.
Killam, E. T., 142 Maiden Lane, New York, N. Y.
Komline, T. R., 768 Upper Blvd., Ridgewood, N. J.
Kozma, Albert B., 43 Barrows Ave., Rutherford, N. J.
Lafferty, W. R., P. O. Box 95, Stratford, N. J.
LeChard, Joseph H., Atlantic City Sewerage Co., Atlantic City, N. J.
Lehmann, Arthur F., 134 Cedar Ave., Hackensack, N. J.
Lendall, Harry N., Prof., Dept. of Mun. & San. Engr., Rutgers Univ., New Brunswick, N. J.
Logan, Robert P., 835 Madison Ave., Elizabeth, N. J.
Long, James C., Box 82, N. J. State Hospital, Greystone Park, N. J.
McClane, S. Wood, Jr., 600 Gorge Rd., Cliffside Park, N. J.
McLaughlin, John, 157 Harrison St., Bloomfield, N. J.
McMenamin, C. B., 307 Melrose Ave., Bound Brook, N. J.
Molitor, Edward P., Sewage Plant Operator, 327 Morris Ave., Springfield, N. J.
Mowrey, A. F., 243 Reading Ave., Barrington, N. J.
Mowry, R. B., 1649 N. Broad St., Philadelphia, Pa.
Ocean City Sewer Service Co., E. S. Steelman, Mgr., 10th St. & West Ave., Ocean City, N. J.
Pope, Lester, 2025 Genesee St., Trenton, N. J.
Probasco, S. R., 311 St. Mary St., Burlington, N. J.
Radcliffe, Jack C., 533 Trotters Lane, Elizabeth, N. J.
Reiners, A. H., Sales Rep., Chloroben Corp., 225 Mercer St., Jersey City, N. J.
Riker, I. R., Princeton, N. J.
Rudolfs, Willem, Dr., Short Course Bldg., Agricultural Experiment Station, New Brunswick, N. J.
Seid, Sol., 58 Suydam St., New Brunswick, N. J.
Simmerman, John S., 215 Wildwood Ave., Pitman, N. J.
Smith, R. C., 463 Belleville Ave., Glen Ridge, N. J.
Terhune, A. S., Sewage Plant Operator, 64 Glenwood Place, East Orange, N. J.
Van De Vliet, Henry, Sewage Plant Operator, 522 Bergen Ave., Maywood, N. J.
West, Leslie E., 118 S. Kingman Rd., South Orange, N. J.
Whitehead, F. E., 770 Bogert Rd., River Edge, N. J.
Wittwer, N. C., R. F. D. No. 2, Box 286, Trenton, N. J.

New York State Sewage Works Association

Mr. A. S. Bedell, c/o State Dept. of Health, Albany, N. Y.

Abbott, W. D., 161 E. Quaker St., Orchard Park, N. Y.
Abrams, M. F., 17 Battery Place, New York, N. Y.
Aeryns, Albert N., 716 Greenwood Avenue, Brooklyn, N. Y.
Agar, Charles C., 210 Delaware Ave., Delmar, N. Y.
Agostinelli, Anthony J., Plant Operator, 38 Holden St., Charlotte Station, Rochester, N. Y.
Albrecht, Robert H., Supt. of Pub. Wks., Hamilton, N. Y.
Aldrich, E. H., c/o Reeves Newson, 500 Fifth Avenue, New York, N. Y.
Andersen, C. George, Box No. 174, Rockville Centre, N. Y.
Andres, William H., Gowanda State Hospital, Collins, N. Y.
Angell, J. M., Jr., 155 E. 44th St., New York, N. Y.
Armstrong, Frank W., 13 Hubble St., Bath, N. Y.

Artese, Philip, 122 McLaren St., Red Bank, N. J.

Ashe, John R., 179 Chestnut Ave., Waterbury, Conn.

Babcock, Irving, 264 S. Grove St., Freeport, N. Y.

Bachmann, Frank, c/o Dorr Co., Inc., 570 Lexington Ave., New York 22, N. Y.

Bacon, Henry G., 20 Joralemon St., Brooklyn, N. Y.

Badger, Irvin S., 742 Ostrom Ave., Syracuse, N. Y.

Baffa, John J., 341 99th St., Brooklyn, N. Y.

Barker, Stanley T., Comdr., C. E. C., U. S. N. R., c/o U. S. Naval Aviation Mission, Lima, Peru, So. Amer.

Barnhill, Kenneth G., 547 Riverside Dr., New York City

Barron, James L., 42 Laurel Lane, Rosyln Hts., L. I., N. Y.

Bates, R. D., State Dept. of Health, 65 Court St., Buffalo, N. Y.

Bedell, A. S., Div. of Sanitation, State Dept. of Health, Albany, N. Y.

Benjamin, L. F., Dormitory Area Y., Naval Training Sta., Sampson, N. Y.

Bennett, Christopher F., 133 Bedford Ave., Buffalo, N. Y.

Bernhardt, Carl J., 133 Linwood Ave., Jamestown, N. Y.

Berton, Charles J., 9008 76th St., Woodhaven, N. Y.

Besselievre, Edmund B., The Dorr Co., Inc., 811 West 7th St., Los Angeles, Calif.

Best, Robert B., 25 Maple St., Great Neck, N. Y.

Bevacqua, Joseph, 1340 Ridge Rd., E., Rochester, N. Y.

Bevan, John G., Guggenheim Bros., 3771 Tenth Ave., New York City

Bidwell, Milton H., 191 Green Ave., Freeport, N. Y.

Biele, F. J., 184 Nassau Ave., Huntington, N. Y.

Binger, Walter D., Commr. of Borough Works, Municipal Bldg., New York, N. Y.

Blinder, Jacob W., Woodridge, N. Y.

Blood, Lloyd, City Hall, Rome, N. Y.

Bogert, C. L., 624 Madison Ave., New York City

Boriss, M. E., Capt., 2062 21st Ave. So., Birmingham, Ala.

Boyce, Ralph E., 555 Rugby Rd., Brooklyn, N. Y.

Boyd, George E., c/o Wailes Dove Hermiston Corp., 17 Battery Place, New York, N. Y.

Bradner, B. E., 240 Halstead Ave., Harrison, N. Y.

Brallier, Paul S., P. O. Box 616, Niagara Falls, N. Y.

Brigham, John C., State Dept. of Health, State Office Bldg., Albany, N. Y.

Brigham, John C., Jr., Cedar Grove, Essex Co., N. J.

Brower, J. Singleton, 39 Center St., Woodmere, L. I., N. Y.

Brown, James M., Jr., Lt., Sn. C., Course No. 17 C. W. S., Edgewood Arsenal, Md.

Brumbaugh, W. V., Nat'l Lime Ass'n, 927 15th St., N.W., Washington, D. C.

Buck, Geo. H., 4704 Chevy Chase Blvd., Chevy Chase, Md.

Burgess, Harold, 212 5th Ave., North, Troy, N. Y.

Bush, Archie E., 376 S. Buffalo Road, Orchard Park, N. Y.

Butrico, Frank, 1609 E. 172nd St., New York City

Cadwell, Ivan W., 50 Pearl St., Buffalo, N. Y.

Cahill, Jr., Wm. J., 44 Broad Street, Haverstraw, N. Y.

Caird, James M., Cannon Bldg., Troy, N. Y.

Carmichael, David W., 82 Personette Ave., Verona, N. J.

Carpenter, George D., 903 E. State St., Ithaca, N. Y.

Carpenter, Harry C., 218 Wisner Ave., Middletown, N. Y.

Carpenter, Wm. T., 125 Worth St., New York City

Carroll, George B., P. O. Box 27, Industry, N. Y.

Cary, F. Arthur, 185 North Main St., Fairport, N. Y.

Cerny, Paul J., 441 Lexington Ave., Room 1209, New York, N. Y.

Chamberlain, L. H., c/o American Well Works, 475 5th Ave., New York 17, N. Y.

Chamberlain, Wm. T., Dept. of Public Wks., Rm. 816, 125 Worth St., New York, N. Y.

Chase, E. Sherman, Metcalf & Eddy, 1300 Statler Bldg., Boston, Mass.

Chasick, Abraham H., 1296 Sheridan Ave., Bronx, New York, N. Y.

Chisholm, Colin B., Bird Island Sewage Treatment Wks., Buffalo, N. Y.

Cipriano, Anthony G., 795 7th St., Buffalo, N. Y.

Clark, A. T., Water & Sew. Wks. Mfgrs. Assoc., 12 E. 41st St., New York 17, N. Y.

Clark, Boyd H., 7 Shaper Ave., Canajoharie, N. Y.

Clark, Robert N., Major, Hdqtrs. 1st Service Command, 808 Commonwealth Ave., Boston, Mass.

Coates, John J., c/o Sheppard T. Powell, 330 N. Charles St., Baltimore, Md.
Cochrane, John C., c/o Wallace & Tiernan Co., Box 178, Newark 1, N. J.
Cohn, Morris M., 1101 Lexington Ave., Schenectady, N. Y.
Colbert, David, 2553 Hubbard St., Brooklyn, N. Y.
Cole, E. Shaw, 21 Erwin Park Rd., Montclair, N. J.
Cook, Rodney E., Quogue, N. Y.
Copeland, Wm. R., 887 Asylum Ave., Hartford, Conn.
Collyer, Joseph C., Room 2100, Municipal Bldg., New York, N. Y.
Colquhoun, Colin, 101 Southard Ave., Rockville Centre, N. Y.
Cordell, Miss Mona, 34-20 83rd St., Jackson Hts., L. I., N. Y.
Cornelius, Harold B., 201 W. Lincoln St., Ithaca, N. Y.
Costello, John J., 266 W. Henry St., Elmira, N. Y.
Cottfell, H. S., 117 Liberty St., New York, N. Y.
Cowles, M. W., Hackensack Water Co., Dept. Filtration & Sanitation, New Milford, N. J.
Cox, C. R., Div. of Sanitation, State Dept. of Health, Albany, N. Y.
Cranch, Eugene T., 304 Eastchester Rd., New Rochelle, N. Y.
Crawford, N. V., General Electric Co., Schenectady, N. Y.
Culley, Walter M., Major, Sn. C., Surgeon's Office, Medical Branch, Governors Island 4, N. Y.
Cullison, Eugene F., 1 Cooks Lane, Highland Falls, N. Y.
D'Aleo, A. R., c/o Lehman Sewer Pipe Co., Inc., 32 Court St., Brooklyn, N. Y.
Davis, Arthur E., 1617 22nd St., Niagara Falls, N. Y.
Davis, Clarence A., E. I. du Pont de Nemours & Co., Station B., Buffalo, N. Y.
Davis, Walter S., 686 Myrtle Avenue, Albany, N. Y.
Dawson, Arthur, 226 5th Ave., Greenport, L. I., N. Y.
Dayton, Alfred E., 273 Murray Street, Newark, N. Y.
DeGroat, Frank N., 125 High Ave., Nyack, N. Y.
DeMunn, E. M., Main St., Genesee, N. Y.
Denise, Wm. D., 486 Denise Road, Rochester, N. Y.
Dent, Harry, 37 Spruce St., Great Neck, N. Y.
Devendorf, Earl, Div. of Sanitation, State Dept. of Health, Albany, N. Y.
Dewart, Donald M., 423 Oak Ave., Ithaca, N. Y.
Dobson, Wm. T., 20 Wilton Rd., Pleasantville, N. Y.
Dobstaff, Robert, Jr., 4867 Seneca St., Ebenezer, N. Y.
Dobstaff, Robert W., Sr., 135 Aurora Ave., Sta. D., Buffalo, N. Y.
Doman, Joseph, 196 Milbank Ave., Greenwich, Conn.
Donaldson, Wellington, Dept. of Public Wks., 125 Worth St., New York City.
Downing, Francis J., 1038 City Hall, Buffalo, N. Y.
Drexel, Frederick, 62-66 60th Drive, Maspeth, L. I., N. Y.
Driscoll, Timothy J., 247 Benziger Avenue, Staten Island 1, N. Y.
Duffiey, Frank J., 4300 Martha Ave., Bronx, N. Y.
Dyckman, Warren W., Room 2142, Municipal Bldg., New York, N. Y.
Eager, Vernon, 60 Dewey Avenue, Buffalo, N. Y.
Edighoffer, Albert, 27 Parkwood Ave., Kenmore, N. Y.
Edinger, Harry F., State Dept. of Health, 61 Albany Ave., Kingston, N. Y.
Edwards, Gail P., Wards Island Sewage Treatment Plant, Wards Island, N. Y.
Edwards, William L., Gowanda State Hospital, Gowanda, N. Y.
Eglof, Dr. Warren K., Niagara University, N. Y.
Ehle, Virgil, 21 Grand Ave., Gloversville, N. Y.
Eich, Henry F., Lt., O'Reilly G. H.-M. D. R. P., c/o Postmaster, Springfield, Mo.
Eliassen, Rolf, Major, North Atlantic Division, Corps of Engineers, 270 Broadway, New York City
Enslow, L. H., Water Wks. & Sewerage, 155 E. 44th St., New York, N. Y.
Erickson, W. J., State Dept. of Health, 217 Lark St., Albany, N. Y.
Eustance, Arthur W., State Dept. of Health, Geneva General Hospital, Geneva, N. Y.
Eustance, Harry W., 159 Rock Beach Rd., Rochester, N. Y.
Evans, Byron B., Black River, N. Y.
Faber, Harry A., 50 East 41st St., New York, N. Y.
Fair, Gordon M., Prof., 7 Scott St., Cambridge, Mass.
Fanning, Harold R., 510 W. 2nd St., Elmira, N. Y.
Farrell, Michael, 222 Mason St., Canandaigue, N. Y.

Fawls, James F., State Dept. of Health, 61 Albany Ave., Kingston, N. Y.
Feierstein, Jacob L., 6801 19th Ave., Brooklyn, N. Y.
Fenger, J. W., 24 Idlewood Place, Hamburg, N. Y.
Fenton, John V., Professional Bldg., Lynbrook, N. Y.
Ferris, James E., Niagara Alkali Co., 60 E. 42nd St., New York City
Field, Emerson & Morgan, Inc., Flower Bldg., Watertown, N. Y.
Field, Wm. T., Major, C. E., 1466 Lake Ave., Wilmette, Ill.
Findlay, A., Main Pump Station, Bird Island Sewage Treatment Plant, Buffalo, N. Y.
Fischer, Anthony J., c/o The Dorr Co., Inc., 570 Lexington Ave., New York, N. Y.
Fitzgerald, J. A., 271 Main St., Hudson Falls, N. Y.
Five, Helge, 7 N. Ravine, Great Neck, N. Y.
Fleet, Gerald A., Capt., A.P.O. 717, 34th Mal. Cont. Unit, c/o Postmaster, San Francisco, Calif.
Forbes, Albert F., Box 285, Watkins Glen, N. Y.
Fort, Edwin J., Huntington, Long Island, N. Y.
Fortenbaugh, J. Warren, 155 Hamlin Rd., Buffalo, N. Y.
Frazier, Leonard H., 206 Catherine St., Scotia, N. Y.
Friedman, Wm. M., Jr., 45 W. Mohawk St., Buffalo, N. Y.
Friendly, Hugo H., City Hall, New Rochelle, N. Y.
Fuller, Nelson M., 106 Highland Parkway, Olean, N. Y.
Fynn, George F., 468 Taunton Pl., Buffalo 16, N. Y.
Gard, Charles M., Coll. of Engr., New York University, University Heights, New York City
Gardner, George W., San. Engr., Navy Sect., Navy No. 103, c/o Fleet P. O., New York City
Garlock, Samuel C., 41 E. 8th St., Oswego, N. Y.
Gavett, Weston, 973 Kenyon Avenue, Plainfield, N. J.
Gelbke, Arthur W., Ch. Engr., E. Leitz Co., 730 5th Ave., New York 19, N. Y.
Gere, William S., 117 James St., Syracuse, N. Y.
Gerling, Philip C., 27 Park Ave., Dansville, N. Y.
Gifft, H. M., Sch. of Civ. Engr., Cornell Univ., Ithaca, N. Y.
Gilcreas, F. Wellington, Div. of Laboratories & Res., New Scotland Ave., Albany, N. Y.
Gilman, Floyd, 19 South Ave., Manchester, N. Y.
Glace, I. M., Cons. Engr., 20 S. 22nd St., Harrisburg, Pa.
Glynn, William J., Frazier St., Brockport, N. Y.
Goldsmith, Philip, Coll. of Engr., San. Lab., New York Univ., University Heights, New York City
Gorman, Richard C., Jr., 44 Genesee St., Hornell, N. Y.
Gould, Richard H., 125 Worth St., New York, N. Y.
Greiff, V., 159 Beach 142nd St., Neponsit, L. I., N. Y.
Greig, John M. M., 624 Madison Ave., New York 22, N. Y.
Grelick, David, 100 Van Cortlandt Park, S., New York, N. Y.
Griffen, F. T., Box 408, Beaufort, So. Car.
Grover, Robert H., 18 Princeton St., Williston Park, L. I., N. Y.
Grubin, Herman, 105 Bennett Ave., New York City
Haberer, John C., State Dept. of Health, State Off. Bldg., 34 So. St., Middletown, N. Y.
Hackett, Peter, 20 Willow Ave., South Nyack, N. Y.
Haemmerlein, Victor E., Village Hall, East Aurora, N. Y.
Hale, Arnold H., 365 Linden Rd., Brighton Station, Rochester 10, N. Y.
Hall, Frank H., 181 Elderberry Rd., Mineola, N. Y.
Hallock, Emerson C., 6 Northview Place, White Plains, N. Y.
Halpin, John, 18 Park Avenue, Port Washington, N. Y.
Hamm, William C., 9 Locust Avenue, Port Washington, N. Y.
Hanson, John R., 9 Douglas Ave., Babylon, N. Y.
Hardenbergh, W. A., 310 East 45th St., New York, N. Y.
Harding, J. C., Comm. of Pub. Wks., County Off. Bldg., White Plains, N. Y.
Hardy, C. Asa, 115 N. 14th St., Olean, N. Y.
Harrison, Edward F., 2450 North Broad St., Philadelphia, Pa.
Hart, Chas. G., c/o Onondaga Public Wks. Comm., 109 Court Hse., Syracuse, N. Y.
Hartman, Byron K., c/o Link Belt Co., 2045 W. Hunting Park Ave., Philadelphia 40, Pa.
Harvey, Carl, 4819 S. Paul Blvd., Rochester, N. Y.
Hastie, James, 236 E. Shore Rd., Great Neck, L. I., N. Y.

Hawley, Arthur A., 25 7th St., Woodlawn, Lackawanna, N. Y.
Hayes, John A., South St., Extension, Warwick, N. Y.
Hazé, Richard, c/o Malcolm Pirnie, 25 West 43rd St., New York, N. Y.
Hedgepeth, L. L., Research Chemist, Pa. Salt Mfg. Co., 1000 Widener Bldg., Philadelphia, Pa.
Heller, Austin N., Lt. (j.g.), U. S. N. R., Indus. Hyg. & San. Office, U. S. Navy Yard, New York, N. Y.
Henderson, Charles F., 10 School St., Port Washington, N. Y.
Herberger, Arthur Henry, 40 Stowe Ave., Baldwin, L. I., N. Y.
Herzog, Henry, 315 Linden Rd., Brighton 10, N. Y.
Hess, Seth G., 60 Hudson St., New York, N. Y.
Heubi, Thomas, 45 Washington Avenue, Fredonia, N. Y.
Higgins, William J., 245 W. 107th St., New York 25, N. Y.
Hill, G. Everett, 15 Bell St., Orange, N. J.
Hiller, Paul W., Innis Speiden & Co., 117 Liberty St., New York, N. Y.
Hines, Leon H., Box 656, Collins, N. Y.
Hoag, 36 E. Wright Ave., Waterloo, N. Y.
Hoey, John B., 477 Middle Neck Rd., Great Neck, N. Y.
Hoffman, Howard F., 18 Pearl St., Utica, N. Y.
Hogan, James W. T., 83-33 247 St., Queens, New York City
Hogan, William J., 574 Willow Avenue, Cedarhurst, L. I., N. Y.
Holland, Frank H., 312 Archer St., Freeport, N. Y.
Holmes, Glenn D., 304 W. Kennedy St., Syracuse, N. Y.
Holmquist, Charles A., State Dept. of Health, Albany, N. Y.
Hopkins, L. S. R., 76 William St., New York, N. Y.
Hopper, Allen O., Turbine Equipt. Co., Rm. 1503, 75 West St., New York 6, N. Y.
Horgan, John J., 53 Park Place, New York, N. Y.
Hotchkiss, H. T., Jr., Supervising Chemist, Municipal Building, Larchmont, N. Y.
Howson, J. R., 116 Elm St., Westfield, N. Y.
Hoyt, Clinton W., Webster Road, Orchard Park, N. Y.
Huber, Harold, 5214 Broadway, Lancaster, N. Y.
Hunt, Raymond L., R. D. No. 3, Ithaca, N. Y.
Hurst, William O., Millbrook, N. Y.
Hutcheson, H. D., 604 Colton Ave., Newark, N. Y.
Jarlinski, Thaddeus T., 1020 Whirlpool St., Niagara Falls, N. Y.
Jerge, Ray, 607 Iroquoit Bldg., Buffalo, N. Y.
Johnson, Clement, 3 Water St., Rockville Centre, N. Y.
Johnson, Herbert O., 10 Broadway, Great Neck, N. Y.
Johnson, J. Clifford, 140-30 Sanford Ave., Flusing, N. Y.
Johnson, John W., 65 Tillinghast Place, Buffalo, N. Y.
Jones, Daniel, 14 Burling Lane, New Rochelle, N. Y.
Jordan, Harry E., Secretary, Amer. Water Works Association, 500 5th Ave., New York City
Kaplovsky, A. J., 11 Jones Ave., Chatham, N. Y.
Kappe, S. E., 5230 Massachusetts Ave., Washington, D. C.
Karsa, William J., 66 Walnut St., Lackawanna, N. Y.
Kass, Nathan L., 167 Beaumont St., Brooklyn, N. Y.
Kassay, Albert E., 29 Gordon Ave., North Tarrytown, N. Y.
Keeler, J. Harold, 795 Lake St., White Plains, N. Y.
Keller, Jacob, East Avenue, Shortsville, N. Y.
Keller, Lyndon M., Major, State Dept. of Health, 217 Lark St., Albany, N. Y.
Kellogg, Clarence E., 3 Barone Avenue, Mt. Morris, N. Y.
Kelly, Clarence, 403 Westminster Road, Cedarhurst, N. Y.
Kelsey, Walter, c/o Lord & Burnham Co., Irvington, N. Y.
Kemp, Harold A., 1721 N. Huntington St., Arlington St., Arlington, Va.
Kennedy, Wm., Huntington Sewer Plt., Huntington, L. I., N. Y.
Ketcham, Joseph M., Gilbert St., Northport, N. Y.
Kibler, Harry J., 1180 Ellicott Creek Rd., Tonawanda, N. Y.
Kidd, Carl W., 65 Franklin St., Dansville, N. Y.
Kieffer, Jos. D., 519 Robineau Rd., Syracuse, N. Y.
Kiker, J. E., Jr., Capt., Sn. C., Med. Br., Hdq. 7th Ser. Comm., New Federal Bldg., Omaha 2, Nebr.
Kilcawley, Edward J., Rensselaer Polytechnic Inst., Troy, N. Y.
Kin, Stephen R., Assoc. San. Engr., c/o Post Engr., Fort Bragg, N. Car.
Kirsner, Charles, Box 142, Riverside Sta., Miami, Fla.

Kivell, Wayne A., San. Engr., The Dorr Co., Inc., 570 Lexington Ave., New York City

Klegerman, M. H., 50 Church St., New York, N. Y.

Klinck, Frank, 408 Westminister Road, Cedarhurst, L. I., N. Y.

Knowles, Coyle E., 10 Maltbie Rd., Gowanda, N. Y.

Koplowitz, Sol, 1st Lt., San. C., MDRP, O'Reilly GH, Springfield, Mo.

Krell, A. J., Lt., M. D. R. P. A. S. F. U. C. T., Camp Ellis, Ill.

Kreuter, Clarence, 116 East William St., Waterloo, N. Y.

Kulberg, Abraham, 125 Worth St., Rm. 823, New York, N. Y.

Lacy, Ilbert O., 16 Spruce St., Lockport, N. Y.

Langford, Leonard L., 441 Lexington Avenue, New York, N. Y.

Larkin, W. H., 80 Centre St., New York City

Larsen, Ernest A., 294 William St., Geneva, N. Y.

Laughlin, William G., 270 Madison Ave., New York City

LaValley, Edward C., State Dept. of Health, 314 E. State St., Ithaca, N. Y.

Lawrence, John, 43 Columbia St., Liberty, N. Y.

Ledford, George L., 8943 Jollet Avenue, Niagara Falls, N. Y.

Lewis, John V., 54 Court Street, Rochester, N. Y.

Lieber, Maxim, Capt., San. Off., Sta. Hosp., Luke Field, Ariz.

Lippelt, Hans B., 9428 78th St., Ozone Park, N. Y.

Lobee, Frank A., 304 McKinley Bldg., Buffalo 2, N. Y.

Loomis, Harry E., 1112 Teall Ave., Syracuse, N. Y.

Losee, James R., 25 Rosehill Ave., Tarrytown, N. Y.

Lowe, Walter M., Supt. of Sewers, Lakewood, N. Y.

Lozier, William S., 10 Gibbs St., Rochester, N. Y.

Lynch, Daniel E., Jr., 810 Ocean Ave., Brooklyn, N. Y.

Lynch, James T., 23 Morris St., Auburn, N. Y.

Lyons, William, 295 Lyndale Ave., Buffalo, N. Y.

McCabe, Brother Joseph, Manhattan College, Spuyten Duyvil Parkway, New York City

McCarthy, Justin J., 69 School St., Arlington, Mass.

McCarthy, William F., 112 McAllister Avenue, Syracuse, N. Y.

McDade, Frank, Buffalo Sewer Authority, Bird Island, Buffalo, N. Y.

McDonnell, George H., Capt., San. C., Sta. Hosp., Camp Blanding, Fla.

McGann, Robert J., Commissioner of Works, City Hall, Oswego, N. Y.

McKeeman, Edwin C., 123 New York Avenue, Freeport, L. I., N. Y.

McLaughlin, Carroll W., 266 Fulton Ave., Hempstead, N. Y.

McLean, Clement, Ioka Sanitarium, Rochester, N. Y.

MacCallum, C., 12 Reid Ave., Port Washington, L. I., N. Y.

MacCrea, J. M., 153 Oakland St., Syracuse, N. Y.

Macauley, J. W., c/o Lehman Sewer Pipe Co., Inc., 32 Court St., Brooklyn, N. Y.

Magee, George W., Hudson River State Hospital, Poughkeepsie, N. Y.

Malcolm, W. L., Director, School of Civil Engr., Cornell University, Ithaca, N. Y.

Mangones, Robert J., 409 College Ave., Ithaca, N. Y.

Mann, Alfred H., 111 North 18th St., Olean, N. Y.

Mann, Karl M., 24 W. 40th St., New York City

Mann, Uhl T., 6 Samson St., Cortland, N. Y.

Marchon, Seigmund S., 120 Shepherd St., Rockville Centre, N. Y.

Marshall, E. A., 167 Lafayette Ave., Geneva, N. Y.

Marshall, Leslie S., 43 Dietz St., Hempstead, N. Y.

Marshall, W. B., 2314 Wyoming Place, Apt. E., Milwaukee, Wisc.

Martin, A. E., 35 Man Avenue, Kenmore, N. Y.

Martin, Alexander G., 36 Kinsy Avenue, Kenmore, N. Y.

Martin, Edward J., Jr., 24 S. Washington St., Tarrytown, N. Y.

Marx, Frank, Highland, N. Y.

Mathers, George, 112 Roosevelt Avenue, Garden City, N. Y.

McDonnell, Geo. H., Capt., c/o Jas. Bain, 14 School St., S. Hadley Falls, Mass.

Meara, John W., Commissioner of Public Works, City Hall, Middletown, N. Y.

Meeker, Herbert J., Mgr. Sewage Div. Worthington Pump & Machy. Corp., Harrison, N. J.

Mendelsohn, I. W., Capt., 1145 Mistletoe Dr., Ft. Worth 4, Tex.

Mesner, Elmer C., 9 Ravenswood Terrace, Cheektowaga, N. Y.

Michaels, John, 1663 Carrol St., Brooklyn, N. Y.

Miller, Fred M., 9 Maple Ave., Glen Cove, N. Y.
Miller, Wallace T., Mun. Bldg., Ossining, N. Y.
Mitchell, Louis, College of Applied Science, Syracuse University, Syracuse, N. Y.
Monsell, Harry M., 525 First St., Greenport, N. Y.
Moor, Alex., 202 Dellwood Rd., Eggertsville, N. Y.
Moore, George W., 26 Culver Parkway, Rochester, N. Y.
Morey, Burrows, c/o Miss Grace M. Morrison, 703 W. Ferry St., Buffalo 9, N. Y.
Mowbray, George A., 31 Hobart Avenue, Port Chester, N. Y.
Munding, Miss Germaine G., 522 Ocean Ave., Brooklyn, N. Y.
Murphy, Reginald A., Willard, N. Y.
Neves, Dr. Lourenco Baeta, Prof. da Universidade de Minas Geraes, Rua Claudio Manoel, 1185 Bello Horizonte, Minas Geraes, Brazil, So. Amer.
Nevitt, I. H., 1091 Eastern Ave., Toronto, Ont., Can.
Newsom, Reeves, 500 Fifth Avenue, New York, N. Y.
Nichols, A. E., 56 Clark St., Yonkers, N. Y.
Nicholson, C. P., 93 Pierce Avenue, Hamburg, N. Y.
Niebergall, Herbert J., 144 Wellworth Pl., Cheektowaga, N. Y.
Nielsen, A. F., 120 Broadway, New York, N. Y.
Niles, Chas. A., Bridgehampton, L. I., N. Y.
Nugent, Harold F., Exchange St., Alden, N. Y.
Nussbaumer, Newell L., 327 Franklin St., Buffalo, N. Y.
Nussberger, Fred, 44 14th Road, Broad Channel, N. Y.
O'Brien, Earl F., 1953 Biltmore St., N.W., Washington, D. C.
O'Connor, Wm. F., 716 Sixth Avenue, Patterson Hts., Beaver Falls, Pa.
Ockershausen, Richard W., Technical Service Div., General Chemical Co., Edgewater, N. J.
O'Dell, W. H., 30 West Main St., Webster, N. Y.
O'Donnell, Charles F., R. F. D. No. 1, Grover Rd., East Aurora, N. Y.
Ogden, Henry N., Prof., 416 Hanshaw Rd., Ithaca, N. Y.
O'Hara, Franklin, 75 Stowe St., Lowville, N. Y.
Okun, Abraham H., 4 Lakewood Avenue, Monticello, N. Y.
Okun, W. H., 125 Worth St., New York, N. Y.
Orchard, W. J., Sales Mgr., Wallace & Tiernan Co., Newark, N. J.
O'Rourke, John J., 51 Beal Blvd., Sidney, N. Y.
Ousterhout, Alfred, 2970 Eggert Rd., R. F. D. No. 1, Tonawanda, N. Y.
Pallo, Peter E., Hackensack Water Co., New Milford, N. J.
Patterson, Roy K., 38 Graham Rd., Scarsdale, N. Y.
Paul, Lewis G., R. F. D. No. 3, Hamburg, N. Y.
Pawlak, John S., Plant Opr., 129 Pleasant Pkwy., Cheektowaga, N. Y.
Peake, J. B., c/o Mathieson Alkali Wks., 60 E. 42nd St., New York City
Peck, Lawrence J., 11 Salisbury Rd., Delmar, N. Y.
Pecker, Joseph S., Pecker, Simpson, & Gladeck, 200 Madison Ave., New York, N. Y.
Pecker, Joseph S., Consulting Engr., 524 Victory Bldg., Philadelphia, Pa.
Perrine, J. Franklin, 31-35 Buell Place, East Elmhurst, N. Y.
Peterson, Earl L., P. O. Box 267, Nyack, N. Y.
Phelps, E. B., Prof., 630 West 168th St., New York, N. Y.
Phillips, H. N., 140 St. Andrews Lane, Glen Cove, N. Y.
Pincus, Sol, 225 W. 86th St., New York, N. Y.
Pinkney, Glenn E., 40 South Avenue, Webster, N. Y.
Pitkin, Ward H., 70 Bay Drive Harbour Green, Massapequa, N. Y.
Pohl, C. A., Dr., 39 Cortlandt St., New York, N. Y.
Pollock, John M., 28 Amherst Road, Port Washington, N. Y.
Porter, William, 55 Union St., Ballston Spa, N. Y.
Potts, Clyde, 30 Church St., New York, N. Y.
Powell, A. R., Dr., Koppers Research Corp., Kopper Bldg., Pittsburgh, Pa.
Provost, Andrew J., Dr., P. O. Box 216, Noroton, Conn.
Purdie, David J., Room 504, 20 Vessey St., New York 7, N. Y.
Quaely, Martin F., 520 W. 190th St., New York 33, N. Y.
Raisch, William, 227 Fulton St., New York City
Rath, Henry M., 35-36 76 St., Jackson Hts., New York City
Rehler, Joseph E., Lt. Comdr., C. E. C., U. S. N. R., Beach Ave. & 1st St., Cape May, N. J.
Reisch, E. A., 508 Stockbridge Ave., Buffalo, N. Y.
Reisert, Michael J., 488 Oakland Avenue, Cedarhurst, L. I., N. Y.
Remson, John, 31 St. John's Place, Freeport, N. Y.
Requardt, G. J., 1304 St. Paul St., Baltimore, Md.

Ribner, Morris, 1st Lt., Sn. C., Post Sanitary Engineer, Office of the Post Surgeon, Camp Pickett, Va.
Ribreau, Gilbert E., 14-65 162nd St., Beechurst, L. I., N. Y.
Rice, Lawrence G., 908 College Ave., Niagara Falls, N. Y.
Rickard, Grover E., 130 East St., Oneonta, N. Y.
Riddick, Thomas M., 369 E. 149th St., New York City
Riedel, John C., 505 Macon St., Brooklyn, N. Y.
Riis-Carstensen, Erik, 1040 Delaware Ave., Buffalo, N. Y.
Roberts, C. R., Dr., 524 West 57th St., New York, N. Y.
Roberts, Jack, 515 Dorlands Ave., Toronto, Ontario, Can.
Robertson, George E., 23 Church St., Roslyn, L. I., N. Y.
Rocco, John, 20 Queen St., Freeport, N. Y.
Rock, Harold F., State Dept. of Health, 16 Dietz St., Oneonta, N. Y.
Roe, Frank C., Carborundum Co., c/o Porous Products & Lab. Ware Dept., Niagara Falls, N. Y.
Rogers, Allan H., 110 Seventh St., Garden City, N. Y.
Ryan, J. Samuel, 99 Olean St., Bolivar, N. Y.
Ryan, Wm. A., 18 Ridge Road, West, Rochester, N. Y.
Saetre, Leif, Box 484, Great Neck, N. Y.
Sage, Howard D., 192 So. Main St., Mechanicsville, N. Y.
Salle, Anthony, 81 Buffalo Ave., Long Beach, N. Y.
Salvato, J. A., Jr., Capt., Sn. C., S. U. 2414, APO 702, c/o PM, Seattle, Wash.
Sammis, L. A., P. O. Box 96, East Northport, L. I., N. Y.
Samson, Channel, 176 Midland Ave., Kenmore, N. Y.
Samuelson, Andy, Thomas Indian School, Iroquois, N. Y.
Sanborn, J. F., 101 Park Ave., New York City
Sander, Irwin P., 3235 Grand Concourse, New York City
Sanderson, W. W., c/o State Dept. of Health, Div. of Laboratories & Res., New Scotland Ave., Albany, N. Y.
Savage, Edward, Guggenheim Brothers, 120 Broadway, New York, N. Y.
Saville, Thorndike, Prof., Hydraulic & Sanitary Engineering, Box 65, New York University, University Heights, N. Y.
Schaefer, Edward J., 111-21 125th St., So. Ozone Park, N. Y.
Schreiner, W. R., c/o Dr. Burke Diefendorf, 412 Rogers Bldg., Glens Falls, N. Y.
Schulhoff, Henry B., 268 Handy St., New Brunswick, N. J.
Schwartz, Chas. F., 413 N. Main St., Minoa, N. Y.
Schwartz, Louis, 395 E. 3rd St., Brooklyn, N. Y.
Scott, Rossiter S., 17 East 42 St., New York City
Scott, Walter M., 145 South Third Avenue, Mount Vernon, N. Y.
Scovill, John R., 138 Forest Avenue, Pearl River, N. Y.
Searls, Glenn, Pine Grove Avenue, Rochester, N. Y.
Seifert, William P., 77 Highview Avenue, Tuckahoe, N. Y.
Setter, Lloyd R., 217-16 51 Ave., Bayside, N. Y.
Shapiro, Robert, 159-07 14th Ave., New York City
Shehlee, Girard, Supt. of Public Wks., Village Hall, Warsaw, N. Y.
Shepperd, Frederick, "Municipal Sanitation," 21 W. 40th St., New York City
Shockley, Homer G., 500 American St., Catasauqua, Pa.
Sickler, Archie H., 52 Dellwood Rd., Eggertsville, N. Y.
Sigworth, E. A., 18 Minell Place, Teaneck, N. J.
Simmons, Harold, 103 Crossfield Dr., Rochester, N. Y.
Simon, Samuel S., 125 Worth St., Rm. 816, New York, N. Y.
Simpson, R. W., 115 Hopkins Blvd., Biloxi, Miss.
Simson, Paul W., State Dept. of Health, 35 Market St., Poughkeepsie, N. Y.
Slocum, Adelbert I., 515 Beach 68th St., Arverne, N. Y.
Slough, John, 55 S. Highland Ave., Wellsville, N. Y.
Smith, Benjamin L., Room 808, 11 North Pearl St., Albany, N. Y.
Smith, E. A. Cappelen, 120 Broadway, New York, N. Y.
Smith, Edward J., 1112 Ferry Avenue, Niagara Falls, N. Y.
Smith, Frank J., American Well Works, 475 5th Ave., New York 17, N. Y.
Smith, Harold, 143 North Long Beach Rd., Rockville Centre, N. Y.
Smith, L. R., 4 Pine St., Canton, N. Y.
Snow, Willis J., State Water Commission, State Office Bldg., Hartford, Conn.
Snyder, N. S., 692 Ellicott Square, Buffalo, N. Y.
Solomon, G. R., 257 Broadway, Troy, N. Y.

Sowdon, Wm. K., 342 Madison Ave., New York City
Sparr, A. E., 1 Miami Court, Brooklyn, N. Y.
Spry, Fred J., Lincoln Hall, Cornell University, Ithaca, N. Y.
Stanhope, Clifford T., Suite 2214-30 Church St., New York, N. Y.
Stankewich, M. J., State Dept. of Health, 65 Court St., Buffalo, N. Y.
Steacy, John J., 2 Park Place, Cobleskill, N. Y.
Steffensen, S. W., 125 Worth St., Room 821, New York, N. Y.
Steiner, S. K., 79 Madison Ave., New York, N. Y.
Stepanek, Charles H. B., 506 East 19th St., New York, N. Y.
Sterns, Edw. A., 303 Pleasant Ave., Hamburg, N. Y.
Stevenson, Albert H., U. S. Public Health Service, Sub-Treasury Bldg., Pine & Wall Streets, New York City
Stewart, W. H., P. O. Box 767, Syracuse, N. Y.
Stilson, Alden E., 216 E. 45th St., New York City
Stratton, Chas. H., 3614 Avenue K, Brooklyn 10, N. Y.
Straub, Conrad P., U. S. Public Health Service, 15 Pine St., New York 5, N. Y.
Strong, Bruce F., 1111 Washington St., Olean, N. Y.
Strowbridge, John C., 14 Millard St., Dundee, N. Y.
Studebaker, Leo, 1020 Whirlpool St., Niagara Falls, N. Y.
Sutherland, Henry M., 132 Leonard Ave., Freeport, N. Y.
Svenson, Sven H., 957 E. Ferry St., Buffalo, N. Y.
Swanz, Howard G., 29 Woodlawn Ave., Buffalo, N. Y.
Sweeney, R. C., Lt. Col., 252 Wildrose Ave., San Antonio, Tex.
Swenholt, John, 162 S. Main St., Albion, N. Y.
Sylvester, Wm. L., 336 Kenmore Rd., Douglaston, N. Y.
Symons, G. E., c/o Water Works & Sewerage, 155 E. 44th St., New York City
Taggart, Robert S., 268 Guy Park Ave., Amsterdam, N. Y.
Tallamy, Bertram D., 5488 Main St., Williamsville, N. Y.
Tamer, Paul, Hackensack Water Co., New Milford, N. J.
Taylor, Henry W., Consulting Engr., 11 Park Place, New York City
Taylor, Warren G., Prof., 38 Union Ave., Schenectady, N. Y.
Terhoeven, G. E., 76 Navel Ave., Buffalo, N. Y.
Terry, Frank, 29 Willow Ave., Freeport, N. Y.
Tetzlaff, Frank, 4606 Walsh St., Chevy Chase, Md.
Thamasett, Otto E., J. N. Adams Memorial Hospital, Perrysburg, N. Y.
Thatcher, Fred A., 18 Belleview Ave., Port Washington, N. Y.
Thayer, Reginald H., 21 Morsemere Place, Yonkers, N. Y.
Thompson, F. N., Room 403, 18 Pearl St., Utica, N. Y.
Thomson, J. B. F., 322 Main St., Huntington, N. Y.
Todd, Stanley B., 41 Bigelow Ave., Dundee, N. Y.
Tolman, S. L., c/o Jeffrey Mfg. Co., Columbus, Ohio
Tomm, LaVern M., 11 Clinton St., Tonawanda, N. Y.
Trautwein, Frederick, 100 Washington St., Freeport, N. Y.
Ulip, Anthony, 42 St. Marks Ave., Freeport, N. Y.
Upton, Frank W., 604 Wolcott Ave., Beacon, N. Y.
Urbana, Robert C., 138 46 Northern Blvd., Flushing, N. Y.
Van Atta, J. W., Vice-President, Ralph B. Carter Co., 53 Park Place, New York City
Van Denburg, J. W., c/o Dept. of Pub. Wks., 125 Worth St., New York City
Vanderlip, Arthur N., Capt., Route No. 2, Storrs, Conn.
Van Deusen, E. J., 21 Pearl St., Malone, N. Y.
Van Wyck, George W., 134 Main St., Nyack, N. Y.
Velz, C. J., Edgars Lane, Hastings-on-Hudson 6, N. Y.
Velzy, C. R., Rm. 1717, 299 Broadway, New York City
VerDow, William H., 269 Murray St., Newark, N. Y.
Victoria, John, Riverhead, N. Y.
Voigt, Richard C., 1060 Military Rd., Kenmore, N. Y.
Vredenburg, Edward L., 20 Van Orden Avenue, Spring Valley, N. Y.
Vrooman, Morrell, 21-23 N. Main St., Gloversville, N. Y.
Wagenhals, H. H., 411 Herald Bldg., Syracuse, N. Y.
Wagner, E. P., Lt. Comdr., U. S. C. G., C. E. Sect., 1300 E St., N.W., Washington, D. C.
Walker, Charles L., 201 Fairmont Avenue, Ithaca, N. Y.
Wardle, J. McClure, Dept. of Public Works, Hudson, N. Y.

Ware, Howard, Union, N. Y.
Warren, George D., Cor. Broad & Church St., Lyons, N. Y.
Washburn, Howard C., East Main St., Shortville, N. Y.
Waters, Leslie W., Box 94, Kerhonkson, N. Y.
Watson, Carl H., 19 Barstow Rd., Great Neck, N. Y.
Weatherby, Charles H., Box 2, 7 W. Lake St., Celoron, N. Y.
Wechter, William H., 1436 Clay St., Bronx, N. Y.
Wedeman, John D., P. O. Box 17, Amawalk, N. Y.
Welch, George C., Plant Opr., 235 W. Main St., Riverhead, N. Y.
Welker, Leland A., 323 Liberty St., Penn Yan, N. Y.
Welsch, W. Frederick, 25 Fairway, Hempstead, N. Y.
Westergaard, Viggio, Dept. of Public Works, 125 Worth St., New York, N. Y.
Wheeler, Robert C., 36 State St., c/o Barker & Wheeler, Albany, N. Y.
Whitley, F. H., Capt., Sn. C., Station Hospital, MacDill Field, Fla.
Whitlock, Ernest W., c/o Malcolm Pirnie, 25 W. 43rd St., New York, N. Y.
Wigley, Chester G., Shelton Hotel, 49th St. & Lexington Ave., New York City
Williams, R. L., c/o Guggenheim Bros. Lab., 202nd St. & 10th Ave., New York, N. Y.
Winfield, Wilmer M., 1319 Rosewood Ave., Schenectady, N. Y.
Wing, Frederick K., 1314 Prudential Bldg., Buffalo, N. Y.
Winne, George, 144 Maple Avenue, Altamont, N. Y.
Woelfle, Arthur H., 758 Main St., Dunkirk, N. Y.
Woese, Carl F., Foote Bldg., Syracuse, N. Y.
Wolfteich, John, 5 Fifth St., Atlantic Beach, N. Y.
Wood, Herbert M., 117 W. Sunrise Highway, Freeport, N. Y.
Wormuth, W. H., 5 Grove St., Baldwinsville, N. Y.
Wright, Chilton A., 99 Livingston St., Brooklyn, N. Y.
Wyckoff, Charles R., 790 Riverside Dr., New York City
Young, Alden W., 235 Osborn Ave., Riverhead, N. Y.
Zack, Samuel L., 71 Cloverdale Rd., Newton Highlands, Mass.
Zollner, Frederick D., 35 State St., Batavia, N. Y.

North Carolina Sewage Works Association

Mr. R. S. Phillips, *Secretary-Treasurer*, P. O. Box 1170, Durham, N. Car.

Abernethy, P. L., Water Dept., Hickory, N. Car.
Adkins, W. W., Supt. of Plants, Water Department, Asheboro, N. Car.
Alexander, Allen Y., Jr., Opr., Sewage Plant, 222 Monmouth Ave., Durham, N. Car.
American Enka Corporation, Mr. B. W. Crutchfield, Enka, N. Car.
Bailey, J. Kenneth, 73 Jackson Ave., Hampton, Va.
Baity, H. G., Prof. of San. & Municipal Engr., University of North Carolina, Box 899, Chapel Hill, N. Car.
Berk, Morton, 1865 E. 24 St., Brooklyn 29, N. Y.
Blalock, Wm. W., Jr., Fort Bragg Water Wks., Box 5, Manchester, N. Car.
Booker, Warren H., Director, Div. of Sanitation, State Bd. of Health, Raleigh, N. Car.
Bunker, F. L., P. O. Box 1122, Chicago Pump Co., Charlotte, N. Car.
Camp, Cecil S., Assoc. Prof. Hydr. & San. Engr., University of Tennessee, Ferris Hall, Knoxville, Tenn.
Carolina Aluminum Co., Mr. A. J. Rice, Asst. Property Supt., Badin, N. Car.
City Water Dept., H. S. Douglass, Supt., Statesville, N. Car.
Cramerton Mills, Inc., C. O. Young, Supt., Cramerton, N. Car.
Davis, H. F., Distr. Mgr., 1902 Pinewood Circle, Wallace & Tiernan Co., Inc., Charlotte, N. Car.
Davis, P. D., Assoc. Engr., W. M. Piatt, Constr. Engr., Durham, N. Car.
Durham Water Dept., D. M. Williams, Supt., Durham, N. Car.
Dunn, Town of, Robert E. Wooten, Supt. of Water Works, Dunn, N. Car.
Franklin, W. M., Box 3162, Dilworth Sta., Charlotte, N. Car.
Gotaas, Harold B., Capt., 5314 Sixteenth Rd., N., Arlington, Va.
Gutierrez, Andrew, c/o Post Engineer, Camp MacKall, N. Car.
Hall, W. H., Dean of Engineering, Duke University, College Sta., Durham, N. Car.

Heyward, T. C., Mech. & Elec. Engr., 1408 Independence Bldg., Charlotte, N. Car.
Kellogg, James W., Asst. Director, State Lab. of Hygiene, Raleigh, N. Car.
Kin, Stephen R., Assoc., San. Engr., c/o Post Engineer, Fort Bragg, N. Car.
LeClere, Arthur B., Sales Engr., T. C. Heywood, 1408 Independence Bldg., Charlotte, N. Car.
Luther, Robert W., Plant Supt., Public Utility Commission, Box 56, Elizabeth City, N. Car.
Malone, J. R., Chemist, Durham Water Dept., 1312 N. Gregson St., Durham, N. Car.
Michael, A. M., Supt. Water & Sewer, Mebane, N. Car.
Moggio, Wm. A., Lt., Box 1042, Burlington, N. Car.
Moore, George S., Supt. Water & Light Dept., Albemarle, N. Car.
Moses, James E., Shop Foreman, City Hall, Durham, N. Car.
Moss, E. H., Supt. Sewage Plants, Water & Sewer Dept., Greensboro, N. Car.
Munroe, City of, W. H. Crow, Supt. Water & Lights, Munroe, N. Car.
Mutzberg, F. A., Supt. Water Wks. Utilities, U. S. Army, P. O. Box 751, Fort Bragg, N. Car.
Nance, E. L., Erwin Creek Plant, Charlotte, N. Car.
Olsen, W. C., Consulting Engineer, Raleigh, N. Car.
Phillips, R. S., Water Dept., P. O. Box 1170, Durham, N. Car.
Piatt, Wm. M., Cons. Engr., 111 Corcoran St., Durham, N. Car.
Purser, Mr. John R., Jr., Treas., J. R. Purser Sales Eng., Inc., Suite 816, Independence Bldg., Charlotte, N. Car.
Ratcliffe, Clyde, Water Department, Wadesboro, N. Car.
Rawlins, George S., Cons. Engr., J. N. Pease & Co., Johnston Bldg., Charlotte, N. Car.
Redding, Harry P., Asst. Supt., Durham Water Dept., Durham, N. Car.
Starling, Charles H., 1st Lt., Corps Engr., c/o Post Engrs., Camp Butner, N. Car.
Stiemke, Robert E., Assoc. Prof. of San. Engr., N. Car. State College, Raleigh, N. Car.
Swab, Bernal H., 1319 Williamson Dr., Raleigh, N. Car.
Swartz, Martin, Supt. Water & Light Comm., Greenville, N. Car.
Thomas, E. R., Supt. Municipal Water Dept., Burlington, N. Car.
True, Albert O., San. Engineer, Proximity Mfg. Co., Denim Branch, Greensboro, N. Car.
Valdese Water Wks., Frank W. Pons, Asst. Treas., Valdese, N. Car.
Vest, W. E., Supt. Water Works, Charlotte, N. Car.
Warrenton Water Co., Moore, J. C., Supt., Water Department, Warrenton, N. Car.
Water Department, C. B. Brooks, Supt., Hemp, N. Car.
Water Department, M. P. Lloyd, Supt., Box 386, Hillsboro, N. Car.
Yow, W. E., Supt., Water Dept., Asheboro, N. Car.

Ohio Sewage Works Conference Group

Mr. D. D. Heffelfinger, *Secretary-Treasurer*, 1101 N. Walnut, Alliance, Ohio

Ackerman, E. G., Sew. Treat. Plant, Bucyrus, Ohio
Backherms, A. B., 3438 Sherel Circle, Cincinnati, Ohio
Bailey, J. W., 617 N. Main St., Bowling Green, Ohio
Barnes, George E., Prof., Case School of Applied Science, Cleveland, Ohio
Barnes, L. B., 127 Meeker St., Bowling Green, Ohio
Barstow, E. D., Barstow & LeFeber, Inc., 31 N. Summit St., Akron, Ohio
Barton, Ben H., 207 Locust St., Findlay, Ohio
Behnke, George C., 400 E. College St., Oberlin, Ohio
Bidlack, C. E., 633 Penton Bldg., Cleveland, Ohio
Braidech, Mathew M., 100 E. 207th St., Euclid, Ohio
Britt, C. E., 505 South Maple St., Bowling Green, Ohio
Browne, Floyd G., Box 27, Marion, Ohio
Bryant, C. T., Supt., 102 E. First St., Springfield, Ohio
Burger, A. A., Engr., Cleveland, Ohio
Collier, James, 1194 Gulf Rd., Elyria, Ohio
Craun, J. M., 355 Hippodrome Annex, Cleveland, Ohio
Decker, C. D., 111 E. Maple St., Bryon, Ohio
Dixon, G. Gale, 37 Carpenter Lane, Germantown, Philadelphia, Pa.
Ellms, J. W., 1130 West 112th St., Cleveland, Ohio
Ewart, K. L., City Bldg., Cuyahoga Falls, Ohio

Finkbeiner, Carleton S., 725 Nicholas Bldg., Toledo, Ohio

Fischer, F. P., Wallace & Tiernan Co., 811 Perry-Payne Building, Cleveland, Ohio

Flower, G. E., 4720 Morningside Drive, Cleveland, Ohio

Fuller, Raymond H., 2201 N. Fourth St., Columbus, Ohio

Gerdel, W. E., c/o City Hall, North Section, Cleveland, Ohio

Hagerty, L. T., Sewage Disposal Plant, Bedford, Ohio

Hall, G. Albro, State Dept. of Health, Columbus, Ohio

Hauck, Charles F., House EE212, Apco, Ohio

Havens, William L., 1140 Leader Bldg., Cleveland, Ohio

Heffelfinger, D. D., 1011 N. Walnut, Alliance, Ohio

Henry, Thomas B., 2210 Eastbrook Drive, Toledo, Ohio

Hess, John S., 1555 S. Seneca Ave., Allianee, Ohio

Hoagland, D., 914 Bennett, Marion, Ohio

Hommon, Charles C., 140 22nd St., N. W., Canton, Ohio

Huffman, Lloyd C., 1966 Burbank Drive, Dayton, Ohio

Hufford, L. E., 1501 Broadway, Piqua, Ohio

Irwin, Forrest, Wullman-Wolfe Corp., Columbus, Ohio

Janes, N. D., 1069 Madison Ave., Columbus, Ohio

Jones, Frank Woodbury, 1140 Leader Building, Cleveland, Ohio

Jones, Harvey P., Toledo Trust Bldg., Toledo, Ohio

Kane, R. D., 2775 Pittsburgh Ave., Cleveland, Ohio

Keller, Dwight, 111 Oakwood Ave., Lancaster, Ohio

Kline, H. S., 37 Pointview Avenue, Dayton, Ohio

Kroone, T. H., 319 Plymouth Bldg., Cleveland, Ohio.

Kussmaul, T. C., c/o John C. Taylor, 117 S. Prospect St., Granville, Ohio

LauRue, Luther, 501 Municipal Bldg., Akron, Ohio

Leach, Walter L., 1140 Leader Bldg., Cleveland, Ohio

Leatherman, W. L., Sew. Treat. Plant, Van Wert, Ohio

Leist, Ervin F., 109 Seyfert Ave., Circleville, Ohio

Lesher, Carl, 1085 Homewood Dr., Lakewood, Ohio

Luchtenberg, R. O., 256 N. Ardmore Rd., Columbus, Ohio

Lyman, C. S., Sewage Treatment Wks., Bay View Park, Toledo, Ohio

McGuire, C. D., 448 Clinton St., Columbus, Ohio

McIntyre, F. J., 58 Oleutangy St., Columbus, Ohio

McKee, S. C., Sanitary Engr., Lucas County Court House, Toledo, Ohio

MacDowell, R. F., 401 Chester-Twelfth Bldg., Cleveland, Ohio

MacLachlan, Angus, 1740 East 12th St., Cleveland, Ohio

Monroe, S. G., Assoc. Pub. Health Engr., U. S. Public Health Service, 831 Mercantile Bank Bldg., Dallas, Tex.

Morehouse, W. W., Director of Water Dept., Rm. 309, Municipal Bldg., Dayton, Ohio

Nelson, Frederick G., c/o The Dorr Co., Inc., 221 No. LaSalle St., Chicago, Ill.

Niles, A. H., Supt., Sewage Treatment Works, Bay View Park, Toledo, Ohio

O'Flaherty, Dr. Fred., Director, Dept. of Leather Research, University of Cincinnati, Cincinnati, Ohio

Palocsay, Frank S., c/o Havens & Emerson, 1140 Leader Bldg., Cleveland 14, Ohio

Parrish, Rial T., 945 U. S. Bldg., Dayton, Ohio

Pease, Maxfield, 1900 Euclid Ave., Rm. 606, Cleveland, Ohio

Pollex, Elmer, Foreman, Div. of Sew. Disp., c/o Sew. Treat. Wks., Bay View Park, Toledo, Ohio

Powers, E. C., Mgr. Lime Sales, Marble Cliff Quarries, 20 N. 5th St., Columbus, Ohio

Roth, R. F., 116 W. Spring St., Oxford, Ohio

Ruck, Franklin, Water Softener & Sewage Disposal Plant, R. R. No. 3, Troy, Ohio

Rupp, Daniel H., Water Department, City Hall, Topeka, Kans.

Sargent, Edward C., 2376 Northland Ave., Lakewood, Ohio

Schade, Willard F., 1st Lt., 2240 Briarwood Rd., Cleveland Hts. 18, Ohio

Schaetzle, T. C., Rm. 501, Municipal Bldg., Akron, Ohio

Schick, V. R., 1053 W. Main St., Van Wert, Ohio

Schoepfle, O. F., 908 Vine St., Sandusky, Ohio

Sheets, W. D., Capt., 0-511889, Station Hospital, Camp Cooke, Calif.

Singer, Oscar C., Lucas County Distr. Bd. of Health, 902 Adams St., Toledo, Ohio

Smith, A. H., 2140 Ashland Ave., Toledo, Ohio

Smith, E. E., Supt., Water & Sewage, Lima, Ohio

Snyder, Clifford A., 78 W. Summit St., Barberton, Ohio
Snyder, R. F., 1717 Milton Ave., n.e. Massillon, Ohio
Specht, James E., 1115 Perry St., Orrville, Ohio
Stepleton, Harold A., 3515 Maxwell Rd., Toledo, Ohio
Straker, M. L., Box 65, Versailles, Ohio
Tatlock, M. W., 2600 Salem Ave., Dayton, Ohio
Tolles, Frank C., 1140 Leader Building, Cleveland, Ohio
Turner, J. R., 136 Rae Ave., Mansfield, Ohio
Uhlmann, Paul A., 2525 N. High St., Columbus, Ohio
Walker, C. C., 1826 W. 1st Ave., Columbus, Ohio
Wenger, J. H., 83 E. Broadway, Westerville, Ohio
Wertz, Leroy F., Town Hall, Lebanon, Ohio
Wirts, J. J., Easterly Sew. Treatment Wks., 14101 Lake Shore Dr., Cleveland, Ohio
Wittmer, Earl F., 506 Mt. Vernon Ave., Marion, Ohio
Woodruff, F. L., 13452 Merl Ave., Cleveland, Ohio

Oklahoma Water and Sewage Conference

Mr. H. J. Darcey, *Secretary-Treasurer*, State Dept. of Health, Oklahoma City, Okla.

Bretz, C. E., 1221 North Pennsylvania Ave., Oklahoma City, Okla.
Cunningham, M. B., Supt. & Engr., Oklahoma City Water Dept., Rm. 203, Municipal Bldg., Oklahoma City, Okla.
Darcey, H. J., c/o State Dept. of Health, Oklahoma City, Okla.
Fridley, Jesse R., Col., Utilities Dept., Oklahoma City Air Depot, Tinker Field, Oklahoma City, Okla.
Moutrey, Curtis, c/o Capt. R. M. Dixon, Sanitation Section, Repair & Utilities Div., Eighth Service Command, Dallas, Tex.
Schouten, Ernest W., 828 Braniff Bldg., Third & Robinson Sts., Oklahoma City, Okla.
Stapley, Edward R., 27 College Circle, Stillwater, Okla.
Taylor, Frank S., Filtration Engineer, 2809 Northwest 17th St., Oklahoma City, Okla.

Pacific Northwest Sewage Works Association

Mr. W. P. Hughes, *Secretary-Treasurer*, City Engineer, Lewiston, Idaho

Anderson, Fred A., R. F. D., No. 2, Bothel, Wash.
Baker, Stanley L., 1218 E. 89th St., Seattle, Wash.
Bamford, J. H., Water Superintendent, Dayton, Wash.
Barney, J. W., City Mgr., Hillsboro, Ore.
Bartow, Leslie W., Sewer Engineer, City of Portland, 6515 S. W. Burlingame Ave., Portland, Ore.
Blust, T. L., Water Supt., City Hall, Silverton, Ore.
Bow, Wilson F., State Dept. of Health, 1403 Smith Tower, Seattle, Wash.
Brewer, E. E., Water Supt., Shelton, Wash.
Briggs, Raymond J., Consulting Engr., Noble Bldg., Boise, Idaho
Buchecker, A. L., Prin. Asst. City Engr., City of Spokane, 725 Chelan Ave., Spokane, Wash.
Campbell, M. S., Washington State Health Dept., 1403 Smith Tower, Seattle, Wash.
Casad, C. C., Supt., Bremerton Water Dept., Bremerton, Wash.
Chambers, Grover, Water Supt., Cheney, Wash.
Charlton, David, Dr., 2340 S. W. Jefferson St., Portland, Ore.
Clare, H. C., Sanitary Engineer, Dept. of Public Health, Boise, Idaho
Cloyes, W. J., Sanitarian, Lane County Health Dept., Court House, Eugene, Ore.
Corey, R. H., Consulting Engineer, 407 Corbett Bldg., Portland, Ore.
Cotta, Maurice L., Assoc. San. Engr., Farm Sec. Admin., 1305 Terminal Sales Bldg., Portland, Ore.
Crow, Harry B., Sewer Supt., P. O. Box 3084, Kirkland, Wash.
Cunningham, John W., 1112 Spalding Bldg., Portland, Ore.
Davis, G., Jr., 209 Eden Rd., Boise, Idaho
DeMoss, Samuel, 1746 W. 59th, Seattle, Wash.
Dodson, Roy E., Jr., Asst. San. Engr., 806 Oregon Bldg., Portland, Ore.
Early, Mart, Water Supt., Moscow, Idaho

Forsbeck, C. D., City Engineer, Dept. of Public Works, Tacoma, Wash.
Fowler, H. D., P. O. Box 3084, Seattle 14, Wash.
Gearhart, J. N., Myrtle Point, Ore.
Gilman, N. A., City Hall, Yakima, Wash.
Gooch, E. W., City Engr., 210 Lottie St., Bellingham, Wash.
Goodnight, V. L., City Engineer, Corvallis, Ore.
Green, Alvin W., City Hall Annex, Tacoma, Wash.
Green, Carl E., 1112 Spalding Bldg., Portland, Ore.
Hadin, Leon A., 2551 N. E. Dekum St., Portland, Ore.
Hall, G. D., Engr., 116 A. W. Larson Bldg., Yakima, Wash.
Hallam, G. C., Water Supt., P. O. Box 447, Orofino, Idaho
Hamilton, R. F., Lt. Col. C. E., P. O. Box 1474, Colorado Springs, Colo.
Harding, Robert G., Consulting Engr., 1141 Utah Savings & Trust Bldg., Salt Lake City, Utah
Harrison, B. D., Harrison Pipe Co., 3615 East B St., Tacoma, Wash.
Heis, Edward A., Pac. N. W. Div. Mgr., Wallace & Tiernan Sales Corp., 917 Terminal Sales Bldg., Seattle, Wash.
Hill, W. R., Parker & Hill, Civil & Consulting Engrs., 2021 Smith Tower, Seattle, Wash.
Holter, A. L., City Engineer Office, County-City Bldg., Seattle, Wash.
Howard, C. M., Concrete Pipe & Products Ass'n, 4319 Stoneway, Seattle, Wash.
Hoydar, Albert L., Water & Sew. Supt., 24 Naches, Selah, Wash.
Hughes, W. P., City Water Supt., Lewiston, Idaho
Irwin, G. M., City Engineer, City Hall, Victoria, British Columbia, Can.
Jensen, Emil C., 526 Hutton Bldg., Spokane, Wash.
Kingwell, E. G., 615 N. 14th St., Salem, Ore.
Kipp, W. H., Mgr., Waterworks Supplies Co., 947 S. E. Market St., Portland 14, Ore.
Knittel, E. A., Water Supt., Lynden, Wash.
Koon, Ray E., Spalding Building, Portland, Ore.
Kramer, Harrison, W., H. D. Fowler Co., Box 3084, Seattle, Wash.
Layport, H. R., 4324 Bagley Ave., Seattle 3, Wash.
Lovejoy, W. L., City Engr. & Water Supt., Hoquiam, Wash.
McHugh, Basil, City Engineer, Enumclaw, Wash.
McLean, R. F., Supt. Water Dept., Walla Walla, Wash.
Malony, W. L., Symons Bldg., Spokane, Wash.
Mathews, Frank E., P. O. Box 487, Ellenburg, Wash.
Morrison, James E., P. O. Box 178, Renton, Wash.
Morrow, Ben S., Engineer's Office, Water Bureau, City Hall, Portland, Ore.
Nelson, Ben O., City Manager, Pullman, Wash.
Pierron, Wm. Jr., City Hall, Sanitary Inspector, Bellingham, Wash.
Rice, Archie H., 3244 N. E. 15th, Portland, Ore.
Ruppert, E. L., Public Health Engr., Washington State Dept. of Health, Seattle 44, Wash.
Seeger, M. Dean, City Comptroller, Bellingham, Wash.
Shera, Brian L., Service Engr., Pennsylvania Salt Mfg. Co., Tacoma, Wash.
Shirley, Mr. Donald L., 820 First Avenue South, Seattle 4, Wash.
Signor, C. V., Water Supt., Grants Pass, Ore.
Sisler, H. H., Cons. Engr., 2821 29th Ave. West, Seattle, Wash.
Small, R. L., Sanitarian, Box 1009, Boise, Idaho
Smith, Harvey J., City Engr., City Hall, Moscow, Idaho
Smithson, Thomas, Cons. San. Engr., 5301 N. Kerby Ave., Portland, Ore.
Snyder, M. K., Prof., Civil Engineering Dept., Washington State College, Pullman, Wash.
Spaulding, L. H., 6851 E. Marginal Way, Seattle, Wash.
Sylliassen, M. O., 1401 52nd Ave., N.E., Seattle, Wash.
Thiel, James A., City Hall, Bellingham, Wash.
Turner, W. S., W. S. Turner & Co., Pacific Building, Portland, Ore.
Tyler, R. G., Prof., Dept. of Civil Engineering, University of Washington, Seattle, Wash.
Van Horn, R. B., Prof., Dept. of Civil Engineering, University of Washington, Seattle, Wash.
Vognild, R. O., Hooker Electrochemical Co., Tacoma, Wash.
Volpp, A. G., Water Supt., Box 114 Willamette, West Linn, Ore.
Walker, Miss Irene, Pacific Builder and Engineer, 3102 Arcade Building, Seattle, Wash.
Ward, Paul, Asst. State San. Engr., Division of Public Health, Boise, Idaho
Washington State Pollution Commission, Gig Harbor Laboratory, Gig Harbor, Wash.
Williams, Charles, City Engr., & Water Supt., 826 Percival St., Olympia, Wash.

Pennsylvania Sewage Works Association

Mr. Bernard S. Bush, *Secretary-Treasurer*, Penna. Dept. of Health, Kirby Health Center, Wilkes-Barre, Pa.

Alexander, J. D., City Councilman, City Bldg., New Castle, Pa.

Allen, James H., Engr., The Interstate Commission on the Delaware River Basin, 581 Broad St., Station Bldg., Philadelphia, Pa.

Bailey, S. C., Danville State Hospital, Danville, Pa.

Bainbridge, David W., 208 Yeakel Avenue, Chestnut Hill, Philadelphia, Pa.

Barker, J. Conrad, Jr., Supt. of Pumping Stations, Lower Merion Twp., 75 E. Lancaster Ave., Ardmore, Pa.

Barney, John J., Sewage Treatment Wks., Byberry, Philadelphia, Pa.

Baum, H. J., City Engineer, 3205 Broad Ave., Altoona, Pa.

Barrick, M. J., Dist. Engr., Penna. Dept. of Health, 138 E. Third St., Williamsport, Pa.

Beamesderfer, Jas. A., Chief Opr., Lebanon Sewage Tr. Plant, 613 N. 8th St., Lebanon, Pa.

Beaumont, H. M., 480 Martin St., Rox., Philadelphia, Pa.

Beckett, R. C., State Sanitary Engineer, State Board of Health, Dover, Del.

Binkley, Alvin G., Rep., Boro of Mt. Penn., 2054 Fairview St., Mt. Penn, Reading, Pa.

Boardman, John, Sanitary & Hydraulic Engineer, 426 Walnut St., Philadelphia, Pa.

Boardman, Wm. Hunter, Jr., Civil, Hydr. & San. Engineer, 426 Walnut St., Philadelphia, Pa.

Bogardus, Theodore S., 141 Murphy St., Berea, Ohio

Bolenius, Robert M., Chemist, 561 S. Queen St., Lancaster, Pa.

Boone, Geo. H., Chief Opr., Norristown Sew. Treat. Plt., 713 Church St., Norristown, Pa.

Brown, Dr. Glenn V., 312 East Main St., Mechanicsburg, Pa.

Brown, Michael, 7019 Mower St., Philadelphia, Pa.

Brumbaugh, W. V., Nat'l Lime Ass'n, 927 15th St., N.W., Washington, D. C.

Buckley, Thomas, Phila. Bureau of Engr., City of Philadelphia, 1103 City Hall Annex, Philadelphia 7, Pa.

Bush, Bernard S., Dist. Engr., Penna. Dept. of Health, Kirby Health Center, Wilkes-Barre, Pa.

Campbell, John, Chester Engrs., 210 E. Parkway, Pittsburgh, Pa.

Carpenter, J. D., Civil Engr., Gannett, Eastman & Fleming, Inc., Harrisburg, Pa.

Caulwell, Wilson, S. Opr., Boro of Ephrata, 223 W. Franklin St., Ephrata, Pa.

Chase, E. Sherman, Metcalf & Eddy, 1300 Statler Bldg., Boston, Mass.

Cleland, R. R., 222 Hartswick Ave., State College, Pa.

Clouser, L. H., Tennessee Valley Authority, 502 Union Bldg., Knoxville, Tenn.

Colitz, Michael J., 197 Dock St., Schuylkill Haven, Pa.

Coltart, Rodney F., Link Belt Co., 2045 W. Hunting Park Ave., Philadelphia, 40, Pa.

Corddry, W. H., Gannett, Eastman & Fleming, Inc., Harrisburg, Pa.

Craig, Robert H., Consulting Engr., Chamber of Commerce Bldg., Harrisburg, Pa.

Cunningham, H. L., Allentown State Hosp., Allentown, Pa.

Daniels, F. E., Chief, 2615 N. 2nd St., Harrisburg, Pa.

Darby, W. A., The Dorr Co., 570 Lexington Ave., New York City

Dawson, T. T., Harwood Beebe Company, Montgomery Building, Spartansburg, S. C.

Dermitt, C. W., Field Rep., Pa. Salt Mfg. Co., 541 Union Trust Bldg., Pittsburgh, Pa.

Diefendorf, Fred G., Supt., P. O. Box 1533, Erie, Pa.

Durr, John J., Jr., Box 83, Bartley, N. J.

Eastburn, W. H., Rep., The Mathieson Alkali Works, Inc., Widener Bldg., Philadelphia, Pa.

Edgerley, Edward, 343 N. West End Avenue, Lancaster, Pa.

Elias, George A., Distr. Engr., Penna. Dept. of Health, Suite 303, Keystone Bldg., Philadelphia, Pa.

Emerson, C. A., Havens & Emerson, Woolworth Bldg., New York City

Emigh, William C., Coatesville, Pa.

English, Joseph, Jr., Municipal Sewage Tr. Wks., 927 Ford St., Bridgeport, Pa.

Evans, David A., Sanitary Disp. Engr., P. O. Box 862, Reading, Pa.

Faber, Harry A., 50 E. 41st St., New York City.

Flanagan, Joseph E., Jr., 1792 Northwest Blvd., Columbus, Ohio

Fleming, M. C., Engineer, Hardinge Company, Inc., York, Pa.

Foster, Norman, Cons. Engr., Damon & Foster, Chester Pike & High St., Sharon Hill, Pa.

Freeburn, H. M., Dist. Engr., Phila., Suburban Water Co., 1251 Montgomery Ave., Wynnewood, Pa.

Freund, J. P., Vice-Pres. & Plant Engr., Wyomissing Valley Disposal Co., P. O. Box 940, Reading, Pa.

Fricker, Augustus E., Ind. Wastes & Sewage Wks., Easton Rd., Roslyn, Pa.

Friel, F. S., Albright & Friel, 1520 Locust St., Philadelphia, Pa.

Fuehrer, Carl W., Borough Mgr., Borough of Ephrata, 21 E. Locust St., Ephrata, Pa.

Funk, John T., Jr., Borough Engr., Borough of Tyrone, Municipal Bldg., Tyrone, Pa.

Gerhart, Edgar, Opr., Sew. Disp. Plt., Spring City, Pa.

Gidley, H. K., State Health Dept., Charleston, W. Va.

Gilbert, J. J., 201 Wheatsheaf Lane, Abington, Pa.

Gill, Paul, 725 Chestnut St., Indiana, Pa.

Gilligan, Howard, Plant Supt., Borough of State College, 809 W. Beaver Ave., State College, Pa.

Glace, I. M., Jr., c/o J. H. Pease & Co., Johnston Bldg., Charlotte, N. Car.

Glace, I. M., Consulting Engr., 20 South 22nd St., Harrisburg, Pa.

Goff, Wm. A., Broad St. Sta. Bldg., 16th & Penna. Blvd., Suite 1411, Philadelphia, Pa.

Gracenin, Sylvester, 923 Darr Ave., Farrell, Pa.

Grossart, L. J. H., 816 Chew St., Allentown, Pa.

Haddock, Fred R., Chief Engineer, Roberts Filter Manufacturing Co., Darby, Pa.

Hart, W. B., Supt. Gas, Acid & Drainage Dept., 3144 Passyunk Ave., Philadelphia, Pa.

Hartzell, E. F., Supt., Palmerton Disposal Co., Palmerton, Pa.

Harvey, J. R., Asst. Engr., State Dept. of Health, Suite 303, Keystone Bldg., 261 N. Broad St., Philadelphia, Pa.

Haseltine, T. R., 4817 Centre Ave., Pittsburgh, Pa.

Haworth, J. Victor, Borough Secretary, Moylan, Rose Valley, Pa.

Haydock, Charles, Cons. Engr., 311 Commercial Trust Bldg., Philadelphia, Pa.

Hedgepeth, L. L., Research Chemist, Pa. Salt Manufacturing Co., 1000 Widener Building, Philadelphia, Pa.

Hess, Daniel J., Jr., 7530 St. Charles Ave., New Orleans, La.

Hill, Theo. C., Hill & Hill, Engineers, North East, Pa.

Hodge, W. W. Head, Dept. of Chemical Engineering, West Virginia University, Morgantown, W. Va.

Jones, Frank Woodbury, 1140 Leader Bldg., Cleveland, Ohio

Keefer, R. K., Supt., Sewage Treatment Plant, 339 South St., Clarion, Pa.

Herr, H. N., 114 Java Ave., Hershey, Pa.

Hewitt, A. C., Chief Engineer, American Lime and Stone Co., Bellefonte, Pa.

Hibschman, Charles A., Supt., Ambler Borough, Ambler, Pa.

Hoak, Richard D., Mellon Institute of Industrial Res., Pittsburgh, Pa.

Hoeflich, G. C., 619 Saude Avenue, Essington, Pa.

Hoffert, J. R., Penna. Dept. of Health, Harrisburg, Pa.

Hutton, H. S., Wallace & Tiernan Co., Inc., Newark, N. J.

Johnson, Earle P., Flannery Bldg., Pittsburgh, Pa.

Jones, Everett M., Gen. Mgr., Simplex Valve & Meter Co., 68th & Upland Sts., Philadelphia, Pa.

Kappe, S. E., 5230 Massachusetts Ave., Washington, D. C.

Kay, Frank E., Asst. San. Engr., Penna. Dept. of Health, 2225 Taggart St., Philadelphia, Pa.

Kelly, Francis W., U. S. Engineers Office, 900 Custom House, 2nd and Chestnut Sts., Philadelphia, Pa.

Kelsey, Walter, Lord & Burnham Co., Irvington On Hudson, N. Y.

Kern, Andrew G., Treas., Nazareth Sewerage Co., Easton Rd., Nazareth, Pa.

Kinderman, Wm., Sew. Plt. Supt., 200 N. 26th St., Camp Hill, Pa.

Kinsel, Harry L., 6 Holland St., Newton, Mass.

Kochin, Milton S., Capt., 0-484117, Sta. Hosp., Camp Livingston, La.

Kratz, Fred R., County Line, R. F. D., Hatboro, Pa.

Krum, Harry J., Jr., Sanitary Engr., U. S. Engineers, 270 Broadway, New York City

Krum, Harry J., City Chemist, Jefferson & Lawrence Sts., Allentown, Pa.

Lang, Wm. H., San. Engr., R. F. D. No. 1, Denbigh, Va.

Langford, Leonard L., 441 Lexington Ave., New York City

Lauer, Charles N., Supt., Sewage Disposal Plt., City Hall, York, Pa.

Leh, Willard, Capt., 1376 Perkiomen Ave., Reading, Pa.

Leimbach, Harry, Operator, Sewage Treatment Plant, 235 Greenwich St., Kutztown, Pa.

Leithiser, E., New Eastern State Penitentiary, c/o Mr. John H. Flohr, Sr., Graterford, Pa.

Link-Belt Company, George M. Sharer, Philadelphia, Pa.

Long, George S., Designing Engineer, 816 Chinook Ave., Akron, Ohio

Longley, Paul N., Supt., Radnor-Haverford Sewage Treat. Plt., Glendale Road, Bon Air, Newtown Square P. O., Pa.

Lutz, Howland C., U. S. Public Health Service, Florida State Board of Health, Jacksonville, Fla.

McAdoo & Allen Welting Co., S. Hellertown Ave., Quakertown, Pa.

Mansfield, M. G., Rep., Morris Knowles, Inc., 1312 Park Bldg., Fifth Ave. & Smithfield St., Pittsburgh, Pa.

Matter, L. D., 2536 Lexington St., Harrisburg, Pa.

Mebus, George B., Consulting Engineer, 112 S. Easton Road, Glenside, Pa.

Merkel, Paul P., Cons. Chem., 1707 Olive St., Reading, Pa.

Miller, J. John, Major, C. E., 308 Warren St., W. Pittston, Pa.

Miller, Lewis B., Consulting Engr., 245 Forrest St., Ambler, Pa.

Milligan, Francis B., 2314 Walnut St., Camp Hill, Pa.

Moon, James N., Sewer Supt., Media, Pa.

Moore, Charles A., Opr., Sewage Disposal Plant, 450 Green St., Royersford, Pa.

Morris, Paul J., Sewage Treat. Plt., 319 South 6th St., Reading, Pa.

Moses, H. E., 1522 N. Second St., Harrisburg, Pa.

Mowrey, J. Hase, Rep., Boro of Chambersburg, Public Utilities, Chambersburg, Pa.

Mowry, R. B., 1649 N. Broad St., Philadelphia, Pa.

Mulvihill, F. J., 1028 Connecticut Ave., Washington 6, D. C.

Murdock, Wm., San. Engr., 3984 Drexel Hill Rd., Pittsburgh, Pa.

Nugent, Franklin J., 10 N. Greenwood St., New Castle, Pa.

O'Donnell, R., 119 S. Atherton St., State College, Pa.

O'Hara, John, Opr., White Haven Sanitorium, White Haven, Pa.

Olewiler, Grant M., Asst. Supt. of Health & Drainage, 75 E. Lancaster Ave., Ardmore, Pa.

Paul, Richard B., Sewage Operator, New Eastern State Penitentiary, Graterford, Pa.

Payrow, Harry G., Rep., Asst. Prof. Sanitary Engineering, Dept. of Civil Engineering, Lehigh University, Bethlehem, Pa.

Phillips, Roy L., City Engr., Meadville, Pa.

Ralston, Wilmer R., Sewerage Opr., 214 William St., Downingtown, Pa.

Reese, Marshall, Rep., Buckhill Falls Co., Buck Hill Falls, Pa.

Reeve, Lester G., 309 Loney St., Fox Chase, Philadelphia, Pa.

Regester, George E., Jr., Borough Engr., Borough of Kennett Square, Kennett Square, Pa.

Reuning, Howard T., Engineering Dept., Elk Tanning Co., Montmorenci Rd., Ridgway, Pa.

Rhoads, Edward J., Supt. Sewage Treatment Plant, City of Lancaster, 531 Chester St., Lancaster, Pa.

Rice, John M., Consulting Engineer, Century Building, Pittsburgh, Pa.

Roeller, R. S., Field Sales Manager, Penna. Salt Mfg. Co., 1000 Widener Bldg., Philadelphia, Pa.

Roetman, Edmond T., Sanitary Engineer, American Viscose Corp., Marcus Hook, Pa.

Rogers, D. Paul, State Dept. of Health, Harrisburg, Pa.

Rosengarten, W. E., Twp. Engr., 75 E. Lancaster Avenue, Ardmore, Pa.

Schaut, George G., 1308 W. Ontario St., Philadelphia, Pa.

Scheffer, Louis K., 1013 Green St., Harrisburg, Pa.

Schmick, Mark F., 2430 Sanger St., Philadelphia, Pa.

Schuyler, Howard L., Industrial Wastes & Sewage Wks., Edison, Bucks County, Pa.

Schwartz, H. L., Eastern Dist. Rep., The American Well Wks., Inc., 528 Commercial Trust Bldg., Philadelphia, Pa.

Searight, George P., Capt., 275 Parker St., Carlisle, Pa.

Seltzer, J. M., Elkins Tannery, Elkins, W. Va.

Shank, John J., Director, Wayne Laboratories, 17 E. Main St., Waynesboro, Pa.

Sheen, Robert T., 7711 Orchard Way, Chestnut Hill, Pa.

Shertzer, J. H., City Engineer, Lancaster, Pa.

Showalter, Charles M., Steward, Laurelton State Village, Laurelton, Pa.

Siebert, Christian L., Executive Engineer, Sanitary Water Board, Pa. Dept. of Health, Harrisburg, Pa.

Siple, H. M., Certified Land Surveyor, P. R., Rupert Firm, 2822 23rd St., North, Arlington, Va.

Smith, Marvin L., 513 Bishopthorpe St., Bethlehem, Pa.

Snelsire, William, Rep., Penna. Salt Mfg. Co., 641 Union Trust Bldg., Pittsburgh, Pa.

Spear, William B., Sewage Disposal Plant, R. D. No. 7, Chambersburg, Pa.
Speiden, H. W., Dept. of Civil Engineering, West Virginia University, Morgantown, W. Va.
Stewart, H. M., 35th & Allegheny Ave., Philadelphia, Pa.
Strockbine, Walter, Sewage Plant Supt., Budd Mfg. Co., 3433 Ryan Ave., Philadelphia, Pa.
Susa, Stephen A., Supvr. of Sewage Plant, 306 Hamilton Ave., Farrell, Pa.
Swinehart, Eugene B., Chief Operator, Pottstown Boro Sewage Disp. Plant, 1133 South St., Pottstown, Pa.
Thorn, Wm. J. Branch Mgr., Innis, Speiden & Co., 401 North Broad St., Philadelphia, Pa.
Trebler, H. A., Chemical Engr., 1403 Eutaw Place, Baltimore 17, Md.
Turner, Homer G., Research Engr., State College, Pa.
Tygert, C. B., Representative, Wallace & Tiernan Co., Inc., 208 Jackson Avenue, Rutherford, N. J.
Umbenhauer, E. J., Dept. of Water & Sewage, El Paso, Tex.
Van Atta, J. W., Vice-President, Ralph B. Carter Co., 53 Park Place, New York City
Wagner, Edwin B., Downingtown, Pa.
Walker, Elton D., Dept. of Civil Engr., Penna. State College, State College, Pa.
Weachter, Horace, Rep., Boro of Lansdale, 110 Courtland St., Lansdale, Pa.
Weisel, W. O., City Engr., Supt. of Pub. Wks., Borough Hall, Doylestown, Pa.
Wertz, C. F., P. O. Box 4821, Miami, Fla.
Weston, Roy F., 3144 Passyunk Avenue, Philadelphia, Pa.
Whitby, Stephen S., Chicago Pump Co., 2019 Rittenhouse Square, Philadelphia, Pa.
Whitcomb, Leon R., 408 West Ave., Jenkintown, Pa.
Wiest, Gordon J., 32 Home Road, Hatboro, Pa.
Williams, A. C., Township Engr., Haverford Township, Upper Darby Post Office, Oakmont, Pa.
Winslow, Wm. H., Somerton Ave., Philadelphia 16, Pa.
Wirt, R. M., Can. Engr., Court House, Arlington, Va.
Wood, Alan H., Sales Engr., Builders Providence, 310 Chandler Bldg., Washington, D. C.
Woodring, R. W., City Chemist & Bact., Bethlehem City Lab., Third & Adams Sts., Bethlehem, Pa.
Woodward, John D., 204 E. 10th Ave., Conshohocken, Pa.
Worrest, Howard A., Supt. of Water & Sewers, Borough of Millersville, Millersville, Pa.
Wright, Arthur, 6112 Oakley St., Philadelphia 11, Pa.
Wyant, Clifford, Asst. to Chief Operator, Richboro, Pa.
Yenchko, John, Asst. Sanitary Engr., Pa. Dept. of Health, Kirby Health Center, Wilkes-Barre, Pa.
Yerkes, Milton R., Engineer, Radnor Twp., Wayne, Pa.
Young, C. H., Dist. Engr., Pa. Dept. of Health, 608-09 Crawford County Trust Bldg., Meadville, Pa.
Young, Norman C., Borough Manager, Borough Hall, Pheonxville, Pa.
Zeigler, C. H., Opr., Nazareth Sewerage Co., Nazareth, Pa.

Rocky Mountain Sewage Works Association

Mr. Carroll H. Coberly, *Secretary-Treasurer*, 1411 Welton St., Denver, Colo.

Amend, J. E., Water & Sewer Supt., City Hall, Brighton, Colo.
Brownson, Bruce, City Manager, City Hall, Grand Junction, Colo.
Cary, Glen, Sr., Operator, Ft. Logan Sew. Treatment Plant, 2926 Eaton St., Denver, Colo.
Cederberg, C. R., 1420 Dahlia St., Denver, Colo.
Coberly, Carroll H., Consulting Engineer, 1441 Welton St., Denver, Colo.
Coy, Burgis, City Hall, Ft. Collins, Colo.
Dagger, G. E., Unit 3, Rt. 2, Box 103, Littleton, Colo.
Davis, Charles A., City Sanitary Engr., City and County Bldg., Denver, Colo.
Donnell, George M., Consulting Engr., Worland, Wyo.
Fox, Paul S., Major, Sn. C., 3629 Agnes Ave., Kansas City 3, Mo.
Franks, John T., 7th Service Command, 3041 N. 50th St., Omaha, Nebr.
Freeman, W. B., Mgr., Lock Joint Pipe Co., 1716 California St., Denver, Colo.
Greene, J. F., 804 W. 5th St., Loveland, Colo.
Gross, Dwight D., Chief Engr., Bd. of Water Commissioners, City & County Building, Denver, Colo.

Heaslit, Mr. Walter, Water & Sewer Supt., Arvada, Colo.
Hendryx, Clarence E., 132 W. J. St., Casper, Wyo.
Hill, Frank C., Water & Sewer Supt., City Hall, Montrose, Colo.
Howe, Ben V., State Sanitary Engr., Argonaut Hotel, Denver, Colo.
Leonard, W. V., State San. Engr., Dir. of Pub. Health Engr., Cheyenne, Wyo.
Jenks, Glen, Sewage Plant Supt., 150 W. Heald St., Sheridan, Wyo.
Johnson, Russell, 1145 N. Gibson, Casper, Wyo.
Kepner, Dana E., 1921 Blake St., Denver, Colo.
Knollman, Fred, 2644 S. Lincoln, Denver, Colo.
Lilly, Geo. M., 1217 S. Conwell St., Casper, Wyo.
McClintock, H. C., City Manager, Boulder, Colo.
Melburg, Fred, 1407 S. Fenway St., Casper, Wyo.
Moran, Alton B., 1421 5th Ave., Scottsbluff, Nebr.
Moudy, R. B., Casper Air Base, 616 S. Wolcott, Casper, Wyo.
Osborn, L. C., 1368 Ash St., Denver, Colo.
Radcliff, Robt. C., Laramie, Wyo.
Reybold, E. C., Secy., Dorr. Co., Inc., The, 1009 17th St., Denver, Colo.
Ruckel, Paul J., Sr., Associate Sanitary Engineer, Camp Hale, Pando, Colo.
Ryan, Alfred J., Consulting Engr., First National Bank Bldg., Denver, Colo.
Rymer, Mary E., Mrs., City Hall, Colorado Springs, Colo.
Schirk, J. M., 804 E. 3rd, Casper, Wyo.
Schmit, J. M., City Engineer, City Hall, Lewiston, Mont.
Simson, George, Jr., Vice-Pres., Denver Sewer Pipe & Clay Co., P. O. Box 2329, Denver, Colo.
Slee, Angus E., City Engr., Longmont, Colo.
Streeter, Robert L., Box 411, Greeley, Colo.
Thompson, N. J., Thompson Pipe & Steel Co., 3001 Larimer, Denver, Colo.
Urquhart, M. B., Mfgrs., Representative, 16th & Blake Sts., Denver, Colo.
Van Ness, Joseph A., 1515 E. 2nd St., Casper, Wyo.
Vaseen, V. A., Lt., Post Sanitation Officer, Station Hospital, Craig Field, Selma, Ala.
Veatch, F. M., 4706 Broadway, Kansas City, Mo.
Watson, Henry G., City Engineer, 102 City & County Bldg., Cheyenne, Wyo.
Williams, L. O., Jr., State Bd. of Health, Cheyenne, Wyo.

Sewage Division—Texas Section, S. W. W. A.

Mr. V. M. Ehlers, *Secretary-Treasurer*, State Dept. of Health, Austin, Tex.

Allison, S. L., 1218 6th St., Corpus Christi, Tex.
Bandy, W. A., 4402 Avenue F., Austin, Tex
Beard, F. W., 1835 Garrett, Dallas, Tex.
Becker, Philip G., Jr., 1009 Orange St., Fort Worth, Tex.
Berg, E. J. M., Route 7, Box 219, San Antonio, Tex.
Billings, L. C., Supt. & Chief Chemist, Water & Sewage Treatment, City of Dallas, Dallas, Tex.
Bryan, A. C., c/o Post Engineer, Camp Hood, Tex.
Connell, C. H., Major, Sn-C., c/o E. H. O'Shields, 4546 Shoalwood Ave., Austin 21, Tex.
Dickson, D. B., 3001 Milton St., Dallas, Tex.
Dietz, Irving M., San. Engr., c/o Post Engineer, Ellington Field, Tex.
Dixon, R. M., Capt., C. E., Southwestern Division, Engineer's Office, 323 Santa Fe Bldg., Dallas, Tex.
Dodson, Lewis, Capt., Headquarters Eighth Service Command, A. S. F., Repairs & Utilities Branch, Santa Fe Bldg., Rm. 225, Dallas 2, Tex.
Fowler, James D., Consulting Engr., Great Nat'l Life Bldg., Dallas, Tex.
Gaunt, W. C., Pfc., ASTU, 3877-Med. Br. Univ. Texas, Galveston, Tex.
Griffith, L. B., 904 Medical Arts Bldg., Waco, Tex.
Helland, H. R. F., Consulting Engr., 130 W. Rosewood, San Antonio, Tex.
Horner, J. L., Water Works Supt., Henderson, Tex.
Koch & Fowler, Engrs., 701 2 Great National Life Bldg., Dallas, Tex.
Lamar, Jones C., Sewage Plant Supt., Box 582, Big Spring, Tex.
McAfee, H. D., 610 Jerome St., Texarkana, Tex.
Mahlie, W. S., Chemist in Charge of Water & Sewage Purification, Fort Worth, Tex.
Menefee, James H., 1206 Lee St., Jefferson City, Mo.
Moor, W. C., Chemist in Charge of Sewage Plant, Armour & Company, Stock Yards Station, Fort Worth, Tex.
Norman, James E., Box 577, Lubbock, Tex.

Paessler, Alfred H., Supt., Sew. Tr. Plant, City of Austin, Austin, Tex.
Pampa, City of, c/o J. B. Massa, Pampa, Tex.
Pearl, Emanuel H., 1st Lt., C. E., 4549 Bellaire Ave., Dallas 5, Tex.
Phillips, R. W., U. S. Engineers Area Office, Air Support Command Base, P. O. Box 58, Galveston, Tex.
Powell, W. L., Lt. Comdr. (CEC) USNR Public Works Dept., Marine Barracks, Quantico, Va.
Puckhaber, Fred H., District Sales Office, Wallace & Tiernan Co., Inc., 1112 Liberty Bank Building, Dallas, Tex.
Schwob, Carl E., Major, Office of Civilian Defense, Mercantile Bank Bldg., Dallas, Tex.
Seligmann, Irving S., Seguin, Tex.
Standley, J. B., c/o Post Engineer, A. E. F. Camp, Huntsville, Tex.
Street, Haskell R., Chemist on Stream Pollution, State Dept. of Health, c/o City-County Health Dept., El Paso, Tex.
Ussery, A. E., 108 D. Louisiana Ave., Forest Glenn, Pineville, La.
Weiss, R. H., Engr., Texas State Dept. of Health, 1512 South St., Kerrville, Tex.
Welch, W. H., 1620 N. Fannin Ave., Tyler, Tex.
Welsh, James M., San. Engr., Box 297, South Houston, Tex.
Williams, J. E., Post Engineer, Camp Bowie, Tex.

The Canadian Institute on Sewage and Sanitation

Dr. A. E. Berry, *Secretary-Treasurer*, Sanitary Engineering Div., Ontario Dept. of Health, Toronto, Ontario, Canada

Aeri, L. P., 28 Grove Avenue, Toronto 3, Ontario, Canada
Anderson, C. S., Engr., Tisdale Twp., South Porcupine, Ontario, Canada
Armstrong, C. G. R., Cons. Engineer, Bartlet Building, Windsor, Ontario, Canada
Baird, E. M., Scarboro Township Engineer, 11 Avalon Blvd., Toronto 13, Ontario, Canada
Bayard, G. A., 732 Langlois Ave., Windsor, Ontario, Canada
Berry, A. E., Director, Sanitary Eng. Division, Ontario Dept. of Health, 235 Gainsboro Road, Toronto 8, Ontario, Canada
Brakenridge, Charles, City Engr., City Hall, Vancouver, B. C.
Brereton, W. P., 1015 Grosvenor Ave., Winnipeg, Manitoba, Canada
Brickenden, F. M., Dist. Engineer, Dept. of P. & N. Health, P. O. Box 4710, Postal Station "B," Cor. Magnus & Main Sts., Winnipeg, Manitoba, Canada
Browne, F. G., Engr., Teck Township, Kirkland Lake, Ontario, Canada
Brownridge, F. B., Town Clerk, Cornwall, Ontario, Canada
Burn, G. A. H., Asst. Sanitary Engineer, Ontario Dept. of Health, Parliament Bldgs., Toronto 2, Ontario, Canada
Burnett, A. H., Supt. Union Sewerage Comm. of Mimico & New Toronto, 249 Church St., Mimico, Ontario, Canada
Carlson, A. J., Distr. Engr., Dept. of P. & N. Health, 9 James St., St. Catharines, Ontario, Canada
Chisholm, D. M., Sales Mgr., Norton Co. of Can., Ltd., Hamilton, Ontario, Canada
Cleveland, E. A., Chairman, Vancouver & Dists. Joint Sewerage & Drainage Board, Bekins Bldg., Vancouver, B. C., Canada
Collins, W. H., Sewer Eng., City of Hamilton, 16 Senator Avenue, Hamilton, Ontario, Canada
Conant, F. M., Engr., Link Belt, Ltd., 791 Eastern Ave., Toronto, Ontario, Canada
Cook, S. J., Off. in Charge, Res. Plans & Publ., Nat. Res. Council, Ottawa, Ontario, Canada
Coulson, C. L., City Engr., 53 Maple Avenue, Welland, Ontario, Canada
Cousineau, A., Supt. Engr. Div. of Sanitation, Dept. of Health, City Hall Annex, Montreal, P. Q., Canada
Cyr, Rene, Asst. Chief Engr., Ministry of Health, 89 E. Notre Dame St., Montreal, Quebec, Canada
Daly, James A., Managing Editor, Engineering & Contract Record, 347 Adelaide St., West, Toronto, Ontario, Canada
Darling, E. H., Consulting Engineer, 513 Pigott Bldg., Hamilton, Ontario, Canada
Deslauriers, Alfred Joseph, City Hall, 1 18th Avenue, Lachine, Quebec, Canada
Desmarais, R. J., City Engineer, 451 Park St., W. Windsor, Canada
Durrant, W. K. F., Chief Operator, Sewage Disposal Works, P. O. Box 43, Mosse Jaw, Saskatchewan, Canada
Edgecombe, G. H., Distr. Engr., Dept. of Pensions & Nat'l Health, Box 296, St. John, New Brunswick, Canada

Elnor, George E., City Foreman, City Warehouse, North Bay, Ontario, Canada

Falls, O. M., Commissioner of Works, York Twp., 40 Jarvis St., Toronto 1, Ontario, Canada

Ferguson, G. H., Chief Engineer, Dept. of Pensions & National Health, 325 Daly Building Annex, Ottawa, Ontario, Canada

Francis Hankin & Company, Ltd., 2028 Union Ave., Montreal, Canada

Fraser, Charles E., Fraser Brace, Ltd., 107 Craig Street W., Montreal, Quebec, Canada

French, R. Del., Prof. of Highway & Municipal Engineering, McGill University, Montreal, Quebec, Canada

Gardiner, W. E., Town of Cambrose, Alberta, Canada

Garrett, R. W., City Engineer, City Hall, London, Ontario, Canada

Gibbons, E. V., Chief Chemist, Sternson Laboratories, Brantford, Ontario, Canada

Gibeau, H. A., Asst. Chief City Engr., 5618 Phillips Ave., Montreal, Quebec, Canada

Gill, A. F., National Research Council, Ottawa, Ontario, Canada

Goodwin, S. E., Ont. District Manager, Chas. Warnock & Co., Ltd., Harbor Comm. Bldg., Toronto, Ontario, Canada

Hall, W. N., Development Manager, Alkali Div., Canadian Industries, Ltd., P. O. Box 10, Montreal, P. Q., Canada

Hallgren, R. A., Waterworks Supt., Crystal Beach, Ontario, Canada

Harris, R. C., Commissioner of Works, City Hall, Toronto 2, Canada

Howe, J. P., Town Engineer, Pembroke, Ontario, Canada

Hoey, A. C., Nepean Twp., 345 Richmond Rd., Ottawa, Ontario, Canada

Hubel, J. H., Chemical Engineer, Development Department, Canadian Industries, Ltd., P. O. Box 10, Montreal, P. Q., Canada

Jack, David, City Engr., Kingston, Ontario, Canada

Jack, Grant T., Commissioner of Works, Township of East York, 787 Coxwell Avenue, Toronto 6, Ontario, Canada

Jardine, M. E., Town Clerk, Hespeler, Ontario, Canada

Ker, M. F., Engineer, 2057 Drummond Rd., Niagara Falls, Ontario, Canada

Kingston, T. M. S., City Manager-Engineer, Harrison Hall, Chatham, Ontario, Canada

Kinney, J. B., Mgr., Wallace & Tiernan Co., Ltd., 345 Sorauren Avenue, Toronto, Ontario, Canada

Knight, C. H., The Dorr Co., Inc., 80 Richmond St., West, Toronto 1, Ontario, Canada

Lafreniere, Theo. J., Provincial San. Eng., Bureau of Health of Quebec, 89 East, Notre-Dame, Montreal, Quebec, Canada

Laidlaw, C. T., City Engr., Sarnia, Ontario, Canada

Lamb, Charles, Chairman, Bd. of Wks., 159 Lindsay St., S. Lindsay, Ontario, Canada

Lamson, B. F., City Engineer, St. Catherines, Ontario, Canada

Langlois, Zachee, 105 Mountain Hill, Quebec City, P. Q., Canada

Lawson, W. S., Chief Eng., Dept. of Justice, Confederation Bldgs., Ottawa, Ontario, Canada

Lea, W. S., Consulting Engineer, 1226 University St., Montreal, P. Q., Canada

Lemieux, R. A., City Mgr. & Engr., 219A Davis, Arvida, P. Q., Canada

Ley, Charles H., Sales Engr., Dominion Wheel & Foundries, Ltd., 171 Eastern Avenue, Toronto, Canada

Lloyd, G. H., 610 Federal Bldg., Toronto, Ontario, Canada

MacLaren, J. F., Cons. Engr., 1130 Bay St., Toronto 5, Ontario, Canada

MacLean, J. D., Town Engr., Box 633, Timmins, Ontario, Canada

McArthur, Franklin, Township Engineer, Etobicoke Twp., Etobicoke Twp. Hall, Islington, Ontario, Canada

McCannel, D. A. R., City Engineer, City Hall, Regina, Saskatchewan, Canada

McDonald, N. G., Consulting Engineer, 1130 Bay St., Toronto, Ontario, Canada

McFaul, W. L., City Engineer, Hamilton, Ontario, Canada

McKay, R. Donald, Sanitary Engineer, Dept. of Public Health, Halifax, Nova Scotia

McManamna, T. L., Vice Pres. International Water Supply Co., 373 Wortley Road, London, Ontario, Canada

McNiece, L. G., Town Engineer, Orillia, Ontario, Canada

McWilliams, D. B., Mgr. Dresser Mfg. Co., Ltd., 60 Front St., W. Toronto, Ontario, Canada

Marsh, H. M., Vice-President, W. J. Westaway Co., Ltd., Hamilton, Ontario, Canada

Menzies, D. B., Prov. Sanitary Engineer, 218 Administration Bldg., Edmonton, Alberta, Canada

Menzies, J. Ross, Distr. Engr., Dept. of National Health, Rm. 201, 379 Common St., Montreal, P. Q., Canada

Merlo, Louis A., Jr., c/o Sterling Construction Co., Windsor, Ontario, Canada

Micklethwaite, W. E., United Steel Corp'n, 12 Kings-Lynn Rd., Toronto 9, Ontario, Canada

Mills, S. W., 105 Glengrove Avenue, Toronto, Ontario, Canada

Montreal, City of, Public Works Dept., Hydro-Electric Div., City Hall, Montreal, Quebec, Canada

Morin, A., Town Engr., 407 Boulevard Melancon, St. Jerome, P. Q., Canada

Morgan, Geo., General Mgr., Victaulic Co. of Canada, 200 Bay St., Toronto 1, Ontario, Canada

Morrissette, Romeo, 15 rue Longval, Cap de la Madeleine, P. Q., Canada

Mott, C. A., City Engineer, Belleville, Ontario, Canada

Mulholland, R. A., State Dept. of Health, Austin, Tex.

Munroe, E. H., Supt. Disposal Plant, York Twp., 18 Normanna Ave., Toronto 10, Ontario, Canada

Nicklin, H. S., City Engineer, City Hall, Guelph, Ontario, Canada

Oke, Ernest E. W., Manager and Engineer, Public Utilities Commission, Ontario, Canada, Cochrane

Orr, Wm. S., City Clerk & Engr., City Hall, Niagara Falls, Ontario, Canada

Parsons, R. H., City Engineer, 133 Simcoe St., Peterborough, Ontario, Canada

Phelps, Geo., Engineer of Sewers, Department of Works, City Hall, Toronto, Ontario

Plamondon, Sarto, 5792 DesFrables St., Montreal, P. Q., Canada

Pringle, H. L., Manager, Public Utilities Commission, Whitby, Ontario, Canada

Rawson, E. Otto, Town Engineer, Barrie, Ontario, Canada

Redfern, W. B., Consulting Engr., Excelsior Life Bldg., 36 Toronto St., Toronto 1, Ontario, Canada

Reid, G. Graham, Consulting Engineer, 7 Edmund Avenue, Toronto 5, Ontario, Canada

Richards, G. H., City Engineer, Brantford, Ontario, Canada

Riehl, W. H., City Engineer, City Hall, Stratford, Ontario, Canada

Robertson, L. T., Sewage Disposal Engr., 565 William St., London, Ontario, Canada

Robinson, B., District Mgr., Hardinge Co., Inc., Room 305, 200 Bay Street, Toronto, Ontario, Canada

Robinson, G. G., President, Concrete Pipe, Ltd., 402 Harbor Comm. Bldg., Toronto, Ontario, Canada

Robinson, I. F., Contractor for Removal of Sludge, 28 Langarth St., London, Ontario, Canada

Rogers, M. W., Mgr. Public Utilities Commission, Carleton Place, Ontario, Canada

Rumble, G. B., Senior Asst. Engineer, Dept. of Works & Bldgs., R. C. A. F., Lisgar Bldg., Ottawa, Ontario, Canada

Russell, J. P., Asst. Editor, "Canadian Engineer," 344 Church St., Toronto, Ontario, Canada

Scheak, H. M., 75 Rosedale Heights, Toronto, Ontario, Canada

Scott, W. M., Chairman of Comm. Greater Winnipeg Sanitary Dist., 185 King St., Winnipeg, Canada

Shook, H. R., Asst. Sales Manager, National Sewer Pipe Co., 44 Victoria St., Toronto, Ontario, Canada

Shupe, S., City Engr., City Hall, Kitchener, Ontario, Canada

Spellman, W. A., Engr., Teck Twp., Stayner, Ontario, Canada

Storrie, Wm., Consulting Engineer, 1130 Bay St., Toronto, Ontario, Canada

Sturegon, R. G., Town Engr., Port Elgin, Ontario, Canada

Sutcliffe, H. W., Sutcliffe Co., Ltd., New Liskeard, Ontario, Canada

Ternent, A., Commissioner of Works, 83 De Forest Rd., Swansea, Ontario, Canada

Thomas, A. H. R., Supt. Public Utilities Comm., 874 Lake Shore Road, New Toronto, Ontario, Canada

Traill, G. R., Brown Engineering Co., 15 Alcorn Ave., Toronto, Ontario, Canada

Underwood, J. E., Consulting Engr., 502 Grain Bldg., Saskatoon, Sask, Canada

Waddell, W. H., City Engr., Owen Sound, Ontario, Canada

Walters, F. Y., John Inglis Co., Ltd., 14 Strachan Ave., Toronto, Ontario, Canada

Watmough, W. W., Depew Disposal Plt., 61 Erie Ave., Hamilton, Ontario, Canada

Wilkes, F. Dean, Mgr., Control & Metering, Ltd., 454 King St. West, Toronto, Ontario, Canada

Williamson, R. C., Technical Service, Canadian Industries, Ltd., House, P. Q. Box 10, Montreal, Quebec, Canada

Wilson, Wm. B., 31 S. F. T. S., Annandale Apts., Sydenham St., Kingston, Ontario, Canada

Withington, C., Sales Mgr., Canada Vitrified Products, Ltd., St. Thomas, Ontario, Canada

Wood, J. R., Assistant City Engineer, City Hall, Calgary, Alberta, Canada

Woodhouse, H. M., City Engineer, Fort William, Ontario, Canada

Yaeck, Arthur W., 104 Margaret St., Apt. 4, Kitchener, Ontario, Canada

The Institute of Sewage Purification—England

Mr. J. H. Garner, *Secretary*, 28 Aberford Road, Wakefield, Yorks., England

Aldred, H., 40 Ash Tree Rd., Burnley, Lancs., England
Allen, F. W., Hacken Sewage Works, Great Lever, Bolton, Lancs., England
Artist, L. J., 2 Warren Ave., Portobello, Wakefield, Yorks., England
Balfour, D. & Sons, 45 So. St., Durham, England
Barraclough, D. H., Sewage Works, Denton, Lancs., England
Bell, H. D., Sewage Works, Burton Grange, Lund Wood, Barnsley, England
Beswick, G., Sewage Works, Slacks Valley, Middleton Junction, Lancs., England
Bolton, J. F., Ames Crosta Mills & Co., Ltd., Moss Iron Works, Heywood, Lancs., England
Box, G. E. P., 52 Cobham St., Gravesend, Kent, England
Calvert, A., 43 Station Road, Darnall, Sheffield, Yorks., England
Campbell, J. L., Willow Holme Sewage Works, Carlisle, England
Christian, J. A., 84 Preston Old Rd., Freckleton, Preston, Lancs., England
Clements, G. S., 51 The Drive, Bexley, Kent, England
Covill, R. W., Sewage Disposal Works, Lower Marsh Lane, Surbiton, Surrey, England
Clifford, W., "Mayeroft" Stourbridge Road, Wombourn, Wolverhampton, England
Crundall, S. F. W., c/o Peter Spence & Sons, Ltd., National Bldgs., St. Mary's Parsonage, Manchester, England
Drummond, A. H., Sewage Works, Hook Rd., Epsom, Surrey, England
Edmondson, J. H., Sewage Works, Wincobank, Sheffield, England
Elsdon, Dr. G. D., Lancashire Rivers Road, 50 Mosley St., Manchester, England
Egans, S. C., Sew. Dis. & Refuse Destructor Wks., Windmill Rd., Luton, Bed., England
Finch, J., Sewage Works, Aldwarke, Parkgate, Rotherham, England
Flowers, E., Kettering Sewage Works, Wellingborough, Northants., England
Fowler, G. J., c/o Central Hotel, Bangalore, So. India
Freeborn, W. F., 34 Cardinal's Walk, Hampton-on-Thames, Middlesex, England
Garner, J. H., Brynfield, 28 Aberford Rd., Wakefield, Yorks., England
Gibbs, R. C., c/o Dorr-Oliver Co., Ltd., Abford House, Wilton Road (Victoria), London, S.W. 1, England
Gillard, J. E., Sewage Works, Leamington, Warwickshire, England
Goldthorpe, H. H., Sewage Works, Deighton, Huddersfield, England
Hambleton, F. T., Outfall Works, Prestbury, Nr. Macclesfield, Cheshire, England
Hamlin, C. H., Sewage Works, Windmill Road, Luton, Beds., England
Harris, L., Riverside Works, Rainham, Essex, England
Hicks, R., Hamilton Sewage Works, Bothwell Bridge, Bothwell, Lanarkshire, Scotland
Hirst, J., 65 Teal Rd., Eastbourne, Darlington, County Durham, England
Hodgson, E., Irrigation Farm, Harrington Rd., S. Norwood, London, S. E. 25, England
Hodgson, H. J. N., 22 Brae Rd., St. Georges, Adelaide, So. Australia
Holroyd, A., Chemist, Dagenham Urban Distr. Council, Riverside Sewage Wks., Rainham, Essex, England
Howarth, J. P., Sewage Disposal Works, Longford Road, Cannock, Staffs., England
Hoyle, W. H., "Dilkusha" 17, Victoria Rd., Topsham nr. Exeter, Devon., England
Hurley, J., Sewage Works, Tettenhall, Wolverhampton, England
Hunter, A., Sewage Dept., City Chambers, 50 John St., Glasgow, Scotland
Jennings, A., Sewage Works, Sefton Lane, Maghull, Nr. Liverpool, England
Jones, C. B. O., City of Coventry Chemical Lab., Whitley, Coventry, England
Kershaw, Arnold, Chippenham Lane, Slough, Bucks., England
Klein, L., Davyhulme Sewage Works, Urmston, Manchester, England
Lamb, P., Esq., Sewage Disposal Works, Bromwich Road, Worcester, England
Lea, J. E., The Lea Recorder Co., Ltd., Cornbrook Park Road, Manchester 15, England
Leigh, H. G., 28 West Leigh Rd., Blackburn, Lancs., England
Lockett, W. T., West Middlesex Main Drainage Wks., Oak Lane, Isleworth, Middlesex, England
Longbottom, V., Sewage Works, Ashwood Dale, Buxton, Derbyshire, England
Lovett, M., W. Riding Rivers Board, 71 Northgate, Wakefield, Yorks., England
Lumb, C., Sewage Dept., Salterhebble, Halifax, England
McNicholas, J., Brockhurst House, Bescot Crescent, Walsall, Staffs., England

Makepeace, W. H., Sewer Engineer's Office, Leek Road, Stoke-on-Trent, England
Miller, A. S., Sewage Works, Manor Farm, Reading, Berks., England
Modak, N. V., City Engr., Bombay Municipality, Bombay, India
Monk, H. E., County Laboratory, County Buildings, Worcester, England
Moore, R. L., Brighouse Sew. Wks., Cooper Bridge, Mirfield, Yorks., England
Mountfort, L. F., "Claverings," Montagu Road, Edmonton, London, N. 9, England
Murray, K. A., P. O. Box 4497, Johannesburg, South Africa
Nixon, J., Sewage Works, Deighton, Huddersfield, Yorks., England
Pledger, A., "Grant," Wolseley Rd., Camels Head, Plymouth, Devon., England
Poole, S. B., 11 Clive Avenue, Dales Lane, Whitefield, Manchester, England
Reynoldson, T. B., Sewage Works, Deighton, Huddersfield, Yorks., England
Scott, W., Sewage Works, Bury, Lancs., England
Sellers, A. E., The Homestead, Newsome Road South, Huddersfield, Yorks., England
Sidle, R. S., Ministry of Works, Sanitary Engr., Div., Cleland House, Park St., London, S.W. 1, England
Smith, G. C., Sewage Works, Campbell Road, Swinton, Manchester, England
Snook, W. F. A., Bretons Farm, Rainham Rd., Rainham, Essex, England
Stanbridge, H. H., Sewage Works, Hook Road, Epsom, Surrey, England
Staknes, E. H., Sewage Works, Mitchell Laithes, Dewsbury, England
Stone, A. R., Stoke Farm, Stoke Bardolph, Nottingham, England
Sutton, R. W., County Analyst, County Offices, St. Mary's Gate, Derby, England
Taylor, H., Stalybridge and Dukinfield, Joint Sewage Works, Bradley Hirst, Dukinfield, Ches., England
Taylor, J., "Langwood," Foxdenton Lane, Chadderton, Oldham, England
Thatcher, H. D., Lismore, 17 Foley Rd., Streetly, Birmingham, England
Thomas, A., "The Lodge," Sewage Disposal Wks., Appledram Lane, Chichester, Sussex, England
Thompson, J. T., c/o Sewerage Engr's Dept., Civic Hall, Leeds, 1, Yorks., England
Townend, C. B., Mogden Wks., Isleworth, Middlesex, England
Ward, A. R., Sewage Works, Heathside Farm, Cheadle Heath, Stockport, England
Watson, W., Sewage Works, Dockfield, Shipley, Yorks., England
Weir, E. McG., 1 Underly St., Burnley, Lancs., England
Whitehead, H. C., Birmingham, Tame & Rea Drainage Board, Rookery Park, Erdington, Birmingham, England
Windridge, M. E. D., 79 Kewbridge Crescent, Wolverhampston, Staffords., England
Wishart, J. M., Rivers Dept., Town Hall, Manchester, England
Wontner-Smith, H., Sewage Works, Esholt Hall, Mr. Shipley, Yorks., England

The Institution of Sanitary Engineers—England

Mrs. E. M. Kerry, *Acting Secretary*, 118 Victoria St., Westminster, S.W. 1, London, England

Alford, John S., M. Inst. C. E., F.I.S.E., 13 Victoria St., Westminster, S.W. 1, London, England
Armstrong, J. D., 69 Brockwell Court, Effra Road, London, S.W. 2, England
Ashby, E. Hamilton, E. S. I., M. R. I. P. H. M. I. S. E., 1 Mitre Court Bldg., Inner Temple, London, E.C. 4, England
Aslamidis, A., 25 Woodland Terrace, Charlton, S.E. 7, England
Balsom, E. V., 96 Victoria St., Westminster, S.W. 1, London, England
Barclay, W. G., M. R. San. I. M. I. S. E., "Carlisle," 71 Wensleydale Rd., Hampton, Middlesex, England
Blizard, W. E., 25 Victoria St., London, S.W. 1, England
Brassey-Edwards, S., c/o Messrs. Ames Crosta Mills & Co., Ltd., Abbey House, Victoria St., London, S.W. 1, England
Brown, W. Fillingham, B.Sc., A. M. I. C. E., M. I. S. E., Claxton, Copthorne Rd., Rickmansworth, Herts, England
Clark, H. W., 1 North Terrace, North Road, Retford, Nottingham, England
Collard, A. E., 24 St. Mary's Road, Ealing, London, W. 5, England
Collins, A. J., 44 Manoel Rd., Fulwell Park, Twickenham, Middlesex, England
Coombs, E. P., 96 Victoria St., Westminster, S.W. 1, London, England
Cotterell, G. T., A. P. I. Cotterell & Son, 54, Victoria St., Westminster, London, S.W. 1, England

Easdale, W. C., 32 Grove Gardens, Teddington, Middlesex, England

Fly, E. H., B.Sc., Assoc. M. Inst., C.E., A. M. I. S. E., 14 Spenser Road, Herne Hill, London, S.E. 24, England

Faulkner, T. G., Esq., 41 Wantage Road, Didcot, Berkshire, England

Gregory, L. L., Corporation Sewage Works, Salisbury, Wiltshire, England

Haworth, W. D., Assoc., M. I. C. E., M. S. E. A. M. I. S. E., 23 Collomore Ave., London, S.W. 18, England

Hesford, L., M. R. San. I., F. I. S. E., "Dorlan," Scalford Road, Melton Mowbray, Leicestershire, England

Hodges, H. E. W., M. R. San. I., A. M. I. S. E., 67 Longlands Park Crescent, Sidcup, Kent, England

Landshaw, C. L., 26 Lansdowne Court, Brighton Rd., Purley, Surrey, England

Moore, F. Owen, 484 Upper Richmond Rd., Barnes, S.W. 15, England

Murray, A. E. Scott, Esq., Barnfield, Blyth Rd., Bromley, Kent, England

Porteous, W. K., 6 Netherton Road, St. Margarets, Twickenham, Middlesex, England

Sciver, A., 28 Victoria St., London, S.W. 1, England

Streeter, S. H., Capt., "Santasu," Warren Road, Guilford, Surrey, England

Summers, M. W., Assoc., M. Inst. C. E. A. M. Inst. W. E. F. I. S. E., "Arran," Broom Way, Oatlands Park, Weybridge, England

Taylor, Godfrey M. C., M. C., M. Inst. C. E., F. I. S. E., Artillery House, Artillery Row, Westminster, S.W. 1, England

Watson, David M., "Beechlawn," Gerrards Cross, Bucks., England

Westwood, H. W. D., Sc. (Eng.) F. R. S. A., Assoc. M. Inst. C. E., 176 Station Road, Wylde Green, Birmingham, England

White, R. H., 46 Heliers Ave., Hounslow, Middlesex, England

Williams, G. Bransby, Killay House, Kewhurst Ave., Cooden, Bexhill-on-Sea, England

FEDERATION OF SEWAGE WORKS ASSOCIATIONS
ALPHABETICAL LIST OF MEMBERS
DECEMBER 31, 1943

Abbott, W. D. New York
Abeles, Joseph C. New Jersey
Abernethy, P. L. North Carolina
Abplanalp, C. C. Central States
Abrams, M. F. New York (Dual New England)
Ackerman, E. V. Ohio
Acri, L. P. Canada
Adams, Chas. L. Central States
Adams, Frank. Central States
Adams, J. J. California
Adams, J. K. New Jersey
Adams, Milton P. Michigan
Adkins, W. W. North Carolina
Adolphe, Robt. C. California
Aeryns, Albert N. New York
Agar, Chas. C. New York
Agnano, Paul. Federal
Agostinelli, Anthony J. New York
Ahrens, G. C. Iowa
Albers, J. C. California
Albrecht, Robt. H. New York
Aldred, H. England (I. S. P.)
Aldrich, Ellwood H. New York
Aldrich, Lloyd. California
Aldridge, Frederick F. Federal
Aldridge, M. G. Georgia
Alexander, Allen Y., Jr. North Carolina
Alexander, J. D. Pennsylvania
Alexander, Louis J. California
Alford, John S. England (I. S. E.)
Algonquin, Village of. (Corporate) Central States
Alikonis, J. J. Central States
Allen, Edw. H. Florida
Allen, F. W. England (I. S. P.)
Allen, Herbert B. New England
Allen, James H. Pennsylvania
Allen, Wm. A. California
Allin, Claud R. California
Allison, S. L. Texas
Aluminum Co. of America. Associate
Amend, J. E. Rocky Mt.
American Brass Co. Associate
American Cast Iron Pipe Co. Associate
American City Magazine. Associate
American Enka Corp. North Carolina
American Well Works. Associate
Ames, City of. Iowa
Anaya, Marvin. California
Andersen, C. Geo. New York
Anderson, C. S. Canada
Anderson, Fred A. Pacific Northwest
Anderson, Geo. H. Central States
Anderson, Herbert A. Central States
Anderson, Lewis D. Federal
Anderson, Norval E. Central States
Anderson, R. A. Michigan
Andres, Wm. H. New York
Andrews, John. Federal
Angas, Robert M. Florida
Angell, J. M., Jr. New York
Antl, John C. Central States
Arbogast, Joseph. Central States
Armco Drainage Products Assn. Associate
Armeling, Geo. Maryland-Delaware
Armstrong, C. G. R. Canada
Armstrong, Frank W. New York
Armstrong, J. D. England (I. S. E.)
Arnold, Earl H. North Dakota
Arnold, Everett W. Michigan
Arnold, G. E. California (Dual Federal)
Arnold, Geo. Central States
Artese, Philip. New York
Artist, L. J. England (I. S. P.)
Ashby, E. Hamilton. England (I. S. E.)
Ashdown, W. L. Central States
Ashe, John R. New York
Aslamidis, A. England (I. S. E.)
Automatic Control Co. Associate
Avis, R. L. California

Babbitt, H. E. Central States
Babcock, Irving. New York
Bachmann, Frank. New York
Backherms, A. B. Ohio
Backmeyer, David. Central States
Bacon, Henry G. New York
Bacon, Vinton. California
Badger, Irvin S. New York
Baer, Arlie. Central States
Baetz, C. O. Central States
Baffa, John J., New York
Bailey, J. Kenneth. North Carolina
Bailey, J. W. Ohio
Bailey, S. C. Pennsylvania
Baillie, E. P. Central States
Bainbridge, David W. Pennsylvania
Baird, Chas. O., Jr. New England
Baird, E. M. Canada
Baity, H. G. North Carolina
Baker, C. M. Central States

Baker, Hugh L. Georgia
Baker, Stanley L. Pacific Northwest
Baldwin, C. W. New England
Balfour, D. & Sons. England (I. S. P.
Balmer, Robt. R., Jr. New England
Balsom, E. V. England (I. S. E.)
Bamford, J. H. Pacific Northwest
Bandy, W. A. Texas
Banks, Harvey O. California
Banta, A. Perry. California
Barbour, Frank A. New England
Barclay, W. G. England (I. S. E.)
Bargman, R. D. California
Barker, J. Conrad, Jr. Pennsylvania
Barker, Stanley T. New York
Barklage, O. F. Iowa
Barnard, Archer F. California
Barnes, Geo. E. Ohio
Barnes, L. B. Ohio
Barnett, G. R. Central States
Barney, John J. Pennsylvania
Barney, J. W. Pacific Northwest
Barnhill, Kenneth G. New York
Barraclough, D. H. England (I. S. P.)
Barrick, M. J. Pennsylvania
Barron, James L. New York
Barstow, E. D. Ohio
Barton, Ben H. Ohio
Bartow, Edw. Iowa
Bartow, Leslie W. Pacific Northwest
Bartz, Erwin A. Central States
Bass, Jerry Connor. Central States
Bates, R. D. New York
Batty, Frederic A. (Alt.) Calif.
Bauer, Henry W. New England
Baum, H. J. Pennsylvania
Bavone, A. L. North Dakota
Baxter, R. R. Central States
Bayard, G. A. Canada
Bayliss, John R. Central States
Beamesderfer, James A. Pennsylvania
Bean, Carl S., Capt. Georgia
Beard, F. W. Texas
Beatty, E. J. Central States
Beaumont, H. M. Pennsylvania
Beaudoin, Robt. E. Central States
Beck, A. J. Central States
Becker, Fred G. California
Becker, Philip G., Jr. Texas
Beckett, Richard C. Pennsylvania
Bedell, A. S. (Honorary) New York
Behnke, Geo. C. Ohio
Bejcek, Otto. Arizona
Bekaskas, Anthony J. Central States
Bell, H. D. England (I. S. P.)
Belt, Elmer B. California
Bender, Dwight O. Central States
Benjamin, Leland F. New York
Bennett, Christopher F. New York
Bennett, S. G. California
Berg, E. J. M. Texas
Berk, Morton. North Carolina
Berlin, A. Martin. California
Bernauer, Geo. F. Central States
Bernhardt, Carl J. New York
Berry, A. E. Canada
Berry, C. Radford. Federal
Berry, Geo. A. Central States
Bers, G. D. Central States
Berton, Chas. J. New York
Besozzi, Leo. Central States
Besschevre, Edmund B. New York (Dual California)
Bessert, J. Ervin. Central States
Best, Robt. B. New York
Beswick, G. England (I. S. P.)
Beukema, Robt. (Alt.) Mich.
Bevacqua, Joseph. New York
Bevan, John G. New York
Bidlack, C. E. Ohio
Bidwell, Milton H. New York
Biele, F. J. New York
Bielmaier, Joe. South Dakota
Billings, L. C. Texas
Binger, Walter D. New York
Bingley, W. McLean. Maryland-Delaware
Bird, Neal. Central States
Birdsall, L. I. Central States
Birkeness, O. T. Central States
Birkley, Alvin G. Pennsylvania
Biship, H. N. California
Bjelajac, Vaso. Central States
Black, Hayse H. Central States
Black & Veatch (Corporate) Central States
Blalock, Wm. W., Jr. North Carolina
Blew, Michael J. Federal
Blinder, Jacob W. New York
Blizard, W. E. England (I. S. E.)
Blood, Lloyd. New York
Bloodgood, Donald E. Central States
Boardman, John. Pennsylvania
Boardman, Wm. Hunter, Jr. Pennsylvania
Boeke, Harley C. Central States
Bogardus, Theodore S. Pennsylvania
Bogema, Marvin. Central States
Bogert, C. L. New York
Bogren, Geo. G. New England
Bolenius, Robt. M. Pennsylvania
Boley, Arthur L. Central States
Bolton, J. F. England (I. S. P.)
Bond, Eugene L. New England
Bond, Philip E. New England
Bond, Richard C. Iowa
Booker, Warren H. North Carolina
Boone, Geo H. Pennsylvania
Borchardt, Jack A. Central States

Boriss, M. E. New York
Borland, Victor J. California
Borquist, E. S. Arizona
Bosch, Herbert M. Central States
Botkin, Gilbert E., Jr. Central States
Bott, Roderick F. Central States
Bow, Wilson F. Pacific Northwest
Bowen, M. R. California
Bower, Stanley. Michigan
Bowers, T. C. Michigan
Bowler, Edmond Wesley. New England
Bowlus, Fred D. California
Bowman, C. R. South Dakota
Boyce, Earnest. Kansas (Dual Federal)
Boyce, Ralph E. New York
Boyd, Geo. E. New York
Boyd, J. W. Michigan
Boyle, J. R. Lester. California
Box, G. E. P. England (I. S. P.)
Bradlee, Warren R. New England
Bradner, Basil E. New York
Bradney, Leland. Central States
Bragg, J. M. Georgia
Bragg, Robt. E. Central States
Bragstad, R. E. Central States
Braidech, Mathew M. Ohio
Brakenridge, Charles. Canada
Brallier, Paul S. New York
Brassey-Edwards, S. England (I. S. E.)
Brennan, Ralph F. Florida
Brensley, A. S. Central States
Brereton, W. P. Canada
Brethour, Herman. Kansas
Bretz, C. E. Oklahoma
Brewer, E. E. Pacific Northwest
Brickenden, F. M. Canada
Bridges, F. B. Missouri
Briggs, Raymond J. Pacific Northwest
Brigham, John C. New York
Brigham, John C., Jr. New York
Briley, Harold D. Florida
Britt, C. E. Ohio
Britton, Benj. A., Jr. New England
Brody, James. Central States
Brook, Harry L. Central States
Brooks, John H., Jr. New England
Brower, J. Singleton. New York
Brower, James. Central States
Brown, Cleo. Missouri
Brown, Edward S., Jr. New England
Brown, Glenn V. Pennsylvania
Brown, James M., Jr. New York
Brown, Kenneth W. California
Brown, Michael. Pennsylvania
Brown, R. F. California
Brown, W. Fillingham. England (I. S. E.)
Brown, Walter H., Jr. New England
Browne, F. G. Canada
Browne, Floyd G. Ohio
Browning, Claud F. Federal
Brownridge, F. B. Canada
Brownson, Bruce. Rocky Mountain
Bruden, C. O. Central States
Brule, Abundius A. New England
Brumbaugh, W. V. New York (Dual Pennsylvania)
Brunner, Paul L. Central States
Brunstein, Maurice. New Jersey
Bruss, O. E. Central States
Bryan, A. C. Texas
Bryand, W. G. Georgia
Bryant, C. T. Ohio
Buchecker, A. I. Pacific Northwest
Buck, Geo. H. New York
Buck, Robinson D. New England
Buck, Ross J. Central States
Buckingham, C. E. Michigan
Buckley, Thomas. Pennsylvania
Buckman, Millard E. California
Buell, Walter E. Iowa
Bugbee, Julius W. New England
Bugbee, Raymond C. New England
Builders-Providence, Inc. Associate Att'n: C. G. Richardson (Dual New England)
Bunker, F. L. North Carolina
Burack, W. D. New Jersey
Burden, Harry P. New England
Burden, Robert P. New England
Burdoin, Allen J. New England
Burger, A. A. Ohio
Burger, Arnold W. Central States
Burgeson, J. H. Central States
Burgess, Harold. New York
Burley, Fred H. Michigan
Burn, G. A. H. Canada
Burnson, Blair I. California
Burnett, A. H. Canada
Burr, R. S. New England
Burrell, Robert. New England
Burrin, Thomas J. Central States
Burt, Gordon L. Central States
Bush, Archie E. New York
Bush, A. F. California
Bush, Bernard S. Pennsylvania
Bushee, Ralph J. Central States
Butrico, Frank. New York
Butterfield, C. T. Federal
Byxbee, J. F. California

Cadwell, Ivan W. New York
Cahill, Wm. J., Jr. New York
Caird, James M. New York
Calder, Charles L. Central States
Calderara, O. J. Federal
Caldwell, David H. California

Caldwell, H. L. Central States
Callen, Loy A. Central States
Callon, Harry A. Central States
Calvert, A. England (I. S. P.)
Calvert, C. K. Central States
Cambridge Instrument Co. Associate
Cameron, A. B. Michigan
Cameron, Geo. New Jersey
Camp, Cecil S. North Carolina
Camp, Thomas R. New England
Campbell, A. S. South Dakota
Campbell, John. Pennsylvania
Campbell, J. L. England (I. S. P.)
Campbell, M. S. Pacific Northwest
Capano, Sam J. New Jersey
Capen, Charles H., Jr. New Jersey
Capone, Domenic. Federal
Capraro, Paul E. Central States
Capwell, Walter. New England
Cardillo, Wm. V. California
Cardwell, Edw. C. Central States
Carey, Wm. N. Central States
Carl, Charles E. Missouri
Carlson, A. J. Canada
Carlson, H. R. Federal
Carmichael, David W. New York
Carnahan, Chas. T. Federal
Carolina Aluminum Co. North Carolina
Carothers, Chas. H. Florida
Carpenter, Carl B. Central States
Carpenter, Geo. D. New York
Carpenter, Harry C. New York
Carpenter, Howard F. New England
Carpenter, J. D. Pennsylvania
Carpenter, Wm. T. New York
Carroll, Geo. B. New York
Carson, Caryl C. New England
Carson, R. G. Central States
Carter, Alton B. California
Carter, Earl. Central States
Carter, Ralph B. Associate
Att'n: J. W. Van Atta New York (Dual—Pennsylvania and New England)
Cary, Edmund S. California
Cary, F. Arthur. New York
Cary, Glen, Sr. Rocky Mt.
Cary, Wm. H. Michigan
Cary, Willis E. New England
Casad, C. C. Pacific Northwest
Casey, Albert E. New England
Casey, John J. California
Castagna, Samuel C. Federal
Castello, W. O. California
Caster, Arthur. Central States
Caulwell, Wilson S. Pennsylvania
Cederberg, C. R. Rocky Mt.
Cenicola, Samuel. New Jersey
Ceriat, Eugene. California
Cerny, Paul J. New York (Dual—New England)
Chain Belt Company. Associate
Chamberlain, L. H. New York
Chamberlain, Wm. T. New York
Chamberlain, Noel S. New Jersey
Chambers, Grover. Pacific Northwest
Chamier, Albert. Michigan
Chandler, John B. Georgia
Chanlett, Emil T. California
Chapman, Howard W. Federal
Chapman Valve Manufacturing Co. Associate
Charlton, David B. Pacific Northwest
Chase, E. Sherman. New England (Dual—Pennsylvania and New York)
Chasick, Abraham H. New York
Cheadle, Wilford G. Central States
Chicago Pump Company. Associate
Chisholm, Colin B. New York
Chisholm, D. M. Canada
Chisholm, Henry. New England
Christensen, Gordon R. Central States
Christian, J. A. England (I. S. P.)
Church, Dean F. Central States
Chutter, W. H. California
Cipriano, Anthony G. New York
City Water Dept. (Statesville, N. Car.). North Carolina
Clare, H. C. Pacific Northwest
Clark, Alfred. Kansas
Clark, Arthur T. Central States (New York—Comp.)
Clark, Boyd H. New York
Clark, H. W. England (I. S. E.)
Clark, J. C. California
Clark, L. K. North Dakota
Clark, M. S. Michigan
Clark, Robt. N. New York
Clarke, Samuel M. Central States
Clarke, V. B. New England
Clay Products Association. Associate
Clear Lake, City of. Iowa
Cleary, Edw. J. New Jersey
Cleland, R. R. Pennsylvania
Clem, Curtis B. Central States
Clements, G. S. England (I. S. P.)
Cleveland, E. A. Canada
Clifford, Gilbert W. Florida
Clifford, W. England (I. S. P.)
Clore, L. B. Central States
Clouser, L. H. Pennsylvania
Cloyes, W. J. Pacific Northwest
Coates, John J. New York
Cobb, Edwin B. New England
Coberly, Carroll H. Rocky Mt.
Coburn, S. E. New England
Cochrane, John C. New York
Cochrane, W. F. South Dakota

Cochrum, G. W. Kansas
Coffey, Joseph H. Federal
Cohn, Morris M. New York (Dual—New England)
Colahan, J. G. South Dakota
Colbert, David. New York
Cole, Chas. W. Central States
Cole, E. Shaw. New York
Cole, Hawley M., Jr. California
Colitz, Michael J. Pennsylvania
Collard, A. E. England (I. S. E.)
Collier, James. Ohio
Collins, A. J. England (I. S. E.)
Collins, A. Preston. California
Collins, W. H. Canada
Collison, Okla C. Missouri
Collyer, Joseph C. New York
Colquhoun, Colin. New York
Coltart, Rodney F. New England (Dual—Pennsylvania)
Compton, C. R. California
Conant, F. M. Canada
Condrey, Lawrence M. Central States
Connell, C. H. Texas
Connell, Maurice H. Florida
Consoer, Arthur W. Central States
Cook, John O. Arizona
Cook, Lawrence H. California
Cook, Max E. California
Cook, Rodney E. New York
Cook, S. J. Canada
Cooley, E. C. California
Coombs, E. P. England (I. S. E.)
Copeland, Wm. R. New England (Dual New York)
Copley, Chas. H. New England
Corbett, Walter E. New England
Corddry, W. H. Pennsylvania
Cordell, Miss Mona. New York
Corey, R. H. Pacific Northwest
Cornelius, Harold B. New York
Cornell, R. M. Central States
Cornilson, C. K. Central States
Corrington, Kingsley. Central States
Corson, B. I. New Jersey
Corson, H. C. Michigan
Cortelyou, H. P. California
Costello, John J. New York
Cotta, Maurice L. Pacific Northwest
Cotterell, G. T. England (I. S. E.)
Cottrell, H. S. New York
Couch, L. I. Central States
Coulson, C. L. Canada
Cousineau, A. Canada
Covert, Henry Kew. Central States
Covill, R. W. England (I. S. P.)
Cowles, M. W. New Jersey (Dual—New York)
Cox, C. R. New York
Coy, Arthur H. (deceased) New England
Coy, Burgis. Rocky Mt.
Craemer, George H. New England
Craig, Clifford. Central States
Craig, J. D. Georgia
Craig, Robt. H. Pennsylvania
Cramerton Mills, Inc. North Carolina
Cranch, Eugene T. New York
Crane Company. Associate
Crane, H. R. California
Crask, Rex. Central States
Cratin, J. M. Ohio
Crawford, H. V. New York
Crawford, L. C. Iowa
Crecars, T. H. (Alt.) California
Crockett, Vernon P. Federal
Crohurst, Harry R. Federal
Crooks, Howard. Michigan
Cropsey, W. H. Central States
Crow, Harry B. Pacific Northwest
Crundall, S. F. W. England (I. S. P.)
Culley, Walter M. New York
Cullison, Eugene F. New York
Cunningham, H. L. Pennsylvania
Cunningham, John W. Pacific Northwest
Cunningham, M. B. Oklahoma
Currie, Frank S. California
Curtiss Wright Corporation (Corporate) Missouri
Cushing, Robert. Arizona
Cushman, S. P. Central States
Cyr, Rene. Canada
Czerepinski, Henry Peter. Central States

Dagger, G. E. Rocky Mountain
D'Alec, A. R. New York
Daley, Stanley J. Central States
Daly, James A. Canada
Damon, Nelson A. New England
Damon, Wayne F. New England
Daniels, F. E. Pennsylvania
Daniels, P. N. New Jersey
Darby, George M. New England
Darby, W. A. Pennsylvania
Darcey, H. J. Oklahoma
Darling, E. H. Canada
Dashiell, Walter N. Federal
Davey, H. W. (Alt.) California
Davids, E. M. California
Davidson, J. F. California
Davidson, Philip. Central States
Davis, Arthur E. New York
Davis, Charles A. Rocky Mt.
Davis, Clarence A. New York
Davis, D. A. Central States
Davis, F. R., Jr. Central States
Davis, G., Jr. Pacific Northwest
Davis, Howard A. Central States

Davis, H. F. North Carolina
Davis, P. D. North Carolina
Davis, T. J. Georgia
Dawson, Arthur. New York
Dawson, F. M. Iowa
Dawson, Norman. Central States
Dawson, Thomas T. Pennsylvania
Day, L. A. Central States
Dayton, Alfred E. (Alt.) New York
DeBerard, W. W. Central States
Debrun, John W., Jr. Central States
Decker, C. D. Ohio
Decker, Edward P. New Jersey
Decker, Herbert M. Federal
Decker, Walter G. Central States
Deckert, Christ. Central States
DeGroat, Frank N. New York
DeHass, Nicholas. (Alt.) New England
DeHooghe, Bernard A. Michigan
deJarnette, N. M. Georgia
De Lano, Huntley. (Alt.) Michigan
DeLeuw, C. E. Central States
DeMartini, Frank E. California (Dual Federal)
Deming, P. H. California
Demorest, S. L. Michigan
DeMoss, Samuel. Pacific Northwest
DeMunn, E. M. New York
Denise, Wm. D. New York
Dennis, Carl E. Michigan
Dent, Harry. New York
DePoy, A. G. Central States
Depp, David. Central States
Derby, Ray L. California
Dermitt, Chas. W. Pennsylvania
Deslauriers, A. J. Canada
Desmarais, R. J. Canada
Des Moines, City of. Iowa
Deuchler, Walter E. Central States
Devendorf, Earl. New York
Dewante, Randolph H. California
Dewart, Donald M. New York
DeWolf, A. B. Florida
Dick, Robert. Central States
Dickey, Clay Mfg. Co. Associate
Att'n: A. G. Frerking
Dickson, D. B. Texas
Diefendorf, Fred G. Pennsylvnia
Dietz, Irving M. Texas
Dietz, Jess C. Central States
Dietz, John. Central States
Diller, Walter W. Central States
Dimmitt, Bruce S. Central States
Dion, Clarence K. New England
Disario, G. M. New England
Dixon, F. G. South Dakota
Dixon, G. Gale. Ohio
Dixon, R. M. Texas
Doane, C. C. California
Dobson, Wm. T. New York
Dobstaff, Robert, Jr. New York
Dobstaff, Robert W., Sr. New York
Dodd, C. K. S. Florida
Dodge, H. P. Michigan
Dodson, Lewis. Texas
Dodson, Roy E., Jr. Pacific Northwest
Doman, Joseph. New England (Dual—New York)
Domke, L. C. Central States
Domogalla, Bernhard. Central States
Donaldson, Wellington. New York
Donnell, Geo. M. Rocky Mt.
Donnini, Frank L. New England
Donohue, Jerry. Central States
Dopmeyer, A. L. Federal
Dorr Co. Associate
Dorr, Fred. Michigan
Dow Chemical Co. Associate
Dowd, Ira. Michigan
Downer, Wm. J. Central States
Downes, John R. New Jersey
Downing, Francis J. New York
Doyle, Thomas J. Michigan
Doyle, Wm. H. Central States
Drake, James A. Central States
Dreier, D. E. Central States
Drew, Leland F. Florida
Drew, Samuel T. New England
Drexel, Frederick. New York
Driscoll, Timothy J. New York
Drummond, A. H. England (I. S. P.)
Dudley, D. E. Central States
Dudley, Richard E. New England
Duell, Garth H. California
Duffy, Ora. Kansas
Dundas, Wm. A. Central States
Dunmire, E. H. Central States
Dunn, Town of (North Car.) North Carolina
Dunstan, Gilbert H. California
Durand, Edwin M. Michigan
Durham Water Dept. (North Car.) North Carolina
Durr, John J., Jr. Pennsylvania
Durrant, W. K. F. Canada
Dust, Joseph V. Central States
Duvall, Arndt J. Central States
Dwyer, John W. Central States
Dyckman, Warren W. New York
Dyer, Samuel. New England

Eager, Vernon. New York
Earl, Ralph. Georgia
Early, Fred J., Jr. California
Early, Mart. Pacific Northwest
Earnest, Lloyd. Georgia
Easdale, W. C. England (I. S. E.)

Easley, G. E. California
Eastburn, W. H. Pennsylvania
Easter, Charles W. New England
Eckelcamp, Joseph (Alt.) Michigan
Eddy, Harrison P., Jr. New England
Edgecomb, G. H. Canada
Edgerley, Edward. Pennsylvania
Edighoffer, Albert. New York
Edinger, Harry F. New York
Edmond, H. P. Georgia
Edmondson, J. H. England (I. S. P.)
Edwards, Gail P. New York
Edwards, William L. New York
Egan, J. H. California
Egger, Oscar O. Central States
Eglof, Dr. Warren K. New York
Ehle, Virgil. New York
Eich, Henry F. New York
Eidsness, Fred A. Florida
Eimco Corporation. Associate
Elder, Leiton J. California
Eldridge, E. F. Michigan
Electro Rust-Proofing Co. Associate
Elgin, Sanitary District of (Ill.) (Corporate) Central States
Elias, Geo. A. Pennsylvania
Eliassen, Rolf. New York
Ellms, J. W. Ohio
Ellsworth, Samuel M. New England
Elnor, Geo. E. Canada
Elsdon, Dr. G. D. England (I. S. P.)
Ely, E. H. England (I. S. E.)
Emerson, C. A. Pennsylvania
Emigh, Wm. C. Pennsylvania
Engineering News-Record. Associate
English, Joseph, Jr. Pennsylvania
Enloe, V. P. Georgia
Enoch Pratt Free Library. Maryland-Delaware
Enslow, L. H. New York
Epler, J. E. Central States
Epstein, Herman. New England
Erickson, Carl V. Central States
Erickson, E. J. Michigan
Erickson, W. J. New York
Ettinger, M. B. Federal
Eustance, Arthur W. New York
Eustance, Harry W. New York
Evans, Byron B. New York
Evans, David A. Pennsylvania
Evans, F. M. New Jersey
Evans, R. W. Central States
Evans, S. C. England (I. S. P.)
Everson Manufacturing Co. Associate
Everson, R. B. Central States
Ewart, K. L. Ohio

Faber, Harry A. New York (Dual Pennsylvania)
Fair, Gordon M. New England (Dual New York)
Fairbanks, E. G. California
Fales, Almon L. New England
Falls, O. M. Canada
Fanning, Harold R. New York
Farnsworth, George L., Jr. Central States
Farrant, James. New Jersey
Farrar, J. H. California
Farrell, Michael. New York
Faulkner, T. G. England (I. S. E.)
Fassnacht, Geo. G. Central States
Fawls, James F. New York
Feierstein, Jacob L. New York
Feldhake, C. J. Federal
Feltham, John C. Florida
Feltz, Fred C. Central States
Fenger, J. W. New York
Fenn, Ernest G. New England
Fenton, John V. New York
Ferebee, James L. Central States
Ferguson, G. H. Canada
Ferguson, Gerals W. Florida
Ferris, James E. New England (Dual New York)
Field, Emerson & Morgan, Inc. New York
Field, Wm. T. New York
Figeley, Paul. Central States
Filkins, D. A. (Alt.) Michigan
Finch, J. England (I. S. P.)
Finch, Lewis S. Central States
Finch, R. M. Central States
Finck, G. E. Maryland-Delaware
Findlay, A. New York
Fink, Wm. Kenneth. California
Finkbeiner, Carleton S. Ohio
Finley, Dexter L. California
Fischback, Hyman S. Federal
Fischer, Anthony J. New York
Fischer, F. P. Ohio
Fishbeck, Kenneth. Michigan
Fisher, Lawrence M. Federal
Fiskett, F. J. Central States
Fitch, T. A. California
Fittro, Louis L. Federal
Fitzgerald, Edw. P. Central States
Fitzgerald, J. A. New York
Fitzgibbons, F. C. Central States
Fitzmaurice, E. W. California
Five, Helge. New York
Fiveash, Charles E. Florida
Flanagan, Joseph E., Jr. Pennsylvania
Flannery, Harold J. California
Flatt, Truman L. Central States
Fleet, Gerald A. New York
Fleming, M. C. Pennsylvania
Fleming, Paul V. New England
Fletcher, Cecil C. Federal

Flexible Sewer-Rod Equipt. Co. Associate
Flood, Frank L. New England
Flower, G. E. Ohio
Flowers, E. England (I. S. P.)
Fontenelli, Louis. New Jersey
Foote, Kenneth E. New England
Forbes, Albert F. New York
Ford, J. R. Central States
Foreman, Merle S. (Alt.) California
Forsbeck, C. D. Pacific Northwest
Fort, Edwin J. New York
Fortenbaugh, J. Warren. New York
Forton, R. G. Michigan
Foster, Chas. Central States
Foster, Herbert, Jr. California
Foster, Norman. Pennsylvania
Foster, Richard G. Michigan
Foster, William Floyd. California
Foth, Herbert S. Central States
Fowler, G. J. England (I. S. P.)
Fowler, H. D. Pacific Northwest
Fowler, James D. Texas
Fox, Paul S. Rocky Mt.
Foxboro Company. Associate
Francis, Geo. W. Michigan
Francis Hankin & Co. Canada
Franklin, W. M. North Carolina
Franks, John T. Rocky Mt.
Fraschina, Keeno. California
Fraser, Charles E. Canada
Fraters, E. W. California
Frazier, Ernest. Central States
Frazier, Leonard H. New York
Frazier, Royall C. Georgia
Frazier, R. W. Central States
Freeborn, W. F. England (I. S. P.)
Freeburn, H. M. Pennsylvania
Freeland, B. H. Central States
Freeman, A. B. Federal
Freeman, W. B. Rocky Mt.
French, R. Del. Canada
Freund, J. P. Pennsylvania
Frick, A. L., Jr. California
Fricker, Augustus E. Pennsylvania
Frickstad, Walter N. California
Fridley, Jesse R. Oklahoma
Friedman, S. N. New Jersey
Friedman, Wm. M., Jr. New York
Friel, F. S. Pennsylvania
Friendly, Hugo H. New York
Frith, Gilbert R. Georgia
Froehde, F. C. California
Frye, Jacob E. New Jersey
Fuchs, Abraham W. Federal
Fuehrer, Carl W. Pennsylvania
Fuhrman, Ralph E. Federal
Fuller, H. L. Missouri
Fuller, Nelson M. New York
Fuller, Raymond H. Ohio
Fulmer, Frank E. Central States
Funk, John B. Maryland-Delaware
Funk, John T., Jr. Pennsylvania
Fynn, Geo. F. New York

Gadomski, Albert J. New Jersey
Gail, A. L. Central States
Gale Oil Separator Co. Associate
Gard, Chas. M. New York
Gardiner, W. E. Canada
Gardner, Geo. W. New York
Gardner, R. T. California
Garland, Chesley F. Florida
Garlock, Samuel C. New York
Garner, J. H. England (I. S. P.)
Garrett, R. W. Canada
Garthe, E. C. Federal
Garwood, Kirk. Iowa
Gatley, H. K. New Jersey
Gauntt, W. C. Texas
Gause, Frank. Central States
Gavett, Weston. New York
Gearhart, J. N. Pacific Northwest
Gehm, Harry Willard, Jr. New Jersey
Gelbke, Arthur W. New York
Gelston, W. R. Central States
General Chemical Co. Associate
General Electric Co. Associate
Genter, Albert L. Maryland-Delaware
Gentsch, Edward. Michigan
George, J. E. Missouri
Gerard, F. A. Central States
Gerdel, W. E. Ohio
Gere, William S. New York
Gerhart, Edgar. Pennsylvania
Gerling, Philip C. New York
Getz, Murray A. Central States
Gever, John C. Maryland-Delaware
Gibbons, E. V. Canada
Gibbons, M. M. New Jersey
Gibbs, Frederick S. New England
Gibbs, R. C. England (I. S. P.)
Gibeau, H. A. Canada
Gidley, H. K. Pennsylvania
Giesey, J. K. Central States
Gifford, Earl W. Central States
Gifford, J. B. Central States
Gift, H. M. New York
Gilbert, A. J. Arizona
Gilbert, J. J. Pennsylvania
Gilbert, J. Miles. Florida
Gilbertson, W. E. North Dakota
Gilcreas, F. Wellington. New England (Dual New York)
Giles, J. Henry L. New England
Gilkey, A. E. California
Gill, A. F. Canada

Gill, John B. California
Gill, Paul. Pennsylvania
Gillard, J. E. England (I. S. P.)
Gillespie, C. G. California
Gillespie, Wylie W. Florida
Gilligan, Howard. Pennsylvania
Gilman, Floyd. New York
Gilman, Harry I. Georgia
Gilman, N. A. Pacific Northwest
Gisborne, Frank R. (Alt.) New England
Glace, I. M., Jr. Pennsylvania
Glace, I. M. Pennsylvania (Dual New York)
Gladding, Charles. California
Gladue, Donat J. New England
Glamorgan Pipe & Foundry Co. Associate
Glynn, William J. New York
Godfroy, J. I. Michigan
Goff, James S. New England
Goff, Wm. A. Pennsylvania
Goicoechea, Prof. Leandro de. Florida
Goldsmith, Philip. New York
Goldthorpe, H. H. England (I. S. P.)
Golly, M. R. Central States
Gooch, E. W. Pacific Northwest
Goodman, Arnold H. Central States
Goodnight, V. L. Pacific Northwest
Goodridge, Harry E. California
Goodwin, S. E. Canada
Gordon, Arthur. Central States
Gordon, J. B. Federal
Gorman, Richard C., Jr. New York
Gotaas, Harold B. North Carolina
Goudey, R. F. California
Gough, Andrew B. New England
Gould, Richard H. New York
Grabbe Construction Co., H. A. Central States
Graber, Ralph Carl. Federal
Gracenin, Sylvester. Pennsylvania
Graden, Paul W. Central States
Graemiger, Joseph A. New England
Graham, James E. Michigan
Gran, Dr. John E. Georgia
Granger, Geo. (Alt.) Michigan
Grantham, Geo. R. Central States
Graul, Leroy H. New Jersey
Graver Tank & Mfg. Co., Inc. Associate
Gray, Earl G. Michigan
Gray, Harold F. California
Greeley, Richard F. New England
Greeley, Samuel A. Central States
Green, Alvin W. Pacific Northwest
Green Bay Fdy. & Machine Wks. Associate
Green, Carl E. Pacific Northwest
Green, Howard R. Iowa
Green, Wingate. Florida
Greene, J. F. Rocky Mountain
Greene, R. A. Michigan
Greenleaf, John W., Jr. New England
Gregory, L. L. England (I. S. E.)
Gregory, Ted R. California
Gregory, The John H. Sanitary & Municipal Reference Library. California
Greiff, V. New York
Greig, John M. M. New York
Grelick, David. New York
Griffen, F. T. New York
Griffin, A. E. New Jersey
Griffin, Guy E. New England
Griffith, L. B. Texas
Grimsley, J. T. Federal
Grinnell, Russell. Michigan
Groen, Michael A. Michigan
Gross, Carl D. Central States
Gross, Dwight D. Rocky Mt.
Grossart, L. J. H. Pennsylvania
Grosshans, Edw. W. Central States
Grover, Robert H. New York
Grubin, Herman. New York
Gruendler Crusher & Pulverizer Co. Associate
Gruss, A. W. California
Gutierrez, Andrew. North Carolina
Gwin, Thomas. California

Haag, Gerald. Central States
Haberer, John C. New York
Habermehl, C. Austin. Michigan
Hackett, Peter. New York
Haddock, Fred R. Pennsylvania
Hadin, Lion A. Pacific Northwest
Haemmerlein, Victor E. New York
Hager, Fred. Central States
Hagerty, L. T. Ohio
Hagestad, Herman T. Central States
Hale, Arnold H. New York
Hale, Frank C. Central States
Halff, Albert H. Central States
Hall, Frank H. New York
Hall, G. Albro. Ohio
Hall, G. D. Pacific Northwest
Hall, Geo. M. Central States
Hall, Harry R. Maryland-Delaware
Hall, S. P. Central States
Hall, W. H. North Carolina
Hall, W. N. Canada
Hallam, G. C. Pacific Northwest
Hallgren, R. A. Canada
Hallock, Emerson C. New York
Halpin, John. New York
Halvorson, H. O. Central States
Hambleton, F. T. England (I. S. P.)
Hamblett, W. C. Federal
Hamilton, Loeman A. Central States
Hamilton, R. F. Pacific Northwest
Hamlin, C. H. England (I. S. P.)
Hamm, Wm. C. New York

Hammer, Vernon Benjamin. Iowa
Hammond Bd. of Sanitary Commissioners (Corporate). Central States
Hammond, Robt. California
Handley, L. H. Georgia
Hanes, Gilbert C. California
Haney, Paul A. Kansas
Hanlon, D. A. Florida
Hansell, Wm. A. (deceased). Georgia
Hansell, Wm. A., Jr. Georgia
Hansen, Chris A. Federal
Hansen, Paul. Central States
Hanson, George I. New England
Hanson, Harry G. North Dakota (Dual Federal)
Hanson, John R. New York
Hapgood, E. P. California
Harbin, Wm. Central States
Hardenbergh, W. A. New York
Harding, Carl G. Florida
Harding, J. C. New York
Harding, Rogert G. Pacific Northwest
Hardman, Thomas T. Central States
Hardy, C. Asa. New York
Harley, Frank E. New Jersey
Harmeson, D. K. Central States
Harmon, Jacob A. Central States
Harmon, Judson A. California
Harper, Charles E. Central States
Harper, M. J. New England
Harper, Travis C. California
Harr, Neal. Kansas
Harris, Geo. C. Central States
Harris, I. England (I. S. P.)
Harris, R. C. Canada
Harris, T. R. Central States
Harrison, B. D. Pacific Northwest
Harrison, Edw. F. New York
Harrison, John B. California
Harshbarger, J. R. Central States
Hart, Chas. G. New York
Hart, W. B. Pennsylvania
Hartley, G. R. New Jersey
Hartley, John R. New England
Hartline, Wm. C. Florida
Hartman, B. J. Central States
Hartmen, Byron K. Central States (Dual New York)
Hartom, R. A. New Jersey
Hartung, N. E. Central States
Hartzell, E. F. Pennsylvania
Harvey, Carl. New York
Harvey, J. R. Pennsylvania
Harwell, Glen A. Missouri
Haseltine, T. R. Pennsylvania
Hasfurther, Wm. A. Central States
Haskins, Chas. A. Missouri
Hastie, James. New York
Hatfield, W. D. Central States
Hattery, Chas. E. Central States
Hauck, Chas. F. Ohio
Hauer, Gerals E. Michigan
Havens, William L. Ohio
Hawken, Dalton. Michigan
Hawley, Arthur A. New York
Haworth, J. Victor. Pennsylvania
Haworth, W. D. England (I. S. E.)
Hay, T. T. Central States
Haydock, Chas. Pennsylvania
Hayes, John A. New York
Hayob, Henry. Missouri
Hayward, Homer J. Michigan
Hasen, Richard. New York
Heaslit, Walter. Rocky Mt.
Hedgepeth, L. L. Pennsylvania (Dual New York)
Heffelfinger, D. D. Ohio
Heider, Robt. W. Central States
Heinrikson, J. J. Kansas
Heiple, Loren R. Central States
Heisig, H. M. Central States
Heiss, Edw. A. Pacific Northwest
Helland, H. R. F. Texas
Heller, Austin N. New York
Henderson, Chas. F. New York
Hendryx, Clarence E. Rocky Mountain
Henn, Donald E. Central States
Henry, Thomas B. Ohio
Hensel, Eugene C. Central States
Herberger, Arthur Henry. New York
Herda, N. Michigan
Hermann, F. X. Central States
Herr, H. N. Pennsylvania
Herrick, T. L. Central States
Herzig, S. B. Central States
Herzog, Henry. New York
Hesford, L. England (I. S. E.)
Hess, Daniel J., Jr. Pennsylvania
Hess, John S. Ohio
Hess, Seth G. New York
Heubi, Thomas. New York
Heukelekian, H. New Jersey
Hewitt, A. C. Pennsylvania
Heyward, T. C. North Carolina
Hibschman, Charles A. Pennsylvania
Hicklin, R. G. Georgia
Hicks, Cyril. (Alt.) Michigan
Hicks, Geo. W. Central States
Hicks, R. England (I. S. P.)
Higgins, William J. New York
Hill, Frank C. Rocky Mountain
Hill, G. Everett. New York
Hill, K. V. Central States
Hill, Theo. C. Pennsylvania
Hill, W. R. Pacific Northwest

Hiller, Paul W. New England (Dual—New York)
Hillis, Leonard. Michigan
Hilton, E. M. (Alt.) California
Hines, Leon H. New York
Hirschel, Leslie (deceased). New York
Hirst, J. England (I. S. P.)
Hoag C. C. New York
Hoag, Henry J. California
Hoagland, D. Ohio
Hoak, Richard D. Pennsylvania
Hobbs, Roy L. Georgia
Hodek, James J. Maryland-Delaware
Hodge, W. W. Pennsylvania
Hodges, H. E. W. England (I. S. E.)
Hodgson, E. England (I. S. P.)
Hodgson, J. J. N. England (I. S. P.)
Hodkinson, C. T. Central States
Hoeflich, G. C. Pennsylvania
Hoey, A. C. Canada
Hoey, John B. New York
Hoffert, J. R. Pennsylvania
Hoffman, Howard F. New York
Hogan, James W. T., New York
Hogan, M. S. Missouri
Hogan, William J. New York
Hoganson, Lester O. Central States
Holderby, J. M. Central States
Holderman, John S. Central States
Holland, Frank H. Central States
Holmes, Glenn B. New York
Holmes, Harry E. New England
Holmes, Kenneth H. New England
Holmquist, Chas. A. New York
Holroyd, A. England (I. S. P.)
Holst, J. S. South Dakota
Holt, Clayton M. Central States
Holter, A. L. Pacific Northwest
Holtje, Ralph H. New Jersey
Holtkamp, Leo. Iowa
Holway, O. C. Central States
Homan, Arthur R. Missouri
Homelite Corporation. Associate
Hommon, Charles C. Ohio
Hommon, H. B. California (Dual—Federal)
Hoot, Ralph A. Central States
Hope, Malcolm C. Federal
Hopkins, E. S. Maryland-Delaware
Hopkins, Glen J. South Dakota
Hopkins, L. S. R. New York
Hopkins, Omar C. Federal
Hopler, Harold S. Federal
Hopper, Allen O. New York
Horgan, John J. New York (Dual—New England)
Horne, Ralph W. New England
Horner, J. L. Texas
Hoskins, J. K. Federal
Hoskinson, Carl M. California
Hotchkiss, H. T., Jr. New York
Hoth, Fred. Central States
Houser, George C. New England
Houston, W. J. Georgia
Howard, C. M. Pacific Northwest
Howard, P. F. New England
Howard, R. R. Missouri
Howarth, J. P. England (I. S. P.)
Howe, Ben V. Rocky Mountain
Howe, J. P. Canada
Howe, W. A. Central States
Howell, Eugene M. California
Howland, W. E. Central States
Howson, J. T. New York
Howson, L. R. Central States
Hoy, J. R. Florida
Hoy, M. J. South Dakota
Hoydar, Albert L. Pacific Northwest
Hoyle, W. H. England (I. S. P.)
Hoyt, Clinton W. New York
Hromada, Frank M. Central States
Hubbell, Geo. E. Michigan
Hubel, J. H. Canada
Huber, Harold J. New York
Hudson, L. D. Central States
Huebner, Ludwig. California
Huffman, Fred. California
Huffman, Lloyd C. Ohio
Hufford, L. E. Ohio
Hughes, W. P. Pacific Northwest
Humphreys, Walter. California
Humphries, J. I. Georgia
Hunt, Geo. W. California
Hunt, Henry J. Central States
Hunt, H. S. Michigan
Hunt, L. W. Central States
Hunt, Raymond L. New York
Hunter, A. England (I. S. P.)
Hupp, John E., Jr. Central States
Hurd, Charles H. Central States
Hurd, Edwin C. Central States
Hurley, J. England (I. S. P.)
Hurst, Chas. Central States
Hurst, Howard M. California
Hurst, William C. New York
Hurwitz, Emanuel. Central States
Hussong, Ernest W. Central States
Hutcheson, H. D. New York
Hutchins, Will A. Central States
Huth, Norman A. California
Hutton, H. S. Pennsylvania
Hyde, Charles Gilman. California

Illinois Dept. of Public Health (Corporate). Central States
Indiana State Bd. of Health (Corporate). Central States

Infilco, Inc. (Corporate) Associate. Central States
Ingols, Robert. New Jersey
Ingram, Wm. T. California
Iowa City, City of. Iowa
Iowa Valve Co. Associate
Irwin, Forrest. Ohio
Irwin, G. M. Pacific Northwest

Jack, David. Canada
Jack, Grant R. Canada
Jackson, J. Frederick. New England
Jackson, John F. New Jersey
Jackson, R. B. Michigan
Jackson, T. L. Michigan
Jacobs, L. L. Georgia
Jacobson, Geo. L. South Dakota
James, Glenn. Central States
James, Norman S. Florida
Janes, N. D. Ohio
Jardine, M. E. Canada
Jarlinski, Thaddeus T. New York
Jeffrey, H. H. California
Jeffrey Manufacturing Co. Associate
Jenckes, J. Franklin, Jr. New England
Jenks, Glen. Rocky Mountain
Jenks, Harry N. California
Jennings, A. England (I. S. P.)
Jennings, L. R. Michigan
Jensen, Emil C. Pacific Northwest
Jenson, Theodore B. Florida
Jerge, Ray. New York
Jessop, A. H. California
Jeup, Bernard H. Central States
Jewell, H. W. California
Job, Richard C. Georgia
Johannessen & Girand. Arizona
Johns-Manville Corp. Associate
Johnson, Arthur N. Central States
Johnson, Clement. (Alt.) New York
Johnson, Earle P. Pennsylvania
Johnson, Eskil C. New England
Johnson, Floyd E. Central States
Johnson, Herbert O. New York
Johnson, J. Clifford. New York
Johnson, Jess B. Central States
Johnson, John W. New York
Johnson, L. M. Central States
Johnson, R. J. Central States
Johnson, Russell. Rocky Mountain
Johnson, Robt. T. Iowa
Johnson, Verner C. California
Jones, Milton R. Central States
Jones, A. N. Arizona
Jones, Arthur C. Florida
Jones, C. B. O. England (I. S. P.)
Jones, Daniel. New York
Jones, E. M. Pennsylvania
Jones, Frank E. Michigan
Jones, Frank O. Central States
Jones, Frank Woodbury. Ohio (Dual—Pennsylvania)
Jones, John N. Central States
Jones, Martha A., Miss. Central States
Jones, S. Leary. Federal
Jones, Wayland. California
Jordan, Harry E. New York
Jorgensen, Homer W. California
Joy, C. Fred, Jr. New England
Kaar, G. C. Central States

Kachmar, John F. Federal
Kachorsky, M. S. New Jersey
Kafka, John. Central States
Kaiser, C. T. Georgia
Kaler, P. E. Kansas
Kaltenbach, Albert B. Maryland-Delaware
Kammerling, Lane. Michigan
Kane, R. D. Ohio
Kaplan, Bernard. New Jersey
Kaplovsky, A. J. New Jersey
Kappe, S. E. Pennsylvania (Dual—New England and New York)
Karsa, William J. New York
Kass, Nathan I. New York
Kassay, Albert E. New York
Kay, Frank E. Pennsylvania
Kearney, John J. Central States
Keefer, Clarence E. Maryland-Delaware
Keefer, R. K. Pennsylvania
Keeler, J. Harold. New York
Kehr, William Q. Missouri
Keirn, Kenneth A. California
Keller, Dwight. Ohio
Keller, H. James. California
Keller, Jacob. New York
Keller, Lyndon M. New York
Keller, S. K. Florida
Kelley, R. E. Michigan
Kellogg, Clarence E. New York
Kellogg, James W. North Carolina
Kelly, Clarence. New York
Kelly, Earl M. California
Kelly, Francis W. Pennsylvania
Kelsey, Walter. Pennsylvania & New York (Dual—New England)
Kemp, Harold A. New York
Kempkey, A. California
Kendrick, George I. Central States
Kennedy, C. C. California
Kennedy, D. R. California
Kennedy, R. R. California
Kennedy, Wm. New York
Kenney, Norman D. Maryland-Delaware
Kepner, Dana E. Rocky Mountain
Ker, M. F. Canada

Kern, Andrew G. Pennsylvania
Kershaw, Arnold. England (I. S. P.)
Ketcham, Joseph M.
Kibler, Harry J. New York
Kidd, Carl W. New York
Kieffer, Jos. D. New York
Kiker, John E., Jr. New York
Killam, E. T. New Jersey
Kilcawley, Edw. J. New York
Kimball, Jack H. California
Kin, Stephen R. North Carolina (Dual New York)
Kinderman, Wm. Pennsylvania
King, Cooley B. Georgia
King, Henry R. Central States
King, Richard. Central States
King, Wendell. Kansas
Kingsbury, H. N. Central States
Kingston, Paul S. Central States
Kingston, T. M. S. Canada
Kingwell, E. G. Pacific Northwest
Kinney, E. F. Central States
Kinney, J. B. Canada
Kinsel, Harry L. Pennsylvania
Kipp, W. H. Pacific Northwest
Kirchoffer, W. G. Central States
Kirn, Matt. Central States
Kirsner, Charles. New York
Kittrell, F. W. Federal
Kivari, A. M. California
Kivell, Wayne A. New York
Kizler, Wilfred C. California
Kjellburg, G. (Alt.) California
Klann, Martin C. Michigan
Klegerman, M. H. New York
Klein, J. A. Central States
Klein, L. England (I. S. P.)
Kleiser, Paul J. Central States
Kleven, John. North Dakota
Klinck, Frank. New York
Kline, H. S. Ohio
Klippel, Floyd. Iowa
Knapp, Henry A. Georgia
Knapton, Wm. California
Knechtges, O. Central States
Knight, C. H. Canada
Knittel, E. A. Pacific Northwest
Knoedler, H. A. California
Knollman, Fred. Rocky Mountain
Knowles, Coyle E. New York
Knowlton, W. T. California
Koch & Fowler, Texas
Koch, Philip L. Central States
Kochin, Milton S. Pennsylvania
Kochtitzky, O. W., Jr. Federal
Koebig, A. H., Jr. California
Koeckeritz, R. C. Central States
Kolb, Fred W. (Alt.) California
Komline, T. R. New Jersey
Koon, Ray E. Pacific Northwest
Koplowitz, Sol. New York
Koruzo, John E. Georgia
Kozma, Albert B. New Jersey
Kramer, Harrison W. Pacific Northwest
Kramer, Harry P. Central States
Kratz, Fred R. Pennsylvania
Kraus, L. S. Central States
Krell, A. J. New York
Kressly, Paul E. California
Kreutter, Clarence. New York
Kronbach, Allan. Michigan
Kroone, T. H. Ohio
Krum, Harry J., Jr. Pennsylvania
Kuhner, Frank G. Central States
Kulberg, Abraham. New York
Kunsch, Walter. New England
Kunze, Albert T. Michigan
Kussmaul, T. C. Ohio

Lacey, Howard E. South Dakota
Lacy, Ilbert O. New York
Ladlow, John. Arizona
Lafferty, W. R. New Jersey
Lafreniere, Theo. J. Canada
Laidlaw, C. T. Canada
Lak, Gerard J. California
Lakeside Engineering Corp. Associate (Corporate) Central States
Lamar, Jones C. Texas
Lamb, Charles. Canada
Lamb, Clarence F. New England
Lamb, Miles. Central States
Lamb, P. England (I. S. P.)
Lambert, Lowell E. Federal
Lamoureux, Vincent B. Federal
Lamson, B. E. Canada
Lane, Calvin S. New England
Lang, Sheldon L. Federal
Lang, Wm. H. Pennsylvania
Langdon, B. J. Federal
Langdon, L. E. Central States
Langdon, Paul E. Central States
Langelier, W. F. California
Langford, Leonard L. New York (Dual—Pennsylvania and New England)
Langlais, Zochee. Canada
Langshaw, C. L. England (I. S. E.)
Langwell, Louie. Central States
Lannon, William. New England
Lanphear, Roy S. New England
Larkin, W. H. New York
Larsen, Ernest A. New York
Larsen, Stanley J. Central States
Larson, C. C. Central States

Larson, Keith D. Central States
Larson, L. L. Central States
La Rue, Luther. Ohio
Lauer, Charles N. Pennsylvania
Laughlin, William G. New York
Lauster, K. C. North Dakota
Lautz, Harold L. Central States
LaValley, Edward C. New York
Lawlor, J. P. Iowa
Lawrence, John. New York
Lawson, W. S., Layport, H. R. Pacific Northwest
Lea, J. E. England (I. S. P.)
Lea, W. S. Canada
Leach, Walter L. Ohio
Leatherman, W. L. Ohio
Le Bosquet, M. Federal
Le Chard, Joseph H. New Jersey
LeClerc, Arthur B. North Carolina
Lederer, K. California
Ledford, George L. New York
Lee, Chas. H. California
Lee, David B. Florida
Lee, Oliver. Central States
Leemaster, J. F. Michigan
Leh, Willard. Pennsylvania
Lehmann, Arthur F. New Jersey
Leigh, H. G. England (I. S. P.)
Leimbach, Harry. Pennsylvania
Leist, Ervin F. Ohio
Leithiser, E. Pennsylvania
Leland, Benn J. Central States
Leland, Raymond I. Central States
Lemcke, Ewald M. California
Lemieux, R. A. Canada
Lemon, Paul R. California
Lendall, Harry N. New Jersey
Lenneau, F. B. Georgia
Lentfoehr, Charles E. Central States
Leonard, W. V. Rocky Mountain
Leonhard, Harold M. Michigan
Lesher, Carl. Ohio
Lessig, D. H. Central States
Le Van, James H. Federal
Lewis, E. S. Arizona
Lewis, G. M. Federal
Lewis, John V. New York
Lewis, R. K. Central States
Ley, Charles H. Canada
Lieber, Maxim. New York
Lilly, Geo. M. Rocky Mountain.
Limestone Products Corp. of America. Associate.
Lind, A. Carlton. Central States
Lindell, O. V. Missouri
Linderman, Irving E. Central States
Linders, Edward. Federal
Lindsten, H. C. North Dakota
Link-Belt Company. Associate
Att'n: M. B. Tark. Pennsylvania (Dual—New York)
Link-Belt Company (Corporate). Central States. Att'n: Frank W. Lovett
Lippelt, Hans B. New York
Little, August. Missouri
Livingstone, Bard. California
Lloyd, G. H. Canada
Lobee, Frank A., Jr. New York
Locke, Edw. A. New England
Lockett, W. T. England (I. S. P.)
Lockwood, Bronson E. New England
Loelkes, Geo. L. Missouri
Logan, Robert P. New Jersey
Long, Frank V. California
Long, George S. Pennsylvania
Long, H. Maynard. Central States
Long, James C. New Jersey
Longbottom, V. England (I. S. P.)
Longlais, Zachie. Canada
Longley, Paul N. Pennsylvania
Loomis, Harry E. New York
Los Angeles Public Library. California (Municipal Reference Library)
Los Angeles Public Library. California (Serials Division)
Losee, James R. New York
Lourinch, Louis B. Central States
Love, James C. Central States
Lovejoy, W. L. Pacific Northwest
Lovell, Theodore R. Iowa
Lovett, F. W. Central States
Lovett, M. England (I. S. P.)
Lowe, Robt. P. California
Lowe, Walter M. New York
Lowther, Burton. California
Lozier, Wm. S. New York
Lubratovich, M. D. Central States
Luchtenberg, R. O. Ohio
Ludlow Valve Mfg. Co. Associate
Ludwig, Harvey F. California (Dual—Federal)
Ludwig, Russell G. California
Ludzack, F. J. Central States
Luebbers, Ralph H. California
Lueck, Bernard F. Central States
Luippold, G. T. California
Lumb, C. England (I. S. P.)
Lundstrom, Karl A. Central States
Lupher, Leon P., Jr. Central States
Lustig, Joseph. Central States
Luther, Robt. W. North Carolina
Lutz, Howland C. Pennsylvania
Lux, Kathleen E. Central States
Lyman, C. S. Ohio
Lynch, Daniel E., Jr. New York
Lynch, James T. New York

Lynchburg Foundry Company. Associate
Lyons, William. New York

McAfee, H. D. Texas
McAdoo & Allen Welting Co. (Corporate). Pennsylvania
McArthur, Franklin. Canada
McAuley, John Dennis. Federal
McAuley, Wm. F. Georgia
McBride, J. L. California
McCabe, Brother Joseph. New York
McCall, Robert G. Central States
McCallum, G. E. Federal
McCannel, D. A. R. Canada
McCarthy, Joseph A. New England
McCarthy, Justin J. New York
McCarthy, William F. New York
McCaslin, Walter R. Central States
McClane, S. Wood, Jr. New Jersey
McClenahan, W. J. Central States
McClintock, H. C. Rocky Mountain
McClure, Ernest. Central States
McCoy, Ted. Central States
McDade, Frank. New York
McDaniel, C. C. Central States
McDonald, John. New England
McDonald, N. G. Canada
McDonnell, Geo. H. New York
McFarlane, Walter D. Michigan
McFaul, W. L. Canada
McGann, Robt. J. New York
McGarth, C. P. Michigan
McGuire, C. D. Ohio
McGurk, Sam R., Jr. Central States
McHugh, Basil. Pacific Northwest
McIlvaine, Wm. D., Jr. Central States
McIntosh, Pierre B. California
McIntyre, F. J. Ohio
McIntyre, John C. Central States
McKay, R. Donald. Canada
McKee, Frank J. Central States
McKee, Jack E. New England
McKee, S. C. Ohio
McKeeman, Edwin C. New York
McKeen, William H. California
McKenna, Harold K. Michigan
McKinlay, Daniel. California
McLaren, Alfred M. California
McLaughlin, Carroll W. New York
McLaughlin, John. New Jersey
McLean, Clement. New York
McLean, R. F. Pacific Northwest
McMahon, Walter A. New England
McManamna, T. L. Canada
McMenamin, C. B. New Jersey
McMillan, Donald C. California
McMorrow, B. J. California
McNamee, Paul D. Federal
McNicholas, J. England (I. S. P.)
McNiece, L. G. Canada
McRice, Donald J. California
McWilliams, D. B. Canada
Mabbs, John W. Central States
Macabee, Lloyd C. California
Macauley, J. W. New York
MacCallum, C. New York
MacCrea, J. M. New York
MacDonald, J. C. Central States
MacDowell, R. F. Ohio
Machis, Alfred. Maryland-Delaware
MacKenzie, Vernon G. Federal
Mackin, J. C. Central States
MacLachlan, Angus. Ohio
MacLaren, J. F. Canada
MacLean, J. D. Canada
Maga, John A. California
Magee, Geo. W. New York
Maguire, Chas. A. New England
Mahlie, W. S. Texas
Maier, F. J. Federal
Mailloux, Wm. South Dakota
Main, Ralph A. Michigan
Makepeace, W. H. England (I. S. P.)
Malcolm, Wm. L. New York
Maldonado, Ardis. (Alt.) California
Mallmann, W. L. Michigan
Mallory, Edward B. Pennsylvania (Dual Central States)
Malloy, Howard M. Michigan
Malone, J. R. North Carolina
Malony, W. L. Pacific Northwest
Mangones, Robt. J. New York
Mann, Alfred H. New York
Mann, Karl M. New York
Mann, Uhl T. New York
Mannheim, Robert. New England
Mansfield, M. G. Pennsylvania
Manteufel, Lawrence A. Central States
Marchon, Seigmund S. New York
Mariner, W. S. New England
Mark, Richard S. Federal
Marrs, Paul. Florida
Marsh, H. M. Canada
Marshall, E. A. New York
Marshall, J. C. (Alt.) Michigan
Marshall, Leslie S. New York
Marshall, W. B. New York
Martens, Myron M. Central States
Martin, A. E. New York
Martin, Alexander G. New York
Martin, Chas. P. California
Martin, Edw. J., Jr. New York
Martin, Geo. C. Central States
Martin, Sylvan C. Central States
Marx, Frank. New York

Maryland State Dept. of Health. Maryland-Delaware
Marx, Geo. W. Arizona
Mather, Edw. K. South Dakota
Mathers, Geo. New York
Mathews, E. R. South Dakota
Mathews, Frank E. Pacific Northwest
Mathews, W. W. Central States
Mathieson Alkali Works, Inc. Associate
Mathis, Alice. Arizona
Matter, L. D. Pennsylvania
May, D. C. Michigan
May, Harold L. California
McMullen, Wm. Central States
McRae, John C. Central States
Meara, John W. New York
Mebus, Geo. B. Pennsylvania
Mechler, L. W. California
Meckler, Wm. G. Federal
Medbery, H. Christopher. California
Meeker, Herbert J. New York
Melburg, Fred. Rocky Mountain
Mendelsohn, I. W. New York
Menefee, James H. Texas
Menzies, D. B. Canada
Menzies, J. Ross. Canada
Merkel, Paul P. Pennsylvania
Merlo, Louis A., Jr. Canada
Merrick, Ray. Central States
Merrill, Walter E. New England
Merz, H. Spencer. Central States
Mesner, Elmer C. New York
Metyko, Frank J. Michigan
Meyer, Louis P. H. California
Michael, A. M. North Carolina
Michaels, A. P. Florida
Michaels, Hohn. New York
Mick, K. L. Central States
Mickle, Chas. T. Central States
Micklethwaite, W. E. Canada
Middleton, Francis M. Federal
Miick, Fred E. California
Miles, Henry J. California
Miller, A. P. Federal
Miller, A. S. England (I. S. P.)
Miller, Basil. Central States
Miller, Alden W. Arizona
Miller, David R. Central States
Miller, John B. Florida
Miller, J. John. Pennsylvania
Miller, L. W. Central States
Miller, Lewis B. Pennsylvania
Miller, Maurice L. Central States
Miller, Noble. Central States
Miller, Norman A. Michigan
Miller, Robert G. Iowa
Miller, Wallace T. New York
Milligan, Francis B. Pennsylvania
Milling, Martin A. Central States
Mills, J. Ralph. California
Mills, S. W. Canada
Minneapolis-St. Paul Sanitary District (Corporate). Central States
Mitchell, Burton F. New England
Mitchell, Louis. New York
Mitchell, Robt. D. South Dakota
Modak, N. V. England (I. S. P.)
Moeller, Carl. Central States
Mogelnicki, Stanley. Michigan
Moggio, Wm. A. North Carolina
Mohlman, F. W. Central States
Molitor, Edward P. New Jersey
Molitor, Paul Sr. (Deceased). New Jersey (Dual—Pennsylvania)
Monfried, Leon. Central States
Monk, H. E. England (I. S. P.)
Monroe, S. G. Ohio
Monsanto Chemical Company. Associate
Monsell, Harry M. New York
Montgomery, J. R. Michigan
Montgomery, James M. California
Montreal, City of., Public Works Dept. Canada
Moon, James N. Pennsylvania
Moor, Alex. (Alt.) New York
Moor, W. C. Texas
Moore, Charles A. Pennsylvania
Moore, Edward W. New England
Moore, Lee S. Central States
Moore, F. Owen. England (I. S. E.)
Moore, George W. New York
Moore, Geo. S. North Carolina
Moore, Herbert. Central States
Moore, R. B. Central States
Moore, R. L. England (I. S. P.)
Moore, W. A. Federal
Moran, Alton B. Rocky Mountain
Morehouse, W. W. Ohio
Morey, Burrows. New York
Morgan, Edward F., Jr. New England
Morgan, George. Canada
Morgan, Philip F. Central States
Morgenroth, Fritz. New England
Morin, A. Canada
Morkert, Kenneth. Central States
Morrill, Arthur. Michigan
Morris, Arval. (Alt.) California
Morris, D. K. Central States
Morris, Lee. South Dakota
Morris, Paul J. Pennsylvania
Morrison, James E. Pacific Northwest
Morrissette, Romeo. Canada
Morrow, Ben S. Pacific Northwest
Moses, H. E. Pennsylvania
Moses, James E. North Carolina
Moss, E. H. North Carolina

Moss, F. J. Federal
Mott, C. A. Canada
Moudy, R. B. Rocky Mountain
Mountfort, L. F. England (I. S. P.)
Moutrey, Curtis. Oklahoma
Mowbray, Geo. A. New York
Mowrey, A. F. New Jersey
Mowrey, J. Hase. Pennsylvania
Mowry, R. B. New Jersey (Dual Pennsylvania)
Mudgett, C. T. Michigan
Muegge, O. J. Central States
Mueller Company. Associate
Muldoon, Joseph A. New England
Mulholland, R. A. Texas
Mullinex, Chas. D. Iowa
Mulvihill, F. J. Pennsylvania
Mundling, Miss Germaine G. New York
Munroe, City of (N. Car.). North Carolina
Munroe, E. H. Canada
Munroe, W. C. Maryland-Delaware
Munson, Laura A. (Mrs.) California
Murdock, Wm. Pennsylvania
Murphy, John A. Central States
Murphy, Lindon J. Iowa
Murphy, Reginald A. New York
Murray, A. E. Scott. England (I. S. E.)
Murray, K. A. England (I. S. P.)
Murschel, Jacob. South Dakota
Musgrove, Robt. Michigan
Mutzberg, F. A. North Carolina
Myers, Harry L. Central States

Naehr, Harry F. Georgia
Nance, E. L. North Carolina
Nangle, B. A. South Dakota
Nasi, Kaarlo W. California (Dual Federal)
National Water Main Cleaning Co. Associate
Nauer, Louis A., Jr. Central States
Naylor, William. New England
Neiman, W. T. Central States
Nelle, Richard S. Central States
Nelson, Ben O. Pacific Northwest
Nelson, D. H., Dr. Central States
Nelson, Frederick G. Ohio
Nesheim, Arnold. Federal
Nessa, Herbert. Iowa
Neumann, George B. Central States
Neves, Dr. Lourenco Baeta. New York
Nevitt, I. H. New York
Newell, Town of (Iowa). Iowa
Newlands, James A. New England
Newman, Alfred C. Florida
Newsom, Reeves. New York
Newton, City of (Iowa). Iowa
Newton, Donald. Central States
Nicholas, Forrest A. Central States
Nichols, A. E. New York
Nichols Engineering & Research Corp. Associate
Nichols, M. Starr. Central States
Nicholson, C. P. New York
Nickel, Jack B. Central States
Nicklin, H. S. Canada
Niebergall, Herbert J. New York
Nielsen, A. E. New York
Niemi, Arthur G. Central States
Niles, A. H. Ohio
Niles, Chas. A. New York
Niles, Thomas M. Central States
Nixon, J. England (I. S. P.)
Nixon, M. B. Georgia
Nixon, Ray. Kansas
Nold, Vern. Central States
Nordell, Carl H. Central States
Norfleet, Clark T. (Alt.) California
Norgaard, John. Michigan
Norman, G. A. Central States
Norman, James E. Texas
Norris, Francis I. Federal
Nugent, Franklin J. Pennsylvania
Nugent, Harold F. New York
Nugent, Lee M. California
Nussbaumer, Newell L. New York
Nussberger, Fred. New York
Nutter, Frank H. Central States

Obma, Chester A. Central States
O'Brien, Earl F. New York
Ocean City Sewer Service Co. New Jersey
Ockershausen, Richard W. New York
O'Connell, Wm. J., Jr. California
O'Connor, Wm. F. New York
Odbert, Eugene, Jr. Central States
O'Dell, W. H. New York
O'Donnell, Chas. F. New York
O'Donnell, R. Pennsylvania
Oeffler, W. A. Central States
Oeming, L. F. Michigan
O'Flaherty, Fred. Ohio
Ogden, Henry N. New York
Ogle, Harry B. California
O'Hara, Franklin. New York
O'Hara, John. Pennsylvania
Ohr, Milo F. Michigan
Oke, Ernest E. W. Canada
Okun, Abraham H. New York
Okun, Daniel A. Central States
Okun, W. H. New York
Old, H. N. Federal
Olewiler, Grant M. Pennsylvania
Olsen, W. C. North Carolina
Olson, Frank W. Central States
Olson, Herbert A. Michigan
Omega Machine Co. Associate
O'Neill, Ralph W. California

Orchard, W. J. New York
Ongerth, Henry J. California
Orr, Wm. S. Canada
Orton, J. W. Michigan
Osage, City of (Iowa). Iowa
Osborn, L. C. Rocky Mountain
Ousterhout, Alfred. New York
Owings, Noble L. Maryland-Delaware

Pacific Flush Tank Co. Associate (Corporate Central States)
Paessler, Alfred H. Texas
Page, C. A. Georgia
Painter, Carl E. California
Palange, Ralph C. Federal
Pallo, Peter E. New York
Palmer, Benjamin M. New England
Palmer, C. L. Michigan
Palmer, Harold K. California
Palmer, John R. Central States
Palocsay, Frank S. Ohio
Pampa, City of (Texas). Texas
Parker, L. K. New England
Parks, G. A. California
Parrish, Rial T. Ohio
Parsons, Chase. Central States
Parsons, R. H. Canada
Patterson, Roy K. New York
Paul, Lewis C. New York
Paul, Richard B. Pennsylvania
Pawlak, John S. New York
Payrow, Harry G. Pennsylvania
Peake, J. B. New York
Pearl, Emanuel H. Texas
Pearsall, Ted. Central States
Pearse, Langdon. Central States
Pease, Maxfield. Ohio
Peaslee, Geo. A. Central States
Peck, Lawrence J. New York
Pecker, Joseph S. New York
Peightal, Wm. H. California
Peirce, W. A. Central States
Peirson, Henry C. (Alt.) California
Pence, Irel V. Central States
Pennsylvania Salt Mfg. Co. Associate
Perrine, J. Franklin. New York
Perry, Earl R. New England
Perry, J. S. Central States
Peterson, Earl L. New York
Peterson, Ivan C. Central States
Peterson, J. H. California
Peterson, Myhren C. Central States
Peterson, Ralph W. Central States
Petrie, Wm. P. New England
Pett, K. M. Central States
Pfiffer, Fred. California
Phelps, B. D. California
Phelps, E. B. New York
Phelps, Ellis K. Florida
Phelps, Geo. Canada
Phillips, H. N. New York
Phillips, R. S. North Carolina
Phillips, Roy L. Pennsylvania
Phillips, R. W. Texas
Piatt, Wm. M. North Carolina
Pierce, C. L. California
Pierce, George O. Central States
Pierce, H. M. South Dakota
Pierce, W. E. (Alt.) Michigan
Pierron, Wm., Sr. Pacific Northwest
Pincus, Sol. New York
Pinkney, Glenn E. New York
Pinney, F. W. North Dakota
Pirnie, Malcolm, Jr. Federal
Pisano, Frank. California
Pitkin, Ward H. New York
Pittsburgh-Des Moines Co. Associate
Pittsburgh Equitable Meter Co. Associate
Pizie, Stuart G. Florida
Plamondon, Sarto. Canada
Pledger, A. England (I. S. P.)
Plummer, Raymond B. Central States
Pohl, C. A. New York
Poindexter, G. G. Central States
Pollex, Elmer. Ohio
Pollock, John M. New York
Pomeroy, Clarence. Michigan
Pomeroy, Richard. California
Poole, B. A. Central States
Poole, S. B. England (I. S. P.)
Poole, Wm. A. California
Pope, Lester. New Jersey
Porges, Ralph. Federal
Porteous, W. K. England (I. S. E.)
Porter, H. California
Porter, William. New York
Poston, R. F. South Dakota
Potts, Clyde. New York
Potts, Harry G. Michigan
Powell, A. R. New York
Powell, Reuben R. Florida
Powell, S. T. Maryland-Delaware
Powell, W. L. Texas
Powers, E. C. Ohio
Powers, Thomas J. Michigan
Pratt, Gilbert H. New England
Pratt, Jack W. California
Pray, John W. Iowa
Prendergast, John W. Arizona
Price, Charles R. South Dakota
Pringle, H. L. Canada
Probasco, S. R. New Jersey
Proportioneers, Inc. Associate
Proudman, Chester F. New England
Provost, Andrew J. New York
Public Works Magazine. Associate

Puckhaber, Fred H. Texas
Puffer, Stephen P. New England
Purdie, David J. New York
Purser, John R., Jr. North Carolina
Pyle, Wm., Jr. Iowa

Quaely, Martin F. New York
Quartly, Eric V. California
Quigley Company, Inc. Associate
Quinn, Joseph L., Jr. Central States

Racek, L., Jr. Central States
Radcliff, Robert C. Rocky Mountain
Radcliffe, Jack C. New Jersey
Raisch, Wm. New York and New England
Ralston, Wilmer R. Pennsylvania
Ramseier, Roy E., Sr. California
Rankin, R. S. Central States
Rantsma, W. Frank. (Alt.) California
Ratcliffe, Clyde. North Carolina
Rath, Henry M. New York
Rawlins, George S. North Carolina
Rawn, A. M. California
Rawson, E. Otto. Canada
Ray, Clayton B. Georgia
Raymond, Nelson I. Michigan
Read, Homer V. Central States
Reames, H. S. (Alt.) Michigan
Reardon, Wm. R. Central States
Reaves, S. H. Georgia
Rector, K. E. Kansas
Redding, Harry P. North Carolina
Redfern, W. B. Canada
Redmon, Polk. Central States
Reed, Leon H. New England
Reedy, Timothy D. Michigan
Rees, N. B. Central States
Reese, Marshall. Pennsylvania
Reeve, Lester G. Pennsylvania
Reeves, C. F. California
Reeves, R. B. Kansas
Regester, Geo. E., Jr. Pennsylvania
Regester, Robt. T. Maryland-Delaware
Rehler, Joseph E. New York
Reid, Geo. W. Florida
Reid, G. Graham. Canada
Reidell, Alfred G. California
Rein, L. E. Central States
Reiners, A. H. New Jersey
Reinhardt, Arthur W. California
Reinke, E. A. California
Reinoehl, Don. California
Reisch, E. A. New York
Reisert, Michael J. New York
Remsburg, W. N. Kansas
Remsen, John. New York
Requardt, G. J. New York
Reuning, Howard T. Pennsylvania
Reybold, E. C. Rocky Mountain
Reynolds, Leon B. California
Reynoldson, C. G. Central States
Reynoldson, T. B. England (I. S. P.)
Rhoads, Edward J. Pennsylvania
Ribal, Raymond Robt. California
Ribner, Morris. New York
Ribreau, Gilbert E. New York
Rice, Archie H. Pacific Northwest
Rice, John E. Federal
Rice, John M. Pennsylvania
Rice, Lawrence G. New York
Richards, G. H. Canada
Richards, Paul W. Central States
Richardson, C. G. Associate (Dual New England)
Richgruber, Martin. Central States
Richheimer, Chas. E. Florida
Richman, W. F. Central States
Richter, James B. Central States
Richter, Paul O. Central States
Rickard, Grover E. New York
Riddick, Thomas M. New York
Ridenour, G. M. Michigan
Riedel, John C. New York
Riedesel, Henry A. Central States
Riedesel, P. W. Central States
Riehl, W. H. Canada
Riffe, Norman T. California
Riis-Cartensen, Erik. New York
Riker, I. R. New Jersey
Ritter, Bruce. (Alt.) Michigan
Roab, F. H. Central States
Roahrig, Henry L. Central States
Roberton, L. T. Canada
Roberts, C. R. New York
Roberts, F. C., Jr. California (Dual Federal)
Roberts, Jack. New York
Roberts, W. C. California
Robertson, Geo. E. New York
Robertson, John. California
Robins, Maurice L. Central States
Robinson, B. Canada
Robinson, Fred M. Central States
Robinson, G. G. Canada
Robinson, I. F. Canada
Robinson, Philip L. Georgia
Robinson, W. S. (Alt.) California
Rocco, John. New York
Rock, Harold F. New York
Rodwell, Robt. D. Central States
Roe, Frank C. Central States and New York
Roeller, R. S. Pennsylvania
Roetman, Edmond T. Pennsylvania
Rogers, Allan H. New York
Rogers, D. Paul. Pennsylvania
Rogers, Harvey G. Central States
Rogers, Jack C. Federal

Rogers, John A. New England
Rogers, M. W. Canada
Rogers, Milford E. Kansas
Rogers, W. F. Central States
Rohlick, Gerard A. Central States
Roll, A. H. Central States
Romaine, Burr. Central States
Romeiser, C. H. Central States
Rosemeyer, Alfred. Central States
Rosen, Milton. Central States
Rosengarten, W. E. Pennsylvania
Ross, Herman M. Central States
Ross, W. E. Central States
Roth, R. F. Ohio
Rowen, R. W. Central States
Rowntree, Bernard. California
Royer Foundry & Machine Co. Associate
Ruchhoft, C. C. Central States (Dual—Federal)
Ruck, Franklin. Ohio
Ruckel, Paul J. Rocky Mountain
Rudgal, H. T. Central States
Rudolfs, Willem. New Jersey
Rudolph, R. L. California
Ruge, J. Herman. Florida
Ruggles, M. H. Florida
Ruhmann, Ovid G. Central States
Rumble, G. B. Canada
Rumsey, James R. Michigan
Rupp, Daniel H. Ohio
Ruppert, E. L. Pacific Northwest
Russell, George. Missouri
Russell, George S. Missouri
Russell, J. P. Canada
Ryan, Alfred J. Rocky Mountain
Ryan, Joseph P. Central States
Ryan, J. Samuel. New York
Ryan, Wm. A. New York
Ryckman, Seymour J. New England
Rymer, Mary E., Mrs. Rocky Mountain

Saetre, Leif. New York.
Sage, Howard D. New York
Sager, John C. Central States
Sala, David W. Central States
Salle, Anthony. New York
Salvato, J. A., Jr. New York
Sammis, L. A. New York
Samson, Channel. New York
Samuelson, Andy. New York
Sanborn, J. F. New York
Sanchis, Joseph M. California
Sander, Irwin P. New York
Sanders, M. D. Central States
Sanderson, W. W. New England (Dual—New York)
Sargent, Edward C. Ohio
Sauer, Victor W. California
Saunders, E. F. Central States
Savage, Edward. New York
Saville, Thorndike. New York
Sawyer, C. N. Central States
Sawyer, Lee. Michigan
Sawyer, Robt. W., Jr. New England
Scales, E. P. Georgia
Schade, Willard F. Ohio
Schaefer, Edw. J. New York
Schaetzle, T. C. Ohio
Schaut, Geo. G. Pennsylvania
Scheak, H. M. Canada
Scheffer, Louis K. Pennsylvania
Scheidt, Burton A. Central States
Schenk, E. F. Iowa
Schick, V. R. Ohio
Schier, Lester C. Central States
Schirk, J. M. Rocky Mountain
Schlenz, Harry E. Central States
Schliekelman, R. J. Iowa
Schmick, Mark F. Pennsylvania
Schmit, J. M. Rocky Mountain
Schneller, M. P. Central States
Schoeninger, C. J. Michigan
Schoepfle, O. F. Ohio
Scholl, Clarence E. Central States
Schott, Edgar C. California
Schouten, Ernest W. Oklahoma
Schrack, Bert. Iowa
Schreiner, W. R. New York
Schriner, P. J. Central States
Schroeder, Arthur W. Central States
Schroeder, W. L. South Dakota
Schroepfer, George J. Central States
Schubert, Frank J. Central States
Schuck, H. W. California
Schulhoff, Henry B. New York
Schureman, A. L. California
Schuyler, Howard L. Pennsylvania
Schwartz, Charles F. New York
Schwartz, H. L. Pennsylvania
Schwartz, Louis. New York
Schwartz, Oswald. Central States
Schwob, Carl E. Texas
Sciver, A. England (I. S. E.)
Scott, Clifton A. Central States
Scott, Guy R. Federal
Scott, Ralph. Central States
Scott, Roger J. Central States
Scott, Rossiter S. New York
Scott, W. England (I. S. P.)
Scott, Warren J. New England
Scott, W. M. Canada
Scott, Walter M. New York
Scovill, John R. New York
Searight, Geo. P. Pennsylvania
Searls, Glenn. New York
Seaver, Wist D. Missouri

Sedlacek, A. J. Iowa
Seeger, M. Dean. Pacific Northwest
Segel, A. (Alt.) California
Seid, Sol. New Jersey
Seifert, Wm. P. New York
Seligmann, Irving S. Texas
Sellers, A. E. England (I. S. P.)
Seltzer, J. M. Pennsylvania
Senseman, Wm. B. California
Setter, Lloyd R. New York
Sewage Works Engineering. Associate
Shank, John J. Pennsylvania
Shapiro, Maurice A. Florida
Shapiro, Robert. New York
Shaw, Frank R. Federal
Shaw, Morton. Central States
Shaw, Paul A. California
Shaykin, Jerome D. Central States
Shea, Walter J. New England
Shearer, A. B. California
Sheen, Robt. T. Pennsylvania
Sheets, W. D. Ohio
Shehlee, Girard. New York
Shelton, M. J. California
Shephard, W. F. Michigan
Shepperd, Frederick. New York (Dual New England)
Shera, Brian L. Pacific Northwest
Sherman, Leslie K. New England
Shertzer, J. H. Pennsylvania
Shipman, R. H. Central States
Shirley, Donald L. Pacific Northwest
Shockley, Homer G. New York
Shodron, John M. Central States
Shook, H. E. California
Shook, H. R. Canada
Showalter, Charles M. Pennsylvania
Shupe, S. Canada
Sickler, Archie H. New York
Sidle, R. S. England (I. S. P.)
Siebert, Christian L. Pennsylvania
Siegel, John A. California
Signor, C. V. Pacific Northwest
Sigworth, E. A. New York
Silberbauer, Walter R. California
Silberts, S. A. California
Simmerman, John S. New Jersey
Simmons, Harold. New York
Simmons, M. F. Georgia
Simon, Samuel S. New York
Simonton, Lewis R. Georgia
Simplex Valve & Meter Co. Associate
Simpson, Maynard. Central States
Simpson, R. W. New York
Simson, George, Jr. Rocky Mountain
Simson, Paul W. New York
Singer, Oscar C. Ohio
Singleton, M. T. Georgia
Siple, H. M. Pennsylvania
Sisler, H. H. Pacific Northwest
Skinner, J. F. California
Skinner, W. V. (Alt.) California
Sklarevsky, Rimma. Maryland-Delaware
Slagle, Elmer C. Central States
Slee, Angus E. Rocky Mountain
Slinger, J. F. Missouri
Sloan, Garrett. Federal
Slocum, Adelbert I. New York
Slough, John. New York
Small, R. L. Pacific Northwest
Smith, A. H. Ohio
A. P. Smith Manufacturing Co. Associate
Smith, Benjamin L. New York
Smith, C. A. California
Smith, Chas. L. California
Smith, E. A. Cappelen. New York
Smith, Earl T. (Alt.) Michigan
Smith, Edward J. New York
Smith, E. E. Ohio
Smith, F. Burton. Florida
Smith, Frank E. California
Smith, Frank J. New York
Smith, G. C. England (I. S. P.)
Smith, Gilbert M. Central States
Smith, H. G. California
Smith, Harold. New York
Smith, Harold L. Michigan
Smith, Harvey J. Pacific Northwest
Smith, J. Irwin. Central States
Smith, J. F. California
Smith, L. R. New York
Smith, Marvin L. Pennsylvania
Smith, Paul L. Maryland-Delaware
Smith, R. C. New Jersey
Smith, R. L. Central States
Smith, Russell S. Federal
Smith, R. Turmbull. Central States
Smith, Ralph A. Central States
Smith, Robt. J. Michigan
Smith, S. H. Michigan
Smith, W. Austin. Georgia
Smith, Walter E. Michigan
Smithson, Thomas. Pacific Northwest
Snedeker, L. Laverne. Michigan
Sneed, Glenn J. Central States
Snell, J. R. New England
Snelsire, Wm. Pennsylvania
Snook, W. F. A. England (I. S. P.)
Snow, Donald L. Central States
Snow, Willis J. New England (Dual—New York)
Snyder, Clifford A. Ohio
Snyder, John A., Jr. California
Snyder, M. K. Pacific Northwest
Snyder, N. S. New York
Snyder, R. F. Ohio

Solander, Arvo A. Federal
Solomon, G. R. New York
Somers, Verne. Central States
Sorbel, J. L. South Dakota
Souther, Fred L. California
Sowden, Howard J. Central States
Sowdon, Wm. K. New York
Spaeder, Harold J. Central States
Spaeth, Julius. Kansas
Sparr, A. E. New York
Spaulding, L. H. Pacific Northwest
Spear, Wm. B. Pennsylvania
Specht, James E. Ohio
Speiden, H. W. Pennsylvania
Spellman, W. A. Canada
Spencer, Chas. C. Federal
Spencer, City of (Iowa). Iowa
Sperbeck, George E. California
Sperling, Elmer J. Florida
Sperry, Walter A. Central States
Spiegel, Milton. Central States
Spieker, Roy G. South Dakota
Spies, Kenneth H. South Dakota
Spragg, H. J. Iowa
Spry, Fred J. New York
Spurgeon, Ralph. Central States
Staley, H. H. Kansas
Stanbridge, H. H. England (I. S. P.)
Standley, J. B. Texas
Stanhope, Clifford T. New York
Stankewich, M. J. New York
Stanley, C. M. Iowa
Stapf, R. J. South Dakota
Stapley, Edward R. Oklahoma
Stark, Louis. Michigan
Starling, Chas. H. North Carolina
Stauff, Paul V. Central States
Staynes, E. H. England (I. S. P.)
Steacy, John J. New York
Stearns, Donald E. New England
Steffen, A. J. Central States
Steffensen, S. W. New York
Steffes, Arnold M. Central States
Stegeman, Paul. Michigan
Steindorf, R. T. Central States
Steiner, S. K. New York
Stepleton, Harold A. Ohio
Sterling, Clarence I. New England
Sterns, Edw. A. New York
Stevens, Donald B. Federal
Stevens, Harry. Maryland-Delaware
Stevenson, Albert H. New York
Stevenson, Ralph A. California
Stewart, H. M. Pennsylvania
Stewart, Morgan E. California
Stewart, W. H. New York
Stiemke, Robt. E. North Carolina
Stilson, Alden E. New York
Stites, H. L. California
St. Louis County Health Dept. Missouri
St. Louis Public Library. Missouri
Stock, Mitchell B. New England
St. John, Conrad H. Florida
Stone, A. R. England (I. S. P.)
Storey, Benjamin M. Central States
Storrie, Wm. Canada
Stowell, E. Ralph. California
Straker, M. L. Ohio
Strang, J. A. Kansas
Strangard, Edward L. California
Stratton, Chas. H. New York
Straub, Conrad P. New York
Street, Haskell R. Texas
Streeter, H. W. Federal
Streeter, Robt. L. Rocky Mountain
Streeter, S. H. England (I. S. E.)
Strelow, J. L. Iowa
Strickland, Raymond. Central States
Stringer, R. M. Georgia
Strockbine, Walter. Pennsylvania
Stroessenreuther, G. A. Central States
Strong, Bruce F. New York
Strotkamp, Chas. E. California
Strowbridge, John C. New York
Stuart-Brumley Corp. Associate
Studebaker, Leo. New York
Stunkard, C. R. California
Sturgeon, R. G. Canada
Stutz, C. N. Central States
Sulentic, S. A. Kansas
Sullivan, R. H. Georgia
Summers, M. W. England (I. S. E.)
Sund, Gutorm. Central States
Susa, Stephen A. Pacific Northwest
Sutcliffe, H. W. Canada
Suter, Max. Central States
Sutherland, Henry M. New York
Suttie, R. H. New England
Sutton, R. W. England (I. S. P.)
Svenson, Sven H. New York
Svore, Jerome H. North Dakota
Swab, Bernal H. North Carolina
Swartz, Martin. North Carolina
Sweeney, J. Stanley. Florida
Sweeney, R. C. New York
Sweet, Theodore T. Florida
Swender, Harvey P. Iowa
Swenholt, John. New York
Swenson, John P. Georgia
Swinehart, Eugene B. Pennsylvania
Swope, Gladys. Central States
Sylliassen, M. O. Pacific Northwest
Sylvester, Wm. L. New York
Symons, G. E. New York
Szymanski, John R. New England

Taggart, Robt. S. New York
Talbot, F. D. California
Tallamy, Bertram Dalley. New York
Tamer, Paul. New York
Tapleshay, John A. Central States
Tapping, C. H. Central States
Tarbell, W. P. North Dakota
Tarbett, R. E. Federal
Tarlton, Ellis A. New England
Tatlock, M. W. Ohio
Taylor, Arthur. California
Taylor, D. R. Florida
Taylor, Frank S. Oklahoma
Taylor, F. W. Georgia
Taylor, Godfrey M. C. England (I. S. E.)
Taylor, H. England (I. S. P.)
Taylor, Henry W. New York
Taylor, J. England (I. S. P.)
Taylor, Warren G. New York
Teel, Jess W. California
Tempest, W. F. Central States
Tennant, H. V. Central States
Terhoeven, G. E. New York
Terhune, A. S. New Jersey
Ternent, A. Canada
Terry, Frank. New York
Tetzlaff, Frank. New York (Dual Federal)
Thalheimer, Marce. Central States
Thamasett, Otto E. New York
Thatcher, Fred A. New York
Thatcher, H. D. England (I. S. P.)
Thayer, Paul M. Central States
Thayer, Reginald H. New York
Theriault, E. J. Federal
Theroux, Frank R. Michigan
Thews, Vernon W. California
Thiel, James A. Pacific Northwest
Thierman, Frank. Central States
Thoits, Edw. D. California
Tholin, A. L. Central States
Thomas, A. England (I. S. P.)
Thomas, A. H. R. Canada
Thomas, Ariel A. Central States
Thomas, E. R. North Carolina
Thompson, E. H. New England
Thompson, F. N. New York
Thompson, H. Loren. Central States
Thompson, J. T. England (I. S. P.)
Thompson, N. J. Rocky Mountain
Thompson, Robert B. New England
Thomson, J. B. F. New York
Thorn, William J. Pennsylvania
Tierney, Lawrence J. J. New England
Timm, Arthur. Central States
Timmons, Cyrus L. Florida
Tims, Wm. C. Florida
Todd, J. L. California
Todd, Stanley B. New York
Tolagson, Clarence F. California
Toledo, City of (Iowa). Iowa
Tolles, Frank C. Ohio
Tolman, S. L. New York
Tomek, Arthur O. Central States
Tomkins, Lloyd. Michigan
Tomm, La Vern M. New York
Toone, Dean Wm. California
Towne, W. W. South Dakota
Townend, C. B. England (I. S. P.)
Townsend, Darwin W. Central States
Trager, Leonard W. New England
Trautwein, Frederick. New York
Travaini, Dario. Arizona
Trebler, H. A. Pennsylvania
Troimper, Paul A. Central States
Trotter, Roy M. California
True, Albert O. North Carolina
Trulander, Wm. M. Central States
Tuhus, Kenneth. Central States
Turner, Homer G. Pennsylvania
Turner, J. R. Ohio
Turner, Wm. S. Pacific Northwest
Turpin, U. F. Central States
Tuttle, Leon E. New England
Twin City Testing & Engr. Laboratory (Corporate). Central States
Tygert, C. B. Pennsylvania
Tyler, R. G. Pacific Northwest

Udell, Harold. Federal
Uhlmann, Paul A. Ohio
Ulip, Anthony. New York
Ullrich, C. J. (Alt.) California
Umbenhauer, E. J. Pennsylvania
Underwood, J. E. Canada
United States Pipe & Foundry Co. Associate
University of Calif. Library. California
University of Southern California Genral Library. California
Updegraff, W. R. California
Upton, Frank W. New York
Urban, Robert C. New York
Urick, R. H. Iowa
Urquhart, M. B. Rocky Mountain
Ussery, A. E. Texas

Valdese Water Works (N. Car.). North Carolina
Van Atta, J. W. New York (Dual—New England and Pennsylvania)
Van Denburg, J. W. New York
Vanderlip, Arthur N. New York
Van Der Vliet, Henry. New Jersey
Van Deusen, E. J. New York
Van Horn, R. B. Pacific Northwest
Van Kleeck, LeRoy W. New England
Van Ness, Joseph A. Rocky Mountain
Van Praag, Alex., Jr. Central States
Van Wyck, George W. New York

Vapor Recovery Systems Co. Associate
Vaseen, V. A. Rocky Mountain
Vaughan, E. A. California
Veatch, F. M. Rocky Mountain
Veatch, F. M., Jr. Central States
Velz, C. J. New York
Velzy, C. R. New York
Venn, Frank. (Alt.) Michigan
Vensano, H. C. California
VerDow, William H. (Alt.) New York
Vest, W. E. North Carolina
Vickery, John U. Florida
Victoria, John. New York
Vivier, Harvey. New England
Vogelbein, Chas. J. Missouri
Vognild, R. O. Pacific Northwest
Voigt, Richard C. New York
Volpp, A. G. Pacific Northwest
Von Pelt, Richard. California
Vredenburg, Edward L. New York
Vrooman, Morrell. New York

Waddell, W. H. Canada
Wade, Clarence. Central States
Wade, W. J. Central States
Wadhams, S. H. New England
Wagenhals, H. H. New York
Waggoner, E. R. California
Wagner, Edward P. New York
Wagner, Edwin B. Pennsylvania
Wahlstrom, Carl A. Central States
Wailes Dove-Hermiston Corp. Associate
Walbridge, Thornton. Central States
Walker, C. C. Ohio
Walker, Chas. L. New York
Walker, Elton D. Pennsylvania
Walker, Miss Irene. Pacific Northwest
Walker, J. Donald. Central States
Walker, Philip B. New England
Walker, Walter J. (Alt.) California
Walker, William W. Federal
Wallace & Tiernan Co., Inc. Associate
Wallace, W. M. Michigan
Wallach, Arthur. Federal
Walters, F. Y. Canada
Walters, Grover L. California
Walton, Graham. Central States
Ward, A. R. England (I. S. P.)
Ward, C. N. Central States
Ward, Oscar. Central States
Ward, Paul. Pacific Northwest
Warden, Lotus A. Central States
Wardle, J. McClure. New York
Wardwell, T. M. Central States
Ware, Howard. New York
Warren, George D. New York
Warrenton Water Co. North Carolina
Warrick, L. F. Central States
Washburn, Howard C. New York
Washington State Pollution Commission. Pacific Northwest.
Water Department (Hemp, No. Car.). North Carolina
Water Works & Sewerage. Associate
Waterman, Earle L. Iowa
Waters, Geo. E. Central States
Waters, Leslie W. New York
Watmough, W. W. Canada
Watson, Carl H. New York
Watson, David M. England (I. S. E.)
Watson, Henry G. Rocky Mountain
Watson, W. England (I. S. P.)
Watters, T. C. Central States
Weachter, Horace. Pennsylvania
Weasner, Leo. Central States
Weatherby, Chas. H. New York
Weaver, W. H. Georgia
Webber, Roy H. Canada
Wechter, Wm. H. New York
Wedeman, John D. New York
Webber, Earl R. Michigan
Weeber, Wm. Keith. Central States
Weed, Sam A. California
Wiegel, S. R. Federal
Weiner, Daniel J. Federal
Weir, E. England (I. S. P.)
Weir, Paul. Georgia
Weisel, W. O. Pennsylvania
Weiss, R. H. Texas
Welch, Geo. C. New York
Welch, W. H. Texas
Welker, Leland A. New York
Wells, E. Roy. Central States
Wells, S. W. Florida
Welsch, W. Frederick. New York
Welsh, James M. Texas
Welsh, William J. New England
Wenger, J. H. Ohio
Wentworth, John P. New England
Wertz, C. F. Pennsylvania
Wertz, Leroy F. Ohio
West, A. W. Central States
West, Leslie E. New Jersey
Westergaard, Viggio. New York
Westfall, Milton. Central States
Weston, Arthur D. New England
Weston, Roy F. Pennsylvania
Weston, R. S. (Deceased). New England
Westwood, H. W. D. England (I. S. E.)
Wheeler, C. E., Jr. Central States
Wheeler, Robt. C. New York
Whelchel, H. E. Georgia
Whipple, Melville C. New England
Whitby, Stephen S. Pennsylvania
Whitcomb, Leon R. Pennsylvania
White, Geo. C. California
White, Paul R. Central States
White, R. E. California

White, R. H. England (I. S. E.)
White, W. W. California
Whitehead, F. E. New Jersey
Whitehead, H. C. England (I. S. P.)
Whitley, F. H. New York
Whitlock, Ernest W. New York
Whitlock, Henry C. New England
Whitney, Alfred C. Col. Central States
Whittaker, H. A. Central States
Wiegert, Lester O. Central States
Wiest, Gordon J. Pennsylvania
Wieters, A. H. Iowa
Wigley, Chester G. New York
Wilbanks, Lowry G. Georgia
Wild, Harry E. Florida
Wiley, John S. Federal
Wilkes, F. Dean. Canada
Wilkins, George F. California
Willett, C. K. Central States
Williams, A. C. Pennsylvania
Williams, C. C. Central States
Williams, Chas. H. Pacific Northwest
Williams, Chas. W. Central States
Williams, Clyde E. Central States
Williams, G. Bransby. England (I. S. E.)
Williams, J. E. Texas
Williams, Leon G. Central States
Williams, L. O., Jr. Rocky Mountain
Williams, R. L. New York
Williams, W. B. Michigan
Williamson, A. E. Florida
Williamson, F. Martin. Central States
Williamson, Joe, Jr. Florida
Williamson, R. C. Canada
Wilson, C. T. Iowa
Wilson, Harry L. Central States
Wilson, J. B. Central States
Wilson, John. Central States
Wilson, Murray A. Kansas
Wilson, R. D. Central States
Wilson, Robert A. Central States
Wilson, Wm. B. Canada
Winch, Norman M. New England
Windell, Talmage. Central States
Windridge, M. E. D. England (I. S. P.)
Winfield, Wilmer M. New York
Wing, Frederick K. New York
Winne, Geo. New York
Winslow, Wm. H. Pennsylvania
Winter, Orvan V. Central States
Wintersgill, A. T. California
Wirt, R. M. Pennsylvania
Wirth, Harvey E. Central States
Wirts, J. J. Ohio
Wisely, F. E. Central States
Wisely, W. H. Central States
Wishart, J. M. England (I. S. P.)
Wisniewski, Theo. Central States
Witcher, C. Preston. Michigan
Withington, C. Canada
Wittenborn, E. L. Central States
Wittmer, Earl F. Ohio
Wittwer, N. C. New Jersey
Woese, Carl F. New York
Wolfteich, John. New York
Wolman, Abel. Maryland-Delaware
Wolterink, Paul. Michigan
Woltmann, J. J. Central States
Wontner-Smith, H. England (I. S. P.)
Woo, Francis H. California
Wood, Alan H. Pennsylvania
Wood, Herbert M. New York
Wood, J. R. Canada
Wood, R. D., Co. Associate
Woodhouse, H. M. Canada
Woodring, R. W. Pennsylvania
Woodruff, F. L. Ohio
Woodward, John D. Pennsylvania
Woodward, R. L. Federal
Woolley, B. C. Iowa
Worrest, Howard A. Pennsylvania
Worthington, Erastus. New England
Worthington Pump & Machy. Corp. Associate
Wright, Arthur. Pennsylvania
Wright, Charles T. Federal
Wright, Chilton A. New York
Wright, Edw. New England
Wright, Geo. I. Central States
Wright, L. R. California
Wurtenberger, Helen. Central States
Wyant, Clifford. Pennsylvania
Wyatt, Bradley W. California
Wyatt, Wendell C. Kansas
Wyckoff, Charles R. New York
Wyllie, Geo. F. Michigan

Yaeck, Arthur W. Canada
Yaeger, Oscar G. California
Yaffe, C. D. Federal
Yeager, Bert T. Central States
Yenchko, John. Pennsylvania
Yerkes, Milton R. Pennsylvania
Yeomans Brothers Co. Associate (Corporate — Central States)
Yoder, M. Carleton. California
Yost, Harold W. Arizona
Young, Alden W. New York
Young, C. H. Pennsylvania
Young, Norman C. Pennsylvania
Yow, W. E. North Carolina

Zack, Samuel I. New York
Zoddenrust, Albert T. Central States
Zetterberg, Edw. Central States
Zoglmann, Martin. Central States
Zollner, Frederick D. New York
Zuckweiler, G. C. California
Zurbuch, N. F. Central States